PERFORMANCE WORK STATEMENT (PWS)

RIVANNA STATION FACILITIES MAINTENANCE SERVICES (RSFMS)
November 5, 2026

Part 1

General Information

1. **GENERAL:** This is a non-personal services contract to provide facilities and equipment maintenance and support services which are non-governmental in nature. The Government shall not exercise any supervision or control over the contract service providers performing the services herein. Such contract service providers shall be accountable solely to the Contractor who, in turn is responsible to the Government.

1.1 Description of Services/Introduction: The contractor shall provide all personnel, equipment, supplies, facilities, transportation, tools, materials, supervision, and other items and non-personal services necessary to perform support services as defined in this Performance Work Statement (PWS) except for those items specified as government furnished property and services. The contractor shall perform to the standards in this contract.

1.2 Background: The Rivanna Station Facilities Maintenance Services contract (RSFMS) provides facilities staff support services for work which is non-governmental in nature and which exceeds the agencies' present organic resources. The main site is the Rivanna Station complex located in a semi-rural area ten miles north of Charlottesville, Virginia. This site has a land footprint of approximately 75 secured acres and consists of three primary and portions of two ancillary facilities: primary facilities are (1) the NGIC Nicholson Building Sensitive Compartmentalized Information Facility (SCIF) (currently 339K SF), (2) the Boulders One (BOULDERS 1) leased SCIF (64K SF), and (3) about 40% of the jointly operated Remote Delivery Facility (RDF). Ancillary facilities are: (1) a leased warehouse space (26K SF-located eight miles from the station), and (2) a leased overflow parking area on Boulders Road outside the main installation entrance. The population of the station at all locations will consist of military, government civilians, government Contractors, and foreign national mission partners.

1.2.1 See below summary of key specification points for each building.

Buillding	**Nicholson**	**Boulders1**	**Nicholson SCIF Addition**
Total sf	258K	64K	81K
# Floors	5	3	3
# Restrooms	22	8	13
# Locker rooms w/showers	2	0	0
# Kitchenettes	6	3	5
Carpet Floor covering	65% of total sf	65% of total sf	65% of total sf
Tile/Other flooring covering	35% of total sf	35% of total sf	35% of total sf

1.3 Objectives: The RSFMS Contractor shall provide National Ground Intelligence Center (NGIC) with facilities maintenance support services and specified equipment maintenance in a flexible manner without creating excess capability.

1.4 Scope: The Contractor shall schedule and perform Level-I Preventive Maintenance (PM) on systems called out in Section J Attachment 1 "List of Equipment to be Maintained" to keep systems operational and minimize the occurrence of NGIC incurring Level-II Service Order or High Dollar Value (HDV) Maintenance and Projects Level III High Dollar Value type maintenance actions on the aforementioned

systems. Schedule and perform all janitorial tasks for NGIC buildings inclusive of providing all supplies and cleaning equipment necessary for fulfilling janitorial requirements set forth in the PWS. Respond to service order requests whether initiated by Government employees or RSFMS contractor employees and resolve service orders within constraints set forth in the PWS. Act upon event support, general maintenance, furniture and workstation component installation, and removal.

1.4.1 Level-II (Service Order) and Level III High Dollar Value type maintenance when Contracting Officer Representative provides written approval to proceed on such type maintenance. Maintain RSFMS service records to provide Government employees access to reliable data for workload estimates and budget preparations for RSFMS and janitorial. Comply with all security and safety requirements set forth in the PWS with an emphasis on an agile employee training program and monitor security and safety compliance as part of the contractor's quality control plan to assure contractor meets or exceeds the performance standards set forth in the PWS for RSFMS and janitorial. Additionally, Section H content provides post award conditions that set limits when performance increases under the contract are in-scope.

1.4.2 Systems, Equipment, and Component Inventories: The quantities of systems, equipment, and components that the Contractor must maintain is found in Section J Attachment 1 "List of Equipment to be Maintained". The supporting data presented in the Section J Attachment 1 "List of Equipment to be Maintained for each functional area are based on the data available at the time this PWS was prepared. Within thirty (30) calendar days of contract start date, the Contractor shall physically inventory the property and facilities described in Section J Attachment 1 List of Equipment to be Maintained and confirm the categories and quantities of equipment items to be maintained. The completed inventory may become a basis for readjustment, and the Contractor shall conduct a 100% physical inventory at least once annually or as directed by the NGIC Property Book Officer. The completed inventory may become a basis for readjustment.

1.5 Period of Performance: The period of performance shall be for one (1) Base Year and four (4) 12-month option years. The Period of Performance reads as follows:

Base Year	1 September 2027	31 August 2028
Option Year I	1 September 2028	31 August 2029
Option Year II	1 September 2029	31 August 2030
Option Year III	1 Septembert 2030	31 August 2031
Option Year IV	1 September 2031	31 August 2032
FAR Clause 52.217-8	1 September 2032	29 February 2033

1.6 General Information

1.6.1 Quality Control: The contractor shall develop and maintain an effective quality control program to ensure services are performed in accordance with this PWS. The contractor shall develop and implement procedures to identify, prevent, and ensure non-recurrence of defective services. The contractor's quality control program is the means by which he assures himself that his work complies with the requirement of the contract. The Contractor shall provide a proposed initial written Quality Control Plan (QCP) plan to the Contracting Officer (KO) and Contracting Officers Representative (COR) with their proposal. The QCP plan is a living plan. The Contractor's QCP will include measurable QC methods for monitoring the QCP and documenting the regular conduct and enforcement of the provided QCP. An electronic copy of subsequent QCP changes shall be submitted to the KO and COR within 5 working days when changes are made following original submittal. After acceptance of the quality control plan the contractor shall receive the contracting officer's acceptance in writing of any proposed change to his QC system.

1.6.2 Quality Assurance: The government shall evaluate the contractor's performance under this contract in accordance with the Quality Assurance Surveillance. This plan is primarily focused on what the Government must do to ensure that the contractor has performed in accordance with the performance standards. It defines how the performance standards will be applied, the frequency of surveillance, and the minimum acceptable defect rate(s).

1.6.3 Recognized Holidays:

New Year's Day
Martin Luther King Jr.'s Birthday
President's Day
Memorial Day
Juneteenth National Independence Day
Independence Day
Labor Day
Columbus Day
Veteran's Day
Thanksgiving Day
Christmas Day

1.6.4 Hours of Operation: This contract and the personnel supporting it are deemed mission essential. Continued performance of services within this PWS will be coordinated on a situational basis and by agreement of the parties. The contractor is responsible for conducting business during agency core hours (0700-1600) and evening cleaning after core hours as required in the PWS. Monday thru Friday except Federal holidays or when the Government facility is closed due to local or national emergencies, administrative closings, or similar Government directed facility closings. The contractor may be needed outside the core hours of 0700 – 1600 and Monday through Friday. For other than firm fixed price contracts, the contractor will not be reimbursed when the government facility is closed for the above reasons. The Contractor must at all times maintain an adequate workforce for the uninterrupted performance of all tasks defined within this PWS when the Government facility is not closed for the above reasons. When hiring personnel, the Contractor shall keep in mind that the stability and continuity of the workforce is essential.

1.6.5 Place of Performance: The work to be performed under this contract will be performed at Rivanna Station, Charlottesville, VA, and any/all NGIC-occupied facilities within 15-miles radius of Rivanna Station.

1.6.6 Type of Contract: The government will award a Firm-Fixed Price (FFP) type contract.

1.6.7 Security Requirements: Contractor personnel performing work under this contract must have a valid Facility Clearance at the Top Secret Level upon submission of proposal. The Contractors key personnel under this contract shall possess a current (active) DoD TOP SECRET Security Clearance (TS/SCI) with a Special Background Investigation (SBI) and have eligibility for Sensitive Compartmented Information (SCI) indoctrination at time of the proposal submission, and must maintain that level of security clearance for the life of the contract. All other Contractor personnel performing work within the SCIF shall possess a current (active) DoD TOP SECRET Security Clearance (TS/SCI) with SCI eligibility prior to beginning contract performance. Designated services primarily performed outside of the SCIF may be performed by Contractor personnel either without a security clearance or while a clearance is being processed. The security requirements are in accordance with the attached DD254. Contractor personnel performing duties outside the SCIF must have passed a National Criminal Investigation Check (NCIC). RSFMS sub-contractors performing work within the SCIF on an as-needed basis will not require a clearance, however they must be vetted by the Security Office and escorted by the RSFMS Contractor at all times.

Contractor will require access to KLAMATH (KLM) and KLAMATH-Reporting (KLM-R) information at the government site in the execution of the performance work statement. The COR may determine additional program(s) access that may be required in execution of this contract. Contractor agrees to follow guidance outlined in applicable security classification guides, program security plans and as outlined in ICD 906 "Controlled Access Programs". All contractor personnel requiring KLM-KLMR access will be nominated by government COR.

1.6.7.1 Physical Security: The contractor shall be responsible for safeguarding all government equipment, information and property provided for contractor use All personnel and drivers involved in providing the services required by this PWS shall, at Contractor's expense, complete annually an approved Anti-Terrorism and Force Protection (AT/FP) awareness training course. The Contractor shall provide proof of completed training. At the close of each work period, government facilities, equipment, and materials shall be secured.

1.6.7.2 Key Control. The Contractor shall establish and implement methods of making sure all keys/key cards issued to the Contractor by the Government are not lost or misplaced and are not used by unauthorized persons. NOTE: All references to keys include key cards. No keys issued to the Contractor by the

Government shall be duplicated. The Contractor shall develop procedures covering key control that shall be included in the Quality Control Plan. Such procedures shall include turn-in of any issued keys by personnel who no longer require access to locked areas. The Contractor shall immediately report any occurrences of lost or duplicate keys/key cards to the Contracting Officer.

1.6.7.2.1. In the event keys, other than master keys, are lost or duplicated, the Contractor shall, upon direction of the Contracting Officer, re-key or replace the affected lock or locks; however, the Government, at its option, may replace the affected lock or locks or perform re-keying. When the replacement of locks or re-keying is performed by the Government, the total cost of re-keying or the replacement of the lock or locks shall be deducted from the monthly payment due the Contractor. In the event a master key is lost or duplicated, all locks and keys for that system shall be replaced by the Government and the total cost deducted from the monthly payment due the Contractor.

1.6.7.2.2. The Contractor shall prohibit the use of Government issued keys/key cards by any persons other than the Contractor's employees. The Contractor shall prohibit the opening of locked areas by Contractor employees to permit entrance of persons other than Contractor employees engaged in the performance of assigned work in those areas, or personnel authorized entrance by the Contracting Officer.

1.6.7.3 Lock Combinations. The Contractor shall establish and implement methods of ensuring that all lock combinations are not revealed to unauthorized persons. The Contractor shall ensure that lock combinations are changed when personnel having access to the combinations no longer have a need to know such combinations. These procedures shall be included in the Contractor's Quality Control Plan.

1.6.8 Special Qualifications:

1.6.9 Post Award Conference/Periodic Progress Meetings: The Contractor agrees to attend any post award conference convened by the contracting activity or contract administration office in accordance with Federal Acquisition Regulation Subpart 42.5. The contracting officer, Contracting Officers Representative (COR), and other Government personnel, as appropriate, may meet periodically with the contractor to review the contractor's performance. At these meetings the contracting officer will apprise the contractor of how the government views the contractor's performance and the contractor will apprise the Government of problems, if any, being experienced. Appropriate action shall be taken to resolve outstanding issues. These meetings shall be at no additional cost to the government.

1.6.10 Contracting Officer Representative (COR): The (COR) will be identified by separate letter. The COR monitors all technical aspects of the contract and assists in contract administration. The COR is authorized to perform the following functions: assure that the Contractor performs the technical requirements of the contract: perform inspections necessary in connection with contract performance: maintain written and oral communications with the Contractor concerning technical aspects of the contract: issue written interpretations of technical requirements, including Government drawings, designs, specifications: monitor Contractor's performance and notifies both the Contracting Officer and Contractor of any deficiencies; coordinate availability of government furnished property, and provide site entry of Contractor personnel. A letter of designation issued to the COR, a copy of which is sent to the Contractor, states the responsibilities and limitations of the COR, especially with regard to changes in cost or price, estimates or changes in delivery dates. The COR is not authorized to change any of the terms and conditions of the resulting order.

1.6.11 Key Personnel: The follow personnel are considered key personnel by the government: Contract manager and alternate, and General Maintenance Worker. The contractor shall provide a contract manager who shall be responsible for the performance of the work. The name of this person and an alternate who shall act for the contractor when the manager is absent shall be designated in writing to the contracting officer. The contract manager or alternate shall have full authority to act for the contractor on all contract matters relating to daily operation of this contract. The contract manager or alternate shall be available during normal hours of operation to plan, direct, and control the overall management and operational

functions specified herein. The contract manager shall provide the necessary level of contract management and administrative oversight to achieve the qualitative and quantitative requirements of this contract. The contract manager or designated alternate(s) shall be available within thirty (30) minutes during normal work hours to meet on-site with the COR or designated representative. After normal working hours, the contract manager or designated alternate(s), shall be available within two hours after notification, to perform emergency and urgent functions. Qualifications for all key personnel are listed below:

1.6.11.1 The Contract manager shall have at least seven (7) years' experience in facilities maintenance and management, five (5) years of which must be supervisory experience managing a program of this size and scope. The designated alternate shall have at least five (5) years' experience in facilities maintenance and management, with three (3) years of which must be supervisory experience managing a program of this size and scope.

1.6.11.2 General Maintenance Worker: Contractor shall provide General Maintenance worker to perform general maintenance, preventive maintenance and repair of equipment and buildings requiring practical skill and in such trades as painting, drywall, carpentry, minor electrical, minor plumbing, various floor and ceiling systems, masonry work, furniture installation and removal, and event support..

1.6.12 Identification of Contractor Employees: All contract personnel attending meetings, answering Government telephones, and working in other situations where their contractor status is not obvious to third parties are required to identify themselves as such to avoid creating an impression in the minds of members of the public that they are Government officials. They must also ensure that all documents or reports produced by contractors are suitably marked as contractor products or that contractor participation is appropriately disclosed. The Contractor shall ensure that the contract manager and all contractor employees wear clothing that allows visible and clear identification as Contractor staff during the work day, and shall provide such identification and or distinctive clothing at Contractor expense and as Contractor furnished equipment.

1.6.13 Contractor Travel. Contractor will be required to travel CONUS and within the NCR during the performance of this contract to attend meetings, conferences, and training. The contractor may be required to travel to off-site training locations and to ship training aids to these locations in support of this PWS. Contractor will be authorized travel expenses consistent with the substantive provisions of the Joint Travel Regulation (JTR) and the limitation of funds specified in this contract. All travel requires Government approval/authorization and notification to the COR.

1.6.14 Other Direct Costs: *Not applicable*

1.6.15 Organizational Conflict of Interest: Contractor and subcontractor personnel performing work under this contract may receive, have access to or participate in the development of proprietary or source selection information (e.g., cost or pricing information, budget information or analyses, specifications or work statements, etc.) or perform evaluation services which may create a current or subsequent Organizational Conflict of Interests (OCI) as defined in FAR Subpart 9.5. The Contractor shall notify the Contracting Officer immediately whenever it becomes aware that such access or participation may result in any actual or potential OCI and shall promptly submit a plan to the Contracting Officer to avoid or mitigate any such OCI. The Contractor's mitigation plan will be determined to be acceptable solely at the discretion of the Contracting Officer and in the event the Contracting Officer unilaterally determines that any such OCI cannot be satisfactorily avoided or mitigated, the Contracting Officer may effect other remedies as he or she deems necessary, including prohibiting the Contractor from participation in subsequent contracted requirements which may be affected by the OCI.

1.6.16 Phase In /Phase Out Period: To minimize any decreases in productivity and to prevent possible negative impacts on additional services, the Contractor shall have personnel on board, during the the thirty (30) day phase in/phase out periods. During the phase in period, the Contractor shall become familiar with performance requirements in order to commence full performance of services on the contract start date.

1.6.17 Safety Requirements: The Contractor shall complete and submit to the NGIC Safety Office a Job Hazard Analysis (JHA) and completed DA Form 7566 for all activities for which they are appropriate and required by Army regulation, INSCOM or NGIC Safety policy and guidelines.

1.6.17.1 The Contractor shall employ persons who meet the appropriate health standards as prescribed by local, state, or federal public health regulations for the particular type of employment for which engaged. The Contractor shall comply with all Occupational Safety and Health Administration (OSHA) regulations and publications. The Government reserves the right to intervene in Contractor operations to protect the health and safety of Government employees and visitors.

1.6.17.2 The Contractor shall conform to all Rivanna Station fire, security, and safety regulations and requirements covering such premises in effect at any time during the performance of this Contract, including the submission of any required safety or accident reports as directed by referenced publications. The Contractor agrees to take all necessary steps and precautions to prevent accidents and preserve the life and health of Contractor and Government employees performing or in any way coming in contact with performance of this contract on such premises. The COR, upon request, will furnish information concerning safety, fire, and security regulations to the Contractor. Any violation of such regulations, unless immediately corrected as directed by the COR, KO, or other designated personnel, shall be grounds for termination of this contract.

1.6.17.3 The Facilities Office, the COR or his/her designated representative, or any other person designated by them shall have the right to inspect the offices and work areas/operations of the Contractor to assure full compliance with all provisions of this Contract and with the standards of service and safety, including all facilities necessary for processing, storing, transporting, and handling materials of this contract. The Contractor shall turn over premises in as good order and condition as when the same were entered upon by the Contractor; damage by fire, or inevitable accident or ordinary wear and tear excepted.

1.6.18 Health and Safety: The Contractor shall provide for the safety of workers, the public, and the protection of the environment within the scope of all contract services delivered by the Contractor.

1.6.18.1 The Contractor shall take necessary actions, to minimize injuries and fatalities and prevent worker exposures to harmful substances and the environment;

1.6.18.2 The Contractor shall establish clear environmental, safety and health priorities and manage activities in proactive ways that effectively increase protection to the environment and to the public and worker safety and health;

1.6.18.3 The Contractor shall perform all activities in a manner that complies with health, safety, and environmental regulations; minimizes wastes; and assures all work complies with DoD Directives and OSHA requirements.

1.6.18.4 The Contractor shall submit a safety program plan within 30 calendar days following contract award. The Contractor shall maintain an effective safety management system to identify deficiencies, resolve them in a timely manner, and ensure that corrective actions are implemented. Contractor shall ensure that all Contractor personnel have received proper safety training, appropriate to their respective jobs. At a minimum, all Contractor personnel shall have attended OSHA training as identified in 29 CFR Part 1910 and Part 1926.

1.6.18.5 Failure to Comply: If the Contractor fails or refuses to comply with its safety plan or performs work in a manner which creates a health hazard to government or Contractor employees, the Contracting Officer, via recommendation from the COR, may take corrective action.

1.6.19 Security and Force Protection: The Contractor shall employ persons as employees or agents who shall be citizens of the United States of America.

1.6.19.1 The Contractor shall obtain from all employees and agents of the Contractor at the time of their separation any and all installation passes, Common Access Cards, security access badges, or other identification issued to such persons during their employment. It is the responsibility of the COR to ensure the passes are collected and returned to the Nicholson Building security office, or other designated issuing office.

1.6.19.2 The Contractor recognizes that the contracted place of service is a military facility subject to force protection requirements that change from time to time based on the threat level. Force protection requirements may result in searches of Contractor personnel, supplies, and vehicles. During heightened threat levels other restrictions, such as restrictions on guests and temporary closures, are also possible. The Contractor recognizes that force protection requirements are a recognized non-compensable risk.

1.6.19.3 The Contractor shall be subject to and comply with all Federal, DoD, Army, INSCOM and local command Security policies, regulations and orders from authorized local Security staff. Violations of the stated authorities shall be deemed by the Commander and the KO to be sufficient grounds for termination of Contractor employees or termination for default of the Services Contract.

PART 2
DEFINITIONS & ACRONYMS

2. **DEFINITIONS AND ACRONYMS:**

2.1. DEFINITIONS:

2.1.1. CONTRACTOR. A supplier or vendor having a contract to provide specific supplies or service to the government. The term used in this contract refers to the prime.

2.1.2. CONTRACTING OFFICER. A person with authority to enter into, administer, and or terminate contracts, and make related determinations and findings on behalf of the government. Note: The only individual who can legally bind the government.

2.1.3. CONTRACTING OFFICER'S REPRESENTATIVE (COR). An employee of the U.S. Government appointed by the contracting officer to administer the contract. Such appointment shall be in writing and shall state the scope of authority and limitations. This individual has authority to provide technical direction to the Contractor as long as that direction is within the scope of the contract, does not constitute a change, and has no funding implications. This individual does NOT have authority to change the terms and conditions of the contract.

2.1.4. DEFECTIVE SERVICE. A service output that does not meet the standard of performance associated with the Performance Work Statement.

2.1.5. DELIVERABLE. Anything that can be physically delivered but may include non-physical things such as meeting minutes.

2.1.6. KEY PERSONNEL. Contractor personnel that are evaluated in a source selection process and that may be required to be used in the performance of a contract by the Key Personnel listed in the PWS. When key personnel are used as an evaluation factor in best value procurement, an offer can be rejected if it does not have a firm commitment from the persons that are listed in the proposal.

2.1.7. PHYSICAL SECURITY. Actions that prevent the loss or damage of Government property.

2.1.8. QUALITY ASSURANCE. The government procedures to verify that services being performed by the Contractor are performed according to acceptable standards.

2.1.9. QUALITY ASSURANCE Surveillance Plan (QASP). An organized written document specifying the surveillance methodology to be used for surveillance of contractor performance.

2.1.10. QUALITY CONTROL. All necessary measures taken by the Contractor to assure that the quality of an end product or service shall meet contract requirements.

2.1.11. SUBCONTRACTOR. One that enters into a contract with a prime contractor. The Government does not have privity of contract with the subcontractor.

2.1.12. WORK DAY. The number of hours per day the Contractor provides services in accordance with the contract.

2.1.12. WORK WEEK. Is defined as Monday through Friday, unless specified otherwise.

2.2. ACRONYMS:

ACOR	Alternate Contracting Officer's Representative
AFARS	Army Federal Acquisition Regulation Supplement
AIA	American Institute of Architects

AR	Army Regulation
AT/FP	Anti-Terrorism and Force Protection
CCE	Contracting Center of Excellence
CFR	Code of Federal Regulations
CLIN	Contract Line Item Number
CMMS	Computerized Maintenance Mangement System
CONUS	Continental United States (excludes Alaska and Hawaii)
COR	Contracting Officer Representative
COTR	Contracting Officer's Technical Representative
COTS	Commercial Off the Shelf
DA	Department of the Army
DD250	Department of Defense Form 250 (Receiving Report)
DD254	Department of Defense Contract Security Requirement List
DFARS	Defense Federal Acquisition Regulation Supplement
DMDC	Defense Manpower Data Center
DOD	Department of Defense
FAR	Federal Acquisition Regulation
FFP	Firm-Fixed Price
GFP	Government Furnished Property
HDV	High Dollar Value
HIPAA	Health Insurance Portability and Accountability Act of 1996
HQDA	Headquarters Department of Army
IMA	Individual Mobilization Augmentee
KO	Contracting Officer
MACOM	Major Army Command
MSC	Major Subordinate Command
NGIC	National Ground Intelligence Center
OCI	Organizational Conflict of Interest
OCONUS	Outside Continental United States (includes Alaska and Hawaii)
ODC	Other Direct Costs
PIPO	Phase In/Phase Out
PM	Preventive Maintenance
POC	Point of Contact
PRS	Performance Requirements Summary
PWS	Performance Work Statement
QA	Quality Assurance
QAP	Quality Assurance Program
QASP	Quality Assurance Surveillance Plan
QC	Quality Control
QCP	Quality Control Program
SO	Service Order
TE	Technical Exhibit
TS/SCI	Top Secret/Sensitive Compartmented Information

PART 3
GOVERNMENT FURNISHED PROPERTY, EQUIPMENT, AND SERVICES

3. GOVERNMENT FURNISHED ITEMS AND SERVICES:

3.1. Services: The Government will provide:

3.2 Police And Fire Protection: The Contractor shall notify the appropriate office for emergency services and shall cooperate with all police and fire programs, drills, and instruction. The Contractors' personnel shall be fully aware of all Rivanna Station emergency services, procedures, telephone numbers, and equipment locations.

3.3 Facilities: The Government will provide administrative and operational space in Rivanna Station facilities for Contractor use that are appropriate to the intended purpose. The government shall inspect the facilities available to the Contractor for compliance with the Occupational Safety and Health A ct (OSHA) and abated hazards. No alterations to the facilities shall be made without specific written permission from the government. In the case of alterations necessary for OSHA compliance, such permission shall not be unreasonably withheld. The Contractor shall return the facilities to the government in the same condition as received, fair wear, tear, and approved modifications excepted.

3.4 Local Area Network Capabilities: The government will furnish the Contractor with access to the existing Local Area Network(s) (LAN) with Internet access. The government will be responsible for connectivity of equipment to the existing access point. The Contractor shall notify the appropriate office when maintenance, repair, or change in service is required. Contractor personnel shall not relocate government furnished access point(s) to the LAN or in any way tamper with the LAN lines. The government is responsible for approving Contractor requests for upgrades or changes in the LAN service provided at the government discretion. The government will furnish the Contractor with access to the electronic mail system along with any necessary standard software packages it uses. Any nonstandard software requirements shall be the responsibility of the Contractor. These systems shall be utilized for official business only.

3.5 Electronic Storage: The government will provide or make available file data storage systems adequate for the Contractor to provide specified master planning support services. Electronic systems will be used to the extent possible and when space restrictions limit the availability of hard copy storage.

3.6 Utilities: The Government will provide all utilities for the contractor's use in performance of tasks outlined in this PWS. The Contractor shall instruct employees in utilities conservation practices. The contractor shall be responsible for operating under conditions that preclude the waste of utilities, such as turning off the water faucets or valves after using the required amount.

3.7 Equipment: The Government will or make available automation information systems (typically PCs), shared copiers, printers, fax machines and plotters as necessary to perform services defined in the PWS. The Contractor shall return any accepted GFP in the same condition as received, normal wear and tear excepted, on the contract termination date. The Contractor shall be responsible for the cost of any maintenance, repairs, or replacement caused by negligence, abuse, or accidents by the Contractor. Title to all GFP shall remain with the Government. Lack of property does not relieve the Contractor from performing the tasks within this contract.

3.8 Materials: The Government will provide materials and supplies for the Contractor to utilize/install as part of general maintenance, Level II Service Orders or Level III High Dollar value (HDV) maintenance under this contract. When Government provides materials and supplies for general maintenance, Level II Service Orders or Level III HDVs, such orders shall reflect just the contractor's labor cost as approved by the COR.

3.9 Government Work Order Reception And Processing System: The government will provide and make available to the contractor a government network-based work order reception system for receiving service requests from the workforce and scheduling and tracking contractor service delivery for the reported issues.

PART 4
CONTRACTOR FURNISHED ITEMS AND SERVICES

4. CONTRACTOR FURNISHED ITEMS AND RESPONSIBILITIES:

4.1 General: The Contractor shall furnish all supplies, equipment, facilities and services required to perform work under this contract that are not listed under Section 3 of this PWS.

4.2 Secret Facility Clearance: The contractor shall possess and maintain a Top Secret facility clearance from the Defense Security Service. The Contractor's employees, performing work in support of this contract shall have been granted a Top Secret security clearance from the Defense Industrial Security Clearance Office and eligible for access to Special Compartmented Information (SCI). The DD 254 is provided as Attachment.

4.3. Materials *Not applicable*

4.4. Equipment: The Contractor shall provide all personal safety protective equipment required by OSHA to perform work in the PWS safely. The Contractor shall ensure that personnel are issued, possess and wear protective clothing and equipment (to include gloves, reinforced toe shoes, hearing and eye protection appropriate for the task being performed) while working in the warehouse and handling supplies and equipment at all specified work locations. The Contractor shall provide safety protective uniforms, complying with OSHA, to all personnel as required.

PART 5
SPECIFIC TASKS

5. Specific Tasks:

5.1. Basic Services. The contractor shall provide the following levels/categories of maintenance and repair for each listed category of equipment serviced at all NGIC Facilities, owned or leased by the US Government and occupied by workforce in direct support of NGIC operations, on or within 15-miles of the installation designated as RIVANNA STATION, Charlottesville VA.

5.1.1 Level I Preventive Maintenance (PM): Preventive maintenance includes scheduling and performing recurring scheduled labor, materials, supplies, and component parts, collectively termed as "preventive maintenance (PM)" or operator level maintenance checks and services, to be performed as Firm Fixed Price (FFP) services upon all categories of mission equipment or areas of the facilities on at least a monthly recurring basis, as described or defined by this PWS. Scheduled PM services include performing at least monthly recurring care and maintenance activities, by which the Contractor shall confirm proper and safe operation of the equipment, maintain clean, safe, and functional work spaces and mission equipment, and comply with both manufacturer's guidance and NGIC requirements for the care of all spaces and categories of equipment listed in or defined by this PWS. PM prerequisites shall include inventorying, identifying and entering all equipment items or systems and their specific individual major components into an approved computerized maintenance management system (CMMS) within 30 days of contract award, and physically tagging each item of equipment with unique identifier codes. Actual PM activities shall include periodic inspection, cleaning, adjustment, calibration, operational and safety checks, assessments of equipment performance and condition, written summary of findings and actions taken during the PM, and proactive recommendations for repairs or replacement of components or systems. PM actions shall routinely involve performing operator start-up/shut-down tasks, assessing and trouble-shooting equipment quality of performance IAW manufacturer's standards and defined NGIC requirements, and making minor repairs or adjustments intended to maintain or improve performance and prevent unexpected or pre-mature equipment breakage or failure. Actual cost details to perform Level-I PM services shall be documented in the CMMS and shall capture all man-hours, supplies and parts for each PM service, with a PM cost summary included for each completed PM event. All PM work activities shall be entered in the CMMS and also shall be entered into General Fund Enterprise Business System (GFEBS) as/when directed by the PWS requirements for contractor use of that Army system. PM as described in this section shall be included in the Firm Fixed Price (FFP) basic contract services and cost. All incidental supplies and materials required to deliver these specified services shall be included in the FFP cost for this service category and not separately invoiced.

5.1.2 Level II Service Order (SO) Maintenance: Shall be comprised exclusively of repairs or other maintenance actions to PWS-listed mission equipment or facility areas which are estimated to cost less than $2,000 per completed repair action. Level-II SO maintenance actions may be required due to unscheduled equipment failure, poor equipment or system performance or other causes or requirements encountered or discovered during or as a result of routine operation, and shall also be termed as "Service Order (SO)" work. SO's requirements also may be identified or initiated during conduct of scheduled PM services, but shall include all maintenance, repair, alteration, and equipment service requirements, which are low-cost and minor in scope, and which are required to restore the equipment, system or facility area to acceptable condition, operation or performance. SO repairs may be identified by equipment or system operators or by maintenance staff. SO work will be funded as a separate Contract Line Item Number (CLIN) and shall be performed without further input from the Government once approved by the COR. Work performed under approved Service Orders shall be completed by the Contractor in compliance with the COR's assigned priority level and quality of maintenance standards mandated for the affected equipment or facility area. Service orders may also be used to replace (repair by replacement) minor equipment items listed under this PWS. Additional examples of SO category work are defined in the specific PWS equipment or system subparagraphs. The Contractor shall include and present a list of SO work performed and cost invoiced for each SO as part of the monthly contract in-process review (IPR) meeting and related reports as required by the PWS or contract deliverables schedule.

5.1.3 Level III High Dollar Value (HDV) Maintenance and Projects: Shall be used for maintenance, repair, replacement or procurement of new/similar equipment for operational support exceeding the ($2000) scope of Service Orders, but not to exceed (NTE) $250,000.00 for a single task. HDV maintenance shall be defined as "New Work" when not covered under the FFP elements of the contract, and the HDV work will be Cost Reimbursable based upon negotiated proposals for labor, materials and equipment required to accomplish the approved scope of work for each event. The Contractor shall provide estimates for each HDV event compliant with FAR requirements for construction costs exceeding $2,000. The Contractor shall detail the price of the work, including an estimate of the material, labor (detailed hours by specialty), and equipment. The Contractor's proposal will be evaluated to determine if: (1) the scope has been clearly and accurately identified, (2) labor categories have been properly identified, and (3) equipment and material proposed are reasonable and properly documented. If the Contracting Officer determines that the proposal is accurate and the price is reasonable, the Contracting Officer will issue a modification to the contract to provide the HDV CLIN with the approved funding. Receipt of the contract modification document shall be the Contractor's notice to proceed. If during the course of work the Contractor encounters unforeseen conditions which impact the work or cost and which could not be evaluated or foreseen during the initial estimation and proposal process, the Contractor shall contact the COR immediately and shall not proceed further without Contracting Officer authorization. If negotiations and a modification to the contract are required, the Contractor shall not proceed until the additional modification has been issued. If the Contractor is directed to stop the HDV event work, the Contractor shall clean and secure the work site. Contractor completion of all Level-III HDV work shall include a detailed written report and confirmation that a government acceptance inspection of the work has been performed.

5.1.4 General Maintenance: Shall be comprised of completing various general and specialized trade skills, including but not limited to carpentry, electrical, painting, concrete, drywall, door hardware, wall hangings or various ceiling and flooring systems. Repair and change locks in the building(s) and perform complex lock servicing to ensure maximum safety of all people. Responsible for the disassembly, movement, reassembly, and installation of facility furnishings to include furniture and furniture systems. Responsible for developing supply estimates for various projects, gathering technical data, material, and fiscal requirements for assigned projects. May assist project coordinator in planning, cost estimating, designing, developing, and completing local projects. Technician(s) shall be knowledgeable of all current safety policies, procedures, and personal protection equipment (PPE) required related to his or her assigned job description, IAW with Occupational Safety and Health Administration (OSHA), facility, system equipment security, Environmental Compliance Assessment Protocol (ECAP) and National Electrical Code (NEC) safety standards. Technician shall wear appropriate safety equipment at all times while performing their assigned task. Shall also be required to attend periodically safety training classes related to their job description. Able to lift and/or carry objects up to 50 pounds, climb ladders, walking up several flights of stairs, working on elevated surfaces and/or working in unusual or uncomfortable body positions or environmental conditions. Performance of work outdoors during various weather conditions may be required. Assist in oversight or escort for contractors on repair projects, as required. Provide set-up and tear-down labor support to indoor and outdoor events furniture (table, chairs, etc) configurations as required.

5.1.4.1 The contractor shall deliver supporting services to the U.S. Government S4 Division in a broad range of sub-areas associated with space management, to include equipment/personnel relocations; coordination for all room-alteration projects for NGIC; events and special functions setup; space utilization support services for the coordination and implementation of short and long range work space construction and renovation projects; and surge support to inventory management functions. The contractor shall provide direct support services to the planning, inventory scheduling and execution of NGIC space management operations. The contractor shall also evaluate existing workstations, components, and furniture and make repair or replacement recommendations to the USG.

5.1.4.2 The contractor shall provide furniture and workstation assembly, installation, disassembly, minor repairs and alterations within the areas on Rivanna Station owned or leased by NGIC. The contractor shall perform this work for small furniture projects. A small project is defined as a

project affecting fifteen (15) or fewer workstations or offices at a time. Small project work shall include the following services:

(a) Assembly, installation and disassembly of modular, systems and free-standing furniture, furniture components and accessories, including the electrical work to install powered furniture and panels.
(b) Minor furniture and fabric/upholstery cleaning.
(c) Configuration, reconfiguration, alteration and repair of modular, systems and freestanding furniture.
(d) On-site/in-house delivery of furniture from the NGIC warehouse.
(e) Crating and uncrating products either on-site or at the NGIC warehouse

5.1.4.3 The USG shall provide all parts and materials required by the contractor to assemble or repair workstations and furniture.

5.1.4.4 The contractor shall schedule and provide services for workstation component inventory; key & lock inventory and issue; chair and furniture inventory, issue, turn-in, and minor adjustments; workforce furniture use instructions and demonstrations. The contractor shall comply with all applicable guidance as included in references provided at PWS section 6.0 Applicable Publications, and in all NGIC or S4 SOPs.

5.1.5 Events and Special Functions: The contractor shall provide for furniture moving; auditorium, divider and chair set-up for special functions on Rivanna Station. The COR and Logisitcs personnel will coordinate with the contractor on a weekly basis to provide a detailed schedule, layout diagram, and additional transportation requirements for upcoming events. The COR and Logisitcs personnel will provide no less than 24 hours notice of any alterations to the events and special functions schedule. The contractor shall comply with all applicable guidance as included in references provided in section 6.0 Applicable Publications and all NGIC or S4 SOPs.

5.1.6 Maintenance Management. The Contractor shall plan, program, coordinate, estimate, respond to Government schedule, and evaluate resources for work requests approved by the COR for performance by the Contractor. In conjunction with these functions, the Contractor shall prepare, input, and maintain Contractor- generated data in the government provided or approved work management system/s databases. Contractor data shall include operational data to provide complete and accurate outputs/reports required herein. Work management shall include maintaining a suspense system with appropriate registers and files, and routing and distributing reports related to services and deliverables required within this contract.

5.1.7 Supervision. The Contractor shall have a contract manager with authority to provide sufficient labor, materials and equipment in accordance with requirements of this contract and to act on the Contractor's behalf. At minimum, the Contractor's contract manager or alternate contract manager shall be available during normal working hours and shall be physically available to the Contracting Officer or designated government representative within one (1) hours during normal working hours. Instruction given by the Contracting Officer or designated representative to the Contractor's contract manager or alternate shall be considered to have been given directly to the Contractor.

5.1.8 Maintenance Service Order Log. The computerized maintenance management system (CMMS) constitutes the Service Order Log. The Contractor shall maintain the status of all Service Orders (Level-II Maintenance & Repairs) received and responded to and retain one copy of the annotated original printed Service Order for a minimum period of twelve months. The Contractor shall deliver to the Government a complete electronic copy of the entire service order database at the conclusion of each contract period of performance.

5.1.9 Service Order (SO) Process. Service Orders will be generated by customer requirements received in-person, via email, phone or other method provided by the Government, and the Contractor shall enter each SO into the CMMS, to include a work priority, and all work detail until the SO is completed or closed by

the Contractor. When the Contractor identifies work for service orders, the Contractor shall enter relevant details into the CMMS with the Contractor's Customer ID.

5.1.10 Schedules. The Contractor shall schedule, control, and perform all work described herein in accordance with all terms and conditions contained in the contract. The Contractor shall develop and provide plans and schedules to include a Level I operation and maintenance schedule for daily, weekly, biweekly, monthly, quarterly, semi-annual, and annual, start-up and shutdown work. The Contractor's schedule shall be divided by functional area and Bid Line Items. Since LEVEL-II (Service Order) Maintenance Service Order work occurs sparadically, it need not be individually scheduled. However the Contractor shall indicate the estimated number of hours expected to be expended against Service Orders each month. The Contractor shall keep the schedules current. Work shall be scheduled by the 21st day of each month and provided to the Government in an MS Excel or similar COR approved format electronically and in paper copy.

5.1.11 Records And Reports. Complete and accurate operating, maintenance, and repair records of all work shall be maintained by the Contractor in accordance with AR 25-400-2 and as otherwise specified in the contract. The Contractor shall provide and comment upon a written weekly progress report submitted at the weekly contract meeting with the Facility Management team.

5.1.12 Work Order Files. The Contractor shall maintain individual Work Order files on each active Work Order, regardless of maintenance level. The Contractor shall retain the all Work Order files for five (5) years and shall make these files available for the COR's review. All forms submitted shall be accurately filled out showing actual start and completion dates, total labor hours expended, and cost of equipment and materials utilized. Copies of any material receipts, letters of authorization, sales slips, invoices, etc., relating to the job order shall be retained by the Contractor in the equipment/facility file as a maintenance and repair history. The Contractor shall provide the COR access to the Contractor maintained files during the term of the contract. All files are the property of the Government and shall be turned over to the Government upon completion or termination of the contract.

5.1.13 Filing. The Contractor shall maintain and retain files in accordance with AR 25-400- 18 Nov 22 86, Appendix B, AR 420-1.

5.1.14 Operating Files and Logs. The Contractor shall maintain operating logs and an operating log file on equipment. The Contractor shall use standard Government forms, charts, and logs as described and referenced herein. The Contractor shall maintain operating logs for a minimum of two years unless otherwise specified herein and these documents shall be available for COR review. All operating files and logs shall be turned over to the Government upon contract completion or termination.

5.1.15 Manufacturer's Manuals. The Contractor shall obtain electronic copies of manufacturer's manuals on all new equipment installed by the Contractor. The Contractor shall notify the Government of the electronic file location. These manuals and operating instructions shall become the property of the Government at the expiration or termination of the contract.

5.1.16 Input/Updates To Facility As-Built Drawings. The Contractor shall provide maintenance and repair related updates (red-lines) for facility as-built drawings to the government or other designated service provider responsible for the drawings maintenance as part of the services under the contract. All utility repairs, component replacements, modifications, alterations, and additions to all systems and components shall be electronically redlined as well as submitted for notation to the hard copy drawings upon completion of work. The Contractor shall redline annotate all components replaced during the period of the contract and annotate all items removed from service. Hard copy markups and electronic redlines shall be delivered to the Government at the completion of each major project as identified by the Government, or quarterly. The contractor shall submit ALL changes from contractor maintenance or repairs performed for integration into the master data set of as-built drawings maintained for the Government. The Contractor shall validate all drawings for accuracy and content. All electronic data and hard copy products remain the property of the Government and shall be turned over to the Government upon the completion of the contract.

5.1.17 Operations and Maintenance (O&M) Manuals and Job Specifications. The Contractor shall be responsible for maintaining and updating O&M manuals and project specifications as part of the services under this contract. Operating manuals and specifications shall be filed, indexed, and cross referenced to corresponding project plans and as-built drawings in the drawing files.

5.1.18 General Maintenance and Repair. The Contractor shall perform all work required by the Contract to maintain and provide services to the NGIC Nicholson Building and NGIC Boulders 1 lease space and other NGIC-occupied facilities or areas within the Rivanna Station vicinity for Work Levels I and II as defined below. The Contractor shall perform general maintenance and repair work in all functional areas described below.

5.1.19 Level I Preventive Maintenance (PM) Scheduling. Within thirty (30) calendar days after contract award, and prior to the start of work, the Contractor shall submit to the COR, for approval, a detailed PM schedule for all functional areas specified in this PWS. The schedule shall clearly differentiate between each functional area and shall reference the specific equipment item being maintained by equipment identification number or building number, equipment name and equipment location. The PM program shall be executed in compliance with the checkpoints identified in each functional area of the specification. Lists of equipment to be maintained are provided with each functional area description. Work on this contract shall not commence until this schedule has been approved. The program shall be designed to minimize future repair requirements and to keep each system or component operating properly. Due to operational requirements, the schedule shall be subject to change or revision at any time during the contract as directed by the COR. If a schedule change is to take place, the Government will notify the Contractor at least five (5) working days prior to the change. The Contractor shall adhere strictly to the scheduled PM dates to facilitate Government verification inspections. If the Contractor finds it necessary to reschedule a PM, a formal written or email request shall be made to the COR detailing the reasons for the request at least five working days prior to the originally scheduled PM date. No scheduled PM dates shall be changed without prior approval of the Facility Engineer or COR. All PM services are provided under the Level I portion of the contract.

5.1.20 Preventive Maintenance (PM) Records. The Contractor shall maintain PM records. Sample forms for documenting the PM shall be submitted within fifteen (15) calendar days of contract award to the COR for approval. These records shall be available to the COR upon request and shall be provided to the Government upon expiration/ termination of this contract.

5.1.21 PM After Action Reports. After a PM inspection is made, the Contractor employee performing the PM shall make all required entries in the CMMS for each PM action performed.

5.1.22 Defects or Deficiencies. Defects or deficiencies identified but not corrected by the Contractor during a scheduled PM shall be written up and submitted to the COR within three (3) working days of completion of the PM for correction through Service Order or appropriate Level of work. The COR will approve or disapprove the work. If approved, the Contractor shall proceed under Service Order or approved level of work.

5.1.23 Equipment Replacement (Government Property). If an item of Government property is determined by the Contractor to be beyond economical repair, the Contractor shall recommend to the COR in writing (see section 5.1.20) that such equipment be replaced. Substantiating data to support the recommended replacement shall be included. If the Government decides that such equipment should be replaced or repaired, and replacement or repair is authorized, the Contractor shall accomplish the work in accordance with the appropriate work level criteria. Disposal instructions will be provided by the COR.

5.1.24 New Equipment Documentation. The Contractor shall provide justification documents with recommendations to purchase new or replacement equipment (Government property). The Contractor's justification shall comply with the FAR and shall include the following information:

-Minimum two quotes in addition to Contractor’s own quote

-The age (purchase date) and original cost of the equipment recommended for replacement.
-Maintenance Control Designator (MCD).
-Cost Benefit Analysis (repair vs. replace)
-The rationale for replacement rather than repair.
-Whether or not the new equipment will fit into the existing/available space, perform the required function, and operate on available installed utility services.
-Facility Engineer Work Request (DA Form 4283).

5.1.25 Salvage. The Government retains all salvage rights to replaced property of value. The Government will determine the value of the property. Items of no value shall be disposed of at the Contractor's expense. For items of value, and for all Government equipment regardless of value, the Contractor shall prepare DD Form 1348-1 for property disposal.

5.2. FACILITY MAINTENANCE RECORDS SERVICES - General. The Contractor shall provide administrative support to organize and manage plans, programs, reports, and files established under US Army Regulation 210-20.

5.2.1 Level I – Preventive Maintenance - The Contractor shall provide related data resulting from routine maintenance (PM), repairs and equipment replacement performed by the contractor to the S4/Logistics designated persons or office charged with maintaining all Real Property Master Planning electronic and hardcopy files, drawings, documents, professional facility studies, and related publications maintained in the NGIC S4/Logistics office IAW established Army and Professional Architectural Institute standards and systems to include; HQDA, MACOM, MSC, and IMA plans, existing condition (as-built) plans, Real Property Inventory, Resource Management Plans, Natural Resource Management Plans, Cultural Resource Management Plans, Environmental Resource Management Plans, Utility Systems studies and plans, Critical Infrastructure Protection and Force Protection Plans, Information Systems and Plant-in-Place Management Plans, Army Installation Status Reports (ISR), Annual Inspection and Maintenance Plans and Schedules, Meeting Memoranda, Briefings, and Notes from coordination with Army HQ, units, organizations, and other planning agencies; garrison, unit, or tenant activity plans and initiatives (for example; Installation Strategic Plans, Community Activity Plans, etc.)

5.2.1.1 The Contractor shall organize and file materials IAW AR 25-400-2 and The American Institute of Architects Standards (AIA). File organization shall include indexing systems which allow authorized personnel to reasonably obtain information on a self-help basis. Self-help access to files will be limited to NGIC facility and logistics staff. Index lists shall provide sufficient data to determine the project description, date, origin, association with Master Plans and phased projects, and cross reference to all deliverables in the original project package including warranties. The Contractor shall retrieve, provide, and return files upon request by authorized Army requestors (requestors designated by NGIC Logistics Chief). The Contractor shall provide filing, copy, and data formatting services as requested.

5.3 FOOD SERVICES EQUIPMENT (NGIC Occupied Buildings). The Contractor shall provide all work and services required to maintain equipment safety, cleanliness and satisfactory operating functions, install, remove and/or repair as applicable, dining facility and food service related equipment in all NGIC buildings or spaces, to include the commercial kitchen, Nicholson kitchenettes on floors one through five, Command area kitchenette, D-wing and similar equipment located in food use areas in any NGIC leased or storage facility. The terms dining facility and food service include items supporting the storage, preparation and processing, serving and disposal of foods and beverages. Contractor work and responsibility shall include inspecting, coordination with user, installing and repairing food service, and all related services necessary to efficiently maintain and repair the equipment. The NGIC food services equipment to be included is listed in Section J Attachment 1 “List of Equipment to be Maintained”. PM described in this section shall be included in the Firm Fixed Price (FFP) basic contract services. All incidental supplies and materials required to deliver these specified services shall be included in the FFP cost for this service category.

5.3.1 Level I Preventive Maintenance - Food Service operations have a direct affect upon the health, safety, welfare, morale, etc., of personnel using the food service facilities. The Contractor shall maintain and repair

cooking equipment in a manner which precludes any deterioration of food service operations caused by inoperable food service equipment per Section J Attachment 1.

5.3.1.1 Contractor Response. The Contractor shall respond within one hour to calls of non-operative or malfunctioning kitchen equipment. Repairs for major kitchen appliances shall be completed or scheduled for repair within four hours, and shall be restored to fully operational status within three work days.

5.3.1.2 Equipment Replacement. Food service equipment is subject to repair limits as specified in appropriate documents. If an item is determined by the Contractor to be beyond economical repair, the Contractor shall recommend to the Government in writing that such equipment be replaced in accordance with section 5.1.7.

5.3.1.3 Equipment Familiarization. The Contractor shall provide limited on-site orientation, operator care, safety, and routine maintenance familiarization to food service staff for each existing or equipment newly installed by the Contractor. Approximately three to five personnel will require training each occurrence.

5.3.1.4 Calibration. The Contractor shall calibrate all thermostatically controlled kitchen equipment, in accordance with manufacturer's instructions, as an element of PM. All calibrated equipment shall be within calibration dates. Results will be recorded and reported IAW section 5.1.8.

5.3.1.5 Minor repairs including, but not limited to, tightening loose fittings/nuts/bolts/screws, tightening loose electrical connections, and the reinstallation of handles and knobs shall be performed as part of preventive maintenance. All lubricants, refrigerants, filters, belts, fittings, indicator light bulbs, and fasteners are to be provided by the Contractor as part of the preventive maintenance requirement. The Contractor shall report, in writing, all deficiencies beyond the scope of preventive maintenance to the COR on the next workday following PM actions taken.

5.3.2 Level II Service Order Maintenance. The Contractor shall perform Service Orders for maintenance and repairs of Nicholson Bldg Food Services and commercial Kitchen Equipment in compliance with sections 5.1.2 of this contract.

5.3.3 Level III High Dollar Value (HDV) Maintenance and Projects. The Contractor shall perform HDV maintenance, repair, and associated services on Nicholson Bldg Dining Facility systems and equipment as ordered under High Dollar Value (HDV)) Maintenance requests and defined in PWS section 5.1.3.

5.3.4 Equipment Replacement Criteria. The Government will determine serviceability and reparability of equipment. The Contractor shall repair and if required, install replacement ranges, ovens, deep fryers, dishwashers, refrigerators, freezers or other large appliances on the same Service Order that initiated the action if replacement costs are within service order limits. If not within service order limits, the Contractor shall replace equipment as specified under Level-III HDV maintenance.

5.3.5 Installation and Removal of Food Service Equipment. When ordered under Projects Level-II (Service Order) Maintenance or Level III High Dollar Value (HDV) Maintenance and projects, the Contractor shall install and remove food service equipment in a manner compliant with all local building and safety codes including NFPA standard 96. All replaced parts and salvageable items shall be disposed of in accordance with disposition instructions from the COR.

5.3.6 New Equipment Characteristics. The Contractor shall ensure that new equipment has the correct utilities characteristics for available electrical circuits, gas, and water services prior to installation of any new equipment.

5.3.7 Installation of New Equipment: The Contractor shall assemble, install and commission new equipment according to the manufacturer's instructions for preparation and installation. When completed, no leakage shall occur and all doors will open easily and have a tight fit. Unit shall be level and all assembly bolts tight. The Contractor shall retain and file all operator and service manuals for installed equipment as described in PWS sections. 5.1.9, 5.1.10 and 5.1.12.

5.3.8 Utility Connection: The Contractor shall install new food service equipment, as required, connecting equipment with utility service as necessary. All electrically operated equipment shall be grounded. Caution should be exercised when working at wet/damp locations. Ground fault interrupters shall be installed where wet conditions could cause shock hazard.

5.3.9 Shutdown. The Contractor shall perform shutdown services, as necessary, to protect equipment that is to be inactivated or placed on standby use and to conserve materials. Work shall include inspecting and servicing equipment, as necessary, to ensure it is properly secure, protected against deterioration, and in stable condition.

5.4 PHYSICAL FITNESS EQUIPMENT MAINTENANCE - Perform Preventive Maintenance of Fitness Equipment in the Nicholson Building. The Contractor shall perform preventive maintenance of the equipment listed in PWS (see attached List of Equipment to be maintained). Minor repairs, including, but not limited to tightening loose nuts/bolts/screws/seats/covers, tightening loose electrical connections, and the reinstallation of handles, knobs, and accessories shall be performed as part of preventive maintenance. All lubricants, belts (including trend mill belts), fittings, indicator light bulbs, controls, and fasteners are to be provided by the Contractor as part of the preventive maintenance requirement. The Contractor shall report, in writing, all deficiencies beyond the scope of preventive maintenance to the COR on the next workday. PM described in this section shall be included in the Firm Fixed Price (FFP) basic contract services. All incidental supplies and materials required to deliver these specified services shall be included in the FFP cost for this service category.

5.4.1 Level I Preventive Maintenance - The Contractor shall conduct and inform the government of cost comparison of sustainment of equipment versus replacement of physical fitness equipment and major components.

5.4.1.1 Equipment Replacement. Fitness equipment is subject to repair limits as specified in appropriate documents. If an item is determined by the Contractor to be beyond economical repair, the Contractor shall recommend to the Government in writing that such equipment be replaced in accordance with sections 5.1.20 and 5.1.2.

5.4.1.2 Sustain, test, and inspect all government owned physical fitness equipment. The Contractor shall develop testing and inspection schedules for each type of equipment in the Nicholson Building Fitness Center in such a manner to keep equipment safely operating at all times.

5.4.2 Level-II (Service Order) Maintenance: The Contractor shall perform Service Orders on Rivanna Station fitness Equipment in compliance with sections 5.1.2 of this contract.

5.4.3 Level III High Dollar Value (HDV) Maintenance and Projects. The Contractor shall perform maintenance, repair, and associated services on Rivanna Station fitness equipment under this contract as defined under High Dollar Value (HDV) Maintenance requests, section 5.1.8.

5.4.4 Equipment Replacement Criteria. The Government will determine serviceability and reparability of equipment. The Contractor shall repair and if required, install replacement on the same Service Order that initiated the action if replacement costs are within service order limits. If not within service order limits, the Contractor shall replace equipment as specified under HDV maintenance.

5.4.5 Installation and Removal of Fitness Equipment. When ordered under Level II Service Orders and Level III High Dollar Value (HDV) Maintenance and Projects, the Contractor shall install and remove equipment in a manner compliant with all local building and safety codes including NFPA standard 96. All replaced parts and salvageable or salable items shall be disposed of through the NGIC S4 and in accordance with any disposition instructions from the COR.

5.4.6 Installation of New Equipment. The Contractor shall assemble and install new equipment according to the manufacturer's instructions for preparation and installation. When completed, equipment will be fully operational.

5.5 GENERAL MISSION MAINTENANCE SUPPORT SERVICES. This work category typically shall be performed as Preventive Maintenance Services and General Maintenance support. The Contractor shall schedule operational maintenance and support work in the Nicholson and Boulders 1 Buildings and other NGIC-occupied facilities with the COR to coordinate dates and times to gain access to affected work spaces. Work involves short suspense general maintenance and operational support tasks required continually to maintain a fully functioning and professional office and quality of life environment inside the Nicholson Building. Work includes support for the normal operational expansion of IT network systems within the building as personnel and activities change. Work also provides for contingency support operations to manage utility interruptions, facilitate quick recovery and repairs, prevent further escalation, or stabilize conditions until permanent repairs can be planned and coordinated. Contractor shall provide services as follows without additional costs to the government. The painting requirements exceed 200 square feet which requires compliance with Federal Acquisition Regulation (FAR) contract clauses 52.222-6, Construction Wage Rate Requirements and 52.222-11, Subcontracts (Labor Standards).

5.5.1 General Maintenance including but not limited to carpentry, painting, concrete, drywall, door hardware, or various ceiling and flooring systems. Repair and change locks in the building and perform complex lock servicing to ensure maximum safety of all people. Responsible for the disassembly, movement, reassembly, and installation of facility furnishings to include furniture and furniture systems. Support shall be included in the Firm Fixed Price (FFP) basic contract services. All incidental supplies and materials required to deliver these specified services, contractor shall provide a quote for materials only. For painting, all surfaces shall be patched and finished smooth and one coat of surface appropriate paint applied to match existing color and finish as closely as possible. Patched areas shall receive a second coat to insure coverage.

5.5.1. The Contractor shall remove or install wall hangings (pictures, plaques, white boards, etc.) within offices or work areas in the Nicholson and Boulders 1 Buildings and other NGIC-occupied facilities. The Contractor shall patch all damaged walls, partitions, prime, and paint to match. Hardware for wall hangings shall be well suited for the surface, sufficiently strong, and provide a neat finished appearance.

5.5.2 Rolling File Maintenance (library storage system). The Contractor shall provide inspection and maintenance services for rolling library files in room A3038. This work category typically shall be performed as level-I Preventive Maintenance Services.

5.5.2.1 Level-I Preventive Maintenance shall include bi-annual inspection, grease and lubricants, minor hardware, adjustments, and calibrations required for shelving to operate IAW the manufacturer’s specifications. Shelving tracks shall be included in maintenance routines. The Contractor shall provide a report of all level-II repairs performed and any items exceeding the service order dollar limit.

5.6 MISSION EQUIPMENT MAINTENANCE SUPPORT: The services described in this category typically shall be performed as Preventive Maintenance Services.

5.6.1 Material Handling Equipment (MHE) and Powered Sweepers. Perform Level I Preventive Maintenance on all powered and mechanical MHE and all powered sweepers IAW product manufacturer specifications and in support of NGIC operator/user requirements.

5.6.2 Powered Mobility Equipment (Scooters). Perform Level I Preventive Maintenance IAW product manufacturer specifications and in support of NGIC operator/user requirements.

5.6.3 Exterior Patio Furniture. The Contractor shall schedule and provide routine Level I Preventive Maintenance care for exterior metal dining/patio furniture (chairs, tables & umbrellas) identified in Section J Attachment 2 List of Equipment to be Maintained, to include minor corrosion control, lubrication of

moving umbrella limb components and other OEM metal and fabric component care recommendations on a scheduled monthly recurring basis.

5.6.4 Disintegrator System Operation & Maintenance: The Contractor shall operate, inspect, test, perform operator-level maintenance (PM), and sustain the NGIC disintegrator system located in the Nicholson Building. The Contractor shall ensure all operator checks and services, diagnostic testing, calibrations, repairs and regular preventive maintenance is performed IAW the unit manufacturer's operations manual and OEM maintenance instructions. Blades shall be sharpened every four months to the manufacturer's exact specifications. Two complete blade sets shall be maintained at all times, one in operation and one sharpened and stored. Contractor shall notify the COR when blades are ready for replacement. Blades shall be replaced as level III HDV maintenance. The Contractor shall provide fully cleared operators after normal duty hours to destroy NGIC classified waste. Document destruction (operating the machine) currently averages about 20 hours a week for a single worker. In addition, the Contractor shall provide services for agency clean-out days which requires 40 hours a week of document destruction service for a single worker bi-annually. The Contractor shall operate, maintain, and repair all components of the system and dispose of debris off site regularly without build up and without assistance from the government. The Contractor shall fully comply with air particulate standards enforced by Ft Belvoir Environmental and participate in air sampling.

5.6.5 Portable Shredders: The Contractor shall schedule and conduct at least monthly PM, operate, inspect, test, and maintain - all portable shredder equipment, as included in Section J Attachment 1 List of Equipment to be Maintained and currently located in both the Nicholson and BOULDERS 1 buildings. The Contractor shall ensure all diagnostic testing, calibrations, repairs and regular preventive maintenance (PM) is performed IAW the unit manufacturer's operations manual and maintenance instructions, and shall provide a report IAW the contract deliverables schedule.

5.6.6 High Dollar Value (HDV) Maintenance and Projects. The Contractor shall perform maintenance, repair, or life cycle replacement and associated services on all listed mission systems and equipment in NGIC occupied facilities as ordered under HDV maintenance requests, and as described in section 5.1. 3.

5.6.7 Outage Operational Support: The Contractor shall provide "Operator Support" during non-duty hours for up to four events averaging 16 hours for each event. The intent is for the Contractor to maintain operational control over critical Nicholson and Boulders 1 Building systems, which could impact mission systems or SCIF security. Support provides, as a minimum, PM Supervision of the activity, and electrical support to items maintained by contract. No additional equipment or materials, other than those normally maintained by the Contractor shall be required to perform this service. The actual maintenance work may or may not be "by others".

5.7 CUSTODIAL SERVICES, NICHOLSON AND BOULDERS 1 BUILDINGS (NGIC) and Warehouse

5.7.1 Preventive Maintenance Services: Support shall be included in the Firm Fixed Price (FFP) basic contract services. All incidental supplies and materials required to deliver these specified services shall be included in the FFP cost for this service category.

5.7.1.1 The Contractor shall provide PM janitorial services for the Nicholson Building and for Leased Building Boulders 1 (Lobby, Basement, and floors 2, 3, 4) at frequencies specified in Section J Attachment 2, Cleaning & Custodial Tasks & Frequency of Services. Custodial vacuuming of individual work areas shall be done outside core hours. Any custodial services requested for leased off-site warehouse and remote delivery facility (RDF) will be performed only when requested and approved as a level-II or level-III funded action. All cleaning services under this section shall be performed in accordance with the latest editions of the Green Seal Environmental Standard for Cleaning Services GS-42 and ASTM E 1971-05 Standard Guide for Stewardship for the Cleaning of Commercial and Institutional Buildings.

5.7.1.2 The Contractor shall perform heavy cleaning of tile floor surfaces of the cafeteria, kitchen, and related food service spaces quarterly, per standards of the current version of Technical Bulletin (TB) Med-530 Tri-Service Food Code, and as further specified in PWS attachment 3, Special Areas Cleaning Services

22-1. This work category typically shall be performed as Preventive Maintenance Services and included in the Firm Fixed Price PM services.

5.7.1.3 The Contractor shall, as specified in PWS attachment 2, Special Cleaning item 21-1, provide bi-monthly “top-down” scrubbing of all surfaces in the cafeteria, kitchen and related food service spaces. The Contractor shall provide their plan for tasks to include in top-down cleaning for government review and approval. The Contractor shall coordinate the cleaning schedule with the kitchen operator and the IMCOM BASOPS contractor to avoid scheduling conflicting dates or times, and with the food services COR prior to accomplishing the service.

5.7.1.4 Window/Glazing Cleaning Services: (Nicholson Building Only) The Contractor shall maintain both surfaces of all building window glass, or glazing, in a reasonably clean state free of smudges, fingerprints, oily film, cobwebs, dust, streaks, water marks, and all other types of soilage. This requirement applies to both exterior (exterior wall) and interior glazing (office windows, door glass, and similar glazing).

5.7.1.5 The contractor shall perform Exterior window cleaning annually, dependent upon weather or environmental conditions. Additional window cleanings may be requested and approved as a HDV maintenance action. This work category typically shall be performed as level-I Preventive Maintenance Services and included in the Firm Fixed Price PM services.

5.7.1.6 Low height interior glazing such as doors, sidelights, railings, and similar glazing exposed to frequent soilage shall be cleaned on a weekly basis as a minimum.

5.7.1.7 Interior office glazing shall be cleaned, as a minimum, semi-annually or on an “as needed” basis with the approval of the COR or his designated representative.

5.7.1.8 High height interior glazing such as transoms, clerestory, glazing over the Nicholson Building Central Monitoring Station (CMS,), and the “humanly accessible” windows/glazing shall be cleaned quarterly as a minimum.

5.7.1.9 The “humanly inaccessible” side of interior curtain walls more than one story in height, as a minimum, shall be cleaned semi-annually.

5.7.1.10 Interior Light Fixture, High Cleaning. At least once annually all interior lighting fixtures shall be vacuumed/dusted/cleaned to prevent accumulation of dust, bugs or other air-borne debris.

5.7.1.11 Suspended, open top light fixtures shall be cleaned at least once annually in a manner which removes the maximum amount of accumulated debris from the fixture.

5.7.1.12 Enclosed light fixtures shall be cleaned in combination or deferred to coincide with other scheduled fixture preventive maintenance or repairs which require fixture disassembly in both the Nicholson and Boulders 1 buildings.

5.7.1.13 Trash Removal: (Nicholson and Boulders 1 Buildings) The Contractor shall insure that all occupied facilities are maintained in as high of a trash-free state as possible. Special emphasis shall be placed on high trash generating areas such as auditoriums, conference rooms, IWA rooms, individual floor kitchenettes, break rooms and other common areas. As a minimum, trash receptacles within the Nicholson and Boulders 1 Buildings shall be removed and emptied on a daily basis after 1400 each day. Trash also shall be deposited in the nearest external dumpster trash container(s) for pickup and removal from the site. The trash removal requirement applies to designated recyclable materials which shall be deposited in designated containers for recycling. Recycle containers inside the building are GFE. The Contractor shall utilize Government provided external collection containers for both common recycle materials and universal waste materials.

5.7.1.14 The Contractor shall clean all interior flooring, walls and partitions, cubical panels, sinks and water coolers, kitchenettes, microwaves, refridgerators, restrooms, fitness center lockers, showers, and

benches, furniture, shelving, blinds, wall hangings, fixtures, door hardware, casework, hand railing, stairs, fitness center equipment, wheel chairs (GFE), scooters (GFE), grounds, and mechanical rooms at frequencies specified in Section J Attachment 2, Cleaning & Custodial Tasks & Frequency of Services.

5.7.1.15 Special Events: A special event is defined as a large meeting, workshop or similar activity at an NGIC facility attended by visitors in addition to the NGIC workforce. Special events are typically scheduled well in advance, and the government will provide the contractor at least 5 days advance notice of and coordinate support for the activity. The Contractor shall provide peak demand restroom and cleaning supplies for an estimated 12,000 annual visitors to the Nicholson Building at no additional cost to the government. Contractor shall provide cleaning services after specified core hours for special events (normally involving food and drinks) to include trash collection and removal, cleaning carpets and resilient flooring, and cleaning tables and furniture.

5.7.1.16 The Contractor shall provide emergency call response to clean up common spills (example – food or drink), bio-hazard spills (example –toilet overflows), or blood borne pathogen hazard (example – employee gets a cut) in the building. The Contractor shall provide or verify that all contract cleaning personnel responding to clean up a blood borne pathogen hazard have been fully trained in blood borne pathogen personnel protection and cleanup processes (annual training). The contractor Emergency response shall include any required heavy clean up, stain removal, or sanitizing services required to achieve thorough cleaning, sanitizing, and a neat finished appearance.

5.7.1.17 The Contractor shall schedule and provide services for minor furniture and upholstery cleaning to include of fabric and resilient surfaces. The Contractor shall provide specification and MSDS sheets for all contractor recommended cleaning products and processes to the COR and NGIC Safety Office for review and approval prior to starting work.

5.7.1.18 The Contractor shall schedule and provide routine custodial care for exterior metal dining/patio furniture, to include cleaning and sanitizing top surfaces on a scheduled periodic basis.

5.7.1.19 The Contractor shall provide limited custodial services and trash removal for the NGIC designated smoking shelter. The contractor shall remove waste from government provided trash can(s) and government provided cigarette receptacle(s) only.

5.7.1.20 The Contractor shall clean all internal HVAC Air Supply vents in the Nicholson and Boulders 1 leased building semi-annually. Contractor shall ensure all dust and dirt are cleaned off vents.

5.7.2 Data Center Custodial (Nicholson & Boulders 1 Buildings) The CCER clean-room standard custodial services typically shall be performed as Preventive Maintenance Services. Support shall be included in the Firm Fixed Price (FFP) basic contract services. All incidental supplies and materials required to deliver these specified services shall be included in the FFP cost for this service category.

5.7.2.1 Level 1 Preventive Maintenance Work. The Contractor shall provide all personnel, equipment, tools, expendable supplies, materials and other items necessary to perform specialized custodial services (per current standards list at website www.adccp.org) to areas designated by the Government as Class 8 clean room areas, and shall deliver services as described in Section J, Attachment 3, Clean Room Tasks & Frequency of Services & Training for Nicholson Building Computer and Communications Equipment Rooms.

5.8. CONTRACTOR MANPOWER REPORTING (CMR) :The Office of the Assistant Secretary of the Army (Manpower & Reserve Affairs) operates and maintains a secure Army data collection site where the Contractor shall report ALL Contractor manpower (including subcontractor manpower) required for performance of this contract. The Contractor shall completely fill in all the information in the format using the following web address https://Contractormanpower.army.pentagon.mil. The required information includes: (1) Contracting Office, Contracting Officer, Contracting Officer's Technical Representative (COTR) or also know as the Contracting Officer's Representative (COR); (2) Contract number, including task and delivery order number; (3) Beginning and ending dates covered by reporting period; (4)

Contractor's name, address, phone number, e-mail address, identity of Contractor employee entering data; (5) Estimated direct labor hours (including sub-Contractors); (6) Estimated direct labor dollars paid this reporting period (including sub-Contractors); (7) Total payments (including sub-Contractors); (8) Predominant Federal Service Code (FSC) reflecting services provided by Contractor (and separate predominant FSC for each sub-Contractor if different); (9) Estimated data collection cost; (10) Organizational title associated with the Unit Identification Code (UIC) for the Army Requiring Activity (the Army Requiring Activity is responsible for providing the Contractor with its UIC for the purposes of reporting this information); (11) Locations where Contractor and sub-Contractors perform the work (specified by zip code in the United States and nearest city, country, when in an overseas location, using standardized nomenclature provided on website); (12) Presence of deployment or contingency contract language; and (13) Number of Contractor and sub-Contractor employees deployed in theater this reporting period (by country). As part of its submission, the Contractor shall provide the estimated total cost (if any) incurred to comply with this reporting requirement. Reporting period shall be the period of performance not to exceed 12 months ending September 30 of each government fiscal year and must be reported by 31 October of each calendar year. Contractors may use a direct XML data transfer to the database server or fill in the fields on the website. The XML direct transfer is a format for transferring files from a Contractor’s system to the secure website without the need for separate data entries for each required data element at the website. The specific formats for the XML direct transfer may be downloaded from the website.

PART 6
APPLICABLE PUBLICATIONS

6. **APPLICABLE PUBLICATIONS (CURRENT EDITIONS)**:

6.1. The Contractor must abide by all applicable regulations, publications, manuals, and local policies and procedures.

6.1.1 PROGRAM MANAGEMENT:
• AR 420-1 Army Facilities Management

• AR 200-1 Environmental Protection and Enhancement

• DA Pamphlet 420-11 Project Definition and Work Classification

6.1.2 PROPERTY MANAGEMENT :
• DoD Guidebook for Contarct Property Administration

• DoD 7000.14-R, DoD Financial Management Regulation, Volume 12, Chapter 14, Transferring, Disposing, and Leasing of Real Property and Personal Property

• DoD 7000.14-R, DoD Financial Management Regulation, Volume 12, Chapter 7, Financial Liability for Government Property Lost, Damaged, or Destroyed

• DoD 7000.14-R, DoD Financial Management Regulation, Volume 4, Chapter 24, Real Property

• DoD 7000.14-R, DoD Financial Management Regulation, Volume 4, Chapter 25, General Equipment

• DoD 7000.14-R, DoD Financial Management Regulation, Volume 4, Chapter 26, Accounting for Leases

• DoD 7000.14-R, DoD Financial Management Regulation, Volume 4, Chapter 27, Internal Use Software

• Accountable Property System of Record (APSR)

6.1.3 ENVIRONMENTAL SAFETY AND OCCUPATIONAL HEALTH SUPPORT SERVICES
• 9 VAC 25-91-10- et seq “Facility and Aboveground Storage Tank Regulation,” Virginia Department of Environmental Quality (VDEQ) Water Division
• 9 VAC 5, Chapter 40, Part II, Article 1, Visible Emissions and Fugitive Dust/Emissions

• 9 VAC 5, Chapter 130, Regulations for Open Burning

• 9 VAC 5, Chapter 45, Consumer and Commercial Products

• ACGIH – Threshold Limit Value

• ANSI Standard S1.4, Specifications for Sound Level Meters

• ANSI Standard Z358.1-2014 (R2020), Emergency Eyewash and Shower Equipment

• ASTM F2413, Protective Footwear, Personal Protection

• Clean Air Act (CAA) of 1963 as codified in Title 42 USC, Chapter 85

• Clean Water Act (CWA) of 1977 as codified in Title 33 USC, Chapter 26

• HQ INSCOM Environmental Compliance Notebook

• HQ INSCOM Facilities Handbook

• DoD Directive 4715.1E, Environment Safety and Occupational Health

• DoD Instruction 4715.03, Natural Resources Management

• DoD Instruction 4715.23, Integrated Recycling and Solid Waste Management

• DoD Instruction 4715.6, Environmental Compliancein the United States

• 32 CFR Part 651 Environmental Analysis of Army Actions

• DoD Instruction 6050.5, DoD Hazard Communications Program

• DoD Instruction 6055.01, DoD Safety and Occupational Health (SOH) Program

• DoD Instruction 6055.05, Occupational and Environmental Health (OEH)

• DoD Instruction 6055.6, DoD Fire and Emergency Services Program

• DoD Instruction 6055.7, Mishap Investigation, Reporting, and Recordkeeping

• Emergency Planning and Community Right-To-Know Act (EPCRA)

• Energy Policy Act of 1992 as codified in Title 42 USC, Chapter 134

• Executive Order 11514, Protection and Enhancement of Environmental Quality

• Executive Order 12088, Federal Compliance with Pollution Control Standards

• Federal Facilities Compliance Act (FFCA)

• Federal Insecticide, Fungicide, and Rodenticide Act (FIFRA) as codified in Title 7 USC, Chapter 6

• Ft. Belvoir Regulations, Directives, and SOP's for the Environment

• National Environmental Policy Act (NEPA) as codified in Title 42 USC,

• OSHA "Powered Industrial Truck Operator Training," 63 Federal Register 66237-66274

• Pollution Prevention Act of 1990, as codified in Title 42 USC, Chapter 133

• Resource Conservation and Recovery Act (RCRA) of 1976, as codified in Title 42 USC

• Safe Water Drinking Act (SWDA) as codified in Title 42 USC

• Toxic Substance Control Act (TSCA) as codified in Title 15 USC, Chapter 53

• Universal Waste Act

• Technical Bulletin (TB) Med 530 Tri-Service Food Code

6.1.4 SECURITY SUPPORT SERVICES: Reference paragraph 4.16

• DoD Manual 5200.02, Procedures for the DoD Personnel Security Program

• 32 CFR Part 117 NISPOM Rule

6.1.5 FACILITY ENGINEERING:

• Leadership In Energy and Environmental Design Standard - Silver

• International Existing Building Code

• International Electric Code

• International Mechanical Code

• International Energy Conservation Code

- NFPA 101 Life Safety Code
- NFPA 70 National Electric Code
- Americans With Disabilities Act(ADA)
- Chief Financial Officers Act of 1990
- Statement of Federal Financial Accounting Standard No. 6 Accounting for Property, Plant and Equipment
- DoD Unified Facilities Criteria
- DoDI 4165.14 Real Property Inventory & Forecasting
- DoDI 4165.70 Real Property Management

6.1.6 SITE MAINTENANCE:
- DoD Unified Facilities Criteria
- Force Protection Equipment Maintenance & Repair
- DoD Instruction 2000.12, DoD Antiterrorism Program Support to Force Protection
- DoD Instruction 2000.16, DoD Antiterrorism Standards
- DoD Instruction 3020.52, DoD Installation Emergency Management Program
- DoD Instruction 6055.6, DoD Fire and Emergency Services Program
- Unified Facilities Criteria 4-010-01, DoD Minimum Antiterrorism Standards for Buildings (Unclassified)
- TM-5-602-1, Computer, Intelligence, Surveillance, and Reconnaissance (C4ISR) Facilities Utility Systems Terrorism Countermeasures for Command, Control, Communications

6.1.7 CUSTODIAL SERVICES:
- Green Seal Environmental Standard for Cleaning Services GS-42
- ASTM E E1971-24 Standard Guide for Stewardship for the Cleaning of Commercial & Institutional Buildings
- Current Industry Practices and Techniques (To be approved by the government)

6.1.8 SAFETY WASH EQUIPMENT:
- OSHA (29 CFR 1910.151)

6.1.9 ELECTRICAL SYSTEMS OPERATION & MAINTENANCE:
- Army Technical Manuals TM-5-601 through and including TM-5-698-6, As Applicable
- NFPA 70 National Electrical Code (NEC)
- NFPA 70B Recommended Practice for Electrical Equipment Maintenance
- Institute of Electrical and Electronics Engineers (IEEE), National Electrical Safety Code

TECHNICAL EXHIBIT 1

Performance Requirements Summary (Sample)

The contractor service requirements are summarized into performance objectives that relate directly to mission essential items. The performance threshold briefly describes the minimum acceptable levels of service required for each requirement. These thresholds are critical to mission success.

Performance Objective	Standard	Performance Threshold	Method of Surveillance
Within thirty (30) calendar days of contract start date, the Contractor shall physically inventory the property and facilities described in this PWS and the List of Equipment to be maintained and confirm the categories and quantities of equipment items to be maintained IAW PWS Section: 1.4.1	Survey all NGIC facilities and physically inventory and label, and record on equipment list all property to be maintained or operated by type and quantity; COR MS Excel approved format.	100% compliance; omissions or additions will be added to inventory list as discovered/procured.	100% Inspection
The contractor shall provide a complete and comprehensive QCP to the KO and COR within 30 days after award. IAW PWS Section: 1.6.1	The QCP shall implement specific procedures to identify, prevent, and ensure nonrecurrence of defective services and demonstrate to the Government that contractor's internal quality control process minimizes defective performance reoccurrences.	100% compliance at 30 days	100% Inspection
The contractor shall (must) maintain an adequate workforce, at all times, for the uninterrupted performance of all tasks defined within the PWS when the Government Facility is not closed. IAW PWS Section: 1.6.4	No uninterrupted performance of all tasks defined within the PWS when the Government Facility is not closed.	Proposed and accepted Full-Time-Equivalent (FTE) manning levels at time of award shall not fall below 90% each month and proposed subcontractor's shall have a 90% on time response each month.	Unscheduled observations within rating period and/or Customer complaints.
Contractor personnel performing work under this contract shall maintain a DoD TS security clearance with SBI and indoctrinated for SCI at the time of performance. IAW PWS Section: 1.6.7	100% of contractor's employees working inside the SCIF shall have a DoD TS security clearance with SBI and indoctrinated for SCI.	100% compliance at all times.	100% inspection

Contractor shall establish, implement, and maintain methods to assure that all keys and key cards issued to contractor by the Government are controlled and not used by unauthorized persons; No keys may be duplicated. IAW PWS Section: 1.6.7.2	100% of government keys must be accounted for at all times or reported to government and replaced or re-keyed at contractor expense.	No more than 2 defects within the full contract period of performance.	Random sampling and/or Unscheduled observations within rating period; 100% inspection at end of each contract period of performance.
The contractor shall provide a complete and comprehensive Safety Program Plan to the KO and COR within 30 days after award. IAW PWS Section: 1.6.17	The safety plan shall support reporting identified deficiencies to government within 24-hours and verifying OSHA training for all contractor employees.	100% compliance at 30 days	100% Inspection
Maintenance Management. Contractor shall plan, program, coordinate, estimate, respond to the Government schedule, and evaluate resources for work requests approved by the COR. IAW PWS Section: 5.1.4	The Contractor shall prepare, input, and maintain Contractor-generated data in the government provided or approved work management system/s databases	No more than 4 defects within a rating period (month)	Random sampling and/or Unscheduled observations within rating period.
Schedules- Contractor shall schedule, control, and perform all work described herein in accordance with contract. Contractor shall develop and provide plans and schedules for daily, weekly, bi-weekly, monthly, quarterly semi-annual, annual, start-up and shutdown work. Contractor's schedule shall be divided by functional area. IAW PWS Section: 5.1.8	The Contractor shall keep the schedules current. Maintenance work shall be scheduled by the 21st day of each month for the following month and provided to the Government in approved electronic and paper format.	No more than 4 defects within a rating period (month)	Random sampling and/or Unscheduled observations within rating period.
The Contractor shall maintain individual Work Order files on each active Work Order, regardless of maintenance level. The Contractor shall retain the all Work Order files for five (5) years and shall make these files available for the Facility Engineer Branch and COR's review IAW PWS Section: 5.1.10	All forms submitted shall be accurately filled out showing actual start and completion dates, total labor hours expended, and cost of equipment and materials utilized. Copies of any material receipts, letters of authorization, sales slips, invoices, etc., relating to the job order shall be retained by the Contractor in the equipment/facility file as a maintenance and repair history	No more than 4 defects within a rating period (month)	Random sampling and/or Unscheduled observations within rating period.

PM After Action Reports. After a PM inspection is made, the Contractor employee performing the PM will fill out an L&E Utilization Preventive Maintenance (EHSC Form 4288-2) line entry for each PM action performed for entry into the work management system	The L&E form will be completed in all required fields and submitted to the Work Order system for entry within one work day following completion of the PM.	No more than 4 defects within a rating period (month)	Random sampling and/or Unscheduled observations within rating period.

Section J Title	Content
PWS Attachment 1	List of Equipment to be Maintained
PWS Attachment 2	Cleaning & Custodial Tasks & Frequency of Services
PWS Attachment 3	Clean Room Tasks & Frequency of Services & Training
PWS Attachment 4	DD Form 254 and all DD Form 254 attachments and addendums.
PWS Attachment 5	DD Forms 1423 Contract Deliverables