EDDYVILLE QUARTERS WINDOW REPLACEMENT

Shawnee National Forest
Hidden Springs Ranger District
Pope County, Eddyville, Illinois

PART 1 GENERAL

1.1 Statement of Work:

A This project is for the removal and installation of vinyl clad windows at the Eddyville Quarters. Contractor shall provide all materials, equipment and labor necessary to remove and dispose of the existing windows and provide and install new windows.

1.2 Contractor Use of Premises

A General: The contractor should coordinate entry into the quarters with the COR. At the time of advertisement, the quarters are occupied.

B Contractor shall conduct his operations to ensure the least inconvenience to the building occupant.

C Power, water and sanitary facilities are available on site.

D Confine storage of materials to areas as approved by the CO.

1.3 Field verification

A Contractor shall field verify all new and existing dimensions affecting the work of this contract before ordering products.

1.4 Cleaning and Disposal of Material

A Contractor shall remove and dispose of all debris offsite, including materials removed from building.

B The Contractor shall ensure all work areas are clean and free of dust, debris and construction waste generated by the project. This includes interior and exterior of building

1.5 Security - The Contractor shall be responsible for protecting all equipment and supplies for use on the project and stored on the site. The Contractor shall be responsible for all costs required to provide such protection. The construction area shall be secured and placed in a safe condition at the end of each working day.

1.6 Disturbances - Noise, lights, or other activities that disturb neighboring residents shall not be permitted between the hours of 6:00 pm and 7:00 am.

1.7 Stage Area - The Contractor shall coordinate with the COR on a staging area location. Access must be maintained to residence and other facilities on the site. The Contractor shall operate all equipment and store, transport, and handle materials in a manner that will not damage the existing facilities, roads, parking lots, and landscaping.

PART 2 PRODUCTS

2.1 Submittals:

A Submit all shop drawings, product data and samples for the Contractor, subcontractor(s) and supplier(s).

B Mark each submittal, with the contract number, date of submittal and the quantity and size of each window.

C Submit three copies for COR's use or one electronic copy in PDF format.

2.2 Windows:

A Shall be Vinyl clad

B Single hung

C Half screen

D Color White

E Low E

F Sized as shown on the drawings and verified in the field prior to ordering.

2.3 Other Materials"

A Items are to include all material and supplies to properly install the new windows shall include, but not be limited to:
1 Caulk
2 Insulation
3 Shims
4 Sealants

PART 3 EXECUTION

3.1 REMOVAL

A Windows removed shall be replaced within the same day.

B Contractor shall remove any trims with care for reinstallation after installing the windows.

3.2 INSTALLATION

A Set units level, plumb, and true to line, without warp or rack of frames and panels and anchor securely in place.

B Set sill members in bed of sealant or with gaskets, as indicated, to provide weathertight construction.

C Adjust operating panels, screens, and hardware for smooth operation and weathertight closure. Lubricate hardware and moving parts.

D All window units shall be cleaned of grease, sealant, dirt and debris.

E All window glass shall be cleaned of fingerprints, dirt and smudges.