

PERFORMANCE WORK STATEMENT

for

OPERATIONS AND MAINTENANCE SERVICES

of the

FAIRBANKS COMMAND AND DATA ACQUISITION STATION

TABLE OF CONTENTS

SECTION 1.0 **INTRODUCTION**
1.1 General Description

SECTION 2.0 **BACKGROUND**
2.1 Overview

SECTION 3.0 **SCOPE**
3.1 General Scope of Work
3.2 Contract Transition

SECTION 4.0 **APPLICABLE DIRECTIVES**
4.1 General

SECTION 5.0 **PERFORMANCE REQUIREMENTS**
5.1 Staffing
5.2 Operations and Maintenance
5.3 Risk Management
5.4 Information Technology
5.5 Facilities Operations
5.6 Environmental, Safety, and Health
5.7 Property Management and Logistics
5.8 Security Guard Services
5.9 General Management
5.10 Use of Computerized Maintenance Management System
5.11 Quality Control Program (QCP)
5.12 Government Quality Assurance Surveillance Program (QASP) and Reporting Requirements Summary
5.13 Building Operating Plan (BOP)
5.14 Contract Security Requirements
5.15 Optional Support Contract Line Items (CLINS)

APPENDIX A Station Information
APPENDIX B Work Standard References
APPENDIX C Security Guard Tasks
APPENDIX D Quality Assurance Surveillance Program (QASP)
APPENDIX E Reporting Requirements Summary
APPENDIX F Transition Phases
APPENDIX G List of Acronyms and Abbreviations
APPENDIX H Report Format

SECTION 1.0 INTRODUCTION

1.1 General Description. This Performance Work Statement (PWS) is for the National Oceanic and Atmospheric Administration (NOAA), National Environmental Satellite, Data, and Information Services (NESDIS) contracted operations and maintenance (O&M) services for the Fairbanks Command and Data Acquisition Station (FCDAS) at Fairbanks, Alaska. General services are identified under Scope of Work and Performance Requirements.

SECTION 2.0 BACKGROUND

2.1 Overview. FCDAS is a National Critical Asset and, therefore, must remain in operation 24x7x365, including periods of inclement weather and emergencies such as natural and man-made disasters. Mission-essential functions must be maintained at all times, provided no serious hazards to personnel exist. Historically, FCDAS has been a Government-Owned, Contractor-Operated facility. This is a performance-based service contract, wherein the success of the O&M Contractor depends on satisfaction of the technical requirements as well as responsiveness to continually evolving operational requirements and changes in technology. Refer to Appendix A, Station Information, for more detailed site information and challenges.

SECTION 3.0 SCOPE

3.1 General Scope of Work. The Contractor shall be responsible for providing the necessary personnel and resources to accomplish all tasks specified herein unless specifically stated otherwise. The Contractor shall ensure safe, accurate, and timely handling, quality control, and accountability of all Government-owned products under their control. The Contractor shall perform required maintenance to ensure facilities, associated systems, vehicles, and equipment remain operational to meet the Station mission. The Contractor shall comply with environmental protection, safety, and security directives. The Contractor shall conduct required training to ensure personnel are fully qualified to perform PWS tasks.

3.2 Contract Transition. During this period the Contractor shall (1) revise and submit to the CO or their designee within 30 days after commencement of performance an updated building operating plan, (2) inspect the condition of all equipment and systems and buildings for which the Contractor shall assume responsibility, (3) review work order history and equipment inventory information, (4) complete the government-furnished Computerized Maintenance Management System (CMMS) training, (5) Update the preventive maintenance schedule, (6) Develop and submit to the CO or their designee the initial deficiency list report, including an itemized estimate for correcting each deficiency as described in Section 5.5.2 Existing Deficiency Inspection/Initial Deficiency List.

SECTION 4.0 APPLICABLE DIRECTIVES

4.1 General. The Contractor shall comply with all applicable federal, state, local, and international agreements, laws, regulations, plans, policies including, but not limited to, the directives listed herein in performance of the contract effort. The Contractor shall maintain ready access to applicable directives and ensure all employees are familiar with directive requirements. Clarification of applicability should be obtained from the CO and/or appropriate Government subject matter expert if necessary. In the event of conflicting guidance, the most stringent requirement shall be followed.

SECTION 5.0 PERFORMANCE REQUIREMENTS

5.1 Staffing. If necessary to perform tasks beyond or after normal station hours at the Government's request, Table 1, the Contractor shall notify the Contracting Officer's Representative (COR) and Government directed overtime shall only commence upon written authorization from the COR.

Key Personnel identified in the contract shall work on site and include the following positions: Program Manager; Operations Manager; Facilities Manager; and Environmental, Safety, and Health Manager;. The Contractor shall obtain the consent of the CO prior to making key personnel substitutions IAW the contract; industry certifications shall be maintained for each position.

Where specific times have not been identified, Contractor support will be as required (AR). The Contractor must be capable of providing PWS coverage when required for periods of inclement weather and emergencies such as natural and man-made disasters. Any deviation from normal station hours may be approved by the Station Manager.

Table 1 – Normal Station Hours

Department	Mon – Fri	Sat – Sun	Holidays / After Hours
Key Personnel	0700-1500	AR	AR
Operations (shift)	24 hours	24 hours	24 hours
Operations (daytime)	0700-1500	AR	AR
Information Technology	0700-1500	AR	AR
Facilities	0700-1500	AR	AR
Logistics	0700-1500	AR	AR
Security Guard	24 hours	24 hours	24 hours

Recognized holidays:
Contractor holiday observance shall generally match federally recognized holidays.

Staffing Calendar:
The Contractor shall maintain and share with the Government a unified staffing calendar (one document) indicating the work and leave schedule for each contractor. The calendar shall be updated as needed to indicate any changes in staffing.

5.2 Operations and Maintenance. The Contractor shall conduct all necessary O&M to support satellite operations under normal conditions, as well as, during periods of heightened security, inclement weather, or other unique situations. Operations must maintain all FCDAS ground system equipment while maintaining 24x7x365 coverage.

5.2.1 Ground Systems Operation. The Fairbanks Satellite Operations Facility (FSOF) control room shall be staffed around the clock. Personnel shall be able to configure and operate complex, automated satellite ground station equipment from a keyboard interface or front panel, and troubleshoot this equipment when an anomalous condition exists. The Contractor shall ensure a minimum of three O&M technicians are on shift at all times for 24x7x365 coverage with no exceptions for planned or unplanned personnel absences. Staffing surge needs for major planned events such as launch support or significant system upgrades shall be communicated to the COR and Station Manager in writing no later than one week prior to the requirement's commencement.

5.2.1.1 Satellite Pass Scheduling. The Contractor shall de-conflict schedules and assign appropriate assets IAW the latest OSPO mission priority list.

5.2.1.2 Geostationary Operational Environmental Satellite (GOES) and Lagrange 1 (L1) Operations. FCDAS supports GOES and L1 missions. The Contractor shall support GOES and L1 mission control centers as needed during operations, maintenance, and upgrades. The Contractor shall assume primary command and control of spacecraft within 20 minutes of an outage event at other OSPO ground stations.

5.2.1.3 Launch and Early Operations. The Contractor shall publish a FCDAS-specific spacecraft support plan (SSP) for each new mission added to the station mission list. The final SSP shall be published not later than 45 days prior to launch or formal operations transition to FCDAS depending on mission concept of operations.

5.2.1.4 Daily Satellite Operations Reporting. The Contractor shall record in the shift log activities, including system states, maintenance actions, and significant events. The Contractor shall ensure all satellite operations personnel are diligent in reporting system status and personnel activities prior to hand-over to the next crew. The Contractor shall report daily O&M activities in the Ground System Operations and Maintenance Summary (GOMS). The Contractor shall report any significant anomaly or degraded capability at FCDAS in an Equipment Status Report (ESR) within 30 minutes of detection. The ESR shall contain a detailed description of the issue, actions taken or needed to be taken for resolution, and the estimated time for resolution. The Contractor shall maintain the ESR distribution list, and update it annually.

5.2.2 Communications Security (COMSEC). The Contractor shall ensure at least one staff member cleared to Final SECRET is present for each shift, including absences of other clearance holders, to carry out COMSEC user functions such as loading cryptographic keys or resolving COMSEC-related alarms 24x7x365. The Contractor personnel shall be qualified to handle all crypto devices and ensure the proper function of encryptors and decryptors, including loading cryptographic key material. Cleared Contractor personnel shall respond immediately to any alarms within areas containing classified information to determine the validity of alarms and, if needed, to keep the area secure until the COMSEC custodian or alternate can investigate further.

5.2.3 Ground System Maintenance. The Contractor shall inspect, test, replace, and repair (where possible) hardware, including antennas, network and other support equipment; carrying out configuration changes to hardware and software as directed by the Government; verifying software and database settings; updating operating systems and software applications; and coordinating test activities after repairs or configuration changes.

5.2.3.1 Preventive and Corrective Maintenance. The Contractor shall perform periodic maintenance activities and tests on the antennas and associated ground systems equipment including, but not limited to, alignments, calibrations, test measurements, and system performance testing in a manner that will minimize impact on operational support. The Contractor shall perform corrective maintenance to identify, isolate, and rectify a fault so that the failed equipment, machine, or system can be restored to an operational condition within the tolerances or limits established for in-service operations.

The Contractor shall perform an annual baseline of radio frequency (RF) and fiber optic transport levels. Where signal levels are out of spec. or noisy, restoring/improving the system to appropriate levels will be conducted.

5.2.3.2 Calibration Services. FCDAS receives calibration services through an agreement with the U. S. Air Force (USAF). In the event the USAF agreement lapses, or USAF is unable to perform needed services, the Contractor shall coordinate this work with commercial calibration facilities or OEMs as needed. The Contractor shall maintain electronic records of all calibration activities, and submit a monthly calibration report.

5.2.3.3 Maintenance Planning and Reporting. The Contractor shall deliver to the COR a proposed ground systems preventive maintenance plan no later than 60 days after commencement of the initial contract period of performance for review. The Contractor shall review and update the preventive maintenance plan as new items are acquired, but not less than annually. All maintenance actions shall be tracked, scheduled, and reported using the Government-furnished CMMS. The Contractor shall deliver a summary of preventive and corrective maintenance actions to the COR weekly. Negative trends such as increasing failures or excessive workload required to perform these actions should be specified and resolutions recommended.

5.2.4 Ground Systems Performance Metrics. The Contractor shall ensure minimum antenna system operational availability or better as computed on a monthly and annual basis. The information shall be reported to the COR and Station Manager monthly and include identifying risks, issues, and concerns that may impact annual system operational availability requirements. Negative trends must be analyzed and corrected.

The Contractor shall report to the COR monthly latency performance by spacecraft, data types and subtypes for missions levying specific latency reporting requirements on FCDAS. The Contractor shall track and report daily, weekly, and monthly to the COR the number of operational scheduled contacts for each satellite, the number of non-nominal passes, and the overall success rate with the reason for each non-nominal contact documented. The Contractor shall report and analyze all negative trends and provide recommendations to the Government quarterly for their resolution. The Contractor shall track and report daily, weekly, monthly, and annually, all mission and antenna time usage metrics that can be readily utilized for planning, sustainment, maintenance, and support calculations.

System in the context of operational availability includes collecting all elements within a ground system segment that may be considered stand-alone to perform satellite tracking; data reception, recording, and playback; raw data processing and formatting; temporary storage in preparation for off-site data transfer; RF transmission; as well as equipment control, monitoring, and integrated support equipment. For example, an “antenna system” would consist of the aggregate of all components from the antenna assembly to the control room equipment such as a file server used for staging data transmissions to end users.

Availability is generally defined as the probability of a system being able to perform its mission or function under specified conditions when called upon to do so at a random time. This term is applicable to systems that can be repaired or have other maintenance and associated actions performed. Downtime will not include periods in which the system is undergoing planned upgrades and associated testing, nor for Government-mandated outages for the purposes of depot level or other maintenance outside the direct control of the Contractor.

Mean Time Between Maintenance (MTBM) is the mean time between all maintenance activities, both corrective and preventative, resulting in the system to be unavailable.

Mean Downtime (MDT) is the mean system downtime, accounting for the time required to do the maintenance as well as any delays getting required parts, personnel on site, etc.

Operational Availability ("A_O") is computed as a function of MTBM and MDT.

$$A_0 = \frac{MTBM}{MTBM + MDT}$$

Data capture reliability is the measure of the amount of actual science observation data received and recorded from the spacecraft divided by the expected amount of science observation data to be received. Depending on the mission, the quantity of data may be measured in different ways; e.g., file size in bytes, frame counts, or virtual channel counts.

The Contractor shall maintain data capture reliability of 99.5% or better, computed monthly, for each spacecraft supported at FCDAS. Data metrics for non- polar-orbiting spacecraft are not measured in terms of expected frames or bytes. Therefore, data capture reliabilities for non-polar- orbiting spacecraft may be specified in successfully completed activities such as the total time telemetry and science data are received for a given session and the number of scheduled commands transmitted to the spacecraft. The Contractor shall report monthly, and annually, data capture reliabilities by spacecraft to the COR.

Reports shall include, but are not limited to, mission/spacecraft identifier, antenna identifier, mission pass duration (AOS to LOS), and pre-pass and post-pass durations. Reports shall include total daily mission and antenna usage in time as well as percentage and shall include daily totals of antenna in-use time, idle time (operationally available), and down time. Down time shall include scheduled down time, unscheduled down time, and a description/label for the reason (maintenance, failure, troubleshooting, etc.). Antenna "Green", "Yellow", and "Red" status durations shall also be logged.

Table 2 – Minimum Antenna System Availability

System	Minimum A_O	Location
26-meter	0.96	Fairbanks
Datron 13-meter A	0.98	Fairbanks
Datron 13-meter B	0.98	Fairbanks
Datron 13-meter C	0.98	Fairbanks
21-meter	0.98	Fairbanks
Malibu 5-meter B	0.98	Fairbanks
Datron 5-meter A	0.98	Fairbanks
JPSS 4 meter	0.995	Fairbanks

5.2.5 Ground Station Engineering Support. The Contractor shall coordinate all engineering activities between the station, external stakeholders, and the Contractor. Engineering activities include requirements development and validation, planning for new missions, technical studies, design work, integration planning, ground system testing, operational procedure development, and technology research. The Contractor shall provide engineering support to these activities to ensure specified operational and technical requirements are met, and changes to FCDAS ground systems are documented IAW configuration management (CM) policies and procedures. The Contractor shall also assist third parties performing upgrades or other engineering work at FCDAS to minimize any disruptions to satellite operations or FCDAS-caused delays to the third-party activities.

5.3 Risk Management. The Contractor shall recommend to the Government in writing strategies for mitigation or resolution when risks and issues arise. Contractor shall track equipment failures and malfunctions as well as obsolescence and supportability issues from original equipment manufacturers

(OEMs) and suppliers, including their ability and responsiveness to re-supply products. The Contractor shall coordinate with the COR to maintain a level of spare parts to ensure against equipment outages due to the unavailability of parts required for repair of equipment. The Contractor shall ensure that adequate stocking levels of critical and non-critical spares are maintained and replenished. The Contractor shall also assess and recommend equipment upgrades, facility improvements, skill enhancements, logistical support changes, and administrative changes that can be implemented over a period of up to five years. The Contractor's Program Manager shall coordinate, initiate, and present the risk and recommendation materials for review to the COR and Station Manager not less than quarterly for evaluation.

5.4 Information Technology (IT). The management of IT systems does not grant ownership; the Government retains ownership of all systems and its right to administrator-level access for oversight**.** During normal work hours the Contractor shall administer all the components of all FCDAS IT systems, which include satellite operations networks, as well as building control and security systems. All system administrators shall meet and maintain all required training and ability requirements IAW industry and Government standards.

The Contractor shall deliver a summary of preventive and corrective maintenance actions to the COR and Network Engineer weekly. Negative trends such as increasing failures or excessive workload required to perform these actions should be specified and resolutions recommended. The Contractor shall report any anomaly or degraded capability at FCDAS in an ESR within 24 hours of detection.

The Contractor shall maintain, and share (via a secured database similar to Kiteworks), the user access list of all IT systems and components maintained within the O&M and report quarterly.

Information System Administration and Maintenance
IT administration duties include but are not limited to:

a. Develop and implement procedures for managing user accounts.
b. Develop and document common system management procedures (adding additional workstations, adding or deleting user accounts, performing periodic backups). Document procedures for troubleshooting common problems as changes occur.
c. Provide backup and restore functionality and services and provide a backup of the installed configurations on electronic media.
d. Provide the specifications for procurement of new systems and related peripherals and software.
e. Install workstations, peripherals, operating systems and other software.
f. Install printers and configure printing services.
g. Operate, maintain, and augment (as needed), station communications systems, including the station commercial telephone switching system, NOAA-owned data communications equipment, station intercommunications and paging systems, Internet access equipment, and two-way radio equipment.
h. Carry out configuration management of station computer systems and equipment. This includes recommendations for improvement in station capabilities; modification development, control, and implementation; documentation control and updating; and desktop/laptop computer hardware and software configuration control and is reported quarterly.
i. Install and maintain configuration control of station desktop/laptop computers and local area network LAN servers (Non-Admin LAN systems). Perform software installation and maintenance on desktops/laptops IAW NESDIS IT Security Policy.
j. Maintain and/or assist with the security of all systems e.g. access control system, camera systems, building control systems.
k. Provide technical support for all aspects of the Station's security systems including cameras, access control system and motion detectors.
l. Conduct Life Cycle Management IAW IT industry standards or best practices.

m. Maintain and update annually software license inventory and renewal dates.
n. Maintain and update bi-annually all hardware and equipment warranty dates.
o. Create and update/maintain comprehensive drawings and documentation for all networks including local IT infrastructure drawings on a bi-annual basis.
p. Comm rooms and other areas are kept clean and free of obstacles, dust and debris.
q. Will practice clean, neat and labeled cable management.

Telecommunications Provisioning, Management and Support

Operations maintenance and support of existing telephone, radio, Wide Area Network (WAN), and Local Area Network (LAN) equipment at FCDAS falls within the scope of this contract. The Contractor shall install/update software, and cabling relating to telephone, radio, LAN and Wide Area Networks. Contractor personnel also shall escort and assist outside vendors/contractors in preparing for, and assisting the provisioning of, new telecommunications circuits, systems, and devices.

The Contractor shall provide an IT Manager. The IT Manager is responsible for providing strategic leadership, operational oversight, and technical direction for all information technology activities, with a primary focus on IT security and system administration. This role ensures the confidentiality, integrity, and availability of organizational systems, networks, and data while supporting the operational needs of the enterprise. The IT Manager serves as the primary liaison between FCDAS leadership, system owners, IT administrators, and security personnel to ensure compliance, performance, and resilience across all IT systems.

5.4.1 Security. The Contractor shall comply with the IT Security requirements of the Department of Commerce (DOC) as outlined in Commerce Acquisition Regulation (CAR), the DOC IT Security Program Plan, the NOAA IT Security Manual, and the NESDIS IT Security Handbook. The contractor must also comply with the Federal Acquisitions Regulation (FAR) Clauses 52.204-21, 52.224-1, 52.224-2 and 52.239-1. The Contractor personnel shall be screened IAW the requirements for Moderate Risk contracts. Any access by contract personnel who are Foreign Nationals must be IAW the requirements of CAR. The Contractor must submit security forms required by CAR two (2) weeks prior to each new contract employee's start of work date. This includes IT system security plans, updates, and plans of action and milestones (POA&Ms).

5.4.2 Administration. The Contractor IT personnel assigned to these roles shall apply System Owners' approved secure configuration settings to all systems to meet DOC, NOAA, and OSPO standards. Any changes shall be thoroughly tested to ensure (a) implementation requirements are met; and (b) there is no negative impact on satellite operations. IT system administrators also assist the system administration team, the ISSO, and NOAA Computer Incident Response Team (N-CIRT) with investigation of unusual or unauthorized activities as well as provide artifacts, documentation, and other information in support of authorization and accreditation activities. IT security system authorization and accreditation project plans are due annually in the second quarter of the fiscal year.

5.5 Facilities Operations. The Contractor shall provide all necessary management; supervision; labor, materials, equipment and supplies not otherwise provided by the Government; and is responsible for the efficient, effective, economical, and satisfactory operation, scheduled and unscheduled maintenance, repair of equipment and systems and buildings, cleaning of spaces identified, and grounds care services within the property line of FCDAS. The Contractor will have the use of Government vehicles to perform such services.

Table 3 – FCDAS Buildings

Building	Approx Area (ft^2)
Boom Truck Garage	744
Contingency Operations Area	5,711
Covered Storage Building	3,200
Covered Storage, Warehouse Supply Yard	640
Facilities Building	10,198
Fairbanks Satellite Operations Facility (FSOF)	20,240
Guard Houses	965
Gravel Storage Building	488
Gilmore Creek Geophysical Observatory (GCGO)	10,972
Old Gate House	160
Power House	11,100
Supply Warehouse	2,492
Visitors Kiosk (Old Kiosk)	325
Water Storage Building	4,166
Wood Cabin	580
Communications Shelter Conex	160
Vehicle Storage Building	5,000
Guard House Generator Shed	160

The following equipment and systems are included in this scope of work:

a. Electrical generation and distribution systems and equipment.
b. Heating, ventilation, and air conditioning (HVAC) systems and equipment.
c. Plumbing systems and equipment.
d. Fire protection and life safety systems and equipment.
e. Building Automation System (BAS) and other controls.
f. Architectural and structural systems, fixtures, and equipment within the site (to the property line).
g. Computerized maintenance management system (CMMS).
h. Locks, fences, gates, vehicle barrier systems.
i. Dock levelers and roll-up and sliding garage doors.
j. Elevator and vertical transportation systems.
k. Storm drainage systems.
l. Roofing.
m. Flag poles, lighting and pulley systems.
n. Vehicles and mobile equipment.
o. Water and fuel storage tanks.
p. Monitoring and scheduling of septic waste removal.

The Contractor shall deliver a summary of preventive and corrective maintenance actions to the COR weekly. Negative trends such as increasing failures or excessive workload required to perform these actions should be specified and resolutions recommended. The Contractor shall report any anomaly or degraded capability at FCDAS in an ESR within 24 hours of detection.

5.5.1 General Facilities Requirements. The Contractor shall implement an effective Quality Control Plan (QCP). The Contractor shall keep the COR or designee informed of current status of the work being performed, provide work schedules, provide a major equipment and critical system breakdown. The Contractor shall ensure that its employees are properly licensed and certified to operate necessary building systems or equipment for which licensed or certified personnel are required by federal, state, or local law, codes or ordinances. The Contractor shall obtain all applicable licenses, training, and permits. The Contractor shall protect Station structures from damage due to local environmental conditions, such as extreme cold and the formation of structure-threatening aufeis. Equipment necessary to control aufeis will be provided by the Government.

5.5.2 Existing Deficiency Inspection/Initial Deficiency List. The existing deficiency inspection and list is meant to identify and document all deficiencies that exist in the equipment and systems and buildings covered by this PWS, but that will not be repaired during routine preventative maintenance, and includes the Contractor's itemized, fully loaded price for correcting each deficiency. This inspection is required to be documented in the CMMS.

Initial Inspection
The Contractor and the COR or their designee shall, within 30 days of commencement of the contract, make a complete and systematic initial inspection together during the startup or transition phase of the contract that will include all equipment, systems, and buildings for which maintenance and repairs are covered by this PWS. The Contractor shall provide an itemized price (including, but not limited to labor, materials, overhead, and profit) for correcting each deficiency. The Government may elect to have all or any part of this work performed by the Contractor (at the price or prices quoted), by Government employees, or by other Contractors. The existing deficiency list report shall not include any items that would be replaced, repaired, or adjusted during the performance of normal preventive or predictive maintenance.

Initial Deficiency List
The Contractor shall submit an initial deficiency list report not later than ninety (90) days after award of the Contract to the COR or designee. The Contractor’s itemized estimates for correcting each deficiency shall remain in effect for one hundred eighty (180) days after submission of the initial deficiency list report. Deficiencies discovered after the submission of the initial deficiency list report will not be considered pre-existing for purposes of this Contract, unless equipment is operational and cannot be secured and inspected. Any piece of equipment or system that cannot be inspected shall be highlighted at the beginning of the deficiency list stating why it cannot be secured and inspected. An estimate of when the Contractor reasonably expects to be able to inspect the piece of equipment shall be provided.

5.5.3 Facilities Systems Performance Metrics. The Contractor shall comply with the Facilities systems performance metrics in Table 4 below. Acceptable ground systems performance depends on facilities systems performance. Recommended minimum performance values provided in this section are targets which, if met or exceeded, are expected to support acceptable ground system performance and support the Government objectives for facilities operation and maintenance.

Facilities systems performance metrics include percent availability of critical operations power and heating, ventilating, and air-conditioning (HVAC) systems; percent execution of scheduled preventative maintenance, predictive testing and inspection; percent on-time response to service requests; and percent non-hazardous solid waste diversion. Critical operations power systems and critical operations HVAC systems are those which provide electricity service, temperature control, and humidity control for ground system equipment.

Table 4 – Performance Metrics

Metric	Definition	Minimum Performance
Critical Operations Power Systems (COPS) Availability	$100 \times \frac{COPS\ MTMB}{COPS\ MTMB + COPS\ MDT}$	99.99%
Critical Operations HVAC (COHVACS) Availability	$100 \times \frac{COHVACS\ MTMB}{COHVACS\ MTMB + COHVACS\ MDT}$	99.99%
Preventative Maintenance / Predictive Testing & Inspection (PM/PT&I)	$100 \times \frac{Hours\ of\ PM/PT\&I}{Hours\ of\ Reactive\ Work + Hours\ of\ PM/PT\&I}$	70%
On-Time Response to Service Requests	$100 \times \frac{\#\ of\ On-Time\ Responses\ to\ Service\ Requests}{Total\ \#\ of\ Service\ Requests}$	95%

5.5.4 Federal Leadership in Energy, Environmental, Water, Fleet, Buildings, and Acquisition Management. The Contractor shall utilize Government-furnished systems including ENERGY STAR benchmarking and advanced metering, and comparable programs, to manage and improve sustainability performance IAW the NOAA Strategic Sustainability Performance Plan. The Contractor shall perform the required operation and maintenance of the facilities by following the Guiding Principles for High Performance and Sustainable Buildings.

5.5.5 Government-Furnished Equipment. The Government will provide all office furniture and equipment, electronics systems and equipment, communications circuits, buildings, facilities systems, apparatus, utilities, fuel, and vehicles as required for the performance of the services set forth in this PWS. The Government will not provide property for use by the Contractor to support FCDAS activities at an off-site office or technical facility except as specifically authorized by the CO.

5.5.6 Work Standards and References. The Contractor shall obtain all referenced documents in Appendix B with the exception of the General Services Administration Preventive Maintenance Guide (PM Guide) and the General Services Administration PBS-100 Facilities Standards for the Public Buildings Service which will be provided by the Government.

5.5.6.1 Facilities Equipment Inventory. The Contractor shall maintain and update the facilities equipment inventory and equipment labeling; maintain equipment inventories and maintenance records in the CMMS; maintain the same asset identification system currently used for new and replacement equipment unless a national asset identification standard is provided; collect and maintain an inventory of all equipment of types that require maintenance or certifications; collect and maintain the following equipment data: Equipment ID, Equipment Type, Equipment Description, Asset Identification Code, Manufacturer, Model Number, Serial Number, Equipment Status, Building Number, and Location; provide all data to the Government in a format approved by the Government with certification that the inventory is complete and accurate; update equipment data when equipment is added, removed, or retrofitted; review and update equipment records including asset information, maintenance records and preventive maintenance records any time maintenance is performed on a piece of equipment; and report to the Government changes to the

asset inventory and preventative maintenance schedule within five working days of collecting and gathering equipment information.

5.5.6.2 Facilities Progress Reporting. The Contractor shall provide accurate monthly progress information describing the status and impact of all current and future activities involving facilities as described in Appendix H. The Contractor shall host monthly progress meetings as well as develop monthly progress reports for the Station. The Contractor shall develop a monthly progress report using CMMS data, Building Automation System (BAS) data, and other sources describing the status of maintenance and operations as of the last day of the performance month.

5.5.6.7 Capital Improvement Project Management Assistance. Projects for the major repair, replacement, or enhancement of the facilities are often initiated and managed by NOAA and/or the U.S. Army Corps of Engineers and awarded to third party contractors. To assist NOAA in these efforts, and when requested by the Government, the Contractor must provide a qualified onsite individual(s) familiar with the facilities systems and operation (including, but not limited to heating, ventilation, and air conditioning (HVAC), plumbing, electrical, and lighting), with the ability to interpret and understand construction documents, and capable of providing project management assistance through coordinating, and inspecting activities of the construction contractor.

5.5.6.8 Emergency Shutdown and Tour Checklists. Emergency shutdown instructions (including contact name and telephone numbers), lock-out-tag-out procedures, and tour inspection checklists must be posted by the Contractor in all mechanical rooms and or electrical rooms, as applicable to the equipment in the given room, and recorded in the CMMS.

5.5.6.10 Operational Requirements. The Contractor shall operate facilities equipment, systems, and buildings covered under this Contract so as to maximize the availability of critical operations power systems and critical operations HVAC systems, provide acceptable environments for occupants, preserve the asset coop value of facilities, and minimize operating costs to the Government without compromising other Contract objectives or requirements. The Contractor shall provide commercial power outage reporting. The report shall include actual cause, outage start time, stop time, and relevant details within 24 hours of the outage. The Contractor shall install, operate, and maintain electrical power monitoring hardware/software for each building and log, track, and improve electrical power usage across the campus. The Contractor shall deliver a monthly log of power usage by building and provide recommendations/observations to the Government.

5.5.6.11 Continuity of Operations (COOP). The Contractor shall participate in emergency operations to the fullest extent possible during all emergency situations such as fires, accident and rescue operations, strikes, civil disturbances, natural disasters, severe weather, terrorist threats, contingency operations, pandemics, and practice drills (COOP or otherwise) unless ordered to evacuate the building by a Government representative, emergency personnel, or an authority having jurisdiction. The Contractor shall be responsible for developing and executing emergency operations plans within the Station's operating plans and shall ensure all Contractor's employees become thoroughly familiar with the Government's occupant emergency plan (OEP) and other plans as applicable.

5.5.6.12 Indoor Environment. The Contractor shall adjust lighting levels, under the guidance of the CO or their designee, where they can be adjusted without changing fixtures to meet established target lighting levels, light quality, specific occupant requirements, energy conservation, and individual factors are also considered. Except for special conditions, the Contractor shall operate HVAC systems to achieve American Society of Heating, Refrigerating and Air-Conditioning

Engineers (ASHRAE) Standard 55-2004 and ASHRAE 62.1-2007 throughout hours of occupancy. The Contractor shall report significant changes in the operating conditions to the CO or their designee. If the standards cannot be achieved, the Contractor shall submit a written deviation to the CO or their designee for approval.

5.5.6.13 Special Conditions. The Contractor shall comply with special indoor environment conditions.

Special Conditions for Computer Rooms

- **Temperature**: 18° to 27°C (64.4° to 80.6°F)
- **Moisture**: 5.5°C (41.9°F) dew point to 60% Relative Humidity and 15°C (59°F) dew point

Special Conditions for Uninterruptible Power Supply Rooms and Battery Rooms

- **Temperature**: 20° to 25°C (68° to 77°F)
- **Moisture**: 5.5°C (41.9°F) dew point to 60% Relative Humidity and 15°C (59°F) dew point.

Special Conditions for Switchgear Rooms

- **Temperature**: 12.8° to 29.4°C (55° to 85°F), change not more than 5° F per hour.
- **Moisture**: Temperature at least 5°F above dew point at all times.

Antenna Pedestals and Radomes

- **Temperature**: 2° to 29.4°C (35.6° to 85°F)

5.5.6.14 Energy and Water Conservation. The Contractor shall operate facilities equipment and systems as efficiently as possible without compromising service to critical operations or occupants. The Contractor shall analyze the site's electrical, heating fuel, and vehicle fuel usage monthly, and provide quarterly reports identifying areas where conservation can be improved without negative impacts to operations.

5.5.6.15 Service Requests. The Contractor shall respond to routine service requests, initiate corrective actions and identify any repair requirements during business hours. The Contractor shall respond to emergency service requests at all times. The Government may transmit service requests orally, by email, by creation of a work order, or by generation of an automated work order/alarm. The Contractor shall respond according to specified service response times.

Service Request Priority Level Timeframe. The Contractor shall complete service requests based on a tiered priority system. Priority levels are assigned based on the severity of the issue's impact on business operations and the urgency of the required resolution. The Contractor shall adhere to the following table regarding response and resolution milestones:

Table 5 – Service Request Resolution Milestones

Priority Level	Technical Definition	Response Time	Resolution Goal
1 – Urgent (*Emergency*)	Mission-critical outage; operations halted	30 minutes *during* business hours 1 hour *after* business hours	4 hours
2 – High (*Urgent*)	Partial loss of critical functionality; workarounds available	1 hour *during* business hours 4 hours *after* business hours	8 hours
3 – Medium (*Routine*)	Partial loss of non-critical functionality; workarounds available	24 hours	3 days
4 – Low (*Routine*)	General inquiries; minor issues	24 hours	5 days

Response Time: The period between the service request and work assigned.

Resolution Goal: The total time elapsed until the issue is fully resolved or a permanent fix is implemented.

Emergency Service Request
Emergency service requests are for correcting failures that constitute an immediate danger to personnel or property, or that interrupt critical operations power or HVAC systems, including but not limited to: broken water pipes, stalled elevators with trapped passengers, electrical power outages, electrical problems that may cause fire or shock, gas or oil leaks, major air conditioning or heating problems, etc., or any work considered by the COR or their designee to be of an emergency nature.

The Contractor must address onsite emergency service requests within thirty (30) minutes during business hours, and within one (1) hour if originating after business hours. The Contractor shall provide a callback to the Government within thirty (30) minutes if the emergency service request originates after business hours to acknowledge receipt of emergency request and confirm the Contractor is headed to the site or already onsite.

The Contractor must remain on the job until the emergency situation has been secured and adequate temporary repairs have been made. Permanent repair shall be governed by the repair provisions (Para 5.5.12) in this contract. The Contractor must provide a written account of any emergency response, to include costs incurred and plan for permanent correction of the problem, to the CO or their designee the morning of the next working day.

Urgent Service Request
Urgent service requests are for correcting failures that adversely impact personnel or property or operations, but do not pose immediate danger, and does not interrupt critical operations power or HVAC systems; including, but not limited to, inoperative electrical circuits, temperature complaints, inoperative lighting above a workstation, flush valve stuck open, any malfunctions to equipment that affect the operations of building occupants, or any work considered by the CO or their designee to be of an urgent nature.
The Contractor must respond onsite to urgent work requests within one (1) hour during business hours, and within four (4) hours if originating after business hours. The Contractor shall provide a callback to the Government within one (1) hour if the urgent service request originates after business hours.

Routine Service Request
The Contractor must respond within twenty-four (24) hours to routine work requests.

Inspections: The Contractor must perform inspections, provide logs, and utilize checklists according to approved maintenance standards and as mandated by any acts, codes or regulations as contained in Appendix B of this PWS or any state or local requirements. When a maintenance or repair requirement is identified in an inspection, the Contractor shall enter it in the CMMS work order system and perform the required work according to Section 5.12, Repairs and other applicable provisions of this PWS.

Logs and Checklists
The Contractor shall perform inspections, provide logs, and utilize checklists according to approved maintenance standards and as mandated by any acts, codes or regulations. When a maintenance or repair requirement is identified in an inspection, the Contractor shall enter it in the CMMS work

order system and perform the required work. Logs and checklists must be completed at the time of inspection. Information recorded on logs must be adequate to track the operating hours and performance history of the equipment. Logs may be provided through the BAS, if such monitoring and recorded history provides sufficient data to allow for analysis of trends in equipment performance and troubleshooting. Checklists must be readily accessible at major equipment locations.

5.5.6.16 Condensate Pans and Drains. The Contractor shall inspect condensate pans and drains of air handling units, air conditioning (A/C) package units, window A/C units, and other equipment items IAW approved industry maintenance standards. If any condensate pan is inaccessible, the Contractor must notify the Government.

5.5.6.17 Alarm Monitoring and Control Systems. The Contractor is responsible for retaining an adequate level of expertise to manage all alarm, monitoring and control systems. All computers networked with alarm, monitoring and control systems must be maintained by the Contractor to ensure reliability and security are maintained IAW FISMA standards. Other DOC or NOAA requirements may apply. The Contractor shall respond to any alarm generated by the BAS or any other monitoring system, including but not limited to: temperature and humidity alarms, system failure alarms, fire/life safety alarms, under floor water detection alarms and Supervisory Control and Data Acquisition (SCADA) alarms.

5.5.6.18 Building Automation Systems. The Contractor shall maintain the BAS systems using qualified and trained employees. Technicians must be certified to maintain the software. The Contractor shall provide onsite support on a quarterly basis including installation of all necessary software updates. The Contractor shall be responsible for operating the BAS, following proper sequence of operations, responding to and acknowledging alarms, monitoring the space and equipment conditions, and contributing feedback and suggestions to help reach optimal operating procedures. Additionally, the Contractor shall be responsible for proper configuration, operation, calibration, and maintenance of BAS and all associated automatic controls and controllers. The Contractor shall utilize BAS for trending and as an appropriate means of quality control.

5.5.6.19 Protection and Damage. The Contractor shall make reasonable efforts to prevent hazardous conditions and property damage and to maintain security. The Contractor shall report such conditions or activities to the Government, security personnel, or authorities. The Contractor shall protect Government property, materials, equipment, supplies, records, and data within the Contractor's control against unauthorized access, loss, or damage. The Contractor shall establish and implement a system for onsite workforce personnel to report potentially hazardous conditions to the Government. The Contractor, its employees, and subcontractors shall comply with the Government's Rules and Regulations Governing Public Buildings and Grounds and shall report violations by employees, or as otherwise observed, to the COR or security personnel within 24 hours. The Contractor shall provide reasonable assistance to security or emergency response personnel as needed.

5.5.6.20 Key Control. The Contractor shall follow the Government's key control program. Keys issued to the Contractor, or the Contractor's personnel or subcontractors, shall be signed for and not transferred to other personnel unless recorded in the key control log. The Contractor is financially liable for the cost of rekeying if keys are lost or not recovered from terminated employees or subcontractors.

5.5.6.21 Disruptive or Hazardous Tools. The Contractor shall use tools which have the potential to disrupt occupants, for example impact and power-actuated tools, only with permission from the

Station Manager or their designee. Burning or welding equipment may be used only with written permission from the Station Manager or their designee. A Welding and Burning Permit must be issued in advance for each day welding or burning is performed.

5.5.6.22 Disruption to Utilities. Any work that will disrupt HVAC, utilities, fire protection, life safety systems, or other Station infrastructure shall be scheduled and approved, at a minimum, 30 days in advance with the Station Manager or designee.

5.5.6.23 Plumbing. Plumbing systems shall be maintained, repaired, and kept functional. The Contractor shall ensure all system drains, including storm drainage and roof drains, remain clear and unobstructed. The Contractor shall take any necessary steps to prevent odors emitting from drains or other plumbing systems into occupied space, to include keeping water in traps appropriately maintained. The Contractor shall clear toilet and sink blockages, as necessary. Such requests shall be submitted using the service request procedures. When replacing plumbing fixtures, use the most reduced water usage device as approved by the CO or designee.

5.5.7 Facilities Maintenance Program. The Contractor shall establish an effective program and procedure for scheduling and performing preventive maintenance. The Contractor shall submit the Facilities Maintenance Plan to the CO or designee, including the list of items receiving a preventive maintenance procedure, as well as the specific maintenance standard or guide describing the preventive maintenance procedure and frequency within seven days after Contract start date.

5.5.7.1 Maintenance Standard. The Contractor shall propose to the COR or designee, preventive or predictive maintenance standards for each piece of equipment where the manufacturer/designer recommends preventive maintenance IAW the latest version of the PM Guide.

5.5.8 Fuel Ordering and Receiving. The Contractor shall be responsible for ordering and receiving fuel deliveries as needed. All fuel shall include appropriate additives and fuel stabilizers for year-round operations. The Contractor shall provide fuel polishing and testing annually. Emergency generator fuel storage tanks shall be maintained with stable fuel conditions (not oxidized, no contaminants) and tested every six (6) months for combustibility IAW generator OEM specifications. Government approval is required prior to placing any order for fuel. Orders will be placed through Defense Logistics Agency Interagency Agreement. Standards are as follows.

Fuel ordering for emergency generators:

- Normal (standby) condition — Maintain tank level ¾ full, minimum
- Emergency (utility outage) condition — Order when tank level reaches ½ full
- All conditions — Prevent tank level from going below ¼ full

The Contractor shall ensure that each fuel delivery:

- Is ordered in a quantity that will fit into the available empty space in the tank.
- Is supervised by an operator trained as required by federal, state, and local regulations.
- Is protected against spills and overfills IAW EPA and other applicable regulations.
- Is accompanied by a receipt from the fuel vendor, provided to the COR, including fuel type delivered, fuel quantity delivered, date and time of fuel delivery, name of delivery person, vendor name, and telephone number.

The Contractor shall provide a monthly report of fuel usage by type and tank location.

The Contractor shall advise the Government regarding the type(s) and quantities of spill kits required, but the cost of purchasing spill kits is not included in the firm-fixed-price CLINs. The

Contractor shall be responsible for inspecting and maintaining spill kits on site. The Contractor shall be responsible for spill cleanups IAW the Station Spill Prevention Control and Countermeasure Plan. The Contractor shall provide a fuel usage report per tank on the 10th day of the month for the previous month.

5.5.9 Electrical Systems. The Contractor is responsible for electrical systems starting at the point of service delivery to Station infrastructure from the local utility provider. The Contractor shall maintain electronic backups of all powerhouse control and power system configurations and files and software in case critical failures occur and configurations are lost. The Contractor shall ensure that any and all areas restricted to qualified personnel are secured and properly labeled. The Contractor shall ensure all employees working on electrical systems are journeyman-level electricians. At least one electrician shall be professionally qualified in power generation systems with a minimum of two years' experience in power house operations and maintenance.

5.5.10 Water Treatment. The Contractor shall provide water treatment meeting, or exceeding, the GSA PM Guide standards. The PM Guide Water Treatment Standard shall also apply to hot (heating) water systems.

5.5.11 Architectural and Structural Systems Maintenance. The Contractor shall maintain, repair, replace, modify, and restore existing architectural and structural components of the buildings as needed to maintain the integrity, function, and appearance of the space. The Contractor shall conduct routine inspection and maintenance and repair of interior and exterior architectural and structural systems components. All replacement items and parts shall be either the same quality or better than the manufacturer's original parts.

5.5.11.1 Maintenance and Repair. The Contractor shall perform all architectural and structural maintenance and repairs or replacements to all equipment, electrical and mechanical systems, structures, architectural finishes, and utilities (excluding the property maintained by the utility companies, if applicable), located on, within, or beneath, the Station's interior and exterior extending to the legal property line. The Contractor shall use approaches that preserve and protect native plants and wildlife that are entrusted to the Government, and that support habitats for pollinators, including honey bees, native bees, birds, bats, and butterflies.

5.5.11.2 Repair and Replacement Work. Repair and replacement work shall be complete, including touch-up painting and operational checks. The quality of the work shall ensure that repaired areas are fully compatible with and match adjacent surfaces or equipment. All replacement items shall be consistent with design documents and match existing equipment in quality, dimension, material, quality of workmanship, finish, and color.

5.5.11.3 Painting. Painting is considered "touch-up," for purposes of this Contract, when it is to repair a specific damaged area of paint. Painting should extend to logical break points such as the floor, ceiling corner, doorway etc. to avoid a patched look. Re-striping of parking areas, driveways, roads, and vehicle inspection areas is required where striping is damaged or worn in a specific location, but not for general wear and tear of a large area over time. The machinery rooms, including floors and the equipment located within the machinery rooms, shall be painted, as necessary, to maintain the appearance of the room and equipment. When painting, the Contractor shall comply with the American National Standards Institute (ANSI) color coding system outlined in the ANSI A13.1.

5.5.11.4 Interior Signage and Directories. The Contractor shall maintain and update building directories, maps, and emergency directions to include electronic directories and corridor signage

as needed. Buildings shall be clearly marked with identification on the exterior. All rooms shall have numbers. The Contractor shall repair damaged interior or exterior signage IAW the repair's provisions (Para 5.5.12) in this document.

5.5.11.5 Finishes Maintenance. The Contractor shall ensure finishes are maintained to the manufacturer's specifications and levels that preserve a professional appearance and the integrity of the protected surface. The Contractor shall provide touch-up paint on repaired surfaces that seamlessly matches the surface and condition prior to degradation and repair.

5.5.12 Repairs. The intent of this Contract is to ensure that most repairs will be accomplished without use of subcontractors. However, the Government recognizes that occasionally certain repairs require the specialized skills of a subcontractor. If the Contractor identifies a repair, it believes can only be performed by a specialized subcontractor, the Contractor shall provide written justification in advance, to the COR for approval before proceeding. The Contractor shall assure that the subcontractor's cost is fair and reasonable by obtaining multiple quotes, if possible, and approved in advance by the COR. Repairs shall be approved by the Government and will be reimbursed by the Government under the time and materials (T&M) contract line item number (CLIN). The Government reserves the right to order repairs from an outside source.

5.5.13 Grounds Maintenance. The Contractor shall provide all labor for grounds maintenance. Grounds maintenance must be performed in a manner that will promote the growth of healthy grass, trees, shrubs, and plants and present a clean, neat, and professional appearance.

Maintain Improved Grounds

Improved grounds consist of the Station core area. The Station core is bordered by Eisele Road at the south and natural (creek, forest) barriers at the north. Its western limit is approximately thirty (30) feet west of the Facilities Building. Its eastern limit is approximately thirty (30) feet east of the warehouse yard.

a. **Mow**. The Contractor shall mow all improved grounds to look well-manicured, maintained uniformly, free of weeds, overgrowth, bare patches, and trip hazards. Maintain grass height between 3- and 5-inches uniform in appearance, free of skips, gaps, rutting, or scalping.

b. **Edge**. The Contractor shall edge improved grounds for appearance and as necessary for infrastructure protection, edge sidewalks, driveways, street edges, curbs, and other hard surfaces located within the improved grounds. Edging shall include removal of vegetation from expansion joints and cracks in sidewalks, driveways, curbs, and other hard surfaces.

c. **Trim**. The Contractor shall trim improved grounds for appearance and as necessary for infrastructure protection, around trees, shrubs, buildings, fences, poles, fire hydrants, parking lot bumper blocks, boulders, and other fixed obstacles and temporary obstacles/objects on improved grounds.

d. **Remove Debris/Police Grounds**. The Contractor shall perform general litter patrol in all areas of improved grounds and additional areas, as required, for operational safety, and Anti-Terrorism/Force Protection (AT/FP). Remove and dispose of natural debris, (tree limbs, dry brush, rodent habitats, etc.), and man-made debris. The Contractor shall police areas to maintain a neat and professional appearance.

e. **Leaf Removal**. The Contractor shall remove leaves in improved grounds to maintain a neat and professional appearance as required to prevent drainage and lawn disease problems.

f. **Fertilization**. The Contractor shall create a pH adjustment and fertilizer application program. The Contractor shall perform laboratory testing of the soil in improved grounds and apply fertilizer and lime using procedures appropriate for the soil conditions found, type of grass, and season. Apply fertilizer and other soil amendments as necessary to bring soil conditions that are suitable for the vegetation being treated. Limit to only improved grounds.

g. **Weed Control**. The Contractor shall limit weed control to noxious or invasive.

Maintain Semi-Improved Grounds

Semi-improved grounds consist of all other grass covered areas, shoulders of paved and unpaved roads, cable tray routes, antenna fields, and collimation tower fields. Maintain both sides of fences.

a. **Mow/Trim**. The Contractor shall maintain grass height between 7 and 14 inches. Maintain a uniform appearance in all areas. Trimming will only be accomplished to prevent infiltration of manholes, grates, equipment, other infrastructure or for safety. Maintain both sides of fences to prevent infiltration, breach, or damage due to vegetation.

b. **Weed Control**. The contractor shall limit weed control to noxious or invasive weeds.

Maintain Surface Drainage

The Contractor shall maintain surface drainage ditches and culverts to be free of shrubs, trees, silt, and trash, to prevent erosion and ensure continuous flow of water.

5.5.14 Snow and Ice Removal. The Contractor shall track snow and ice accumulation, and perform snow and ice removal when necessary to maintain FCDAS operating capability, safety, and protection of property, including nights, weekends, and holidays. The Contractor shall remove snow and ice from FCDAS roads, parking areas, walkways, antenna pads, roofs, and drains. The Contractor shall use vehicles and vehicle mountable plows furnished by the Government.

5.5.14.1 Snow. The Contractor shall remove snow to provide safe driving conditions and maintain FCDAS operating capability. Snow removal shall begin when a snow event or snow drifting commences, and when the accumulation of snowfall or drifting reaches at least two (2) inches in depth or at the discretion of the equipment operators or Facilities Manager.

5.5.14.2 Ice. The Contractor shall remove ice to provide secure footing and safe driving conditions, to maintain drainage through culverts, and to maintain access to all areas on site. Ice control operations shall begin within one hour of the beginning of an ice event, rain, or unseasonal warming or any other condition that causes dangerous icing conditions or upon notification by the Government.

5.5.15 Custodial Services. The Contractor shall provide custodial and general housekeeping services without negatively impacting the critical operations. The Government will furnish all cleaning equipment, tools, materials and supplies. The Contractor shall maintain the material safety data sheets (MSDS) in a location accessible to all employees at all times and shall advise the Government of its location. All chemicals will be labeled IAW their MSDS. The MSDS shall be available for inspection by the Government on request. Natural disasters, infectious outbreaks, and other one-time events may cause a need for the Contractor to perform Deep Cleaning on an as-needed basis at work offices, shops, and in industrial areas at FCDAS IAW industry standards.

Custodial services are required in the following areas:

a. Fairbanks Satellite Operations Facility: All areas
b. Contingency Operations Area: All areas
c. Facilities Building: Vestibules, corridor, lobby, conference room, supervisor's office, break room, kitchen, restrooms
d. Power House: Office, restroom
e. Gilmore Creek Geophysical Observatory: Working and storage areas
f. Security Guard Buildings

The Contractor shall provide the following services:

a. Weekly trash removal (dumpster and hauling services provided by the Government).
b. Weekly recyclables sorting, removal, hauling, and proper disposal at facilities approved by the Government, with disposal records including weight.
c. Annual scrap removal, hauling, and proper disposal at facilities approved by the Government, with disposal records including weight. Recyclables include, but are not limited to, building materials, cardboard and packing materials, old furniture, obsolete electronics and cables, etc. Recycle scrap where applicable.
d. General housekeeping of the custodial services areas to include dusting, vacuuming, sweeping, wiping down surface areas, and any other services necessary to ensure surfaces are free of visible dirt, dust, smudges, and debris.
e. Any area that has carpet shall receive spot cleaning, as needed, and shampooing services annually.
f. Monthly cleaning of areas containing raised flooring. The Contractor shall maintain all facilities in a clean, sanitary, and professional condition. For areas containing raised flooring or sensitive electrical/data processing equipment, the Contractor shall utilize specialized cleaning methods that prevent static discharge, moisture damage, and dust accumulation without disrupting operations. Carpets shall be maintained free of noticeable stains, odors, and excessive wear.
g. Control rooms and any space with raised flooring shall receive semi-annual static- dissipative solution cleaning.
h. Maintaining data processing rooms to be free of dust and debris, as much as possible without touching the data processing equipment.
i. The Contractor shall provide vacuuming and light dusting of the data processing equipment racks by qualified personnel as part of regular preventive maintenance.
j. The Contractor shall maintain walk off pads at entrances to the data processing room.
k. Annually the Contractor shall inspect the under-floor plenum, and if necessary, use a specialized data center cleaning subcontractor to thoroughly clean.
l. Annually clean and damp wipe the fan wall duct system and the Computer Room Air Conditioning supply ducts that are accessible via the access doors and hatches.
m. Mechanical spaces shall be kept orderly and free of dirt, grime, and shall be swept routinely to prevent the buildup of dust.

5.5.16 Vehicles and Mobile Equipment. The Contractor may operate Government-owned motor vehicles and mobile equipment for official purposes only and solely in the performance of the Contract. The Contractor shall establish and enforce suitable penalties against employees who use, or authorize the use of, such motor vehicles for unofficial purposes, or for other than in the performance of the contract and shall pay any expenses or cost, without Government reimbursement, for unauthorized use. In the event the Contractor takes a Government owned or leased vehicle off FCDAS property, the Contractor shall provide written notification to the Government. Notification shall include name of contract employee using the vehicle, the vehicle being used, departing time and anticipated return time,

date, and destination. Monthly vehicle maintenance, mileage, and fuel reports are required for both GSA and NOAA-owned vehicles/equipment.

5.5.16.1 Operator Responsibilities for General Services Administration (GSA) Fleet Vehicles. For GSA Fleet vehicles, NOAA pays monthly lease and mileage rates that include all maintenance and fuel expenses. The Contractor does not provide maintenance, fuel, or repair of GSA Fleet vehicles, but the Contractor shall fulfill vehicle operator responsibilities as described in GSA publication "Guide to Your Fleet Vehicle."
(https://www.gsa.gov/system/files/05-21-00177_VehicleGuide.pdf)

5.5.16.2 Maintenance and Repair of NOAA-owned Vehicles and Mobile Equipment. The Contractor shall maintain and repair NOAA-owned vehicles and mobile equipment to maximize their availability, using practices that minimize unscheduled repairs and that return vehicles requiring repair to service in as little time as possible, including: (1) reporting odometer/hour readings at least once per month, (2) performing preventive maintenance and repairs to meet federal, state, and local emission standards, (3) reporting through the Federal Automotive Statistical Tool (FAST) using Standard Form 82, Agency Report of Motor Vehicle Data, to ensure uniformity of reporting, and (4) obtaining proper licenses via the DOC Fleet Manager.

5.6 Environmental, Safety, and Health. The Contractor shall ensure personnel have a safe and healthy work environment. The Contractor's safety program shall instruct employees on how to eliminate hazards or cope with them in a safe manner. The Contractor shall comply with all federal, state, and local laws and regulations that relate to maintenance and operation of equipment and systems within the scope of this contract, to include permitting, plans, inspection, and personnel safety, control of hazardous substances, certification, and recordkeeping.

5.6.1 Environmental, Safety, and Health Manager (ESH). The Government requires an ESH Manager to develop and direct the implementation of appropriate plans and procedures to meet federal, state, and local regulations. This is a critical position. The ESH Manager shall have and maintain professional certification appropriate for the type and scope of work environment at FCDAS.

5.6.2 Scheduling and Recordkeeping. The Contractor shall maintain copies of all such tests, certifications, permits, and other required records, and provide copies to the Government upon receipt. In addition, all required safety and environmental tests, certifications, permits, plans, and other procedures required in this document must be scheduled in the CMMS work order system and documented therein.

5.6.3 Environmental Controls. The Contractor shall control refrigerants and maintain records IAW the United States Environmental Protection Agency (EPA) and air quality management district standards. The Contractor shall take appropriate immediate action and report leaks to the Government. Refrigerant control logs must be updated, as required, and a copy sent to the Government. The Contractor shall be familiar with the requirements of the local Air Quality Management District (AQMD), and shall be responsible for obtaining operating permits for generators and other emissions-producing equipment regulated by the district and making copies available to the Government. The Contractor shall comply with all requirements, including record keeping, related to the storage, transport, and disposal, of hazardous or regulated waste and materials used or removed in the performance of the contract or discharged by the building. The Contractor shall annually inspect all transformers containing polychlorinated biphenyls (PCBs) and maintain records of such inspections IAW state, local, and EPA regulations.

5.6.4 Facility Hazards. The Contractor shall identify facility health and safety hazards and report all hazards in writing to the COR. The Contractor shall take immediate action to control hazards that present an imminent danger.

5.6.5 Workplace Safety. The Contractor shall develop a site-specific occupational ESH program specifically addressing applicable Occupational Safety and Health Administration (OSHA) standards as outlined in Appendix B. The ESH program must be submitted to the COR or designee for review and approval no more than 30 days after the Contract award.. By approving the program, the Government assumes no responsibility for the Contractor's occupational ESH program. ESH Program shall include at a minimum (1) pandemic preparation plan, (2) personal protective equipment (PPE), (3) fall protection, (4) lockout/tagout, (5) confined spaces, (6) asbestos management, (7) hazardous materials, (8) labeling and signage, (9) underground and above ground storage tanks, and (10) used oil. The ESH Manager will personally brief visitors on site safety requirements as well as current safety topics.

5.6.5.1 *Pandemic Planning*. Within 30 days after contract award, the contractor shall provide a Pandemic Preparation Plan which fully supports the Station's 24x7x365 operations, and is compliant with all federal, state, NOAA and NESDIS guidelines. The Pandemic Preparation Plan shall be reviewed, and updated if necessary annually, or as required by the CO or his designee.

5.6.5.2 *Personal Protective Equipment.* If the site-specific ESH program includes use of personal protective equipment (PPE), the Contractor shall provide the PPE and implement a PPE program which addresses the hazards present; the selection, maintenance, and use of PPE; the training of employees; and monitoring of the program to ensure its ongoing effectiveness.

The Contractor shall provide general purpose PPE to its employees as required for their respective duties. This PPE includes, but is not limited to, ear, eye, face, head, hand, and foot protection; breathing apparatus or dust masks; flame retardant or arc-flash clothing; cold weather clothing; electrically or thermally insulated gloves, bibs, and coveralls; harnesses, lanyards, or ropes; and hazard exposure monitors.

5.6.5.3 *Fall Protection.* The Contractor shall develop specific fall protection procedures for work on roofs, equipment, and other areas at elevation. The Contractor shall ensure fall protection equipment is provided to its employees and that employees are adequately trained in fall prevention.

5.6.5.4 *Lockout/Tagout.* The Contractor shall develop a lockout/tagout program in accordance with 29 CFR 1910.147 within 30 days of contract award. The program shall include all anticipated energy sources, including but not limited to, electricity, steam, pressurized fluids, and mechanical energy. The Contractor shall communicate the lockout/tagout program to all other affected contractors.

5.6.5.5 *Confined Spaces.* The Contractor shall identify and label all confined spaces in accordance with OSHA requirements. The Contractor shall develop a confined space entry permit system for all permit-required confined spaces within 60 calendar days of commencement of the contract.

5.6.5.6 *Asbestos Management.* The Contractor shall be expected to occasionally perform Class III and Class IV asbestos work as defined in 29 CFR 1926.1101. The Contractor shall be prepared to deal with asbestos on a small-scale, short- duration basis to effect emergency repairs and to clean up small spills. Inadvertent damage to or spillage of asbestos-containing materials may require mitigation within Class III and Class IV definitions or applicable local, state, or federal regulations. The Contractor shall protect building tenants, visitors, and employees from asbestos exposure. The

Contractor shall comply with applicable OSHA regulations and all applicable federal, state, and local asbestos regulations. The Contractor shall immediately become familiar with, comply with, and recommend any appropriate changes to the Government Asbestos Management Plan for each building. If the Contractor must disturb materials it suspects may be Asbestos Containing Material, the Contractor shall immediately report the condition to the CO or designee. Contractor personnel who perform the above mentioned work shall have been appropriately trained in accordance with 40 CFR Part 763.

5.6.5.7 *Hazardous Materials.* The Contractor shall make material safety data sheets (MSDS) available to its employees in accordance with 29 CFR 1910.1200. MSDS shall also be made available to the CO or their designee on request. The Contractor shall prepare and submit a hazardous materials inventory as an appendix to the building operating plan. The inventory shall itemize all hazardous materials by specific type as sold with individual SDS and include information pertaining to approximate quantities of each type and exact locations where hazardous materials are to be stored on the premises. The Contractor shall ensure all chemicals are labeled correctly in accordance with their MSDS.

5.6.5.8 *Labeling and Signage.* The Contractor shall maintain the labeling of existing equipment, pipes, storage areas, containers, confined space, and workspaces as well as associated signage, in accordance with OSHA standards to ensure labels are visible and not obliterated. Any equipment, conduit, pipes, wiring, cabling, doorways, covers, panels and similar alterations newly installed by the Contractor require labeling and signage per OSHA standards. These must be labeled immediately upon completion of the installation and maintained throughout the contract period.

5.6.5.9 *Underground (UST) and Above Ground (AST) Storage Tanks.* The Contractor is responsible for complying with all federal, state, and local requirements for the periodic inspection, monitoring, permitting, certification and maintenance of USTs and ASTs and their systems. For non-regulated USTs and ASTs and their systems, the Contractor shall implement best management practices regarding inspection, monitoring, and maintenance of the tanks and systems to prevent leaks, spills and other unauthorized releases.

5.6.5.10 *Used Oil.* The Contractor shall comply with all local, state, and federal regulation requirements for managing used oil including but not limited to, storage, labeling, transport, recycling, or disposal. All recycling and disposal records shall be kept on-site and provided to the Government upon request.

5.7 Property Management and Logistics. The Contractor shall perform personal property management services for the Station IAW Federal Management Regulation and NOAA personal property management policies and procedures. The Contractor is fully responsible for management and accountability of station property under provisions of FAR 52.245-1. The Station has designated a Government Property Custodian (PC) and a Property Accountability Official (PAO) for oversight and certain inherently Governmental functions. Current personal property inventories and inventory dollar value at the station are approximately:

Table 6 – Personal Property Inventory

Property Class	Approx. Quantity	Dollar Value
Non-Capitalized	1,130 line items	$55,618,086.60
Capital Property	19 line items	$35,289,767
Stocked Items	10,000 line items	$3,000,000

5.7.1 Sunflower Property Management System. The Contractor is directly responsible and accountable for all Government Furnished Property. The Contractor shall maintain a system of security and accountability for all Government Furnished Property IAW all applicable regulations and guidance. The Contractor shall be responsible for keeping the accuracy of the Sunflower property management system up to date as new equipment is procured and obsolete equipment excessed.

5.7.2 Personal Property Inventories. The Contractor shall carry out periodic inventories and an annual inventory as required by the NOAA Personal Property Management Branch (PPMB). In conjunction with the annual inventory, the Contractor shall validate property for turn-in, repair, "keep as emergency spare", auction/recycle, or for scrap. The Contractor shall provide an electronic property status report with make, model, serial number, Sunflower tag number, and any required photos within 30 days of completion/acceptance of annual inventory. In the event personal property is lost, stolen, or otherwise unsighted during the annual inventories, the Contractor shall prepare a complete Board of Review (BOR) package describing the item(s), circumstances surrounding the loss or theft, supporting materials such as a police report, and any efforts made to find or to recover the item(s). Ad hoc inventories and property audits may be required from NOAA's partner agencies to locate their equipment.

5.7.3 Miscellaneous Logistics Services. The Contractor shall (1) recommend and dispose of capital property, equipment, and parts that are either obsolete, damaged, or no longer required; (2) provide shipping and receiving services for the station; (3) prepare requisitions pertaining to orders of supply for parts, equipment, materials, repairs; (4) with Government approval, complete purchases of supplies and services following the FAR, Commerce Acquisition Regulation (CAR), Commerce Acquisition Manual (CAM), and NOAA Acquisition Manual (NAM) for all purchases up to the simplified acquisition threshold (SAT) using available time and material funds; (5) pickup from and delivery to carriers of shipments destined for, or departing from, FCDAS; and (6) provide assistance to operations and facilities personnel in analyzing, reporting, and correction of station anomalies through tracking equipment and component failures, as well as performing liaison with vendors for failure analysis and ensuring timely repairs.

The Contractor shall report quarterly the total number of property items cleared for turn in (per life cycle management), how many queued up for turn in (paperwork complete, but not yet 'shipped'), how many turned in (removed from Sunflower or CMMS), and how many are currently in process for gathering information for turn-in.

5.7.4 Deliveries. The Contractor shall be responsible for receiving all deliveries, including coordinating with vendors and Government personnel, scheduling, unloading, storing, and moving goods at FCDAS. However, formal acceptance of all deliveries shall be performed by a Government representative. Once accepted, the Contractor shall enter, or validate, property information accuracy in Sunflower and/or the CMMS.

5.8 Security Guard Services. The Contractor shall provide licensed, armed contract security officer (ACSO) services at FCDAS to provide a secure environment and protect people, information, and property at the Station. The ACSO's primary responsibility is to perform as a countermeasure to deter, detect, delay, deny, and devalue threats to Federal property, as well as to assist in ensuring the safety of employees and visitors while at Federal facilities. The six basic functions of ACSOs are (1) Access Control; (2) Screening; (3) Visitor Processing; (4) Patrol and Response; (5) Security System Operations; and (6) Common Tasks. A list of all tasks associated with these basic functions is listed in Appendix C. The Contractor shall develop and draft Post Orders in coordination with the Station Manager which shall be updated as required.

5.8.1 Emergency Condition. The Contractor's on-site supervisor or the shift supervisor shall take action as required by the Station Manager to divert personnel from their normal assigned duties to meet

the condition and summon appropriate personnel as may be required by the DOC/NOAA OEP for FCDAS, or as the situation demands.

5.8.2 Duties Performed. In addition to Appendix C, Security Guard Task, the following duties shall be performed by the Contractor as required by the COR or the Station Manager: (1) Maintain a copy of the OEP and be able to coordinate activities during fire or other occupant emergencies; (2) Maintain primary responsibility for emergency lockdown of all main and secondary entrance doors to prevent unauthorized access during demonstrations or other attempts at unauthorized access; (3) Patrol each floor of all buildings, walking up and down the stairwells; patrol the loading dock, and perimeter for at least every two hours, unless otherwise directed; (4) provide escort to any employee requesting such service within the FCDAS campus; and (5) Assist with fire drills and emergency evacuation of facilities with crowd and traffic control.

5.8.3 Hours of Operation and Scheduling. The Contractor shall maintain 24x7x365 coverage. At least one guard shall be available to screen visitors at the main gate at all times during the hours of 0600-1800 Monday through Friday, except federal holidays. Guards shall patrol FCDAS central campus and buildings at least three (3) times during any eight-hour period unless specifically stated otherwise in this PWS or as directed in post orders, which may modify procedures to accommodate exigent circumstances or changes in security threat level. The Contractor shall provide adequate staffing to accommodate guard vacations, illnesses, and short- term needs outside core hours. The Contractor shall staff and maintain posts during inclement weather, natural disaster, terrorist, and other potentially critical incidents. The Contractor shall provide a Contingency Plan within 30 calendar days after contract award for COR approval for deploying staff and maintaining post during inclement weather, natural disaster, terrorist, and other potentially critical incidents. Any plan revisions shall be submitted to the Station Manager for approval at least 14 calendar days prior to implementation, unless circumstances compel more near-term or immediate changes.

5.8.4 ACSO Supervision. The Contractor shall provide ACSO supervision, such as a lead guard, to schedule vacations, cover sick leave, and provide a level of oversight when problems arise or assistance is required.

5.8.5 Guard Qualifications, Licensing, and Training. The Contractor shall provide sufficient staffing with qualified personnel to comply with the requirements of the PWS and Post Orders. The Contractor shall comply with the minimum recommended standards outlined in *Armed Contract Security Officers in Federal Facilities: An Interagency Security Committee Best Practice* for hiring an ACSO.

5.8.6 ACSO Licensing. The Contractor employing ACSOs shall be licensed by the State of Alaska as an Armed ACSO Agency IAW Alaska Administrative Codes (AACs) 13 AAC 60.010 and 13 AAC 60.045. All ACSOs shall be licensed by the State of Alaska as Armed Security Guards IAW AAC 13 60.050 and 13 AAC 60.085. The licensing authority for the State of Alaska is the Commissioner, Alaska Department of Public Safety, Permits and Licensing Unit, 5700 E. Tudor Road, Anchorage, AK 99507.

5.8.7 ACSO Training. In addition to training requirements specified by the State of Alaska for licensing purposes, each ACSO shall be trained in non-lethal and lethal defensive use of force for the protection of themselves or others. Mandatory initial training with annual refresher training will include proper training of the "Use of Force" and "Types of Force"; escalation of force; and type(s) of equipment ACSOs will use. At a minimum, ACSOs shall be trained in use of oleoresin capsicum (OC) and 2-chlorobenzalmalononitrile (CS) irritants for defensive purposes within 60 days of hiring. Intermediate firearms training with an emphasis on defensive handgun shooting shall be conducted as soon as practical but not later than 12 months after initial hiring.

5.8.8 ACSO Vehicles and Equipment. Prior to the start of a new shift, the roving ACSO shall inspect the condition of the vehicle and annotate the condition in the daily report. Another vehicle will be assigned from the Station motor pool when the primary ACSO vehicle is unavailable due to scheduled maintenance or repairs. The ACSO vehicle shall remain at FCDAS at all times unless authorized by the Station Manager. ACSOs will be armed IAW Government policies and procedures.

5.8.9 Reporting and Incident Handling. ACSOs on each shift shall log daily events as they occur during their tour. The report shall include the Security Officer's name, shift worked, and daily events in time sequence occurring on the site. ACSOs shall take immediate action and report all incidents to the appropriate authorities such as the Alaska State Troopers, Bureau of Land Management law enforcement, or the Federal Bureau of Investigation (FBI). The lead ACSO on duty shall inform the Station Manager and operations shift leader of any security incident or safety- related concern as soon as practicable. Detailed incident reports are required for each security incident; e.g., trespassers, threats, or vandalism. Such incidents may require a report to be filed with the appropriate law enforcement authorities. Safety incidents and near-misses shall be documented separately for the Station's ESH Manager. Unauthorized persons discovered on the campus shall be asked to leave and will be escorted off the premises. Unauthorized vehicles approaching and within the grounds of FCDAS shall be monitored, and an incident report shall be made describing such vehicles and their occupants. ACSOs are advised not to coerce, apprehend, or detain persons unless life or Government property is in danger.

5.9 General Management. The Contractor shall provide labor and materials for general Contractor management functions at the station. At a minimum, these functions shall be provided with on-site representation during FCDAS business hours which are 0700-1500 hours local time, Monday through Friday, except Federal holidays.

a. Employment, training, performance evaluation, termination, discipline, and rewarding of Contractor employees.
    - The Contractor shall provide monthly training reports indicating which staff members conducted which training and provide access to training certificates.
b. Negotiating labor agreements, managing labor contracts, coordinating work efforts with the union stewards/business agents, and resolving grievances.
c. Preparing formal technical and cost proposals as requested by the CO for specific work, such as third-party mission support, and submission of these responses to the CO and COTR.
d. Negotiating or substantively participating in negotiations of changes to the contract with the Government;
e. Developing, documenting, implementation, and managing a system of internal audits whereby Contractor performance in the areas of cost control, configuration control, health and safety, regulatory agency compliance (including, but not limited to, EPA, OSHA, EEOC,), records management, reports, property management, security compliance, maintenance management, and mission operations performance may be periodically evaluated.
f. Developing, documenting, implementing, and managing a Quality Control Program that enhances FCDAS' reliability by providing for standards and uniformity of workmanship, routine tests and measurement, completeness and accuracy of reporting, and adherence to established NESDIS and station specifications and standards.
g. Implementing and maintaining a program that effectively manages Environmental, Health, and Safety programs at the station adhering to OSHA and U.S. DOC/NOAA/NESDIS standards, as well as applicable federal, state, and local regulations. The Contractor shall appoint a designated Environmental, Health, and Safety Officer with professional certification.
h. Performing other acts necessary to the total management of FCDAS employees and resources and ensuring Contractor compliance with terms of this contract.

5.9.1 Administrative Support. The Contractor shall (1) assist in the preparation of regularly scheduled reports; (2) develop and maintain a filing system according to NOAA's Records Management Guide and in conjunction with the NOAA Records Disposition Handbook; and (3) provide support to visitors as the point of contact for internal and external clients.

5.9.2 Program Management Support. The Contractor shall receive, read, and interpret the applicability of incoming actions, directives, notices, and invoices; and inform OSPO management of how these apply and what action is required while keeping managers informed both verbally and in writing of Action Item due dates. The Contractor shall keep the shared Action Item calendar updated and respond to the tasking office with station status updates.

The Contractor shall provide a monthly Program Management Review (PMR) to evaluate the status, progress, issues, risks, and performance of on-going and upcoming projects. The goal of a PMR is for the Program Manager to communicate to the Government Staff on the progress of cost, schedule, and performance; identify problems; and determine necessary corrective actions to ensure the program's successful delivery.

5.9.3 Technical Assistance. The contractor shall provide technical assistance by developing and maintaining spreadsheets of ongoing projects; coordinating with NESDIS staff to obtain updates on projects on a continuing basis; tracking project status on a daily/weekly basis utilizing spreadsheets; assisting with updating individual project schedules; and maintaining project-related and workforce-related files.

5.9.4 Equipment Condition Assessment. The Contractor shall continually inspect and note the condition and efficiency of equipment and systems. Any equipment or system that the Contractor determines is reaching the end of its life cycle or in need of immediate repair or replacement must be repaired or replaced. Report findings monthly.

5.9.5 On-Site Reference Library and Records Management. The Contractor shall maintain a comprehensive reference library to include all records, plans, and data generated in the performance of this contract that the Government considers to be essential. This information must be made available to the Government when requested and becomes the property of the Government. The Contractor shall safeguard this information IAW its sensitive nature.

5.9.6 Review of Design Documents. Utilizing the most qualified onsite personnel familiar with the operations of the facilities covered under the scope of this Contract, the Contractor shall review design and construction project documents as requested by the CO or designee. The Contractor may also be requested to provide input or propose ideas that may improve the operations and provide value engineering.

5.9.7 Building Management Support Services. The Contractor shall provide reasonable and competent assistance during business hours to Government personnel or other Government contractors performing energy studies, engineering studies, condition evaluations, project designs, and other access needs. The Government will inform the Contractor as far in advance as possible of the actual date and time these services are needed.

5.9.8 Labeling of Circuits. The Contractor shall maintain electrical, communication and IT circuit labels and electrical single line diagrams up-to-date. Electrical single line diagrams must be updated by creating and maintaining a working copy of record documents or best documents available at commencement of the contract as necessary.

5.10 Use of Computerized Maintenance Management System. The Contractor shall use the Government-furnished CMMS and property management systems to validate and update the equipment inventory database, including all data fields specified by the CO or designee. Where not previously established, the Contractor shall construct the inventory database. The Contractor shall use the CMMS to identify, control, track, and schedule preventive maintenance work, service requests, and equipment inventory. The Contractor shall track historical maintenance and repair activities for each work order received during the performance of the Contract. All work done by the Contractor shall be accomplished under a CMMS work order. The Contractor shall provide reports to the CO or designee as requested and, in a format and media as requested. On a yearly basis, the Contractor shall complete a CMMS audit in a format provided by the CO or designee. The Contractor shall correct any deficiencies noted on the audit within one month of receiving the report. The Contractor shall attend the CMMS training provided by the Government.

5.11 Quality Control Program (QCP). A QCP shall be developed and submitted for approval to the CO or their designee within 45 days after the start of the Contract. Upon approval, the Contractor shall implement the QCP to ensure Contract compliance, and to ensure that potential problems with building equipment and systems are identified, documented in CMMS if applicable, and resolved prior to failure. An acceptable QCP shall include, at a minimum, inspections by onsite supervisory personnel and by one or more qualified outside parties. The system of checklists, inspection methodology, and frequencies shall be documented by the Contractor. The Contractor shall maintain a Local file of all quality control inspections conducted by the Contractor, including the corrective actions taken and submit copies of quality control inspections monthly in the Monthly Progress Report. All documentation shall be made available to the Government upon request during the term of the Contract. The QCP shall include, at a minimum, the program of outside inspections, work orders sampling methodology, and a program for verifying compliance with each Contract requirement.

5.12 Government Quality Assurance Surveillance Program (QASP) and Reporting Requirements Summary. The Government will inspect Contractor performance using a QASP, available in Appendix D, consisting of random inspections, scheduled inspections, or any other method of inspection that the Government determines reflects Contract performance. A consolidated table of reporting requirements from this PWS are available in Appendix E.

5.13 Building Operating Plan (BOP). The Contractor shall revise or prepare and submit for approval to the CO or their designee a BOP, not later than 30 days after commencement of performance under this contract. The BOP shall outline operating and general maintenance procedures for all major building equipment and systems. The BOP is designed to be a standalone document that is a vehicle for the Contractor to document its plan for operating and maintaining the buildings and it is also a repository for several documents required throughout the Contract. The Contractor shall execute the Contract requirements IAW the approved BOP. The Contractor shall coordinate with the CO or their designee in developing the components of the Plan IAW the building operating plan template provided by the CO or designee. The BOP shall be submitted as an electronic file with regular updates that reflect current personnel, subcontractors, equipment, systems, and operating procedures. The Contractor shall review and update the BOP monthly and submit a searchable electronic file of the updated BOP with each change and no less than on each year's anniversary of the Contract start date.

5.14 Contract Security Requirements. All Contractor employees shall undergo preliminary background screening by the Contractor as a condition of employment.

5.14.1 General Security Requirements. When a successful background check or security clearance cannot be obtained by a Contractor employee, the Contractor shall have that individual replaced at no cost to the Government.

5.14.2 Access to Classified National Security Information (CNSI)

Performance of this contract requires access to CNSI (including documents and material) and Controlled Unclassified Information (CUI). CNSI is Government information which requires protection in accordance with Executive Order 13526, CNSI as amended and supplemental directives. CUI is sensitive unclassified information generally not authorized for release to the public governed by Executive Order 13556, Controlled Unclassified Information, 32 CFR Part 2002, and the CUI Registry.

The Contractor shall abide by the requirements set forth in the DD Form 254, Contract Security Classification Specification, an attachment to the contract, and 32 CFR Part 117 National Industrial Security Program Operating Manual (NISPOM) for the protection of CNSI and CUI at authorized contract and government facilities based upon the Facility Clearance Level (FCL) granted by the Defense Counterintelligence and Security Agency (DCSA). When the Contractor is required to have access to CNSI and CUI at a Department of Commerce (Department) or other Government Facility, it shall abide by the requirements set forth by the respective agency(s).

SECURITY REQUIREMENTS:

- Required FCL: The contract company supporting this contract/task order must possess and retain an active and Final Secret FCL granted by DCSA from the time of proposal and throughout the performance period.
- Provide the specific tasks that will require access to CNSI in the performance of the contract. Add rows as needed:

PWS Task / Subtask	**Clearance Level**	**Level of Classified Access**	**Justification for Access to Classified**
5.2.2 Communications Security (COMSEC)	*SECRET*	*COMSEC*	*Carry out COMSEC user functions such as loading cryptographic keys or resolving COMSEC-related alarms 24x7x365.*
Number of Contractor Employees	**Clearance/Access Required**	**Position Description**	
1	*SECRET/COMSEC*	*Operations Manager*	
9	*SECRET/COMSEC*	*O&M Technician**	

*This role can be filled by a Shift Lead, Shift, and Shift Float, as long as there is one Shift Day individual who has the required clearance

5.14.2.1 Contractor employees shall comply with all Government security regulations and requirements including entry and exit control for personnel and property at the government facility. Initial and periodic safety and security training and briefings will be provided by Government security personnel. Failure to comply with Government security regulations and requirements shall require the company to provide the Government with a written remediation/corrective action plan; furthermore, failure to comply with such requirements can be cause for removal and the contractor will not be able to provide service on this contract/order.

5.14.2.2 The Contractor shall not divulge any information, classified or unclassified, about Department files, data processing activities or functions, user identifications, passwords, or any other knowledge that may be gained, to anyone who is not authorized to have access to such information.

The Contractor shall observe and comply with the security provisions in effect at the Department facility. Identification shall be worn and displayed as required.

5.14.2.3 OSY retains the right to request removal of contractor personnel regardless of prior clearance or adjudication status, whose actions, while assigned to this contract, clearly conflict with the interest of the Government.

5.14.2.4. The Contractor shall afford the Government access to the contractor's facilities, installations, operations, documentation, databases and personnel used in performance of the contract/order. Access shall be provided to the extent required to carry out a program of information technology inspection (to include vulnerability testing), investigation and audit to safeguard against threats and hazards to the integrity, availability and confidentiality of data or to the function of information technology systems operated on behalf of the Department, and to preserve evidence.

Additionally, any provision to permit contractor teleworking may be revoked at any time if the Government makes such a determination. Teleworking provisions do not change any task order requirements; all other terms and conditions remain in full force and effect.

5.14.2.5. The Contractor shall notify the COR of all resignations/terminations/deaths of contractors within two (2) business days of the last day of employment. The Contractor shall return to the COR all Department issued identification cards, building passes and equipment when no longer providing contract support to Department /Bureau. The COR shall coordinate with the contract FSO to assist in the facilitation of the timely return and notification of contractors, who are no longer providing contract support to the Department /Bureau as soon as known. If an identification card or building pass is not available to be returned, an incident report shall be submitted to the COR, referencing the pass or card number, name of individual to whom issued and the last known location and disposition of the ID Card or building pass. Refer to the Commerce Acquisition Manual (CAM) and the Office of Security for additional information regarding out-processing.

5.14.2.6. Repeated loss of government property to include ID Card or building pass may be grounds for termination or reduced access for any Department contractor.

5.14.2.7. Insider Risk training for Contractors may be found at: https://doc.csod.com/ui/lms-learning-details/app/course/5511a403-6862-4f2a-a83e-515c3f4ca190. Certificate of training is required for all contractors. All certificates shall be sent to the Insider Risk Management Program Office (IRMPO): insiderrisk@doc.gov and the DOC Contracting Officer Representative. Subsequently, this training must be completed annually.

5.14.3 Classified Work and Access to Classified Information. All personnel requiring a Final Secret determination for access under this contract/order shall undergo a favorably adjudicated Tier 3 (T3) Investigation formerly known as a National Agency Check, Local Agency Check and Credit Check or Access National Agency Check and Inquiries as a minimum investigation. Tier 3 Investigations must be kept current within a 10-year window. To initiate a Secret Periodic Reinvestigation, a Tier 3R investigation must be submitted before the 10-year anniversary of the previous Tier 3. Additionally, all personnel requiring Secret access are required to be enrolled in Continuous Vetting (CV).

5.14.3.1 Suitability Requirements. Contractor personnel performing directly or indirectly on this contract have a requirement to obtain a suitability determination conducted by the Government.

The Contractor is responsible for ensuring the Program Security Officer (PSO), Key Personnel, and others as appropriate, receive formal suitability adjudication by The DOC Office of Security

(OSY). Contractor shall have PSO and Key Personnel provide required information and documents to COR within 10 calendar days after contract award and shall have all other personnel provide the required documentation as soon as practical. The Contractor shall submit suitability packages 45 to 60 days prior to current suitability expiration date.

The Government shall make all Contractor suitability determinations comparable to and IAW criteria outlined in Executive Order 13467, Reforming Processes Related to Suitability for Government Employment, Fitness for Contractor Employees, and Eligibility for Access to Classified National Security Information.

The Contractor is responsible for renewing employees' suitability determination prior to expiration. The Contractor shall remove contract employee(s) upon expiration of suitability.

The Contractor shall submit suitability packages 45 to 60 days prior to current suitability expiration date. The Contractor shall ensure forms submitted to DOC are complete, legible, and accurate. DOC will return illegible or incomplete forms submitted, which may result in delays of the adjudication process.

The Government shall not be responsible for any delays which occur due to the Contractor's inability to submit complete, accurate, and legible forms.

The Contractor shall use an electronic employment eligibility verification system (e-Verify) to verify employment eligibility of:

- Persons hired during contract term by the Contractor, to perform employment duties within the United States; and Persons assigned by the Contractor, to perform work within the United States on Federal contracts.
- The Government provides an electronic fingerprint scanning machine.

The CO shall have express authority to prohibit any employee from performing under contract until the employee comes into full compliance with suitability criteria.

The Contractor is responsible for all costs associated with obtaining and renewing suitability determinations for employees associated with this contract.

Positions involving major and immediate responsibility for, and the ability to act independently without detection to compromise or exploit, the design, installation, operation, or maintenance of critical infrastructure systems or programs, are designated Critical-Sensitive National Security positions. Such employees shall complete a Tier 2 Investigation. This requirement applies to personnel performing satellite operations and maintenance; IT, network, and communications operations, maintenance, and security; electrical power generation and distribution operations and maintenance; and ACSO services.

Positions other than those meeting the criteria for Critical-Sensitive National Security designation shall be deemed Low Risk and will require Tier 1 Investigation.

5.14.3.2 Suitability Determination. Once a prospective contract employee applies for a position and receives a favorable evaluation by Contractor, the Contractor shall submit to the COR a complete National Background Investigations Bureau (NBIS) application for each contract employee. The Government shall have and exercise full and complete control over granting, denying, withholding, or terminating suitability decisions for employees. The Government may, as

deemed appropriate, authorize and grant a temporary suitability decision to contract employees. Issuance of a temporary decision to any contract employee shall not be an assurance that the Government will grant full suitability. Granting of either temporary or full suitability shall in no way prevent, preclude, or bar later withdrawal or termination of any such suitability by Government.

5.14.3.3 Entry on Duty (EOD) Decision. The Government shall have and exercise full control over granting, denying, withholding, or terminating unescorted access to a Government facility and or sensitive Government information access for Contractor employees, based upon results of a background investigation. The Government may, as deemed appropriate, authorize and make favorable EOD decisions based on preliminary security checks. Favorable EOD decision would allow employees to commence work temporarily prior to completion of the full investigation. The Contractor shall not consider a granting of a favorable EOD decision as assurance that full employment suitability authorization will follow as a result thereof. Granting of a favorable EOD decision or a full employment suitability determination shall in no way prevent, preclude, or bar the withdrawal or termination of any such access by the Government, at any time during the contract period. The Contractor shall not allow any Contract employee unescorted access to a Government facility without a favorable EOD decision or suitability determination by DOC. Contractor employees awaiting an EOD decision may begin training for work, provided they do not access sensitive Government information. Limited access to Government facilities is allowable prior to EOD decision if a Government employee escorts a contract employee. Limited access allows contractor employees to attend briefings or non-recurring meetings, and to begin transition work.

5.14.3.4 Classified Visit Authorization. Contractor's request for visit authorization when security access is required shall be submitted IAW the National Industrial Security Program Operating Manual (NISPOM) not later than one week prior to visit.

5.14.3.5 Access Security Credentials. The Government will provide Contractor personnel with the appropriate security credentials to access Government facilities.

5.15 Optional Support CLINs

5.15.1 Base Year

- **Skilled Trades**: Option CLIN for a second Powerhouse Electrician and a Powerhouse Operating Engineer to maintain site mission readiness if safety or regulatory standards mandate a two-person team, or if an operating engineer is unavailable during a power outage.
- **IT**: Option CLIN for a second IT Administrator and an IT Manager should increased support be required to ensure timely IT administration, thorough documentation, and appropriate internal oversight necessary for mission execution.
- **Site Support**: Option CLIN for a second Logistician, an additional Maintenance and Operations (M&O) Laborer, as well as an Administrative Assistant should increased support be required with site support operations.
- **Security**: Option CLIN for a Security Guard Manager and two Armed Guards to should increased support be required within the security department while minimizing reliance on overtime and surge staffing to sustain mission-critical operations.
- **Operations**: Option CLIN for an Antenna Technician and four (4) Operations and Maintenance Technicians should increased support be required for comprehensive coverage to sustain operational passes while facilitating necessary preventive and corrective maintenance on antennas, thereby enhancing system reliability to support mission objectives.

5.15.2 Option Years 1-2

- **Skilled Trades**: Option CLIN for-a Powerhouse Operating Engineer to maintain site mission readiness if safety or regulatory standards mandate a two-person team, or if an operating engineer is unavailable during a power outage.
- **IT**: Option CLIN for a second IT Administrator and an IT Manager should increase support be required to ensure timely IT administration, thorough documentation, and appropriate internal oversight necessary for mission execution.
- **Site Support**: Option CLIN for an additional Maintenance and Operations (M&O) Laborer, as well as an Administrative Assistant should increase support be required with site support operations.
- **Security**: Option CLIN for a Security Guard Manager and two Armed Guards to should increased support be required within the security department while minimizing reliance on overtime and surge staffing to sustain mission-critical operations.
- **Operations**: Option CLIN for an Antenna Technician and four (4) Operations and Maintenance Technicians should increased support be required for comprehensive coverage to sustain operational passes while facilitating necessary preventive and corrective maintenance on antennas, thereby enhancing system reliability to support mission objectives.

APPENDIX A

STATION INFORMATION

LOCATION

The Station is located at 64°58.6'N 147°31.3'W, 12 miles northeast of the city of Fairbanks, Alaska, in a radio-quiet valley on approximately 7800 acres of federally-owned land withdrawn from public use under Public Land Order (PLO) 3708 dated July 2, 1965, as modified by PLO 6709 dated February 15, 1987. PLO 7710 went into effect on June 24, 2008, and extended the withdrawal for an additional 20 years. The facility is accessible via the Steese Highway, a combination of four-lane divided highway and two-lane undivided highway. Highways to the facility are paved and maintained by the State of Alaska Department of Transportation.

SATELLITE OPERATIONS

FCDAS is NOAA's primary command and data acquisition facility for operational environmental satellites. The station also collaborates with other Government and international partners to provide routine and contingency support for non-NOAA spacecraft. Each day, the Station averages approximately 135 satellite contacts, including those conducted through remotely- operated systems.

The Government anticipates significant increases in antenna utilization in the near-term as new partnerships mature with foreign earth observation satellite operators, the US Space Force, and other US government agencies.

Operational antenna systems include three 13-meter Datron antennas; two five-meter Datron antennas; one RSI-Vertex 21-meter antenna; one five-meter CPI-Malibu antenna; one Blau-Knox 26-meter antenna; one four-meter Datron Ka-band antenna; one three- meter SeaSpace antenna; one 2.4-meter Orbital Systems antenna; and two Search-and- Rescue Satellite (SARSAT) LEO-LUTS terminals. Most antenna systems and associated ground equipment are controlled using Epoch IPS software by Kratos- Integral Systems.

New antenna systems in the process of being commissioned for operation are two 2.4-meter Search-and-Rescue Satellite (SARSAT) MEO-LUTS, and one ARGOS 3.0-meter Orbital Systems antenna.

FACILITIES AND INFRASTRUCTURE

Buildings at FCDAS range in age from five to over fifty years old. Operations and most administration personnel transitioned to the Fairbanks Satellite Operations Facility (FSOF) in 2011. Other occupied structures include the Facilities Building, which houses offices and workshops for electrical, plumbing, mechanical, and vehicle maintenance personnel; the Contingency Operations Area (COA), which contains the site's calibration and repair laboratory as well as storage and overflow office space; the Guard House; and the Power House, where generators, switchgear, and uninterruptible power supply systems are located. The Gilmore Creek Geophysical Observatory (GCGO) houses third-party experiments and is also used for warm storage. Large items are stored in one of two warehouses, and a water storage building for the fire suppression system of adjacent buildings. The former operations center, known as the Alaska Building, is planned for demolition in the next several years.

Heating, cooling, and water treatment systems are largely automated, but to varying degrees IAW the particular age of the buildings. Most heat is provided by oil-fired boilers with circulating hot water loops. COA and GCGO heat is electric baseboard.

FSOF incorporates a sophisticated building automation system (BAS). Zone valves and area thermostats are used elsewhere. Most cooling systems are electric direct expansion type.

Golden Valley Electric Association (GVEA) cooperative provides commercial electricity service to FCDAS. FCDAS electrical distribution includes medium voltage (4,160 Volts) underground cables, pad-mounted equipment throughout the site; and low voltage (600 Volts and below) wiring and equipment in buildings. Two uninterruptible power supply (UPS) systems protect critical systems in the event of brief commercial power outages. Three diesel engine-generators and new switchgear, installed in late 2013, are programmed to take over power generation for longer outages. FCDAS normally stores enough fuel to run for four to six weeks without commercial power.

Roads run throughout the 7,200-acre site, and most are unpaved. Approximately six lane miles of paved roads are used for access to buildings and antennas within the central campus. These roads and building parking lots must be kept clear of debris, potholes, and other hazards. The Contractor may be called upon to make minor repairs. Snow removal and ice mitigation are essential to safe vehicular and pedestrian access. An unpaved road to the west collimation tower traverses approximately three miles of steep terrain. This road must be accessible year-round due to the occasional need to maintain communications equipment and scientific instruments at that location. Other roads outside the central campus provide seasonal access to more remote parts of the station. Grading, brush cutting, and culvert clearing are routine summer activities for road maintenance.

SUPPORT ACTIVITIES

Essential functions for "total operation and maintenance" also include management and contractor employee supervision; IT administration and security; shipping and receiving; property management; engineering, operations, and system documentation development; environmental, safety, and health management; configuration management; preparation of acquisition-related documents; performance and administrative reporting; and planning assistance for future missions and site upgrades. Armed security guards, facility maintenance, housekeeping, and groundskeeping services are also required.

STATION CHALLENGES

1. Continuous Improvement

The Station has automated and upgraded all of its satellite tracking antennas, as well as the monitoring and control equipment. This modernization continues routinely through technical refresh of systems and increasing automation. The contractor plays an essential role in planning and executing site upgrades. These upgrades will occasionally require support from the Contractor to perform system integration, testing, and training. The Contractor shall prioritize and schedule these tasks without compromising FCDAS' core mission responsibilities.

Facilities and infrastructure improvements are also on-going. Major activities are coordinated and funded through the NESDIS Facilities Management Branch in Silver Spring, MD. Projects are designed and executed through an agreement with the U. S. Army Corps of Engineers, Alaska District. As subject matter experts, the FCDAS O&M staff are frequently called upon to provide information to assist in developing design requirements and determining suitability of changes for the FCDAS mission and concept of operations.

2. Configuration Management

Configuration management (CM) and documentation of system configurations, interconnections, and procedures are crucial for maintenance, repair, and engineering. System upgrades and other changes shall be documented and approved formally IAW the Office of Satellite and Product Operations (OSPO) Configuration Management Plan. This plan describes the CM requirements for the developmental and operational phases of the NOAA/NESDIS satellite programs, including ground station and data processing systems. Additional agency or program-specific CM requirements may arise for cooperative missions not operated by OSPO but otherwise supported by the Station.

3. IT SECURITY

IT security requirements have increased significantly due to evolving threats. Continuous monitoring, regular vulnerability scanning, and patching of all computer-based equipment are key tasks. NOAA's Office of the Chief Information Officer (OCIO) often requires rapid responses to data calls related to IT security. On-going authorization and accreditation activities include developing and maintaining system documents such as system security and contingency plans; writing interconnection and service level agreements; and resolving issues IAW plans of action and milestones (POA&Ms) levied against the FCDAS networks.

4. PROPERTY MANAGEMENT

Property management requires detailed, cradle-to-grave tracking of non-capital and capital accountable property. This includes entering property description, acquisition cost, inventory control numbers, user, location, and property disposition into NOAA's Sunflower Enterprise asset management system. Policies and procedures are promulgated by the NESDIS Personal Property Management Branch and implemented locally by the FCDAS Property Custodian (PC) and Property Accountability Official (PAO). Both PC and PAO are Government employees. The Contractor is responsible for property tagging, data entry, property disposal, and annual wall-to-wall inventories. The contractor shall work with the PAO to resolve all discrepancies.

5. ACQUISITION PLANNING

There is a general lack of local vendors in the immediate vicinity capable of supplying electronic components and services of the type, quality, and quantity required by the station. The challenge is to anticipate long lead-times for spares, replacements, and repair services requiring performance from vendors located outside Alaska.

Purchase of supplies and services at FCDAS follow federal and DOC acquisition regulations as well as procedures specified by the DOC and the NOAA Acquisitions and Grants Office (AGO). The Contractor prepares documents in support of acquisitions as appropriate for the type and value of the items or services. A purchase may require a clear statement of need, market research, brand-name and sole- source justifications, a cost estimate, and an IT security checklist. A significant change in the acquisition process occurred in 2014 with the implementation of Supply Chain Risk Management procedures for IT purchases, which added additional documentation and approval requirements. In light of inherent procedural delays and the administrative burden of preparing purchase packages, the Contractor shall do careful planning well in advance and consolidate orders as much as possible, particularly for routine expendable supplies, spares, and regularly scheduled services. Acquisition planning as referred to in this PWS shall not include any activities related to the award of FCDAS O&M Services contract.

6. INFORMATION MANAGEMENT

FCDAS has a wide variety of documentation and information needs, which will require a focused effort to intake, update, organize, and distribute. Types and format of information include paper and electronic versions of architectural blueprints and survey drawings; system drawings; technical and operator manuals; standard operating procedures; policies; and outreach, educational, and public relations materials. FCDAS does not have a unified system for organizing and tracking information, and the Government subsequently desires a multi-year plan to achieve an effective information management system.

7. COOPERATIVE SUPPORT SERVICES

NOAA has established FCDAS as a "proprietary research facility." Tenants, typically universities or other government agencies, occasionally use this facility for hosting experiments. Costs of supporting these efforts are generally absorbed by the Station. The support provided typically consists of planning, space allocation, power usage, and minor technical assistance. Other non-NOAA customers may require ad hoc services, which are performed under reimbursable or similar agreements between NOAA and other agencies. Again, the Contractor shall prioritize and schedule these tasks without compromising FCDAS' core mission responsibilities. The Contractor shall also track activities and expenses associated with these projects separately and report them to the COR.

APPENDIX B

WORK STANDARD REFERENCES

- AHERA Asbestos Hazard Emergency Response Act
- ASHRAE Guideline 1 HVAC Commissioning Process
- ASHRAE Guideline 3-1990 "Reducing Emission of Fully Halogenated Chlorofluorocarbon (CFC) Refrigerants in Refrigeration and Air Conditioning Equipment and Applications" and Addendum, or latest version, Federal Acquisition Regulations (FAR) 52.223-2, AHRI Standard 700-1988, or latest edition, and Appendix A to 40, CFR, Part 82, Subpart F
- ASHRAE Guideline 4 Preparation of Operating and Maintenance Documentation for Building Systems
- ANSI/ASHRAE Standard 15 - Safety Code for Mechanical Refrigeration
- ANSI/ASHRAE Standard 34 - Number Designation and Safety Classification of Refrigerants
- ANSI/ASHRAE Standard 55 - Thermal Environmental Conditions for Human Occupancy
- ANSI/ASHRAE Standard 62.1 - Ventilation for Acceptable Indoor Air Quality
- ANSI/ASHRAE Standard 100 - Energy Conservation in Existing Buildings/Commercial
- ANSI/ASHRAE Standard 111 - Practices for Measurement, Testing, Adjusting, and Balancing of Building Heating, Ventilation, Air-Conditioning, and Refrigeration Systems
- ANSI/ASME A17.1 Safety Code for Elevators and Escalators
- ANSI/IWCA I-14.1, Window Cleaning Safety Standard
- ASME A17.1/CSA B44, Safety Code for Elevators and Escalators
- ASME A17.2, Inspector's Manual for Elevators
- ASME Boiler and Pressure Vessel Code
- ASME CSD-1 Control and Safety Devices of Automatically Fired Boilers
- National Board of Boiler and Pressure Vessel Inspectors, National Board Inspection Code
- OSHA 29 CFR 1910 and 29 CFR 1926
- Clean Air Act
- Clean Water Act
- DOE/EE-0157, International Performance Measurement and Verification Protocol
- EPA Green Book
- EPA Purple Book
- General Services Administration PBS-100 Facilities Standards for the Public Buildings Service
- General Services Administration Preventive Maintenance Guide (PM Guide)
- International Building Code
- International Fire Code
- International Plumbing Code
- International Mechanical Code
- National Electrical Safety Code (NESC)
- NEMA Application Guide for AC Adjustable Speed Drive Systems
- NEMA MG-1, National Electrical Manufacturers Association, Motors and Generators
- NEMA TP-1, National Electrical Manufacturers Association, Guide for Determining Energy Efficiency for Distribution Transformers
- NETA Maintenance Testing Specification for Electrical Power Distribution Equipment and Systems
- NFPA 10, Standard for Portable Fire Extinguishers
- NFPA 12, Standard on Carbon Dioxide Extinguishing Systems
- NFPA 12A, Standard on Halon 1301 Fire Extinguishing Systems
- NFPA 13, Standard for the Installation of Sprinkler Systems

- NFPA 14, Standard for the Installation of Standpipe and Hose Systems
- NFPA 17, Standard for Dry Chemical Extinguishing Systems
- NFPA 17A, Standard for Wet Chemical Extinguishing Systems
- NFPA 20, Standard for the Installation of Stationary Pumps for Fire Protection
- NFPA 22, Standard for Water Tanks for Private Fire Protection
- NFPA 24, Standard for the Installation of Private Fire Service Mains and Their Appurtenances
- NFPA 25, Standard for the Inspection, Testing, and Maintenance of Water-Based Fire Protection Systems
- NFPA 70, National Electrical Code (NEC)
- NFPA 70E, Standard for Electrical Safety in the Workplace
- NFPA 72, National Fire Alarm and Signaling Code
- NFPA 85, Boiler and Combustible Systems Hazards Code
- NFPA 92, Standard for Smoke Control Systems
- NFPA 96, Standard for Ventilation Control and Fire Protection of Commercial Cooking Operations
- NFPA 101, Life Safety Code
- NFPA 105, Standard for the Installation of Smoke Door Assemblies and Other Opening Protectives
- NFPA 110, Standard for Emergency and Standby Power Systems
- NFPA 111, Standard on Stored Electrical Energy Emergency and Standby Power Systems
- NFPA 2001, Standard on Clean Agent Fire Extinguishing Systems
- NICET (National Institute for Certification in Engineering Technologies publications and issuances)
- NIOSH (National Institute for Safety and Health publications and issuances)
- OSHA 29 CFR 1910.1200, 29 CFR 1910.146, 29 CFR 1910.147, 29 CFR 1910.1030, 29
- CFR 1910.1001, 29 CFR 1910.178
- Resource Conservation and Recovery Act
- Safe Drinking Water Act, PL 99-339, as amended
- SMACNA Sheet Metal and Air Conditioning Contractors National Association HVAC Systems Testing, Adjusting & Balancing
- Title 40 CFR, Part 761, PCBs in Electrical Transformers
- Title 40 CFR, 141.43, Sections A and D, Environmental Protection Agency Safe Drinking Water
- Toxic Substances Control Act

APPENDIX C

SECURITY GUARD TASKS

The following tasks are taken from (I Appendix A) of the Interagency Security Committee's Best Practices for Armed Security Offices in Federal Facilities.

ASO Specific Tasks as shown per Core Areas (6 Functions/84 Specified Tasks): All ASOs should be able to perform these 84 specified tasks.	
1.0 ACCESS CONTROL	
1.01	Stand post at the entry/exit points to verify all persons' identification and conduct inquiries and surveillance of suspicious items, packages, and people.
1.02	Ensure individuals do not depart with government material unless they are authorized to do so.
1.03	Verbally challenge individuals who are approaching restricted areas.
1.04	Direct individuals who cause a disturbance to leave the property.
1.05	Operate traffic control points.
1.06	Close off areas to traffic, establish perimeters, and set up barricades to secure incident scenes or facilities.
1.07	Control access to incident scenes.
1.08	Help ensure integrity of a crime scene, maintaining it in its original condition until law enforcement personnel take over.
1.09	Coordinate the receipt, issuance, and tracking of all keys, key cards, lock combinations, vehicle passes/decals, etc.
1.10	Identify suspicious persons or vehicles.
2.0 SCREENING	
2.01	Inspect packages, briefcases, containers, or any other items in the possession of people entering or leaving a Federally controlled facility.
2.02	Operate metal detectors to search visitors for prohibited items.
2.03	Operate x-ray machine to search deliveries and visitors' packages, equipment, and hand-carried articles for prohibited items.
2.04	Conduct vehicle inspection that may include inspecting under seats, in the trunk, and under the vehicle.
2.05	Conduct frisks or pat downs for weapons or other unauthorized items.
3.0 VISITOR PROCESSING	
3.01	Verify proper identification of visitors required for issuance of visitor badges.
3.02	Process visitors.
4.0 PATROL AND RESPONSE	
4.01	Inspect appropriate countermeasures, including facility critical protection points and classified containers.
4.02	Inspect facilities for hazards, mechanical problems, and unsafe conditions and report problems to appropriate authorities.
4.03	Close and secure open windows, doors, gates, or other access points.
4.04	Manually open and close heavy gates and doors.
4.05	Conduct patrols in accordance with routes and schedules contained in post orders.
4.06	Inform dispatcher of present status and changes in conditions.
4.07	Patrol locations in areas which are potentially hazardous to the public (e.g., construction sites).
4.08	Inspect the perimeter, property, and buildings for hazards, intruders, and suspicious activities.
4.09	Observe the environment for suspicious vehicles or persons on or around Federal property.

4.10	Review maps, floor plans, diagrams, or other information to become familiar with facility and property boundaries.
4.11	Evacuate individuals from dangerous and/or life threatening situations.
4.12	Guide and assist first responders (e.g., with scene management or security).
4.13	Assess the condition of injured individuals.
4.14	Perform basic first aid in response to emergencies.
4.15	Administer CPR.
4.16	Administer/deploy AED.
4.17	Use fire extinguisher to put out a minor fire.
4.18	Request emergency assistance in response to traffic accidents.
4.19	Assist in conducting accident/incident scene searches/investigations (e.g., check visitor logs, video) in search of relevant evidence and information to determine the facts of the situation.
4.20	Follow directions to and respond to emergency and routine calls for service until the situation is resolved or until relieved by a higher authority.
4.21	Investigate the source of suspicious odors and sounds.
4.22	Pursue fleeing individual.
4.23	Escort money, valuables, or people to provide security.
4.24	Escort facility tenants and visitors to and/or from their vehicles after hours.
5.0 CONTROL CENTER OPERATIONS	
5.01	Check radio equipment for proper operation.
5.02	Monitor security and fire alarms and closed-circuit television to detect security risks, threats, or prohibited items carried by visitors.
5.03	Dispatch ASOs in response to calls for service, alarms, or emergencies.
6.0 COMMON TASKS	
6.01	Report potentially threatening situations and violations of law and security procedures.
6.02	Observe unique characteristics of an individual for identification purposes.
6.03	Collect information about stolen or missing property or suspicious activities to aid investigations.
6.04	Take detailed field notes so reports can be completed.
6.05	Write and/or speak situation reports regarding security-related information (e.g., accidents, bomb threats, unlawful acts, characteristics of individuals).
6.06	Communicate with individuals to establish rapport.
6.07	Adjust communication to ensure understanding.
6.08	Provide direction or information to tenants or visitors.
6.09	Advise persons relative to problems, situations, etc.
6.10	Encourage people to approach by using effective non-verbal communication (e.g., making eye contact, smiling, greeting a person cordially, and nodding).
6.11	Communicate with rude or abusive people.
6.12	Use body language to project control and influence.
6.13	Use voice commands to project control and direct actions.
6.14	Explain rules, regulations, and procedures to individuals.
6.15	Interact with a subject who does not speak English.
6.16	Interact with a subject who has communication impairment (e.g., is deaf, has a speech impediment).
6.17	Interact with a subject who has mobility impairment (e.g., is blind, is wheelchair bound).
6.18	Interact with public, including children.
6.19	Interview witnesses to obtain description of possible suspects or description of what happened.
6.20	Advise appropriate personnel of potentially hazardous conditions (e.g., slippery floors).
6.21	Communicate with first responders.

6.22	Testify in court regarding criminal activity or other incidents.
6.23	Report misconduct of other Security Officers.
6.24	Ensure all security equipment is activated and operating properly; if not, report to proper authority.
6.25	Inventory physical objects (e.g., keys, keycards, vehicles, visitor badges) and log accordingly.
6.26	Locate and review documents and information (e.g., logs, lists).
6.27	Read memos and other written material to acquire and maintain knowledge.
6.28	Participate in search for missing child.
6.29	Activate alarm systems.
6.30	Provide backup assistance to LEOs and other ASOs.
6.31	Maintain situational awareness regarding individuals' body language, projected attitudes, and intentions.
6.32	Care for and maintain firearms.
6.33	Participate in firearms training.
6.34	Participate in training in the use of intermediate force weapons to be used in emergency situations.
6.35	Use intermediate force weapon to temporarily incapacitate a violent individual.
6.36	Operate firearm to protect self and others.
6.37	Maintain positive control and retention of firearms and intermediate weapons at all times.
6.38	Use defensive tactics to prevent or control movements of individuals.
6.39	Defend against violent combative person(s) to prevent injury to self or others.
6.40	Physically control individuals displaying disruptive or violent behavior, to include applying handcuffs.

APPENDIX D

QUALITY ASSURANCE SURVEILLANCE PROGRAM (QASP)

As part of the Government's QASP, the Government may:

a. Review and, if warranted, reject any reports or other submittals required from the Contractor.

b. Review performance and service records, including, if applicable, but not limited to, monthly progress reports, BAS data, CMMS data, Advance Metering System (AMS) data and any computerized or hardcopy records maintained by the Contractor documenting performance under this Contract, and require correction of any unsatisfactory conditions noted.

c. Determine the adequacy of the Contractor's QCP and documentation and the overall success of this program.

d. The Government may order improvements if it determines the programs are insufficient or ineffective.

e. Obtain occupant satisfaction survey information and require improvements in service on the basis of such information to the extent such results correlate with deficiencies in Contract requirements.

f. Conduct random and routine physical inspections of facility equipment and systems, to include programs and files maintained on computers and Contractor onsite offices and work areas, and require correction of deficiencies noted.

g. Perform inspections with Government personnel or independent third-party inspectors.

Requirements Summary Table

Incentive/Disincentive for all is as follows:

Incentive = Option Period considered if funding available and need exists

Disincentive = Notifications, Negative Feedback, or Termination as Appropriate

Required Service or Deliverable	Performance Standards	Acceptable Quality Levels	Method of Surveillance
Maintain at least minimum antenna system operational availability	Specified in PWS 5.2.4, Table 2, computed monthly and annually.	96-98%	Reports Customer analysis Inspections
Maintain at least minimum data capture reliability for each mission for which this metric is specified.	Specified in PWS 5.2.4, computed monthly and annually.	99.5%	Reports Customer analysis Inspections
Spacecraft Support Plan (SSP) IAW PWS 5.2.1.3	Timely (45 days prior to launch or spacecraft transition to FCDAS operations), with minimal to no corrections needed.	98%	100% inspections
Ground System Operations and Maintenance Summary (GOMS) IAW PWS 5.2.1.4	Timely (daily), thorough and accurate, with minimal to no corrections needed.	99%	Reports Customer feedback 100% inspections Evaluations
Equipment Status Report for ground system anomalies IAW PWS 5.2.1.4	Timely (within 30 minutes of anomaly detection)	98%	Reports Customer feedback Inspections Evaluations
Equipment calibration services and reporting IAW PWS 5.2.3.2	Timely (within 15 days of calibration schedule), thorough (per manufacturer guidelines), and effective	99%	Reports Customer feedback Inspections Evaluations
Ground systems preventive maintenance plan IAW PWS 5.2.3.3	Timely (within 60 days of initial POP commencement), with minimal to no corrections needed.	98%	Reports Customer feedback Inspections Evaluations
Preventive and corrective maintenance actions IAW PWS 5.2.3.3	Timely (addressed in a manner consistent with designated priority and mission impact), thorough, and effective	99%	Reports Customer feedback Inspections Evaluations
Mission and antenna time usage metrics Reports IAW PWS 5.2.4	Daily, weekly, monthly, and annually	95%	Reports Customer feedback Inspections Evaluations
Risk Management IAW PWS 5.3	Timely, thorough, and accurate. New risks will be documented within 15 days of identification, or within one day of significant changes to existing risk factors.	98%	Inspections Reports Customer feedback
IT systems administrative support IAW PWS 5.4	Timely (work orders addressed within timeline by priority or project schedule)	98%	Inspections Customer feedback

Telecommunications Provisioning, Management and Support IAW PWS 5.4	Timely (work orders addressed within timeline by priority or project schedule)	98%	Inspections Customer feedback
IT system security documentation created and updated IAW PWS 5.4	Timely (within schedule established by ACIO-S), thorough, with minimal to no corrections needed.	98%	Reports Inspections Customer feedback
IT system security scanning IAW PWS 5.4	Timely (monthly or as needed) and thorough	99%	Reports Inspections Customer feedback
IT system security patches applied IAW PWS 5.4	Timely (within schedule according to severity of identified vulnerability)	98%	Reports Inspections Customer feedback
IT system security controls audit (SCA) artifacts collected and submitted IAW PWS 5.4	Timely (within schedule established by SCA team) and thorough	95%	Reports Inspections Customer feedback
IT security POA&Ms closed on time IAW PWS 5.4	Timely (within project schedule)	90%	Reports Inspections Customer feedback
Equipment Status Report IAW PWS 5.4 and 5.5	Timely (within 24 hours of detection)	90%	Reports Inspections
Existing Deficiency Inspection/Initial Deficiency List IAW PWS 5.5.2	Timely (within 30 days of initial POP commencement), thorough, and accurate	98%	Inspections Customer feedback
Facilities Systems Performance Metrics IAW PWS 5.5.3	Timely (reported monthly) In compliance with PWS 5.5.3 Table 4: Performance Metrics	70-99.99%	Reports Inspections Customer feedback
Facilities Progress Reporting IAW PWS 5.5.6.2	Timely (reported monthly)	98%	Reports Inspections Customer feedback
Facilities Maintenance Program IAW PWS 5.5.7	Timely, thorough, and accurate	98%	Reports Inspections Customer feedback
Grounds maintenance services IAW PWS 5.5.13	Timely, thorough, and accurate	98%	Inspections Customer feedback
Custodial services IAW PWS 5.5.15	Timely, thorough, and accurate	98%	Inspections Customer feedback
Vehicle and mobile equipment fleet management and maintenance IAW PWS 5.5.16	Timely (monthly, quarterly, annually per GSA, DOC, and NOAA per schedules), thorough, and accurate	98%	Reports Inspections Customer feedback
Environmental, Safety, and Health program IAW PWS 5.6	Compliance with federal, state, and local ESH regulations, timely, thorough, and accurate reporting	99%	Reports Inspections Customer feedback
Safety incident reporting and record keeping IAW PWS 5.6.2	Timely (within NOAA SECO and OSHA requirements) for incidents	98%	Reports
Management and accountability of station property under provisions of FAR 52.245-1 and IAW PWS 5.7	Timely (IAW NOAA PPMB deadlines), thorough, and accurate	99%	Reports Inspections Sampling Customer feedback
Annual 100% touch inventory IAW PWS 5.7.2	Timely (IAW NOAA PPMB deadlines), thorough, and accurate	99%	Reports
Shipping, receiving, excess property disposal IAW PWS 5.7.3	Timely (meeting program/project needs), thorough	95%	Reports Customer feedback

Purchase request package preparation IAW PWS 5.7.3	Timely submission to Government for acquisition to meet mission needs, thorough, accurate needing little to no corrections	95%	Reports Customer feedback
Property items cleared for turn in IAW PWS 5.7.3	Timely (meeting program/project needs), thorough	99%	Reports Customer feedback
Security guard services IAW PWS 5.8	Timely, thorough, and accurate	99%	Reports Inspections Customer feedback

APPENDIX E

REPORTING REQUIREMENTS SUMMARY

Deliverable	Reference	Due	Point of Contact
Staffing Calendar	5.1	As needed to indicate any changes in staffing	COR Station Manager
Ground System Operations and Maintenance Summary	5.2.1.4	Daily	COR Station Manager
Equipment Status Report	5.2.1.4	As required by anomalies. Not more than 30 minutes after the event or detection.	COR Station Manager OSPO MOD
Equipment Status Report Distribution List	5.2.1.4	Annually	COR Station Manager
Annual baseline of radio frequency (RF) and fiber optic transport	5.2.3.1	Annually	COR Station Manager
Ground Systems Preventive Maintenance Plan	5.2.3.3	Initial draft no later than 60 days after commencement of the initial contract period of performance; final no later than 90 days of the initial contract period of performance	COR Station Manager
Summary of preventive and corrective maintenance actions	5.2.3.3	Weekly	COR Station Manager Mission Operators PMO Stakeholders
Monthly and annual data capture reliabilities by spacecraft	5.2.4	Monthly and annually	COR Station Manager Mission Operators PMO Stakeholders
Ground system operational availability	5.2.4 Table 2	Monthly and annually	COR Station Manager
Data delivery latency performance by spacecraft, data types and subtypes for missions levying specific latency reporting requirements	5.2.4	Monthly	COR Station Manager Mission Operators PMO Stakeholders
Report number of operational scheduled contacts, non-nominal passes, and overall success rate for each satellite, as well as cancelled passes	5.2.4	Daily, weekly and monthly	COR Station Manager
Report mission and antenna time usage metrics	5.2.4	Daily, weekly, monthly, and annually	COR Station Manager
Report and analyze all negative trends and provide recommendations	5.2.4	Quarterly	COR Station Manager
Risk Management review	5.3	Quarterly	COR Station Manager
Configuration control of station computer systems	5.4	Quarterly	COR Station Manager IT Systems Engineer
System drawings	5.4	Bi-annually	COR Station Manager IT Systems Engineer
Software License inventory and renewal dates	5.4	Annually	COR

			Station Manager IT Systems Engineer
Hardware and equipment warranty dates	5.4	Bi-annually	COR Station Manager IT Systems Engineer
Equipment Status Report	5.4	Within 24 hours	COR Station Manager IT Systems Engineer
IT systems and components	5.4	Quarterly	COR Station Manager IT Systems Engineer
IT system security plans and updates	5.4.1	Not less than annually	COR Station Manager NESDIS OCIO System Owner
IT security plans of action and milestones	5.4.1	As required to mitigate IT system vulnerabilities	COR Station Manager NESDIS OCIO System Owner
IT security system authorization and accreditation project plans	5.4.2	Due annually second quarter of fiscal year	COR Station Manager NESDIS OCIO System Owner
Equipment Status Report	5.5	Within 24 hours	COR Station Manager
Initial inspection deficiency list	5.5.2	Not later than 90 days after contract award	COR Station Manager
Itemized estimates for correcting initial deficiencies	5.5.2	180 days after initial deficiency report	COR Station Manager NESDIS Facilities
Summary of preventive and corrective maintenance actions	5.4 and 5.5	Weekly	COR Station Manager
Facilities equipment inventory and equipment labeling	5.5.6.1	As required	COR Station Manager PAO PC
Facilities Progress Report	5.5.6.2	Monthly	COR Station Manager NESDIS Facilities NESSO
Emergency Shutdown Procedures	5.5.6.8	As required	COR Station Manager
Commercial Power Outage Reporting	5.5.6.10	As required	COR Station Manager
Power Usage Log	5.5.6.10	Monthly	COR Station Manager
Emergency Operations Plan	5.5.6.11	Review and update no less than annually	COR Station Manager
Building Energy and Water Efficiency Use Plan	5.5.6.14	Quarterly	COR Station Manager NESDIS Facilities NESSO
Energy and Water Usage	5.5.6.14	Monthly	COR Station Manager

Facilities Maintenance Plan	5.5.7	NLT 7 days after contract start date	CO COR Station Manager
Proposed preventive or predictive maintenance standards	5.5.7.1	To be negotiated	COR Station Manager NESDIS Facilities
Fuel polishing and testing	5.5.8	Annually	COR Station Manager
Fuel Usage	5.5.8	Monthly	COR Station Manager
Repair cost estimates	5.5.12	As required	COR Station Manager
Under-floor plenum inspection	5.5.15	Annually	COR Station Manager
Clean and damp wipe duct systems	5.5.15	Annually	COR Station Manager
Vehicle maintenance, mileage, and fuel report	5.5.16	Monthly	COR Station Manager GSA Manager Agency Fleet Manager
Air Quality Management District Permits	5.6.3	As required	COR Station Manager NESDIS Facilities
Hazardous Waste, Recycling and Disposal Records	5.6.3	As required	COR Station Manager NESDIS Facilities
Inspect all transformers PCBs	5.6.3	Annually	COR Station Manager NESDIS Facilities
Occupational Safety and Health Program	5.6.5	Submit for review and approval 30 days after award of contract	COR Station Manager
Pandemic Preparation Plan	5.6.5	Submit for review and approval 30 days after award of contract	COR Station Manager
Lockout/Tagout Program	5.6.5	Within 30 days of contact award	COR Station Manager
Confined Space Entry Permit System	5.6.5	Within 60 calendar days of contract commencement	COR Station Manager
Hazardous Materials Inventory	5.6.5	See Building Operating Plan	COR Station Manager
Personal Property Inventory	5.7.2	Annually	COR PC PAO Station Manager NESDIS PPMB
Property status report	5.7.2	Annually	COR PC PAO Station Manager
Recommend and dispose of capital property, equipment, and parts	5.7.3	Quarterly	COR PC PAO

			Station Manager
Security Guard Post Orders	5.8	Reviewed and updated as needed	COR Station Manager
Contingency Plan	5.8.3	Within 30 days of contract award	COR Station Manager
ACSO Training	5.8.7	As required	COR Station Manager
Security Guard Log	5.8.9	Daily	COR Station Manager
Security Incident Report	5.8.9	As required	COR Station Manager
Training Summary	5.9	Monthly	COR Station Manager
Program Management Review	5.9.2	Monthly	COR Station Manager
Facilities Quality Control Plan	5.9.3	Within 45 days after start of the contract	COR Station Manager NESDIS Facilities
Equipment Condition Assessment	5.9.4	Monthly	COR Station Manager
Labeling of Electrical Circuits	5.9.8	As required	COR Station Manager
Building Operating Plan	5.13	30 days after commencement of performance, and Monthly	COR Station Manager NESDIS Facilities
Startup Transition Plan	Appendix F	Not less than 10 days before transition phase startup	COR Station Manager
NAM 1330-52.222-70 NOAA Sexual Assault and Sexual Harassment Prevention and Response	Contract Paragraph H.15	Annually NTL March 1st	CO COR Station Manager

APPENDIX F

TRANSITION PHASES

Transition Phase Startup

The Contractor shall provide transition startup services for thirty (30) days prior ("Transition Phase Startup") to the Contract start date to assist transitioning between Contractors. The purpose of this phase is to permit a transition that is seamless to the facility operations and maintenance, and to assess conditions and incomplete maintenance work at the time of Contractor transition. During this period the Contractor shall:

a. Review work order history and equipment inventory information.
b. Complete the government-furnished CMMS training.
c. Update the preventive maintenance schedule.

Startup Phase Schedule

Not less than ten (10) days before the Transition Phase Startup the Contractor shall submit a schedule and staffing plan for the transition phase. This plan shall describe, by week, work to be accomplished. At the end of each week during the transition phase the Contractor shall submit a letter report describing work accomplished, to the CO or their designee.

Adjustments and Corrections

The Contractor shall be responsible for making immediate adjustments or corrections that fall within the scope of routine preventive maintenance required by this Contract at no additional cost to the Government. This includes, but is not limited to: making adjustments to controls; adjusting the BAS software, e.g., correcting set points; reloading programs; restoring equipment being operated manually to automatic operation (this does not include changing established sequences of operation or programming sequences); applying lubricants; cleaning fan housings, fans, coils, dampers, air handling unit (AHU) Sections, and equipment rooms; and replacing consumable parts or components. The Contractor shall identify for the Government all alarm points with originating point identification information (device ID, point number, description), so that the Government, at its discretion, may arrange for automatic generation of work orders from alarm conditions.

Phase-out Transition Period

When the Contract ends, the Contractor shall cooperate with the incoming Contractor during a phase- out period. For planning purposes, the Contractor shall assume a phase-out period of sixty (60) days. During this phase-out period, the Contractor shall:

a. Assist the CO or their designee and incoming Contractor for a seamless transition in operations and maintenance with no adverse effect on the building tenants;
b. Provide the Government and the incoming Contractor with access to all records and official documentation (both hard copies and electronic as applicable) required by this Contract;
c. Provide training to the incoming Contractor on methods of accessing and programming the BAS and other control systems; and

d. Show the incoming Contractor where all archived programs and systems literature are maintained. On the last performance day of the Contract, the Contractor shall turn over to the CO or their designee all keys and identification badges or cards.
e. Coordinate and complete disposal, cleanup, and transfer of all materials according to applicable laws.
f. Provide all data records (database files, spreadsheets, etc.) relating to building systems, assets, work orders, permits, work activities, etc. to the CO or their designee. The Government owns all data compiled under this Contract or ancillary to this Contract.

APPENDIX G

LIST OF ACRONYMS AND ABBREVIATIONS

AAC - Alaska Administrative Codes

A/C - Air Conditioning

ACSO - Armed Contract Security Officer

ANSI - American National Standards Institute

ASHRAE - American Society of Heating, Refrigerating and Air-Conditioning Engineers

AQMD - Air Quality Management District

BAS - Building Automation System

BOP - Building Operating Plan

BOR - Board of Review

CAM - Commerce Acquisition Manual

CAR - Commerce Acquisition Regulation

CDA - Command and Data Acquisition

CFR - Code of Federal Regulation

CLIN - Contract Line Item Number

CM - Configuration Management

CMMS - Computerized Maintenance Management System

CO - Contracting Officer

COMSEC - Communications Security

COOP - Continuity of Operations

COR - Contracting Officer's Representative

CS - 2-Chlorobenzalmalononitrile

CSAM - Cyber Security Assessment and Management

DOC - Department of Commerce

DSCOVR - Deep Space Climate Observatory

EEOC - United States Equal Employment Opportunity Commission

EOD - Entry on Duty

EPA - United States Environmental Protection Agency

ESH - Environmental, Safety, and Health

ESR - Equipment Status Report

FAR - Federal Acquisitions Regulation

FAST - Federal Automotive Statistical Tool

FBI - Federal Bureau of Investigation

FCDAS - Fairbanks Command and Data Acquisition Station

FISMA - Federal Information Security Management Act

FSOF - Fairbanks Satellite Operations Facility

GOES-W - Geostationary Operational Environmental Satellite-West

GOMS - Ground System Operations and Maintenance Summary

GSA - General Services Administration

HVAC - Heating, Ventilation, and Air Conditioning

IAW - In Accordance With

ISSO - Information Systems Security Officer

IT - Information Technology

MSDS - Material Safety Data Sheets

NAM - NOAA Acquisition Manual

NBIS - National Background Investigations Bureau

N-CIRT - NOAA Computer Incident Response Team

NESDIS - National Environmental Satellite Data and Information Service

NISPOM - National Industrial Security Program Operating Manual

NOAA - National Oceanic and Atmospheric Administration

NSOF - NOAA Satellite Operations Facility

NWS - National Weather Service

OC - Oleoresin Capsicum

OCIO - Office of the Chief Information Officer

OEM - Original Equipment Manufacturer

OEP - Occupant Emergency Plan

O&M - Operations and Maintenance

OSHA - Occupational Safety and Health Administration

OSPO - Office of Satellite and Product Operations

PAAN - Partner Antenna Access Network

PAO - Property Accountability Official

PC - Property Custodian

PCB - Polychlorinated Biphenyl

PM Guide - General Services Administration Preventive Maintenance Guide

POA&M - Plan of Action and Milestone

PPE - Personal Protective Equipment

PPMB - Personal Property Management Branch

PWS - Performance Work Statement

QASP - Quality Assurance Surveillance Program

QCP - Quality Control Plan

RF - Radio Frequency

SAT - Simplified Acquisition Threshold

SCADA - Supervisory Control and Data Acquisition

SSP - Spacecraft Support Plan

T&M - Time and Materials

USAF - U. S. Air Force

APPENDIX H

REPORT FORMATS

Status Reports: Standard Report Structure

Section	Key Content
Identification	Date, Time, System ID, Reporter Name
Symptom	Detailed description of the malfunction or error
Diagnostics	Tools used (multimeters, logs, debuggers) and results
Root Cause	The fundamental reason the failure occurred
Resolution	Steps taken to restore functionality
Prevention	Future tasks to harden the system against this specific failure

Facilities Progress Reports: The reports are listed below and shall include

1. Service calls, Work Orders, and Alarm Response Details:
    a. Date and time received, date and time resolved, work completed/accomplished to resolve issues, source of service call, work order or alarm (person's name or monitoring system).
2. Preventive Maintenance History and Schedule:
    a. Date and time that PM was scheduled and completed, observed equipment condition, work completed/accomplished, name of technician who completed the work.
    b. Any incomplete PMs for the reporting period identified with the following information: PM ticket number, date initiated, PM description, explanation for the incomplete ticket, and a proposed completion date.
3. Repair history documenting all repair work completed; parts and materials used; labor hours used; material and labor costs for every repair; and name of technician or Contractor who completed work.
4. Explanation of any equipment, designed to be controlled by the BAS, operating in manual mode as of the end of the performance month, and of any other overrides to sequences of operations in effect as of the end of the performance month.
5. Operating schedule changes (manual or programmed).
6. Planned outage notifications and scheduling.
7. Description of any lost time accidents or other safety problems, including incidents involving hazardous materials that occurred during the performance month.
8. Copy of quality control inspections performed during the month.
9. Station support services provided during the month.
10. Copy of arrival and departure reports of Government-owned vehicles to include date, time, destination, names of personnel, and mileage.
11. Record of the fuel deliveries, levels and any report findings.
12. Review of energy performance trends as of the end of the performance quarter and description of likely causes of significant changes from the same period one year prior.
13. Reports of inspections and tests, with description of deficiencies and corrective actions.