Performance Work Statement (PWS)
Base Operations

Preventive Maintenance and Repair at Kahuku Training Area (KTA)

Annex A (Overarching Base Operations PWS) to OPORD 24-015

IMCOM Enterprise Base Operations (BASEOPS) Performance Work Statement (PWS)

1.0 Introduction. This is a nonpersonal services contract to provide Preventive Maintenance and Repair (PMR) at Kahuku Training Area (KTA), Island of Oahu, State of Hawaii. The Government will not exercise any supervision or control over the contract service providers. The Contractor shall perform to the standards specified in this Performance Work Statement (PWS). Contract service providers shall be accountable solely to the Contractor who, in turn is responsible to the Government. The Contractor shall furnish all parts required to perform preventive maintenance and authorized repair work under this PWS or under a written firm-fixed-price task order. Part-required repairs shall be performed in accordance with Sections 8.8 through 8.10.

1.2 Objectives. The Contractor shall ensure all work accomplished in the performance of this PWS meets all applicable Federal, State, and Local Laws, Regulations, and Directives to include, but not limited to, the publications in Section 7, Related Documents.

1.2.1 The Contractor shall compile historical data, prepare required reports, and submit all information as specified by the Deliverables presented in the contract. The Contractor shall ensure all work in support of mission requirements tendered to the Government for acceptance conform to the measurable performance standards of quality, timeliness, and quantity specified in the PWS of this contract. The Contractor is also responsible for maintaining and updating Technical Exhibit 1 (TE 1) to reflect any changes or discrepancies identified.

1.3 Climatic Conditions. The average annual rainfall is 33.15 inches, with the wettest months being November through March. Typical daytime temperatures range from about 79 degrees Fahrenheit (December through March) to about 89 degrees Fahrenheit (June through October). Summer temperatures often reach 89 degrees Fahrenheit.

1.4 Facility Access. The Contractor shall ensure access to all fire detection and suppression systems in case of emergencies or for other Fire Department purposes. The Contractor shall inform the Fire Department point of contact (POC), prior to outages that will impact the function of the system, special problems or circumstances, which require Fire Department inspection. The Fire Department will reset alarm systems to operational status.

1.5 Traffic Flow. The Contractor shall maintain the free flow of traffic during surfaced area maintenance. The Contractor shall notify the KO, in writing, a minimum of fourteen (14) calendar days in advance of any scheduled closure of streets. Emergency road closures shall be coordinated with the COR or ACOR.

1.6 Drainage. Maintenance work performed under this contract shall not impede drainage.

1.7 Restoration of Landscape Damage. N/A

1.8 Dust Suppression. N/A

1.9 Utility Location. N/A

1.10 Excavation Permits. N/A

1.11 Work Clearance. N/A

2.0 Requirements.

2.1 Description of Services. The Contractor shall furnish all necessary management, transportation, labor, equipment, materials, supplies, and tools to perform Preventive Maintenance (PM) and Repairs on equipment and systems per manufacturer's recommendations as well as routine repairs at Kahuku Training Area (KTA) on the Island of Oahu. Perform all work in accordance with current Occupational Safety and Health Administration standards, Federal, State and County laws, regulations and commercial standards.

2.1.1 Non-Personal Services. The personnel rendering the services are not subject; either by the contract's terms or by the manner of its administration, to the supervision and control usually prevailing in relationships between the Government and its employees. Nonpersonal service contracts are authorized by the Government in accordance with (IAW) Federal Acquisition Regulation (RFO FAR) Subpart 37.2, under general contracting authority, and does not require specific statutory authorization.

2.1.2 General Information

2.1.2.1 Transition (Phase In/Phase Out). The Contractor shall prepare and submit a transition plan within ten (10) business days after the contract award. The transition plan will have a sixty (60) business day transition period that will be implemented by the Contractor and shall state Contractor key personnel on board. The Contractor shall provide sufficient experienced personnel during the phase in and phase out period to ensure that the services are maintained at the required level of proficiency. During the phase in, the Contractor shall observe all operations pertinent to the requirements of the PWS, to include office functions, procedures, operations, repair/maintenance operations, and any other operations as deemed necessary by the Contractor that will enable Contractor personnel to become both knowledgeable in, and familiar with their assigned areas of responsibility. The Contractor shall commence all operations required by this PWS as of the first day of the contract period. Therefore, on the initial day of performance, the Contractor shall provide a work force which is fully qualified and capable of performing all work required under this contract.

Deliverable
A001 Transition Plan

2.1.2.1.1 Phase In/Phase Out for Incumbent Contractor.
If the Contractor is the incumbent Contractor, the phase out/phase in period shall be no more than thirty (30) calendar days and will primarily consist of administrative transition under the new contract number. All documents shall be updated with the new contract number and new dates and submitted for approval. All previous approvals under the old contract are invalid.

2.1.2.2 Transition (Phase-Out). Thirty (30) business days prior to contract expiration will constitute the phase out period. The Contractor shall develop and implement a plan to affect a smooth and orderly transfer of performance responsibility to a potential successor. The initial phase out plan shall be submitted to the COR for approval no later than six (6) months after the start of the base contract year. The plan shall contain details that include but are not limited to; timelines for events, key personnel involved and interface with the Government and follow on

Contractor. The plan shall fully describe how the Contractor shall approach the following

issues: Employee notification; Retention of key personnel; Turnover of work in progress, inventories and transfer of Government furnished property; Removal of Contractor property; Data and information transfer; deletion of password access to Government systems, installation clearance actions including turn in of windshield decals and controlled access cards (CAC) and any other actions required to ensure continuity of operations. The plan shall also include a joint inventory among the incumbent, the Government, and the successor Contractor; reconciliation of all property accounts and requisitions, turn in of excess property and cleanup of Contractor work areas.

The Contractor shall correct any damage to Government Owned Property caused by employee negligence or mistake, intentional or otherwise. During the thirty (30) business day transition period immediately prior to the end of the previous contract, the Contractor shall permit the successor Contractor (and the successor Contractor's employees) to observe and become familiar with any and all operations under the contract. The Contractor shall not defer any needed repairs or maintenance for the purpose of transferring responsibility to the successor Contractor. The Contractor shall fully cooperate with the successor Contractor and the Government so as not to interfere with their work or duties. The Contractor shall provide reasonable assistance to the Government's contract solicitation process such as verifying workload data and other factual information to be included in a new solicitation and providing access to the workplace for site visit(s) of prospective offers.

2.1.3 Place of Performance and Hours of Operation.

2.1.3.1 Place of Performance. The work to be performed under this contract will be performed at Kahuku Training Area (KTA) on the Island of Oahu, Hawaii.

2.1.3.2 Hours of Operation. The Government's regular (normal) hours are from 0700 – 1600 hours, excluding Federal holidays or when the Government facility is closed due to local or national emergencies, administrative closings, or similar Government directed facility closings. The Contractor shall maintain an adequate workforce for the uninterrupted performance of all tasks defined within this PWS when the Government facility is not closed for the above reasons.

2.1.3.3 Access the Kahuku Training Area (KTA). The Contractor shall coordinate entrance to KTA with Range Control Operations Center, Building 1150, Schofield Barracks, Hawaii.
Cell phone number for KTA (808) 853-0440

2.1.3.4 Due to the remote location of the facilities water is not available.

2.1.4 Federal Holidays. The Contractor’s performance shall not be required on the Federal public holidays listed below, unless there is a requirement to respond to a Priority 1, Emergency. Holidays occurring on weekends will be observed as directed by the Federal calendar (5 United States Code (U.S.C) § 6103, Government Organization and Employees, Holidays).

New Year’s Day	1st day of January
Martin Luther King Jr.'s Birthday	3rd Monday of January
Presidents Day	3rd Monday of February
Memorial Day	Last Monday of May
Juneteenth	19th day of June
Independence Day	4th day of July

Labor Day	1st Monday of September
Columbus Day	2nd Monday of October
Veterans Day	11th day of November
Thanksgiving Day	4th Thursday of November
Christmas Day	25th day of December

NOTE: When a holiday falls on a Sunday, the following Monday will be observed as a holiday, and, when a holiday falls on a Friday or Saturday, the preceding Thursday is observed as a holiday by U.S. Government Agencies. Federal holidays also include any Presidential or Congressionally designated days off other than the holidays listed above.

2.1.4.1 The Contractor shall provide personnel support within two (2) hours of notification outside the normal hours of operation as required, including holidays, to support the Directorate of Public Works (DPW) mission. Prior to the performance of services outside the locally established hours of operation, the Contractor shall request and obtain, in writing, approval from the KO. The Project Manager shall be available after normal hours to serve as the central point of contact for Contractor operations. Overtime is not separately priced. After-hours emergency response required by this PWS is included in the firm-fixed-price, except for KO-authorized unscheduled repairs under a firm-fixed-price task order.

2.1.4.2 Installation Closures.
When an unforeseen Installation closure occurs on a regularly scheduled day of work, the Contractor shall reschedule the work to be performed on the next business day following the closure unless the following day is a Saturday, Sunday, a recognized Federal Holiday, and when routine work is not scheduled for that day.

2.1.4.3 Inclement Weather Delay. If the Contractor determines unsafe weather conditions for continued operations, then the Contractor shall notify the KO if inclement weather suspends operations within two (2) hours. The Contractor shall resume operations with KO/COR approval.

2.1.4.4 Curtailment of Operations. When operations are curtailed due to manmade or natural conditions on a working day, it may be necessary for the KO/COR to interrupt that day's work under this contract. The Contractor shall reschedule the work on any day acceptable to the Government. If the KO agrees, the Contractor may continue the work as scheduled. The KO will provide verbal announcements of immediate curtailment of operations to the Contractor.

2.1.4.5 Days of No Scheduled Activities (DONSA). The Installation has historically granted Military personnel (Enlisted and Officers) DONSA, for example, the Friday after Thanksgiving, in addition to the listed Federal Holidays above.

- DONSA are not considered a day of excused absence for the Government civilian work force or Contractor employees.
- If a DONSA affects scheduled contract work or access to facilities, the work in affected facilities may be rescheduled to compensate for the DONSA.
- However, announced DONSA or exodus of Military personnel may provide the Contractor with an opportunity for unrestricted access to facilities and areas or uninterrupted performance of work (i.e., training facility and area maintenance and supply inventories).

The Contractor shall vary work schedules to take full advantage of such opportunities by planning maintenance that is better accomplished when personnel are not using facilities during those times.

2.1.5 Travel/Temporary Duty. N/A

2.1.6 Emergency Services.

2.1.6.1 Emergency Medical Treatment. The Contractor or their employees shall immediately notify their supervisor of any accident requiring emergency medical treatment. The Contractor shall notify the KO or COR/ACOR immediately, not later than (NLT) two (2) hours of the incident. The Contractor shall be responsible for the emergency medical treatment services for Contractor personnel. However, the Government will provide, on an emergency basis, medical services for injuries incurred while an employee is performing under the contract. The Contractor shall reimburse the Government for emergency medical services provided, upon receipt of invoice from the medical facility. Reimbursement shall be made to the United States (US) Government.

2.1.6.2 Accident Reporting. The Contractor shall comply with Operational Safety and Health Administration (OSHA) for record keeping and reporting of all accidents resulting in death, injury, occupational disease, or adverse environmental impact. A completed typed original plus one (1) copy of ENG FORM 3394 United States Army Corps of Engineers Accident Investigation Report shall be delivered to the KO within five (5) calendar days of occurrence, whenever an accident involving personal injury or government owned property occurs.

2.1.7 Contract Administration and Management.

2.1.7.1 Post Award Conference/Performance Evaluation Meetings. The Contractor shall attend the post award conference convened by the contracting activity or contract administration office IAW RFO FAR Subpart 42.302(a)(3), Post award Orientation. The KO and COR/ACOR will meet quarterly with the Contractor to review the Contractor's performance. Written minutes of meetings will be recorded by the Government and signed by both the Project Manager and the KO. The written minutes will be distributed within five (5) calendar days after the meeting. If the Contractor does not concur with any portion of the minutes, recorded by the Government, the non-concurrence shall be provided in writing to the KO within two (2) calendar days following receipt of the minutes.

2.1.7.2 Notwithstanding the Contractor’s responsibility for total management during the performance of this contract, the administration of the contract requires maximum coordination and cooperation between the Government and the Contractor.

2.1.7.3 The following provides the roles and their respective authority during the performance of the contract:

2.1.7.3.1 Contracting Officer (KO). The KO is the only person authorized to direct changes in any of the requirements under this contract, and, notwithstanding any provisions contained elsewhere in this contract, said authority remains solely with the KO. In the event the Contractor makes any change at the direction of any person other than the KO, the change shall be considered to have been made without authority and solely at the risk of the Contractor. All contract administration will be affected by KO. Communications pertaining to contractual

administrative matters shall be addressed to the KO. No changes in or deviation from the terms and conditions shall be affected, without a written modification to the contract, executed by the KO authorizing such changes. The KO will approve all submittals and plans required in this PWS.

2.1.7.3.2 Contracting Officer's Representative (COR). The KO will appoint a COR during the performance of this contract. Additional Government personnel may be assigned to assist in contract oversight IAW AR 70-13, *Management and Oversight of Service Acquisitions*. Other surveillance personnel may be designated as COR or Alternate Contracting Officer's Representative (ACOR), and shall be trained and appointed IAW DoDI 5000.72, *DoD Standard for Contracting Officer's Representative (COR) Certification* and DFARS 201.602-2. The Alternate Contracting Officer Representative (ACOR) will serve as onsite representatives of the COR in performance of actual contract surveillance, if they meet all COR training and experience requirements and are appointed by the KO as an ACOR. The COR/ACOR will provide assistance in identification and resolution of problems, conflicts in priority, subtask requirement definitions, and other operations type problems. The COR/ACOR will perform IAW the responsibilities and duties identified in the appointment letter.

2.1.7.3.2.1 COR Authority. A letter of designation will be issued to the COR/ACOR by the KO. A copy of the letter will be sent to the Contractor. The letter of designation states the responsibilities and limitations of the COR/ACOR, especially with regard to changes in cost, price estimates, or changes in delivery dates. The COR/ACOR is not authorized to change any of the terms and conditions with regard to cost, quantity, or schedule of the resulting order.

2.1.7.3.3. The Contractor shall not in any way represent the United States (U.S.) Government, or that it has the authority to contract or procure supplies for the account of the United States of America (USA).

2.1.8 COR/ACOR Functions. The COR/ACOR monitors all technical aspects of the contract and assists in contract administration. The COR/ACOR is authorized to perform the following functions: assure the Contractor performs the technical requirements of the contract; perform inspections necessary in connection with contract performance; maintain written and oral communications with the Contractor concerning technical aspects of the contract; issue written interpretations of technical requirements; monitor, document, and report Contractor's performance and notify both the KO and Contractor of any deficiencies; coordinate availability of Government Furnished Property, and coordinate site entry of Contractor personnel.

2.1.9 Quality Control (QC). Quality Control is the responsibility of the Contractor. The Contractor shall provide a Quality Control Plan (QCP) thirty (30) calendar days after the contract award. The Contractor shall provide and maintain a QCP that is acceptable to the KO. Changes to the Contractor's QCP shall be submitted to the KO for review and approval within five (5) business days prior to implementation.

Deliverable
A002 Quality Control Plan

2.1.10 Subcontract Management. The Contractor shall implement and maintain a subcontract management process that ensures all subcontractors meet qualification requirements, comply with all contractual terms, and perform in accordance with the standards set forth in this PWS. The Contractor is responsible for oversight, performance monitoring, and ensuring subcontractor compliance with all applicable laws, regulations, and installation policies.

2.1.11.1 Key Personnel.

2.1.11.1.1 Project Manager (PM). The Contractor shall provide a Project Manager (PM) with full authority to act on all contract matters and oversee all work and administrative duties. The PM shall hold a bachelor's degree or have five years of experience managing contracts of similar scope. The Contractor (or prime/subcontractor team) shall possess and maintain all applicable State of Hawaii Contractor Licenses, including C-13 (Electrical), C-15 (Electronic Systems), and C-52 (Ventilating & Air Conditioning). When the PM is unavailable, the Contractor shall designate an alternate with the same authority and qualifications. The names of the PM and alternate shall be provided in writing to the KO and COR at contract start. The PM or alternate shall be available 0700–1600, Monday–Friday, excluding federal holidays, and shall maintain installation access for the duration of the contract. All key personnel shall be able to read, write, speak, and understand English**.**

2.1.11.1.2 Contractor Employees. The contractor shall employ personnel who are fully qualified and possess the appropriate electrical work license as required to perform the duties specified under this contract.

- Fire Alarm and Mass Notification technicians shall work under a Hawaii C-15 (Electronic Systems) license holder and shall hold NICET Level II or III and NFPA 72 training. A C-13 (Electrical) license may support related power and lighting work.

  Lightning Protection personnel shall hold a Hawaii Electrical Contractor License C-13. Employees shall hold a Journey Worker Electrician (EJ) or Supervising Electrician (ES) license, be trained to NFPA 780, and include staff certified as LPI-IT (Installer Technician) and LPI-IS (Inspection Specialist).

- HVAC Technicians & Licensing: The Contractor or designated HVAC subcontractor shall possess an active State of Hawaii Specialty Contractor License (C-52 Ventilating & Air Conditioning Contractor and/or C-60 Refrigeration Contractor). All HVAC technicians servicing refrigerant-bearing equipment shall possess and maintain a valid Federal EPA Section 608 Universal Certification (or applicable Types I, II, and III) in accordance with 40 CFR Part 82.

    - EPA certification types:
        - Type I limits HVAC technicians to working on appliances which contain no more than five pounds of refrigerant.
        - Type II limits HVAC technicians to perform work on high pressure appliances.
        - Type III limits HVAC technicians to working on low-pressure appliances. This certification is transferable among all states and does not expire.

2.1.11.1.3 GFEBS PM Coordinator Lead. N/A

2.1.11.1.4 GFEBS Certification. N/A

2.1.11.1.5 Common Access Card (CAC). N/A

2.1.11.1.6 All Contractor and subcontractor employees performing under this contract shall be authorized to work in the United States and shall meet USAG-Hawaii installation access requirements. The Contractor shall remove from performance any employee who does not meet these requirements. Contractor personnel shall be able to communicate clearly in English.

2.1.11.1.7 Qualification Standards. The Contractor shall inspect, repair, and maintain systems and components associated with facilities listed in real property records as required throughout this contract utilizing properly trained, skilled, and qualified employees or Subcontractor personnel.

Annex A (Overarching Base Operations PWS) to OPORD 24-015

IMCOM Enterprise Base Operations (BASEOPS) Performance Work Statement (PWS)

2.1.11.1.8 Contractor Identification. The Contractor shall ensure all personnel be identified as Contractor to distinguish themselves (*e.g.,* badge, company logo, or uniform) from Government employees. The Contractor shall ensure all correspondence and reports produced are marked as Contractor products or that Contractor participation is disclosed.

2.1.11.1.9 Standards of Conduct. Contractor personnel's conduct shall not reflect discredit upon the Government. The Contractor shall ensure all personnel present a professional appearance while working on the Government Installation. The Contractor's employees shall observe and comply with all local policies and procedures concerning fire, safety, environmental protection, sanitation, security, and possession of firearms or other lethal or illegal weapons or substance. The Contractor shall ensure all Contractor employees, providing services under this contract, conduct themselves and perform services in a professional, safe, and responsible manner. The Contractor shall remove, from the job site, any employee for reasons of misconduct or security. The Contractor shall ensure employee conduct complies with 41 USC 423, *Procurement Integrity*. The Contractor shall also ensure that no Contractor employees conduct political related activities or events on the Installation. The removal of such a person shall not relieve the Contractor of the requirement to provide personnel to perform adequate and timely service.

2.1.11.1.10 Contractor Hiring Restrictions. The Contractor shall not hire or subcontract with off duty or former Government employees whose employment would result in a conflict with Joint Ethics Regulation (JER) DoD 5500.07-R.

2.1.12 Business Relations. The Contractor shall successfully integrate and coordinate all activity needed to execute the requirement of this PWS. The Contractor shall manage the timeliness, completeness, and quality of problem identification to a degree acceptable to the Government. The Contractor shall provide to the COR/ACOR corrective action plans, timely identification of issues, and effective management of Subcontractors within (10) days or at a mutually agreed upon date. The Contractor shall ensure customer satisfaction and professional and ethical behavior of all Contractor personnel.

2.1.13 Manual Operations. N/A

2.2 Work Management. *Applicable only for SERVICE 411*.

2.2.1 Coordination. The Contractor shall schedule and coordinate with the COR/ACOR to minimize disruptions to the facility mission. All correspondence shall be submitted within the established suspense dates. All extensions, releases, or other relief of suspense requirements shall be obtained from the originating office by the Contractor.

2.2.2 General Fund Enterprise Business System (GFEBS): N/A

2.2.3 Demand Maintenance Orders (DMOs). N/A

2.2.3.1 DMO Desk. N/A

2.2.3.2 DMO Call Receipt and Entry. N/A

2.2.3.3 GFEBS and/or ArMA Case Number. N/A

2.2.3.4 Completed Work. The Contractor, certifying the work was satisfactorily performed, shall sign completed work authorizations.

2.2.4 Preventive Maintenance Orders (PMOs). N/A

2.2.4.1 PMO Program. N/A

2.2.4.2 PMO Schedules. N/A

2.2.4.3 Approved PM Schedule. The Contractor shall strictly adhere to the scheduled PM dates to facilitate verification of work by the COR/ACOR. If the Contractor finds it necessary to reschedule a PM, a written request shall be made to the COR/ACOR detailing the reasons for the proposed change at least five (5) working days prior to the originally scheduled PM date. No scheduled PM dates shall be changed without the prior written approval of the COR/ACOR.

Deliverable
A008 PM Schedule

2.2.4.4 PMO Stickers/Log. N/A

2.2.4.5 Warranty Program. The Contractor shall establish and maintain a Warranty Program to warrant all equipment, parts, components, where the manufacturers provide a warranty and shall be exercised for the duration of this contract. The Contractor shall provide the COR/ACOR with a copy of the warranty and manual for all equipment in an excel sheet format for any new parts/equipment. The warranty excel sheet should be updated as warranty information changes for the equipment. The Contractor shall provide a plan for managing warranties with the capability submission. All warranty data shall be returned to the Government at contract completion. When Contractor personnel determine that a warranted item not installed by the Contractor requires service, the Contractor shall notify the COR in writing no later than 0900 the next working day or give telephone notification within fifteen (15) minutes of detection if the deficiency threatens damage to personnel or property. The COR/ACOR will direct the Contractor to: (1) repair the deficiency if potential damage may result from deferring repairs; or (2) clean the work area and stop work. The Contractor shall not receive payment for work not authorized by the COR/ACOR which is performed on warranted equipment, unless the COR/ACOR concurs that such work was a legitimate response to a true emergency condition.

Deliverable
A007 Warranty Program

2.2.4.6 Operation and Maintenance (O&M) Manual Digital Library. N/A

2.2.5 Operations Work Orders (OWOs). N/A

2.2.6 Project Work Orders (PWOs). N/A

2.2.6.1 Warranty Enforcement Manager. N/A

2.2.6.2 Warranty Management. N/A

2.2.6.3 Routing of Warranty DMOs. N/A

2.2.6.4 Warranty Records. The Contractor shall comply with standard Army execution and warranty claim action reporting programs as defined in AR 700-139.

2.2.6.5 Exceptions. The existence of a warranty does not alleviate the Contractor of his

responsibility to perform the work needed to prevent potential damage to personnel and property or to prevent unnecessary shutdown of facilities and functions.

2.2.6.6 Technical Document Library Operation. N/A

2.3 As Built and Geospatial Information System (GIS). N/A

2.3.1 Maintain As Built. N/A

2.3.2 Real Property Records Updates. N/A

2.3.3 GIS. N/A

2.3.4 GIS Support Services. N/A

2.3.5 GIS Files. N/A

2.3.6 Other Documents. N/A

2.4 Historic Property or Archaeological Site. N/A

2.5 Special Requirements.

2.5.1 Security. For contractors that do not require CAC, but require access to a DoD facility or installation: Contractor and all associated subcontractors' employees shall comply with adjudication standards and procedures using the National Crime Information Center Interstate Identification Index (NCIC-III) and Terrorist Screening Database (Army Directive 2014-05/AR 190-13), applicable installation, facility and area commander installation/facility access and local security policies and procedures (provided by government representative); or, at OCONUS locations, in accordance with status of forces agreements and other theater regulations.

2.5.1.1 Access and General Protection/Security Policy and Procedures. Contractor and all associated subcontractor employees shall provide all information required for background checks to meet installation access requirements to be accomplished by installation Provost Marshal Office, Director of Emergency Services (DES) or Security Office. The contractor workforce must comply with all personal identity verification requirements (installation access and personal identity verification requirements directed by DoD, HQDA, and local policy) as directed by DoD, HQDA and/or local policy. In addition to the changes otherwise authorized by the changes clause of this contract, should the Force Protection Condition (FPCON) at any individual facility or installation change, the Government may require changes in contractor security matters or processes.

2.5.1.2 Motor Vehicle Operators. Contractor's personnel, whose tasks involve require operation of any vehicle, shall possess a valid driver's license, certificates, and permits applicable for the type and class of vehicle being operated.

2.5.1.3 Contractor Vehicle Registration. Currently there is no requirement to register Contractor owned vehicles with the Provost Marshal or DES. However, all vehicles must be registered IAW current state requirements. In addition, the Contractor shall maintain a list of all Contractor owned or operated vehicles and trailers operating on the Installation at all times. The list may be used in case of emergency and/or another contingency. Evidence of vehicle ownership and vehicle liability insurance must be presented upon request.

2.5.1.3.1 Contractor and Vendor Access. All privately owned vehicles or motorcycles or Contractor or vendor furnished vehicles, and equipment must enter the Installation through the

designated secure access control points (ACP). Under the present Installation FPCON, vehicle and equipment operators and passengers must possess identification documents as required by U. S. Army Garrison Hawaii (USAG Hawaii) DES to access the Installation. Vehicle and equipment operators must also possess and be ready to show a valid state and/or commercial driver's license, current vehicle registration, and proof of state required minimum liability insurance. As determined by the Installation FPCON, an elevated FPCON may require additional security screening and/or limited Installation access. All vehicles must be registered IAW current state requirements in which they are registered.

2.5.1.3.2 All Contractor personnel, not possessing a Common Access Card (CAC), requesting access to USAG Hawaii installations will enter through the designated Visitor Control Center (VCC). All Contractor personnel will be required to present a United States National or State issued identification that is capable of being scanned for valid entry. Contractor personnel will receive a visitor's badge at the VCC with the length of access allowed. The maximum access length for visitor badging is one year. Once issued a valid visitor's badge Contractor personnel may enter any Manned Access Control Point/Gate. All Contractor personnel and their vehicles, equipment and packages are subject to inspection or examination (search) at entry/exit of all Military installations in the State of Hawaii. Contractor and all associated sub-contractors employees shall comply with adjudication standards and procedures using the National Crime Information Center Interstate Identification Index (NCIC-III) and Terrorist Screening Database ('Army Directive 2014-05' and 'AR 190-13'), applicable installation, facility and area commander installation/facility access and local security policies and procedures (provided by government representative); or, at OCONUS locations, in accordance with status of forces agreements and other theater regulations.

2.5.1.3.3 **ACCESS TO ARMY INSTALLATIONS – PERSONNEL AND VEHICLES.**
The Government recognizes the important roles companies like you play in our day-to-day operations. That is why USAG Hawaii is enhancing the current access control solution called the Automated Installation Entry (AIE) Program. This program supports security requirements while offering a streamlined access procedure for vendors and contractors, subcontractors, suppliers and service providers. This program is available to new and existing personnel who require access to USAG Hawaii and are not authorized to receive a Department of Defense CAC and desire a streamlined entry into the installation. Sponsorship and participation at each USAG Hawaii location (e.g., Schofield Barracks, Wheeler Army Airfield, Fort Shafter, Tripler Army Medical Center, Pililaau Army Recreation Center and Pohakuloa Training Area) is required.

AIE Credential holders may access the installation through any of the USAG-Hawaii Gates that size allows and will only be subject to random inspections.

Companies that choose not to participate in the AIE Program will have limited access through the Schofield Barracks Lyman gate, Fort Shafter's Buckner Gate and Tripler Army Medical Center Main Gate. All employees will be required to go through the inspection area and will be subject to the standard access control procedures, security screenings, and/or vehicle inspections.

**Access control changes can occur at any time due to security requirements*

Companies that service USAG Hawaii facilities may initiate enrollment in the AIE Program by contacting the COR.

If you have questions regarding the AIE Program at USAG Hawaii, please contact Security Branch Operations, at 808-656-0232.

- AIE Program Enrollment Process for Background Check and Process to obtain AIE Badge

Enroll your company by contacting the COR who will be the Sponsor. The COR will provide the excel spreadsheet for the list of contractor employee information. The following information is required from the contractor: last name, first name, date of birth, status, social security number, company name, and contract number. The COR will complete the Sponsor information and provide the list to the Directorate of Emergency Services (DES) Access Control Division. DES will conduct a background check to vet personnel prior to arrival to pick up their AIE Badge and will ensure a more efficient process while saving time.

The AIE Program performs background screening and credentialing.

DES will contact the COR (Sponsor) once the background checks have been validated to schedule a time for the contractor employees to go to one of the registration locations and complete the process to obtain the AIE Badge.

Contractor employees should bring an acceptable form of identification (see List A and List B) to the appointment. Upon arrival, a photo will be taken to complete the process. Employees will be issued their AIE Badge, which they will use for access to the installation.

Forms of Acceptable Identification for picking up your credential:

List A - One (1) needed
U.S. Passport (unexpired)
Permanent Resident Card or Alien Registration Receipt Card (Form I-551)
Unexpired foreign passport, with I-551 stamp or attached Form I-94 indicating unexpired employment authorization
Unexpired Employment Authorization Document that contains a photograph (Form I-766, I-688, I688A, I-688B)

List B – Two (2) needed
Driver’s license or ID card issued by a state
ID Card issued by federal, state or local government agencies or entities
School ID card with a photograph
Voter’s registration card
U.S. Military card or draft record
Military Dependent’s ID card
U.S. Coast Guard Merchant Mariner Card
Native American tribal document
Driver’s license issued by a Canadian government authority
U.S. Social Security card issued by the Social Security Administration

Certification of Birth Abroad issued by the Department of State (Form FS-545 or Form DS-1350)
Original or certified copy of a birth certificate issued by a state, county, municipal authority or outlying possession of the United States bearing an official seal
U.S. Citizen ID Card (Form I-197)
ID Card for use of Resident Citizen in the United States (Form I-179)
Unexpired employment authorization document issued by DHS (other than those listed under List A)

2.5.1.4 Physical Security. N/A

2.5.1.5 Secure Area Access. N/A

2.5.1.6 Employee Terminations. When an employee is terminated from employment on the contract for any reason, the Contractor shall have an out-processing checklist that identifies the Government issued Installation Access Badge/Pass has been turned into the COR and property items accounted for and back in proper custody. A signature shall be required on the checklist from the appropriate person acknowledging receipt of the items. Checklists shall be retained for the duration of the contract.

2.5.1.7 Departing Employees. The Contractor shall ensure Contractor employees return security photographic identification cards, permits, CAC, GFP, keys, photo passes, range passes, sensor access (slide) cards and that access to the LAN email has been canceled. All out processing Contractor employee CACs must be returned to the COR no later than close of business on the last workday. A formal termination or departing memo must be submitted to the COR and security office with the requested items stating they have been collected.

2.5.1.8 Key Control. The COR/ACOR will coordinate with the contractor to gain access to secured areas requiring access. The Contractor shall assume responsibility of key(s) issued and security of area being accessed for execution of duties. The Contractor shall develop procedures covering key control in a Quality Control Plan. The Contractor shall immediately report any occurrences of lost or duplicate keys to the COR/ACOR. All references to keys include key cards.

2.5.1.8.1 Lost keys shall immediately be reported by written correspondence to the COR. In the event keys (other than master keys) are lost or duplicated, the Contractor shall, upon direction of the Contracting Officer (KO), re-key or replace the affected lock or locks. When the replacement of locks or re-keying is performed by the Government, the total cost of re-keying or the replacement of the lock or locks shall be at no additional cost to the Government. In the event a master key is lost or duplicated, all locks and keys for that system shall be replaced at the Contractor's expense.

2.5.1.8.2 The Contractor shall prohibit the use of Government-issued keys by any persons Other than the Contractor's employees. The Contractor shall prohibit the opening of locked areas by Contractor employees to permit entrance of persons other than Contractor employees engaged in the performance of assigned work in those areas, or personnel authorized entrance by the KO. All references to keys include key cards.

2.5.1.8.3 Lock Combinations. N/A

2.5.2 Security Training.

2.5.2.1 iWatch Training. The contractor and all associated sub-contractors shall brief all employees on the local iWatch Army program (training standards provided by the requiring activity ATO). This local developed training will be used to inform employees of the types of behavior to watch for and instruct employees to report suspicious activity to the COR. This training shall be completed within thirty (30) calendar days of contract award and within five (5) calendar days of new employees commencing performance with the results reported to the COR NLT thirty (30) calendar days after contract award.

2.5.2.2 Anti-Terrorism (AT) Level 1 Awareness Training. All contractor employees, including subcontractor employees, requiring access Army installations, facilities and controlled access areas shall complete AT Level I Awareness training within thirty (30) calendar days after contract start date or effective date of incorporation of this requirement into the contract, whichever is applicable. The contractor shall submit certificates of completion for each affected contractor employee and subcontractor employee, to the COR or to the KO, if a COR is not assigned, within five (5) calendar days after completion of training by all employees and subcontractor personnel. AT level I Awareness training is available at the following website: http://jko.jten.mil.

2.5.2.3 Operational Security (OPSEC) Awareness Training. Per AR 530-1, Operations Security, Contractor employees must complete Level I OPSEC Awareness training. New employees must be trained within thirty (30) calendar days of their reporting for duty and annually thereafter. The contractor shall send to the COR via both electronic and paper copies. Level I OPSEC training is available at the following website: https://securityawareness.usalearning.gov/opsec/index.html.

2.5.2.4 All Contractor employees must complete the DoD Cybersecurity Awareness Training before issuance of network access and annually thereafter. N/A

2.5.2.5 Threat Awareness Reporting Program: For all contractors with security clearances. Per AR 381-12 Threat Awareness and Reporting Program (TARP), contractor employees must receive annual TARP training by a CI agent or other trainer.

2.5.3 Safety. The Contractor shall safeguard and maintain all Government and Contractor property, as well as provide for the safety and wellbeing of personnel employed under this contract. The Contractor shall comply with AR 385-10, *The Army Safety Program*. All Contractor employees shall wear a reflective vest or suitable substitute while working during dark hours. Contractor shall be responsible for any injury to any Contractor's representative, or others, as well as for any damage to any personal or public property that occurs during the performance of this contract that is caused by the Contractor's fault or negligence.

2.5.3.1 Safety Plan. The Contractor shall develop and implement a safety program for its employees. The Contractor shall submit the Safety Plan to the KO for review and acceptance within ten (10) days of commencement of work. Revisions shall be submitted five (5) calendar days prior to the effective date of change.

Deliverable
A003 Safety Plan

2.5.3.2 Occupational Safety and Health Administration (OSHA). The Contractor shall comply with the OSHA standards. The Contractor shall comply with all applicable Federal, State, and Local Laws, Regulations, and Directives. If the Contractor fails or refuses to comply promptly with safety requirements, the Government may issue an order stopping all or part of the work until satisfactory corrective action has been taken. No part of the time was lost due to any such order shall be made the subject of claim for extension of time or for excess costs or damages to/by the Contractor. The Contractor shall be responsible for enforcement of all safety requirements by the Contractor and his Subcontractors/teaming partners and/or joint venture partners.

2.5.3.3 Hot Work Permit.

A Hot Work Permit is required any time heat producing devices are used and shall be issued by the Fire Department prior to ANY work being started.

- Example, welding, grinding, cutting, brazing, etc.
- Hot Work Permits will be closed by the Fire Department, after hot work is completed, and before personnel responsible for the work clears the job site.

2.5.4 Training, Physical Requirements, or other Expertise Required.

2.5.4.1 Certification and Licensure. The Contractor shall ensure all Contractor's employees and associated Subcontractors are certified or licensed in the specific areas required by the State of Hawaii. The Contractor shall ensure employees are certified or licensed in the appropriate Environmental Protection Agency (EPA) areas required. The Contractor shall ensure all required documentation of certification or licensure for Contractor personnel are filed with the COR/ACOR within twenty-four (24) hours prior to employees commencing performance.

2.5.5 Environmental Requirements.

2.5.5.1 Green Procurement. Section 6002 of the *Resource Conservation and Recovery Act of 1976* (RCRA) requires the use of recycled and recovered products identified in the EPA's Comprehensive Procurement Guidelines.

2.5.5.2 The Contractor shall use these recycled or recovered products unless they cannot be procured within a reasonable period of time not to exceed seven (7) calendar days; at prices not to exceed five (5) percent of prevailing rates; or the product(s) does not meet technical or performance standards. EPA Guidelines are the minimum requirement. The Contractor shall use materials and products commonly used in industry. The Contractor shall maintain records and submit an annual report to the COR/ACOR, along with the annual certification required by FAR 52.223-9 (*Certification and Estimate of Percentage of Recovered Material Content for EPA Designated Items)*, upon completion of the base year and each option year.

2.5.5.3 Environmental Compliance. The Contractor shall comply with all Federal, State, Local, and Installation Environmental Laws, Rules, Plans, and Policies. The Contractor shall use and store all materials, chemicals, and equipment used in the performance of services on the

Installation IAW with Industry Standards, Local, State and Federal Laws. The Contractor shall be financially responsible for all fines and associated costs for hazardous waste management, transportation, and disposal of waste due to the Contractor's noncompliance. The Contractor shall submit Safety Data Sheets (SDS) for approval on all materials, five (5) days before delivery of the material, to the COR/ACOR. The Contractor shall provide upon request from the COR/ACOR all required data to meet environmental mandated reporting requirements (e.g., air emission data, hazardous material storage/usage, herbicide/pesticide usage, solid/hazardous waste generation). The Contractor shall provide data to meet reporting deadlines and during compliance inspections upon request from the COR/ACOR.

2.5.5.4 Spill Plan. The Contractor shall notify the COR/ACOR within one (1) hour, if the Contractor spills or releases any hazardous substances, *i.e.,* substances listed in 40 CFR 302, *Designation, Reportable Quantities, and Notification*. The Contractor shall submit a Spill Plan to the KO for approval within thirty (30) days of contract award IAW Spill Prevention Control and Countermeasure Plan. All spills of substances containing EPCRA hazardous substance or oil/fuel will be immediately reported to the Directorate of Public Works Spill Response line at 808-656-1111 or 808-656-3279 (after hours).

Deliverable
A004 Spill Plan

2.5.6 Contingency Plans.

2.5.6.1 General. N/A

2.5.6.2 Mobilization Contingency Plan. N/A

2.5.6.3 Disaster Contingency Plan. This plan shall establish procedures, identify personnel, document essential PWS disaster services and identify the means of maintaining essential PWS services during disasters. Disaster means natural disaster (*e.g.,* earthquake, major storm, flash flood, or hurricane), utility outage, terrorist attack or other special circumstances identified by the Government. The Contractor shall submit a Disaster Contingency Plan within thirty (30) days of contract award.

Deliverable
A005 Contingency Plan

2.5.6.4 Labor Dispute Contingency Plan. This plan shall establish procedures and identify responsible personnel to provide the services below, with no interruption in the event of a labor dispute:

a. Identify and address critical Preventive Maintenance and inspection tasks,
b. Maintain electrical emergency generators, and
c. Process and execute emergency and urgent service and work orders.

The plan shall establish procedures and a time frame to secure replacement personnel in the event of a strike; and shall also record the Contractor’s experience with and establish Contractor procedures for collective bargaining. The Contractor shall submit a Labor Contingency Plan NLT contract start date.

Deliverable
A005 Contingency Plan

2.5.6.5 Plan Updates. The Contractor shall update these plans as changes occur and shall submit a copy of the proposed plan to the KO for approval at least thirty (30) days prior to the proposed effective date of the updated plan.

2.5.6.6 OPSEC program. The contractor shall develop an OPSEC Standing Operating Procedure (SOP)/Plan within 90 calendar days of contract award, to be reviewed and approved by the responsible Government OPSEC officer. This plan will include a process to identify critical information, where it is located, who is responsible for it, how to protect it and why it needs to be protected. The contractor shall implement OPSEC measures as ordered by the commander. In addition, the contractor shall have an identified certified Level II OPSEC coordinator per AR 530-1.

Deliverable
A006 OPSEC SOP/Plan

3.0 Performance Requirements and Standards.

3.1 Performance Task Requirements, Standards and Acceptable Quality Levels (AQLs).

3.2 Quality Assurance (QA). The Government will evaluate the Contractor's performance under the contract IAW the Government's Quality Assurance Surveillance Plan (QASP). QASPs are considered to be "living documents," dynamic, adaptable, and subject to modification based on Contractor performance surveillance results. The QASP is not part of the PWS and will not be issued with the solicitation. The QASP focuses on the procedures and processes the Government will implement to ensure the Contractor is performing IAW the performance standards within the PWS. The Government plan defines the criteria for how the Contractor's performance will be evaluated, the frequency of surveillance, and the items to be inspected. Although the Government will develop a QASP, Government surveillance of Contractor performance is not limited to the QASP, or the performance objectives, outlined in the Performance Requirements Summary (PRS). The Government retains the right to evaluate all services required by the contract. The Government will conduct inspections and tests in a manner that will not unduly delay the work. If any of the services performed do not conform to contract requirements, the Contractor shall perform the services again at no additional cost to the Government.

3.3 Quality Control Plan (QCP). Quality control is the responsibility of the Contractor. The Contractor shall develop, implement, and maintain an effective quality control program which shall be documented in a QCP to ensure services are performed IAW this PWS. The Contractor shall develop and implement procedures to identify and prevent the recurrence of defective services. The Contractor's QCP is the means by which they assure themselves that the work conforms to contract requirements. The basic principle of the plan is that the Contractor is responsible for quality control. The QCP shall be constructed in such a manner that each SERVICE can be extracted and used for that function only and not contain extraneous information. The Contractor's QCP shall include a separate section, which addresses the Contractor's method of managing quality of work. The QCP shall include a description of the inspection system to address services listed in this PWS, and a description of the methods to be used for identifying and preventing defects in the quality of services performed. The plan shall include a description of the Contractor's inspection system to include specifics as to areas to be inspected on a scheduled and unscheduled basis, frequency of inspections, and the title and

organizational placement of the Contractor's inspectors. No lead person or first line supervisor shall be considered a Quality Control Inspector. The Contractor shall develop, maintain, and submit a QCP to the KO for acceptance within thirty (30) calendar days after the contract is awarded. The Contractor shall submit any proposed changes in the QCP to the KO for written approval five (5) working days prior to implementation.

Deliverable
A002 Quality Control Plan

3.4 Quality Control Files. The Contractor shall maintain files of all inspections or tests conducted by the Contractor, to include any corrective actions taken. These files shall be subject to Government review at the COR's discretion during the contract term, to include any extensions of contract term. The Quality Control Files will be the property of the Government and shall be turned over to the Government upon completion or termination of the contract.

3.5 Customer Feedback Program. The Contractor shall establish and operate a customer feedback program as part of the QCP. Performance Requirements Summary (PRS) Matrix.

4.0 Performance Requirements Summary (PRS) Matrix.

Required Services/ Performance Object	PWS Paragraph Number	Performance Standard	Maximum Allowable Degree of Deviation from Requirement (AQL Level)	Incentive/ Disincentive
Preventive Maintenance PM Schedule	8.2	STD: The contractor shall develop a semi-annual PM schedule and submit in MS Word or MS Excel to COR for approval within ten (10) working days before the start of service.	AQL: 10% deviation from standard	Non-conforming services will result in Non-Conforming Reports issued and a potential negative CPARS narrative.
Fire Alarm & Mass Notification Systems.	8.3-8.3.2	STD: The Contractor shall conduct quarterly preventive maintenance to ensure all Fire Alarm and Mass Notification System components remain fully operational and compliant with NFPA 72 and the Hawaii State Fire Code. All inspections, testing, and corrective actions must be completed at required intervals, and any deficiencies shall be corrected immediately. Deficiencies must be documented and reported within 24 hours, including recommended corrective actions. All work shall meet OSHA and facility safety standards. A consolidated written PM report shall be submitted to the COR within five (5) working days after PM completion.	AQL: 5% deviation from standard	Non-conforming services will result in Non-Conforming Reports issued and a potential negative CPARS narrative.

Required Services/ Performance Object	PWS Paragraph Number	Performance Standard	Maximum Allowable Degree of Deviation from Requirement (AQL Level)	Incentive/ Disincentive
Emergency Lighting & Exit Signs	8.4-8.4.1	STD: The Contractor shall perform annual preventive maintenance and shall ensure all emergency lighting units and exit signs remain fully operational, code-compliant, and capable of providing a minimum of 1 foot-candle of illumination upon loss of normal power. Systems shall receive all required annual functional 90-minute full-duration test, with deficiencies corrected immediately. A consolidated written PM report shall be submitted to the COR within five (5) working days after PM completion.	AQL: 10% deviation from standard	Non-conforming services will result in Non-Conforming Reports issued and a potential negative CPARS narrative.
Lightning Protection Systems	8.5-8.5.1	STD: The Contractor shall perform semi-annual PM and shall ensure the Lightning Protection System remains fully operational, code-compliant, and capable of providing effective protection in Hawaii's environmental conditions. The system shall be inspected semiannually. PM shall verify continuity, grounding, bonding, corrosion conditions, and component integrity in accordance with NFPA 780, UL 96A, and UFC 3-575-01.	AQL: 10% deviation from standard	Non-conforming services will result in Non-Conforming Reports issued and a potential negative CPARS narrative.

Required Services/ Performance Object	PWS Paragraph Number	Performance Standard	Maximum Allowable Degree of Deviation from Requirement (AQL Level)	Incentive/ Disincentive
Heating, Ventilation, and Air Conditioning (HVAC) Quarterly PM	8.6-8.6.3	STD: The Contractor shall ensure all HVAC systems listed in TE #1 including central systems, PTAC units, and ductless systems remain operational, efficient, and safe. The Contractor shall conduct preventive maintenance at required intervals and coordinate with facility personnel to minimize disruption. The Contractor shall maintain accurate PM records, including measurements, test results, component conditions, and corrective actions. All inspections, testing, and corrective actions must be completed at prescribed intervals, and any deficiencies shall be corrected immediately. A consolidated written PM report shall be submitted to the COR within five (5) working days following completion of all PM activities.	AQL: 10% deviation from standard	Non-conforming services will result in Non-Conforming Reports issued and a potential negative CPARS narrative.
Preventive Maintenance (PM) Service Report	8.7	STD: The Contractor shall submit a consolidated written PM report to the COR within five (5) working days after PMs have been completed.	AQL: 10% deviation from standard	Non-conforming services will result in Non-Conforming Reports issued and a potential negative CPARS narrative.
Repairs identified during Preventive Maintenance (PM) Services	8.8	STD: Submit a complete TE 2 firm-fixed-price quote to the COR within two (2) business days after a parts-required deficiency is identified during PM. Do not start the parts repair until a written firm-fixed-price task order is issued.	AQL: 10% deviation from standard	Non-conforming services will result in Non-Conforming Reports issued and a potential negative CPARS narrative.
Repairs	8.9	STD: Perform only Contracting Officer-authorized firm-fixed-price task order repairs. Complete each authorized repair within two (2) business days after receipt of required parts unless the task order specifies otherwise. Any cost above the approved firm-fixed-price is at the Contractor's risk. The Government reserves the right	AQL: 10% deviation from standard	Non-conforming services will result in Non-Conforming Reports issued and a potential negative CPARS narrative.

Required Services/ Performance Object	PWS Paragraph Number	Performance Standard	Maximum Allowable Degree of Deviation from Requirement (AQL Level)	Incentive/ Disincentive
		to self-perform or use another entity.---		
Replacement/Repair Parts	8.10	STD: The Contractor shall provide new, KO-approved replacement parts as part of the firm-fixed-price task order, with receipts as backup, and all parts, materials, and labor shall carry a one--year warranty. Manufacturer-warrantied items shall be serviced and replaced by the Contractor at no additional cost to the Government.	AQL: 10% deviation from standard	Non-conforming services will result in Non-Conforming Reports issued and a potential negative CPARS narrative.
Unscheduled/Assessment/Work Request	8.11	STD: Acknowledge the work request within one (1) business day. Perform an on-site assessment within two (2) business days. Submit a complete TE 2 firm-fixed-price quote within five (5) business days of the assessment. Do not commence repair work until a written firm-fixed-price task order is issued. Assessments shall describe the deficiency, the parts and work required, the firm fixed price, and the projected completion date.	AQL: 10% deviation from standard	Non-conforming services will result in Non-Conforming Reports issued and a potential negative CPARS narrative.
Equipment Inventory List	8.12	STD: The Contractor shall provide the updated inventory list to the COR immediately upon any revisions to ensure continued accuracy and accountability.	AQL: 10% deviation from standard	Non-conforming services will result in Non-Conforming Reports issued and a potential negative CPARS narrative.
Invoice	8.13	STD: Upon completion of work the Contractor shall provide invoices, Work Order Request/Repair & Cost Estimate, receipts and all required deliverables to COR NLT the 5th business day of month.	AQL: 10% deviation from standard	Non-conforming services will result in Non-Conforming Reports issued and a potential negative CPARS narrative.

5.0 Common Levels of Service (SERVICE)

The Contractor shall provide overall management, supervision, personnel, labor, generalized or specialized equipment necessary to maintain, repair, operate, and perform all the SERVICE functions of the Base Operations specified below. This shall be done IAW all the Terms, Conditions, General and Special Provisions, Specifications, Drawings, Attachments, and Exhibits contained herein or incorporated by reference.

6.0 Deliverables.

Reference Technical Exhibit (TE 3) Deliverables

7.0 Related Documents.

7.1 Definitions and Acronyms.

7.1.1 Definitions.

7.1.1.1 Acceptable Quality Level (AQL). The AQL is the maximum percent defective (or the number of defects per hundred units) for the purposes of sampling inspection can be considered satisfactory.

7.1.1.2 Alternate Contracting Officer's Representative (ACOR). An employee of the U.S. Government provided by the RA and appointed by the KO to provide support to CORs in monitoring and documenting the Contractor's performance. These alternate surveillance support personnel will serve as onsite representatives of the COR in performance of actual contract surveillance if they meet all COR training and experience requirements and are appointed by the KO as an ACOR.

7.1.1.3 Ashes. N/A

7.1.1.4 Bulk Waste. Large items of solid waste such as household appliances, furniture, auto parts, pallets, shelving, piping, stone, concrete rubble, brick, lumber, toys, and other wastes; the size or weight of which precludes or complicates the handling by normal collection, processing, or disposal methods.

7.1.1.5 Bulky Waste. The waste placed at the collection point or curbside that doesn't fit or is too heavy to be placed in the routine collection container. These wastes include but are not limited to lumber, scrap metals, bricks, blocks, concrete rubble, stones, toys, furniture, appliances, logs, limbs, televisions, cabinets, automotive components, power equipment, crates, wheels, de-rimmed tires, electronics and their components, etc.

7.1.1.6 Cannibalize. Remove parts from Government property for use or for Installation on other Government property.

7.1.1.7 Carpet Care. N/A

7.1.1.8 Child, Youth and School Services (CYS). Overarching naming convention for Child Development Center (CDC), Youth Activity Center, and School Age Services (SAS). CYS is used when referencing all programs.

7.1.1.9 Cleaning. Removing stains, soil, and dirt; accomplished by chemical or mechanical means.

7.1.1.10 Collection. The pickup of accumulated recyclable material, solid waste, including bulky waste, from any collection point, regardless of quantity.

7.1.1.11 Collection Frequency. N/A

7.1.1.12 Collection Point. The location designated on the drawings or maps or described in this performance work statement where solid waste, including bulky materials, will be temporarily stored for collection by the Contractor.

7.1.1.13 Commercial Solid Waste. All types of solid waste generated by stores, offices, restaurants, warehouses, and other non-manufacturing activities, excluding residential and industrial waste.

7.1.1.14 Construction and Demolition (C&D) Waste. The waste building materials, packaging and rubble resulting from construction, remolding, repair, and demolition operation on pavement, housing, commercial buildings, and other structures.

7.1.1.15 Contract Administrator (CA). The official Government representative delegated authority by the KO to administer a contract. This individual, normally working in an appropriate contracting or procurement career field, advises on all technical contractual matters.

7.1.1.16 Contract Discrepancy. A failure of the Contractor to perform IAW contract requirements and specifications, *e.g.,* a failure of the Contractor to provide, or provide on time, the required contract products, or services; or it may result because delivered products or services do not meet specific contract requirements.

7.1.1.17 Contract Discrepancy Report (CDR). A report used to document other than satisfactory Contractor performance. The CDR requires the Contractor to explain, in writing, why performance is other than satisfactory; how performance shall be returned to satisfactory levels; and how recurrence of the problem shall be prevented in the future.

7.1.1.18 Contractor. A supplier or vendor awarded a contract to provide specific supplies or service to the Government. The term used in this contract refers to the prime.

7.1.1.19 Contractor Acquired Property (CAP). Property acquired, fabricated, or otherwise provided by the Contractor for performing a contract. Contractor retains title.

7.1.1.20 Contractor Manpower Reporting Application (CMRA). N/A

7.1.1.21 Contracting Officer (KO). A person with authority to enter, administer, or terminate contracts and make related determinations and findings on behalf of the Government. Note: The only individual who can legally bind the Government.

7.1.1.22 Contracting Officer's Representative (COR). An employee of the U.S. Government appointed by the KO to help administer the contract. Such an appointment shall be in writing and shall state the scope of authority and limitations. This individual has the authority to provide technical direction to the Contractor if that direction is within the scope of the contract, does not constitute a change, and has no funding implications. This individual does NOT have the authority to change the terms and conditions of the contract.

7.1.1.23 Curb Side Pick-up. Collection of solid waste or recyclable materials (to include bulky waste) that is placed next to curb, doorway or alley by the supported activity. This refers to locations that are not serviced by bulk containers (dumpsters or compactors).

7.1.1.24 Damage Caused by Contractor. Damages caused by Contractor employees shall be repaired at no cost to the Government. The Contractor shall notify the COR/ACOR and return the damaged area to its previous condition. The Contractor shall furnish all labor, materials, and equipment to perform the repair work including cultivating and applying seed, sprigging, or placing sod. The Contractor shall maintain all turf repair work to ensure successful growth.

7.1.1.25 Damage Report. The Contractor shall submit a monthly damage report to the COR/ACOR that annotates the damage, corrective action, and date corrected.

7.1.1.26 Debris. Includes, but is not limited to, paper, cans, bottles, cigarette butts, cardboard, plastic, limbs and branches, pine straw and pinecones, leaves, rocks, and other similar items.

7.1.1.27 Defective Service. A service output that does not meet the standard of performance associated with the PWS.

7.1.1.28 Deliverable. Anything that can be delivered can include non-manufactured things, such as meeting minutes, reports or logs.

7.1.1.29 Equipment. A tangible item that is functionally complete for its intended purpose, durable, nonexpendable, and needed for the performance of a contract. Equipment is not intended for sale and does not ordinarily lose its identity or become a component part of another article, when put into use. Equipment does not include material, real property, special test equipment or special tooling.

7.1.1.30 N/A

7.1.1.31 Fertilization. N/A

7.1.1.32 Food Waste. N/A

7.1.1.33 Garbage. Animal and vegetable waste resulting from the handling, preparation, cooking, and consumption of foods.

7.1.1.34 General Fund Enterprise Business System (GFEBS). N/A

7.1.1.35 Generation. The act or process of producing refuse (solid waste) or recyclable materials.

7.1.1.36 Government Furnished Property (GFP). Property in the possession of or directly acquired by the Government and subsequently furnished to the Contractor for the performance of a contract. Government furnished property includes, but is not limited to, spares and property furnished for repair, maintenance, overhaul, or modification. Government furnished property also includes Contractor acquired property if the Contractor acquired property is deliverable under a cost contract when accepted by the Government for continued use under the contract.

7.1.1.37 Government Property. All property owned or leased by the Government. Government property includes both Government furnished property and Government purchased Contractor acquired property. Government property includes material, equipment, special tooling, special test equipment, and real property. Government property does not include intellectual property and software.

7.1.1.38 Grass Cutting. N/A

7.1.1.39 Hard Surface Floor Care. N/A

7.1.1.40 Hazardous Material. Any item or chemical, which is a "health hazard", or "physical hazard", as reflected in Federal Standard (FED-STD) 313 *Material Safety Data and Disposal Data for Hazardous Materials Furnished to Government Activities*, defined in OSHA 29 CFR 1910, and pursuant to FAR 23.301 (Hazardous Materials) Definition. It also includes any other material designated by a Government COR/technical representative as potentially hazardous and require safety controls (*e.g.,* pesticides, fertilizers).

7.1.1.41 Installation Design Guide (IDG). IDGs provide standards for site planning, buildings, vehicular and pedestrian circulation, landscaping, site elements (*e.g.,* signage, utilities), force protection, and sustainable design. The IDGs are specific to each Army Installation.

7.1.1.42 Institutional Solid Waste. It is waste that is generated by educational, health care, correctional and other institutional facilities.

7.1.1.43 Key Personnel. Contractor personnel evaluated in a source selection process and are used in the performance of a contract. When key personnel are used as an evaluation factor in best value procurement, an offer can be rejected if it does not have a firm commitment from the people who are listed in the proposal. The prime Contractor is responsible for performance of all Subcontractors.

7.1.1.44 Lavatories, Latrines, or Bathrooms. N/A

7.1.1.45 Loss of Government Property. Unintended, unforeseen, or accidental loss, damage, or destruction of Government property that reduces the Government's expected economic benefits of the property. Loss of Government property does not include occurrences such as purposeful destructive testing, obsolescence, normal wear and tear, or manufacturing defects. Loss of Government property includes, but is not limited to:

a. Items that cannot be found after a reasonable search,
b. Theft,
c. Damage resulting in unexpected harm to property requiring repair to restore the item to usable condition, or
d. Destruction resulting from incidents that render the item useless for its intended purpose or beyond economical repair.

7.1.1.46 Lot. N/A

7.1.1.47 Lot Size. N/A

7.1.1.48 Material. Property that is consumed or expended during the performance of a contract, component parts of a higher assembly, or items that lose their individual identity through incorporation into an end item. Material does not include equipment, special tooling, or special test equipment or real property.

7.1.1.49 Material Handling Area. N/A

7.1.1.50 Non-Combustible Material. Material that doesn't burn at ordinary temperatures.

7.1.1.51 Non-Personal Services. The personnel rendering the services are not subject, either by the contract's terms or by the manner of its administration, to the supervision and control usually prevailing in relationships between the Government and its employees. Nonpersonal service contracts are authorized by the Government IAW RFO FAR 37.2, under general contracting authority, and do not require specific statutory authorization.

7.1.1.52 Organic Storage Site. N/A

7.1.1.53 Performance Indicator. The characteristic of an output of a work process that can be measured.

7.1.1.54 Performance Requirements Summary (PRS). Identifies the key service outputs of the contract that will be evaluated by the Government to ensure contract performance standards are met by the Contractor (other services may also be inspected under the authority of the Inspection of Service Clause).

7.1.1.55 Physical Security. Actions that prevent the loss or damage of Government property.

7.1.1.56 Plant. N/A

7.1.1.57 Property. All tangible property, both real and personal.

7.1.1.58 Property Administrator (PA). An authorized representative of the KO appointed IAW agency procedures, responsible for administering the contract requirements and obligations relating to Government property in the possession of a Contractor.

7.1.1.59 Property Records. N/A

7.1.1.60 Provide. To furnish, as in Government furnished property, or to acquire, as in the contractor acquired property.

7.1.1.61 Pruning. N/A

7.1.1.62 Public Traffic Areas. Lobbies, hallways, corridors, stairwells, meeting rooms, and lavatories.

7.1.1.63 Quality Assurance (QA). Verification that services being performed by the Contractors are IAW acceptable standards.

7.1.1.64 Quality Assurance Evaluator (QAE). A Government representative responsible for performing surveillance and inspection of Contractor performance.

7.1.1.65 Quality Assurance Surveillance Plan (QASP). An organized document written by the Government specifying the surveillance methodology used for surveillance of Contractor performance.

7.1.1.66 Quality Control. All necessary measures taken by the Contractor to assure that the quality of an end product or service shall meet contract requirements.

7.1.1.67 Raise. N/A

7.1.1.68 Random Number Table. N/A

7.1.1.69 Random Sample. N/A

7.1.1.70 Random Sampling. N/A

7.1.1.71 Real Property. DoD Lands, buildings, structures, utility systems, improvements, and appurtenances, thereto that includes equipment attached to and made part of buildings and structures, but not movable equipment. See Federal Management Regulation 102-71.20 (41 CFR 102-71.20).

7.1.1.72 Recycling. The act of recovering materials from the solid waste stream, separating them by commodity, and returned to the economic mainstream as raw material.

7.1.1.73 Recycling Materials. Commodities include corrugated cardboard, wood, and plastic pallets.

7.1.1.74 Recycling Facility. Any facility employed, beyond the initial collection processes and managing recycling which include, but not limited to electronics, organics, plastics, metals, paper, and cardboard.

7.1.1.75 Regulated Medical Waste. N/A

7.1.1.76 Refuse. All garbage, ashes, debris, trash, rubbish and items intended for disposal are generated in conjunction with the activities in the areas covered in this contract. Items excluded are explosives, incendiary waste, hazardous waste, and pathological waste resulting from medical and radiological processes.

7.1.1.77 Refuse Collection. A system of collecting and transporting solid waste from pickup stations to points of disposal.

7.1.1.78 Refuse/Recycling Storage Containers. Cans, drums, bins, bags, boxes, crates, sidewalk litter containers, dumpsters, roll off containers, or similar receptacles which are used for the temporary storage of solid waste while awaiting collection. The term "container" used in this document shall have the same meaning as solid waste storage container.

7.1.1.79 Reporting Labor Hours. N/A.

7.1.1.80 Residential Solid Waste. N/A

7.1.1.81 Sample Size. N/A

7.1.1.82 Sampling. N/A

7.1.1.83 Scavenging. The uncontrolled and unauthorized removal of materials at any point of the solid waste management stream.

7.1.1.84 Sensitive Property. Property is potentially dangerous to public safety or security if stolen, lost, or misplaced, or that shall be subject to exceptional physical security, protection, control, and accountability. Examples include weapons, ammunition, explosives, controlled substances, radioactive materials, hazardous materials or waste, or precious metals.

7.1.1.85 Service/Maintain. These words are interchangeable.

7.1.1.86 Shrub. N/A

7.1.1.87 Soil. Includes, but is not limited to dust, dirt, stains, grease, smudges, streaks, spots, lint, or odors. Soil can be removed chemically, mechanically, or by a combination of both. Mechanical soil removal is removing soil with a machine such as a vacuum cleaner. Chemical soil removal is removing soil with a liquid that contains cleaning agents such as detergents, surfactants, and emulsifiers. The combination of chemical and mechanical methods such as an automatic floor scrubbing machine uses the chemical method to break down and loosen soil which then the mechanical method picks up and carries the soil away. Which soil removal method is used depends on the cleaning objectives and on size, location, and type of surface to be cleaned and is the prerogative of the Contractor.

7.1.1.88 Solid Waste. Garbage, refuse, sludge, and other waste materials are not excluded by Federal regulations. Solid waste is any solid, liquid, semi solid, or contained gaseous material resulting from institutional, industrial, commercial, mining, agricultural, or community operations and activities. Solid waste is accumulated, stored, or treated before being discarded. Materials are discarded if abandoned and not used, reused, reclaimed, or recycled by being disposed of, burned, or treated. Regulated medical wastes are not included in this category.

7.1.1.89 Solid Waste Management Facility (SWMF). Any facility employed, beyond the initial collection processes and managing solid waste including, but not limited to storage areas or facilities, transfer stations, rail haul or barge haul facilities, landfills, disposal facilities, solid waste facilities, surface impoundment and waste oil storage, repossessing, refining facilities, recyclable handling, recovery facilities and waste tire storage facilities.

7.1.1.90 Source Separation. Source separation is the act of separating recyclable materials at their point of generation by the waste generator.

7.1.1.91 Spray Buffing. N/A

7.1.1.92 Spot Cleaning. N/A

7.1.1.93 Standard. A measure of comparison; an acceptability criterion; a benchmark or yardstick against which a service will be measured.

7.1.1.94 Stairwell Cleaning. N/A

7.1.1.95 Street Wastes. N/A

7.1.1.96 Stripping. N/A

7.1.1.97 Subcontractor. One that enters into a contract with a prime Contractor. The

Government does not have privity of contract with the Subcontractor.

7.1.1.98 Tonnage. Weight measured in tons (not imperial).

7.1.1.99 Transfer Station. N/A

7.1.1.100 Trash Removal. N/A

7.1.1.101 Tree. N/A

7.1.1.102 Trimming. N/A

7.1.1.103 Unit Acquisition Cost.

a. For Government furnished property, the dollar value assigned by the Government and identified in the contract; and
b. For Contractor acquired property, the cost derived from the Contractor's records reflect consistently applied generally accepted accounting principles.

7.1.1.104 Vector. N/A

7.1.1.105 Wash. The act of cleansing using water and soap or detergent.

7.1.1.106 Wide Area Workflow (WAWF). A secure web-based system for electronic invoicing, receipt, and acceptance. WAWF allows Government vendors to submit and track invoices and receipt or accept documents over the web allowing Government personnel to process those invoices in a real-time, paperless environment.

7.1.1.107 Workday. The number of hours per day the Contractor provides services IAW the contract.

7.1.1.108 Work Week. Monday through Friday, unless specified otherwise.

7.1.1.109 Yard Wastes. N/A

7.2 Acronyms.

ACC	Army Contracting Command
ACOR	Alternate Contracting Officer's Representative
AFARS	Army Federal Acquisition Regulation Supplement
AMC	Army Materiel Command
ANSI	American National Standards Institute
AQL	Acceptable Quality Level
ArMA	Army Maintenance Application
AR	Army Regulation
ARC	Army Resource Center
ATO	Antiterrorism Officer
CAP	Contractor Acquired Property
CDC	Child Development Center

CDRL	Contract Data Requirements List
CFE	Contractor Furnished Equipment
CFM	Contractor Furnished Material
CFP	Contractor Furnished Property
CFR	Code of Federal Regulations
CLIN	Contract Line-Item Number
CMRA	Contractor Manpower Reporting Application
CONUS	Continental United States (excludes Alaska and Hawaii)
COR	Contracting Officer's Representative
CORT	Contracting Officer's Representative Tool
CPARS	Contractor Performance Assessment Reporting System
DA	Department of the Army
DCMA	Defense Contract Management Agency
DES	Directorate of Emergency Services
DFARS	Defense Federal Acquisition Regulation Supplement
DID	Data Item Description
DoD	Department of Defense
DOL	Department of Labor
DOT	Department of Transportation
DPW	Directorate of Public Works
ECO	Environmental Compliance Officer
EM	Engineering Manual, U.S. Army Corps of Engineers (USACE)
EO	Executive Order
EPA	Environmental Protection Agency
ERDC	Engineering Research Development Center
FAR	Federal Acquisition Regulation
FIPS	Federal Information Processing Standards
FPCON	Force Protection Condition
GFE	Government Furnished Equipment
GFEBS	General Fund Enterprise Business System
GFM	Government Furnished Material
GFP	Government Furnished Property
HLO	High Level Objective
HQDA	Headquarters Department of the Army
HSPD	Homeland Security Presidential Directive
IAW	In Accordance With
IMCOM	Installation Management Command
IPM	Integrated Pest Management
IPMC	Integrated Pest Management Coordinator
IPMP	Integrated Pest Management Plan
IT	Information Technology
KO	Contracting Officer
N/A	Not Applicable
NGB	National Guard Bureau
NLT	Not Later Than
OCI	Organizational Conflict of Interest
OCONUS	Outside Continental United States (includes Alaska and Hawaii)
OMB	Office of Management and Budget
OSHA	Occupational Safety and Health Administration

PAM	Pamphlet
PM	Preventive Maintenance
POC	Point of Contact
POP	Period of Performance
PPIRS	Past Performance Information Retrieval System
PRS	Performance Requirements Summary
PUB	Publication
PWS	Performance Work Statement
QA	Quality Assurance
QAP	Quality Assurance Program
QASP	Quality Assurance Surveillance Plan
QC	Quality Control
QCP	Quality Control Plan
RCRA	Resource Conservation and Recovery Act
RFO	Revolutionary Far Overhaul
SDS	Safety Data Sheets
SF	Standard Form
TE	Technical Exhibit
USARC	U.S. Army Reserve Command
U.S.C.	United States Code
VCE	Virtual Contracting Enterprise
VIP	Very Important Person
WAWF	Wide Area Workflow
WD	Wage Determination

7.3 Applicable Directives, Publications.

ACC PAM 70-1	Interim Army Contracting Command – Contracting Officer's Representative Policy Guide
AASHTO-T11	Standard Method of Test for Materials Finer Than 75-µm (No. 200) Sieve in Mineral Aggregates by Washing
ANSI A300	Standard Practices for Tree Care Operations
ANSI Z60.1	American Standards for Nursery Stock
ANSI Z87.1-2003	Practice for Occupational and Educational Personal Eye and Face Protection Devices
ANSI Z133.1	Safety Requirements for Tree Care Operations
ANSI/ASQC-Z1.4	National American Standard
ANSI Z245.1	Mobile Refuse Collection and Compaction Equipment – Safety Requirements
AR 11-27	Army Energy Program

AR 40-5	Preventive Medicine (Child Development Centers)
AR 40-400	Medical Services Patient Administration
AR 70-13	Management and Oversight of Service Acquisitions
AR 190-5	Motor Vehicles Traffic Supervision
AR 200-1	Environmental Protection and Enhancement
AR 200-3	Natural Resources; Land, Forest, and Wildlife Management
AR 200-4	Cultural Resources Management
AR 200-5	Pest Management
AR 385-10	Army Safety Program
AR 385-40	Army Accident Investigation and Reporting
AR 420-1	Army Facilities Management
AR 420-70	Facilities Engineering (Transportation Infrastructure and Dams)
AR 420-90	Fire Emergency Services
AR 530-1	Operations Security
AR 600-50	Standards of Conduct for Department of Army Personnel
AR 600-63	Army Health Promotion
AR 608-10	Child Development Services
AR Directive 2014-23	Conduct of Screening and Background Checks for Individuals Who Have Regular Contact with Children in Army Programs
29 CFR Part 1910	Occupational Safety and Health Standards
40 CFR	Protection of the Environment
40 CFR Subchapter I	Solid Wastes
40 CFR 202	Motor Carriers Engaged in Interstate Commerce
40 CFR 257	Criteria for Classification of Solid Waste Disposal Facilities and Practices

40 CFR Part 302	Protection of Environment, Designation, Reportable Quantities and Notification
49 CFR 390-396	Motor Carrier Safety Standards
49 CFR 571	Federal Motor Vehicle Safety Standards
Clean Air Act (CAA)	
Clean Water Act (CWA)	
Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA)	
DA PAM 385-40	Army Accident Investigations and Reporting
DA PAM 420-1-1	Housing Management*
DoD 4160.21-M	Defense Materiel Disposition Manual
DoD Directive 5500.7-R	Joint Ethics Regulation
DoDI 1402.5	Criminal History Background Checks on Individuals in Child Care Services
DoDI 4150.07	DoD Pest Management Program
DoDI 5000.72	DoD Standard for Contracting Officer's Representative (COR) Certification
EM-385-1-1	Safety and Health Requirements Manual
EPA, Method 9095	Paint Liquids Filter Test
EPA, SW-846	Test Methods for Evaluating Solid Wastes, Physical/Chemical Methods
FC 3-260-06F	Air Force Design, Construction, Maintenance, and Evaluation of Snow and Ice Airfields in Antarctica 06-01-2015
Federal Standard #313	Material Safety Data and Disposal Data for Hazardous Materials Furnished to Government Activities
Federal Standard #595	Colors

FIFRA	Federal Insecticide, Fungicide, and Rodenticide Act
FIPS PUB 201-2	Personal Identity Verification (PIV) of Federal Employees and Contractors
Garrison's Snow, Ice, and Sand Removal Control Plan	
HSPD 12	Homeland Security Presidential Directive 12 Policy for a Common Identification Standard for Federal Employees and Contractor
IDG	Installation Design Guide
NFPA 1.12-2	Combustible Fibers
OMB M-05-24	Office of Management and Budget (OMB) Guidance Implementation of Homeland Security Presidential Directive (HSPD) 12 – Policy for a Common Identification Standard for Federal Employees and Contractors
OPORD 13-153	Enterprise Municipal Services Performance Standards
SF 95	Position of Public Trust
TB MED 530 5-28(h)(i)	Tri Service Food Code
TM 5-623	Pavement Maintenance Management
TM 5-624	Maintenance and Repair of Surface Areas
TM 5-634	Solid Waste Management
TM-682	Facilities Engineering Electrical Facilities Safety
TM 5-683	Electrical Interior Facilities
TM 5-820-4	Drainage for Areas other than Airfields
TM-684	Facilities Engineering Electrical Exterior Facilities
TM 5-811.3	Electrical Desing Lighting Stats Electricity Protection
TM 9-6150-226-13	Electrical Feeder System
UFC 1-200-01	DoD Building Code (General Building Requirements)
UFC 4-010-1	DoD Minimum Antiterrorism Standards for buildings (Change 1)
UFC 4-021-01	Design and O&M for Mass Notification Systems

UFC 4-021-02NF	Security Engineering Electronic Security Systems
UFC 3-101-01	Architecture 11-28-2011
UFC 3-110-03	Roofing, with Change 1 05-01-2012
UFC 3-110-04	Roofing Maintenance and Repair 01-11-2007
UFC 3-120-01	Design: Sign Standards, with Change 2 03-01-2014
UFC 3-120-10	Interior Design, with Change 1 06-15-2006
UFC 3-190-06	Protective Coatings and Paints 01-16-2004
UFC 3-201-01	Civil Engineering 06-01-2013
UFC 3-201-02	Landscape Architecture, with Change 1 02-23-2009
UFC 3-210-10	Low Impact Development 07-01-2015
UFC 3-220-01	Geotechnical Engineering 11-01-2012
UFC 3-220-04	Backfill for Subsurface Structures 01-16-2004
UFC 3-220-05	Dewatering and Groundwater Control 01-16-2004
UFC 3-220-06	Grouting Methods and Equipment 01-16-2004
UFC 3-220-08	Engineering Use of Geotextiles 01-16-2004
UFC 3-220-10N	Soil Mechanics 06-08-2005
UFC 3-230-01	Water Storage, Distribution, and Transmission, with Change 2 11-01-2012
UFC 3-230-02	O&M: Water Supply Systems 07-10-2001
UFC 3-230-03	Water Treatment 11-01-2012
UFC 3-230-06A	Subsurface Drainage, with Changes 1-2 01-16-2004
UFC 3-240-01	Wastewater Collection, with Change 1 11-01-2012
UFC 3-240-02	Domestic Wastewater Treatment 11-01-2012
UFC 3-240-03N	Wastewater Treatment System Augmenting Handbook Operation and Maintenance 01-16-2004
UFC 3-240-05A	Solid Waste Incineration 01-16-2004

UFC 3-240-10A	Sanitary Landfill 01-16-2004
UFC 3-240-13FN	Industrial Water Treatment Operation and Maintenance 05-25-2005
UFC 3-250-01FA	Pavement Design for Roads, Streets, Walks, and Open Storage Areas 01-16-2004
UFC 3-250-03	Standard Practice Manual for Flexible Pavements 05-15-2001
UFC 3-250-04	Standard Practice for Concrete Pavements, with Change 2 01-16-2004
UFC 3-250-06	Repair of Rigid Pavements Using Epoxy Resin Grouts, Mortars and Concretes 01-16-2004
UFC 3-250-07	Standard Practice for Pavement Recycling 01-16-2004
UFC 3-250-08FA	Standard Practice for Sealing Joints and Cracks in Rigid and Flexible Pavements 01-16-2004
UFC 3-250-09FA	Aggregate Surfaced Roads and Airfields Areas 01-16-2004
UFC 3-250-11	Soil Stabilization for Pavements 01-16-2004
UFC 3-260-01	Airfield and Heliport Planning and Design 11-17-2008
UFC 3-260-02	Pavement Design for Airfields 06-30-2001
UFC 3-260-03	Airfield Pavement Evaluation 04-15-2001
UFC 3-260-05A	Marking of Army Airfield Heliport Operational and Maintenance Facilities, with Change 1 01-16-2004
UFC 3-260-11 FA	Model Design Build (D-B) Request for Proposal (RFP) For Airfield Contracts 05-25-2005
UFC 3-260-16 FA	FA Airfield Pavement Condition Survey Procedures Pavements 01-16-2004
UFC 3-260-17	Dust Control for Roads, Airfields and Adjacent Areas 01-16-2004
UFC 3-270-01	Asphalt Maintenance and Repair 03-15-2001
UFC 3-270-02	Asphalt Crack Repair 03-15-2001
UFC 3-270-03	Concrete Crack and Partial Depth Spall Repair 03-15-2001

UFC 3-270-04	Concrete Repair 03-15-2001
UFC 3-270-05	Paver Concrete Surfaced Airfields Pavement Condition Index (PCI) 03-15-2001
UFC 3-270-06	Paver Asphalt Surfaced Airfields Pavement Condition Index (PCI) 03-15-2001
UFC 3-270-07	O&M: Airfield Damage Repair 08-12-2002
UFC 3-270-08	Pavement Maintenance Management 01-16-2004
UFC 3-280-01A	Guidance for Ground Water/Fuel Extraction and Ground Water Injection Systems 01-16-2004
UFC 3-280-04	Army Filtration of Liquids 12-17-2003
UFC 3-301-01	Structural Engineering, with Change 1 06-01-2013
UFC 3-310-04	Seismic Design for Buildings 06-01-2013
UFC 3-310-08	Non Expeditionary Bridge Inspection, Maintenance and Repair, with Change 1 08-16-2010
UFC 3-320-06A	Concrete Floor Slabs on Grade Subjected to Heavy Loads 03-01-2005
UFC 3-340-01	Design and Analysis of Hardened Structures to Conventional Weapons Effects (FOUO) 06-30-2002
UFC 3-340-02	Structures to Resist the Effects of Accidental Explosions, with Change 2 12-05-2008
UFC 3-400-02	Design: Engineering Weather Data 02-28-2003
UFC 3-401-01	Mechanical Engineering 07-01-2013
UFC 3-410-01	Heating, Ventilating, and Air Conditioning Systems, with Change 1 07-01-2013
UFC 3-410-02	Lonworks (R) Direct Digital Control for HVAC and Other Local Building Systems, with Change 1 05-01-2012
UFC 3-410-04N	Industrial Ventilation 10-25-2004
UFC 3-420-01	Plumbing Systems, with Change 9 10-25-2004
UFC 3-420-02FA	Compressed Air, with Change 1 05-15-2003

UFC 3-430-01FA	Heating and Cooling Distribution Systems 07-25-2003
UFC 3-430-02FA	Central Steam Boiler Plants, with Change 1 05-15-2003
UFC 3-430-07	Operations and Maintenance: Inspection and Certification of Boilers and Unfired Pressure Vessels, with Change 4 07-24-2003
UFC 3-430-08N	Central Heating Plants 01-16-2004
UFC 3-430-09	Exterior Mechanical Utility Distribution, with Change 1 01-16-2004
UFC 3-430-11	Boiler Control Systems 02-14-2001
UFC 3-440-01	Facility-Scale Renewable Energy Systems 07-01-2015
UFC 3-440-05N	Tropical Engineering, with Changes 1-2 01-16-2004
UFC 3-450-01	Noise and Vibration Control 05-15-2003
UFC 3-470-01	Lonworks (R) Utility Monitoring and Control System (UMCS) 05-01-2012
UFC 3-460-01	Design: Petroleum Fuel Facilities, with Change 2 08-16-2010
UFC 3-460-03	O&M: Maintenance of Petroleum Systems 01-21-2003
UFC 3-501-01	Electrical Engineering, with Change 3 02-03-2010
UFC 3-510-01	Foreign Voltages and Frequencies Guide, with Change 2 03-01-2005
UFC 3-520-01	Interior Electrical Systems, with Change 3 02-03-2010
UFC 3-520-05	Stationary Battery Areas, with Change 1 05-01-2015
UFC 3-530-01	Interior and Exterior Lighting Systems and Controls 04-01-2015
UFC 3-535-01	Visual Air Navigation Facilities 11-17-2005
UFC 3-540-01	Engine-Driven Generator Systems for Backup Power Applications 08-01-2014
UFC 3-550-01	Exterior Electrical Power Distribution with Change 1 02-03-2010
UFC 3-555-01N	400 Hertz Medium Voltage Conversion/Distribution and Low Voltage Utilization Systems 01-16-2004
UFC 3-560-01	Electrical Safety, O&M, with Change 5 12-06-2006

UFC 3-570-02A	Cathodic Protection 03-01-2005
UFC 3-570-02N	Electrical Engineering Cathodic Protection 01-16-2004
UFC 3-570-06	O&M: Cathodic Protection Systems 01-31-2003
UFC 3-575-01	Lightning and Static Electricity Protection Systems 07-01-2012
UFC 3-580-01	Telecommunications Building Cabling Systems Planning and Design 06-22-2007
UFC 3-580-10	Navy and Marine Corps Intranet (NMCI) Standard Construction Practices, with Changes 1-3 07-14-2004
UFC 3-600-01	Fire Protection Engineering for Facilities, with Change 3 09-26-2006
UFC 3-601-02	Operations and Maintenance: Inspection, Testing, and Maintenance of Fire Protection Systems; 09-08-2010
42 U.S.C. 6901	Resource Conservation and Recovery Act (RCRA), Solid Waste Disposal Act (SWDA) of 1976, as amended, including Subtitle D

Technical Exhibit (TE).

Technical Exhibit 1 (TE 1) – Equipment List
Technical Exhibit 2 (TE 2) – Work Order Request/Repair & Cost Estimate
Technical Exhibit 3 (TE 3) – Deliverables
Technical Exhibit 4 (TE 4) – KTA Map Buildings

7.4 Government Furnished Material (GFM)/Property (GFP)/Equipment (GFE).

7.4.1 Utilities. The Government will provide access to electrical services. Due to the remote location, water service is not available. The Contractor shall obtain written approval from DPW prior to installing electrical connections and meters. The Contractor shall instruct employees in utilities conservation practices and shall operate in a manner that avoids waste of provided utilities. Because water service is not available, the Contractor is responsible for furnishing any water required for cleaning vehicles and equipment and for managing its use to prevent waste.

7.5 Contractor Furnished Material (CFM)/Property (CFP)/Equipment (CFE). All Contractor furnished, material, property and equipment shall meet applicable Federal, State, Local, DoD and Army Laws, Codes, and Regulations. Examples are provided below:

7.5.1 Contractor Furnished Material and Responsibilities. The Contractor shall furnish all supplies, equipment, facilities, and services required to perform work under this contract.

7.5.2 Contractor Furnished Items. The Contractor shall provide all facilities, vehicles, equipment, parts, tools, fuel, oil, materials, and any other items required to perform all Contract requirements. The Contractor's property shall be operational as intended by the manufacturer, and be safe, clean, and suitable for use at a Military Installation. All Contractor furnished

property and equipment are subject to KO inspection at all times.

7.5.2.1 Identification of Contractor Vehicles and Trailers. The company name shall be displayed on each of the Contractor's vehicles and trailers in a manner and size that is clearly visible. All Vehicles and trailers shall display a valid State license plate and meet current local and State Vehicle registration requirements.

7.5.2.1.1 The Contractor's equipment and other slow-moving equipment shall be equipped with the slow-moving vehicle sign.

7.5.3. Contractor Facilities. The Contractor shall secure the necessary office space and other facilities required for the performance of this contract, off the Military Installation.

7.5.4 Damage Caused by Contractor. Damages caused by Contractor employees shall be repaired at no cost to the Government. In all instances were Contractor's employees damage Government property or equipment, the Contractor shall provide a verbal report to the KO within four (4) hours of occurrence. The Contractor shall notify the COR/ACOR and return the damaged area to its previous condition. All damage done by the Contractor and/or his Subcontractor/s shall become the Contractor's responsibility. The Contractor shall furnish all labor, materials and equipment to perform the repair work including cultivating and applying seed, sprigging, or placing sod. All turf repair work shall be maintained to ensure successful growth.

7.5.5 Third Party Repair Damaged Areas. In the event the Contractor discovers damage caused by another party, the Contractor shall notify the KO and COR of the extent of the damage and proposed corrective action. The Contractor shall make no repairs until authorized by the KO.

7.5.6 Equipment Replacement (Government Property). If an item of Government property is determined by the Contractor to be beyond economical repair, the Contractor shall recommend to the KO and COR in writing that such equipment be replaced. Substantiating data to support the recommended replacement shall be included. If the Government decides that such equipment should be replaced or repaired, and replacement or repair is authorized, the Contractor shall accomplish the work IAW the appropriate work level criteria. Disposal instructions will be provided by the KO and COR.

7.5.7 Permits. The Contractor shall obtain all appointments, licenses, and permits required for performance of work and for complying with all applicable Federal, State, and Local Laws. Permits and licenses shall be provided to the COR/ACOR before work commences.

7.6 U.S. Department of Labor (DOL) Wage Determination (WD). The Contractor shall refer to SAM.gov (https://sam.gov/content/wage-determinations) for applicable U.S. Department of Labor Wage Determinations (DOL WD) and Service Contract Labor Standards wage rates.

8.0 Description of Services.

The Contractor shall furnish all necessary management, transportation, labor, equipment, materials, supplies, and tools to perform Preventive Maintenance (PM) and Repairs on equipment and systems per manufacturer's recommendations as well as routine repairs at

Kahuku Training Area (KTA) on the Island of Oahu. Perform all work in accordance with current Occupational Safety and Health Administration standards, Federal, State and County laws, regulations and commercial standards. To gain access to KTA the Contractor shall coordinate entrance to KTA with Range Control Operations Center, Building 1150, Schofield Barracks, Hawaii. Cell phone number for KTA (808) 853-0440. NOTE: Due to the remote location, water is not available.

8.1 Preventive Maintenance. The Contractor shall develop and implement a comprehensive PM program based on manufacturer specifications and industry best practices. This includes detailed record keeping, trend analysis, and proactive component replacement to minimize equipment downtime. After completion of a maintenance or repair task, the Contractor shall ensure that the equipment or area is safe and operational. The Contractor shall perform preventive maintenance and repairs in accordance with applicable manufacturer instructions. If a machine/equipment is replaced by the Government, the COR will e-mail the Contractor a copy of the new machine's/equipment's operating manual. Minor corrective work that does not require additional parts or out-of-scope labor is included in the PM service. Part-required repairs shall be processed in accordance with Sections 8.8 through 8.10 and shall not begin until authorized by a written firm-fixed-price task order.

8.2 Preventive Maintenance Schedule. The Contractor shall develop and maintain a semiannual rolling Preventive Maintenance schedule for equipment listed in TE 1 in accordance with manufacturer recommendations, industry standards, and best practices. The schedule shall identify all required quarterly, semiannual, annual, and other manufacturer-required PM activities. The Contractor shall develop and submit the PM schedule in MS Word or MS Excel**,** providing the report to the Contracting Officer's Representative (COR) via electronic mail (email) for approval within ten (10) working days before the start of service. Revisions and updates to the schedule shall be submitted as needed due to operational changes**.** All PM activities should be conducted to ensure minimal disruption to facility operations. If access issues or scheduling conflicts arise, the Contractor shall coordinate with the COR to ensure alignment with facility requirements.

Performance Standard
STD: The contractor shall develop a semi-annual PM schedule and submit in MS Word or MS Excel to COR for approval within ten (10) working days before the start of service.

AQL: 10% Deviation from standard

Deliverable
A008 Preventive Maintenance Schedule

8.3 Fire Alarm & Mass Notification Systems. The Contractor shall perform Quarterly PM on all systems, equipment, and fixtures located at KTA in compliance with manufacturer guidance, applicable industry standards, recognized best practices, and all relevant federal, state, local, and U.S. Army regulations. The Contractor shall coordinate all PM activities involving Fire Alarm and Mass Notification Systems with the appropriate authorities, facility personnel and the COR prior to the start of any testing. The Contractor shall be fully responsible for completing all required on-the-spot preventive maintenance tasks, including providing all necessary labor, materials, and resources needed to perform the services.

8.3.1 Fire Alarm System Quarterly PM. The Contractor shall perform all required inspection,

testing, and PM on fire alarm systems and components listed in TE 1 in full compliance with NFPA 72, the Hawaii State Fire Code, applicable technical manuals, and manufacturer instructions. All system components shall be inspected and tested quarterly (NFPA 72-prescribed). PM shall verify proper operation of control panels, initiating devices, notification appliances, power supplies, batteries, communication pathways, and supervisory functions. Due to Hawaii's corrosive and high-humidity environment, the Contractor shall incorporate enhanced corrosion monitoring, increased visual inspections, and proactive replacement of moisture-susceptible components.

All PM activities shall ensure system integrity, audibility, survivability, and full code compliance. Completed inspection, testing, and maintenance documentation shall be submitted to the Fire Inspector and made available to the Government upon request.

Required tasks include:

- Test smoke and heat detectors
- Test pull stations
- Test horns, strobes, and speakers
- Perform battery load testing
- Check SLC and NAC circuits
- Run panel diagnostics
- Verify communication to monitoring

8.3.2 Mass Notification System Quarterly PM. The Contractor shall perform all required inspection, testing, and PM on Mass Notification System equipment **i**n full compliance with NFPA 72 and the Hawaii State Fire Code**.** All components shall be inspected and tested at the NFPA 72-prescribed intervals**.** PM shall verify the proper operation and condition of speakers, amplifiers, control equipment, communication pathways, backup power, and all indoor/outdoor notification appliances**.** Testing shall confirm that messages are audible, intelligible, and reliably delivered throughout all coverage areas.

Due to Hawaii's high humidity, salt-laden air, and tropical weather exposure, the Contractor shall incorporate enhanced corrosion checks, moisture-intrusion inspections, and early identification of UV-related degradation to maintain system reliability.

Required tasks include:

- Speaker testing (tone and voice)
- Battery load testing
- Panel diagnostics
- Amplifier and circuit checks
- Message board verification
- Outdoor siren testing
- Network supervision check

All inspection, testing, and maintenance documentation shall be retained and made available to the Government upon request.

Performance Standards

STD: The Contractor shall conduct quarterly preventive maintenance to ensure all Fire Alarm and Mass Notification System components remain fully operational and compliant with NFPA 72

and the Hawaii State Fire Code. All inspections and testing shall be completed at required intervals. Deficiencies that can be corrected within the scheduled PM scope and without additional parts or out-of-scope labor shall be corrected during the PM service. All other deficiencies shall be documented and reported within 24 hours, including recommended corrective actions, and processed in accordance with Sections 8.8 through 8.10. All work shall meet OSHA and facility safety standards. A consolidated written PM report shall be submitted to the COR within five (5) working days after PM completion.

AQL: 5% deviation from standard

Deliverable:
A009 Preventive Maintenance Report

8.4 Emergency Lighting & Exit Signs. The Contractor shall perform annual PM on all systems, equipment, and fixtures located at KTA in compliance with manufacturer guidance, applicable industry standards, recognized best practices, and all relevant federal, state, local, and U.S. Army regulations. The Contractor shall coordinate all PM activities involving Emergency Fixtures (Lights and Components) with the appropriate authorities, facility personnel and the COR prior to the start of any testing. The Contractor shall be fully responsible for completing all required on-the-spot preventive maintenance tasks, including providing all necessary labor, materials, and resources needed to perform the services.

8.4.1 Emergency Fixtures (Lights and Components) Annual PM. The Contractor shall inspect, test, repair, and maintain all lighted exit signs and emergency lighting units located within building interiors in compliance with UFC 1-200-01 (DoD Building Code – General Building Requirements). Emergency lighting and egress fixtures within the State of Hawaii shall be maintained in accordance with the Hawaii State Fire Code, which adopts NFPA 101 (Life Safety Code) and NFPA 70 (National Electrical Code) as governing standards. These codes require all emergency lighting systems, exit signs, and battery-backed fixtures to remain fully operational at all times and to undergo:

- Annual full-duration testing (90-minute load test)

These tests verify illumination performance, battery capacity, and charging system integrity.

Due to Hawaii's high humidity, salt-air exposure, and accelerated environmental wear, additional visual inspections are required to identify corrosion, lens degradation, water intrusion, and wiring damage. All emergency fixtures must provide a minimum average illumination of 1 foot-candle along egress paths and must automatically activate upon loss of normal power.

Preventive maintenance activities shall ensure full compliance with NFPA 101, NFPA 70, and the Hawaii State Fire Code, while addressing Hawaii's unique environmental conditions.

PM tasks include, but are not limited to:
- Test battery backup
- Inspect LED and lamp output
- Check charging circuits
- Clean lenses and housings
- Verify exit sign illumination
- Record test results

Performance Standards

STD: The Contractor shall perform annual preventive maintenance and shall ensure all emergency lighting units and exit signs remain fully operational**,** code-compliant**,** and capable of providing a minimum of 1 foot-candle of illumination upon loss of normal power. Systems shall receive all required annual functional 90-minute full-duration test. Deficiencies that can be corrected within the scheduled PM scope and without additional parts or out-of-scope labor shall be corrected during the PM service. All other deficiencies shall be documented and processed in accordance with Sections 8.8 through 8.10. A consolidated written PM report shall be submitted to the COR within five (5) working days after PM completion.

AQL: 10% deviation from standard

Deliverables

A009 Preventive Maintenance Report

8.5 Lightning Protection Systems. The Contractor shall perform semi-annual PM on all systems, equipment and fixtures located at KTA in accordance with the manufacturer's recommendations, industry standards, best practices, as well as all applicable federal, state, local, and U.S. Army regulations. The Contractor shall coordinate all activities related to the lightning protection system and buildings with the appropriate authorities, facility personnel and the COR prior to commencement of testing. The Contractor shall be fully responsible for executing all required on-the-spot PM tasks, including the provision of necessary labor and materials, as part of the PM services.

8.5.1 Lightning Protection Semi-Annual PM. The Contractor shall inspect and maintain all Lightning Protection Systems (LPS) in compliance with NFPA 780**,** LPI-175**,** and all requirements adopted under the Hawaii State Building Code. Due to Hawaii's coastal corrosion, elevated lightning activity, and severe weather exposure, the Contractor shall perform semi-annual inspections.

Preventive maintenance shall verify system continuity, grounding effectiveness, bonding integrity, corrosion conditions**,** and overall compliance with NFPA 780. All components shall remain fully operational and capable of providing effective lightning protection under Hawaii's environmental conditions.

Semi-Annual PM shall ensure compliance with:

- NFPA 780
- UL 96A Master Label requirements
- DoD UFC 3-575-01 (for military installations)

Inspections shall include, at minimum:

- Check for loose, deteriorated, or corroded connections
- Inspect air terminals and conductors for damage or displacement
- Evaluate grounding electrode condition
- Inspect surge protection devices
- Check for mechanical displacement or vibration damage
- Visual inspection of all air terminals, conductors, and bonding points
- Continuity testing

- Ground resistance testing
- Verification of UL Master Label compliance
- Documentation for compliance or insurance purposes

Performance Standards
STD: The Contractor shall perform semi-annual PM and shall ensure the Lightning Protection System remains fully operational, code-compliant, and capable of providing effective protection in Hawaii's environmental conditions. PM shall verify continuity, grounding, bonding, corrosion conditions, and component integrity in accordance with NFPA 780, UL 96A, and UFC 3-575-01. Deficiencies that require additional parts or out-of-scope labor shall be documented and processed in accordance with Sections 8.8 through 8.10.

AQL: 10% deviation from standard

Deliverables
A009 Preventive Maintenance Report

8.6 Heating, Ventilation, and Air Conditioning (HVAC) Quarterly PM. The Contractor shall perform quarterly PM on all HVAC systems listed in TE 1 in accordance with manufacturer recommendations, UFC 3-410-01, ASHRAE standards, and facility maintenance plans**.** All work shall be coordinated with facility personnel to minimize disruption to operations**.** The Contractor shall maintain accurate PM records, including test results, measurements, component conditions, and corrective actions. Any deficiencies identified during PM shall be documented and reported within 24 hours with recommended corrective actions. All work shall comply with OSHA and facility-specific safety requirements**.**

8.6.1 Central HVAC System. The Contractor shall perform quarterly PM on central HVAC systems that include inspection, testing, cleaning, lubrication, calibration, and adjustment of all components to ensure safe, efficient, and reliable operation. Tasks shall include verification of operating pressures and temperatures, inspection of belts and pulleys, cleaning of coils and strainers, testing of safeties and interlocks**,** water-treatment monitoring**,** and completion of seasonal startup and shutdown procedures. All deficiencies shall be documented and reported immediately if corrective maintenance is required.

Required tasks include but are not limited to:

- Coil cleaning (evaporator & condenser)
- Refrigerant check
- Electrical inspection
- Drain line cleaning
- Filter replacement
- Thermostat calibration

8.6.2 Package Air Terminal Units (PTAC). The Contractor shall perform quarterly PM on all PTAC units to ensure proper airflow, temperature control, and reliable operation. PM shall include cleaning, inspection, calibration, testing, and verification of communication with the building automation system (BAS)**.** All deficiencies shall be documented and reported immediately if corrective maintenance is required.

Required tasks include:

- Coil cleaning (evaporator + condenser)

- Filter replacement
- Drain pan and drain line cleaning
- Blower wheel cleaning
- Check for refrigerant leaks
- Inspect electrical component
- Check wall sleeve and insulation

8.6.3 Ductless Split AC System. The Contractor shall perform quarterly PM on all ductless split systems to ensure designed cooling/heating performance, humidity control, and occupant comfort**.** PM shall include inspection, cleaning, testing, and verification of proper refrigerant conditions**,** electrical integrity, system safety, and BAS communication (where applicable). All deficiencies shall be documented and reported immediately if corrective maintenance is required.

Required tasks include:

- Indoor coil cleaning
- Outdoor coil cleaning
- Filter washing verification
- Blower wheel cleaning
- Drain pan and line cleaning
- Refrigerant check
- Electrical inspection

Performance Standards
STD: The Contractor shall ensure all HVAC systems listed in TE #1 including central systems, PTAC units, and ductless systems remain operational, efficient, and safe. The Contractor shall conduct preventive maintenance at required intervals and coordinate with facility personnel to minimize disruption. The Contractor shall maintain accurate PM records, including measurements, test results, component conditions, and corrective actions. All inspections and testing shall be completed at prescribed intervals. Deficiencies that can be corrected within the scheduled PM scope and without additional parts or out-of-scope labor shall be corrected during the PM service. All other deficiencies shall be documented and reported as required and processed in accordance with Sections 8.8 through 8.10. A consolidated written PM report shall be submitted to the COR within five (5) working days following completion of all PM activities.

AQL: 10% deviation from standard

Deliverables
A009 Preventive Maintenance Report

8.7 Preventive Maintenance (PM) Service Report. The Contractor shall prepare and submit one consolidated written PM Service Report to the COR within five (5) working days after completion of each scheduled PM cycle. The PM report shall include the following:

- Date
- Facility/Building Number
- Equipment
- Manufacturer

- Model Number
- Serial # Number
- Name of technician performing the PM for each piece of equipment
- Date/Time the PM was completed
- Deficiencies identified during PM.
- Actions taken for each piece of equipment
- Status (Operational/Inoperative)

Performance Standards
STD: The Contractor shall prepare and submit one consolidated written PM Service Report to the COR within five (5) working days after completion of each scheduled PM cycle.

AQL: 10% deviation from standard

Deliverable:
A009 Preventive Maintenance Report

8.8 Repairs identified during Preventive Maintenance (PM) Services. If repairs are identified during PM, the Contractor shall perform minor repairs that do not require additional parts, ensuring prompt resolution and minimizing operational disruptions. If repairs are identified that require parts, the contractor will initiate a Work Order Request/Repair & Cost Estimate (TE 2) to the COR within two (2) business days for deficiencies identified on the Preventive Maintenance (PM).

The Work Order Request/Repair & Cost Estimate (TE 2) shall include but not be limited to:

- Location/installation
- Description of the problem
- Scope of work
- Cost estimate (to include labor, parts cost, taxes, shipping/handling fees, and other additional charges associated with the repair)
- Estimated time to complete the job

To restore system functionality, the Contractor shall submit a detailed work request/proposal report**,** specifying the required parts, associated costs, and the projected completion date to the COR within two (2) working days. The COR will review and validate the assessment and provide a recommendation to the KO. Only the Contracting Officer may authorize parts-required repair work through issuance of a written firm-fixed-price task order.

The Contractor shall not initiate any repair that requires parts or additional labor until the Contracting Officer has issued a written firm-fixed-price task order. The Contracting Officer, Contract Specialist, COR, and the Contractor may meet to clarify scope, materials, and the firm-fixed-price quote. The Government will evaluate the quote for price reasonableness before issuing the task order. Submission of TE 2 under this paragraph is part of the preventive maintenance effort and does not require a separate assessment visit.

Repair work authorized by the task order shall be performed in accordance with paragraph 8.9. This paragraph 8.8 covers identification of the deficiency during PM, minor no-parts corrective work included in the PM price, and submission of TE 2 for any parts-required repair. It does not authorize the Contractor to order parts or begin the parts repair.

Performance Standards
STD: Submit a complete TE 2 firm-fixed-price quote to the COR within two (2) business days after a parts-required deficiency is identified during PM. Do not start the parts repair until a written firm-fixed-price task order is issued.

AQL: 10% deviation from standard

Deliverable
A010 Work Order Request/Repair & Cost Estimate

8.9 Repairs. The Contractor shall provide all technical services required to troubleshoot and repair system malfunctions, including all necessary labor, parts, materials, and subcontractor support. Repairs shall be performed only after the Contracting Officer has issued a written firm-fixed-price task order. The Contractor shall furnish all labor, materials, parts, and equipment needed to complete the authorized repair in accordance with that task order. Unless the task order specifies otherwise, the Contractor shall complete the repair within two (2) business days after receipt of required parts. Upon completion, the Contractor shall ensure the equipment or area is safe and fully operational, notify the building point of contact, and obtain signature verification of the date and time of completion on the work order. If the Contracting Officer cannot determine the Contractor's TE 2 quote fair and reasonable, or the work is outside the scope of this contract, the Government may perform the repair itself or acquire it from another source.

8.9.1 Authorization of Work. All repair work shall be coordinated with facility personnel and must be authorized by the Contracting Officer prior to initiation. The Contractor shall submit a detailed firm-fixed-price repair quote (TE 2) with a description of the required work and a cost breakdown of labor, parts, materials, equipment, shipping, taxes, and subcontractor costs. Quotes arising from unscheduled assessments (paragraph 8.11) shall be submitted to the COR within five (5) business days of the on-site assessment. Quotes arising from deficiencies identified during PM (paragraph 8.8) shall be submitted within two (2) business days of identification. The Government will evaluate the quote for price reasonableness and establish a firm-fixed-price for the repair. Any costs incurred by the Contractor in excess of the Contracting Officer-approved amount are at the Contractor's own risk and will not be reimbursed. The Contractor shall not commence repair work until a written firm-fixed-price task order has been issued.

Quote Requirements. Repair quotes shall include labor (as a firm-fixed-price lump sum for the complete repair), materials, parts, equipment, shipping, taxes, and any subcontractor cost. Quotes shall be firm-fixed-price, all-in. Hourly labor rates are not a contract line item. Quotes shall also include as applicable, multiple material or equipment cost comparisons and pricing for any subcontractors required to complete the repair.

Performance Standards:
STD: Perform only Contracting Officer-authorized firm-fixed-price task order repairs. Complete each authorized repair within two (2) business days after receipt of required parts unless the task order specifies otherwise. Any cost above the approved firm-fixed-price is at the Contractor's risk. If the Contracting Officer cannot determine the Contractor's TE 2 quote fair and reasonable, or the work is outside the scope of this contract, the Government may perform the repair itself or acquire it from another source.

AQL: 10% deviation from standard

Deliverables:
A010 Work Order Request/Repair & Cost Estimate

8.10 Replacement Parts. The Contractor shall provide new replacement parts of quality equal to the original manufacturer's components. Refurbished or reconditioned parts may be used only when new parts are unavailable and meet industry standards. Parts and materials shall be included in the firm-fixed-price task order. Vendor quotes or catalog pricing may be attached to the TE 2 to support price analysis. Purchase receipts for parts used shall be submitted with the monthly invoice (A011/A013); they are not the invoice basis.

The Contractor shall not purchase parts or begin the parts repair until the Contracting Officer has issued a written firm-fixed-price task order. The task order is the approval to buy parts. All parts, materials, and labor shall carry a one-year warranty. If any replacement part is still under manufacturer warranty, the Contractor shall arrange for warranty service and replacement of defective parts at no additional cost to the Government.

Performance Standards:
STD: The Contractor shall provide new, KO-approved replacement parts as part of the firm-fixed-price task order, with receipts submitted with the monthly invoice, and all parts, materials, and labor shall carry a one-year warranty. Manufacturer-warrantied items shall be serviced and replaced by the Contractor at no additional cost to the Government**.**

AQL: 10% deviation from standard

Deliverables:
A011 Purchase Parts Receipts

8.11 Unscheduled/Assessment/Work Request. For repairs required outside of the regular PM, the COR will provide the Work Order Request/Repair & Cost Estimate by email to the Contractor, who shall acknowledge receipt by email within one (1) business day. The Contractor shall respond within two (2) business days and shall perform an onsite assessment. The Contractor shall inspect, troubleshoot the defective or inoperative components to the level necessary to diagnose and determine the corrective actions needed to place the system back to full operation. The Contractor shall not commence repair work until a firm-fixed-price task order has been issued by the Contracting Officer. Assessment and quote only are required under this paragraph until that task order is issued.

The Contractor shall complete TE 2 as a firm-fixed-price quote covering labor (lump sum for the complete repair), parts, materials, equipment, shipping, taxes, and any subcontractor costs. Hourly labor rates are not a contract line item.
The completed TE 2 shall describe the equipment issue, the parts required, the firm-fixed price, and the projected completion date. The completed TE 2 shall be submitted to the COR within five (5) business days of the on-site assessment. The Government will evaluate the quote for price reasonableness. The Contractor shall not commence repair work until the Contracting Officer has issued a written firm-fixed-price task order. This paragraph covers assessment, diagnosis, and quote only. Authorized repair work is performed under paragraph 8.9.

If parts are unavailable, the quote shall state the lead time and the projected completion date. The assessment and quote do not authorize the Contractor to begin repair work.

Performance Standards
STD: Acknowledge the work request within one (1) business day. Perform an on-site assessment within two (2) business days. Submit a complete TE 2 firm-fixed-price quote within five (5) business days of the assessment. Do not commence repair work until a written firm-fixed-price task order is issued.
Assessments shall describe the deficiency, the parts and work required, the firm fixed price, and the projected completion date.

AQL: 10% deviation from standard

Deliverable
A010 Work Order Request/Repair & Cost Estimate

8.12 Equipment Inventory List. The Contractor shall electronically update the equipment inventory list, TE 1 in a spreadsheet format, ensuring it includes all required data as specified in TE 1. The initial verification/update shall be completed within sixty (60) calendar days from the start of the contract, and the inventory list shall be maintained as a current and accurate record**.** The Contractor shall provide the updated inventory list to the COR immediately upon any revisions to ensure continued accuracy and accountability.

Performance Standards:
STD: The Contractor shall provide the updated inventory list to the COR immediately upon any revisions to ensure continued accuracy and accountability.

AQL: 10% deviation from standard

Deliverable
A012 Technical Exhibits (TE) 1 equipment inventory list

8.13 Invoice. The Contractor shall invoice only for work completed. All invoices shall include supporting documents (PM schedule, work order, Work Order Request/Repair & Cost Estimate, receipts and any other necessary documents). Contractor shall invoice monthly no later than the 5th business day of each month.

Performance Standards
STD: Upon completion of work the Contractor shall provide invoices, cost estimates/quote, receipts and all required deliverables to COR NLT the 5th business day of month.

AQL: 10% deviation from standard

Deliverable
A010 Work Order Request/Repair & Cost Estimate
A011 Purchase Parts Receipts
A013 Invoice