1

| Building Name / Location | Task Description | Unit | Quantity |
|---|---|---|---|
| Mt. Whitney Barracks<br>Lone Pine, CA | **Exterior Painting:** Includes all surface preparations, siding and drywall repairs. | SF | 2000 |
| | **Interior Painting:** .Includes all surface preparations and drywall repairs. | SF | 2000 |
| | **Paint and Repair Main Entrance Ramp**: Includes sanding and preparing ramp surfaces for painting. Wooden ramp & Metal railing). | LS | 1 |
| | **Replace Bathroom Sinks**: Replace existing sinks, including vanity. | LS | 2 |
| | **Replace Back Stairs**: Existing stairs are made of Doug Fir, approximately 4ft x 4ft replace-kind. | LS | 2 |
| | **Replace Kitchen Counter:** Existing sink is approximately 24 inch by 72 inch (Laminate, Formica), replace in-kind. | LS | 1 |
| | **Install New Bathroom Fan/Light Combo:** Replace existing light and vent, with new fan/light combo. Must be vented to exterior. | LS | 2 |
| | **Replace Ceiling Tiles:** Existing ceiling tiles are made of Mineral Fiber, replace-kind. | SF | 1600 |
| | **Roof Replacement:** Existing roof is made of composite shingles, replace in-kind. | SF | 1600 |

2

| Building Name / Location | Task Description | Unit | Quantity |
|---|---|---|---|
| Mt. Whitney House<br>Lone Pine, CA | **Exterior Painting:** Includes all surface preparations, siding and drywall repairs. | SF | 1700 |
| | **Interior Painting:** .Includes all surface preparations and drywall repairs. | SF | 1700 |
| | **Remove Wood Stove**: Includes drywall repair and ceiling/roof penetration repairs. | LS | 1 |
| | **Replace Kitchen Counter:** Existing sink is approximately 24 inch by 72 inch (Laminate, Formica), replace in-kind. | LS | 1 |
| | Replace Double Sink | LS | 1 |
| | **Replace Faucet** | LS | 1 |
| | **Install New Bathroom Fan/Light Combo:** Replace existing light and vent, with new fan/light combo. Must be vented to exterior. | LS | 2 |

3

| Building Name / Location | Task Description | Unit | Quantity |
|---|---|---|---|
| Helitack Barracks<br>Independence, CA | **Exterior Painting:** Includes all surface preparations, siding and drywall repairs. | SF | 2000 |
| | **Interior Painting:** .Includes all surface preparations and drywall repairs. | SF | 2000 |
| | **Replace Sink (Westside):** Wall attachment sink, replace in-kind. Includes plumbing repairs. | LS | 1 |
| | **Replace Kitchen Counter:** Existing counter is approximately 24 inch by 96 inch (Laminate, Formica), replace in-kind. | LS | 1 |
| | **Replace Double Sink** | LS | 2 |
| | **Replace Faucet** | LS | 2 |
| | **Replace Vent Hood:** Replace in-kind. | LS | 2 |
| | **Install New Bathroom Fan/Light Combo:** Replace existing light and vent, with new fan/light combo. Must be vented to exterior. | LS | 2 |
| | **Paint Main Entrance Stairs and Backdoor Stairs:** Existing wooden stairs are approximately 4ft x 4ft. | LS | 2 |
| | **Paint Main Entrance Ramp and Railing:** Existing ramp is approximately 3ft x 20ft. | LS | 1 |
| | **Roof Replacement:** Existing roof is made of composite shingles, replace in-kind. | SF | 1800 |

4

| Building Name / Location | Task Description | Unit | Quantity |
|---|---|---|---|
| Helitack Fire Office,<br>Storage Shed<br>Independence, CA | **Roof Replacement**: Existing roof is made of composite shingles, replace in-kind. | SF | 600 |

| Building Name / Location | Task Description | Unit | Quantity |
|---|---|---|---|
| White Mtn. Fire Barracks<br>Bishop, CA | **Exterior Painting:** Includes all surface preparations, siding and drywall repairs. | SF | 2000 |
| | **Interior Painting:** .Includes all surface preparations and drywall repairs. | SF | 2000 |
| | **Replace Kitchen Counter:** Existing sink is approximately 24 inch by 96 inch (Laminate, Formica), replace in-kind. | LS | 1 |
| | **Repair Kitchen Drawer:** Existing kitchen drawer does not close. | LS | 1 |
| | **Repair Kitchen Window Trim:** Existing window is approximately 32 inch by 36 inch. | LS | 1 |
| | **Paint Main Entrance Stairs and Backdoor Stairs:** Existing stairs are approximately 4ft x 4ft. | LS | 2 |
| | **Paint Main Entrance Ramp and Railing:** Existing stairs are approximately 3ft x 20ft. | LS | 1 |
| | **Replace Fencing, East Side: E**xisting fence is made of Cedar fence boards, approximately 100 ft by 6 ft. Replace in-kind. | LF | 100 |
| | **Repair flooring transitions:** Existing transition is made of aluminum. | LF | 10 |
| | **Repair Bathroom Walls:** Existing bathroom walls have moisture damage/water damage. Includes replacing the cove base (vinyl). | SF | 512 |
| | **Install New Bathroom Fan/Light Combo:** Replace existing light and vent, with new fan/light combo. Must be vented to exterior. | LS | 2 |
| | **Install New Shower Installs** | LS | 2 |

| Building Name / Location | Task Description | Unit | Quantity |
|---|---|---|---|
| White Mtn. Recreation Barracks<br>Bishop, CA | **Exterior Painting:** Includes all surface preparations, siding and drywall repairs. | SF' | 2000 |
| | **Interior Painting:** .Includes all surface preparations and drywall repairs. | SF | 2000 |
| | **Replace Kitchen Counter**: Existing counter is approximately 24 inch by 120 inch, and the kitchen island is 36 inch by 72 inch (Laminate, Formica), replace in-kind. | LS | 1 |
| | **Replace Double Sink** | LS | 1 |
| | **Replace Faucet** | LS | 1 |
| | **Flooring Replacement:** Existing flooring is made of carpet, replace in-kind commercial grade. | SF | 1580 |
| | **Flooring Replacement**: Existing flooring is made of sheet vinyl, replace in-kind, commercial grade. | SF | 500 |
| | **Paint Bathroom Floors:** Includes caulking bottom, end of existing tiles. Use commercial cement paint designed for bathroom floors. | SF | 200 |
| | **Replace Ceiling Tiles:** Existing ceiling tiles are approximately 24 inch by 36 inch, replace in-kind. | LS | 30 |
| | **Replace Exterior Doors:** Exiting doors are approximately 36 inch wide metal doors, replace in-kind. Install doors to open towards the inside. | LS | 3 |
| | **Roof Replacement:** Existing roof is made of composite shingles, replace in-kind. | SF | 3400 |
| | **Replace 90 degree Downspouts** | LS | 3 |
| | **Install New Bathroom Fan/Light Combo:** Replace existing light and vent, with new fan/light combo. Must be vented to exterior. | LS | 2 |

7

| Building Name / Location | Task Description | Unit | Quantity |
|---|---|---|---|
| Smokey Club House<br>Bishop, CA | **Exterior Painting:** Includes all surface preparations, siding and drywall repairs. | SF | 1700 |
| | **Interior Painting:** .Includes all surface preparations and drywall repairs. | SF | 1700 |
| | **Install Metal Grate in Door:** Metal Grate shall be approximately 18 inch by 18 inch for airflow. | LS | 1 |
| | **Update Bathroom Lighting:** Existing vanity light has two fixtures. | LS | 1 |
| | **Paint Back Entrance Railing:** Existing railing is approximately 10ft. | LS | 1 |
| | **Paint Main Entrance Railing:** Existing railing is approximately 40ft. | LS | 1 |
| | **Replace Windows:** Install new window type. See attached window schedule. | LS | 1 |
| | **Roof Replacement:** Existing roof is made of composite shingles, replace in-kind. | SF | 1600 |
| | **Bathroom Flooring Replacement;** Replace with Sheet Vinyl. | SF | 50 |
| | **Replace Fencing, East Side:** Existing fence is made of Cedar fence boards, approximately 100 ft by 6 ft. Replace in-kind. Includes replacing existing wooden gate. | LF | 75 |

8

| Building Name / Location | Task Description | Unit | Quantity |
|---|---|---|---|
| Rock Creek Barracks (East)<br>Toms Place, CA | **Exterior Painting:** Includes all surface preparations, siding and drywall repairs. | SF | 1600 |
| | **Interior Painting:** .Includes all surface preparations and drywall repairs. | SF | 1600 |
| | **Install New Vent Stacks:** Vent stacks are currently installed on the following locations: bathroom (2), laundry, kitchen and HVAC unit. Contractor to confirm count. | LS | 5 |
| | **Sidewalk Replacement:** Existing sidewalk is made of concrete and is approximately 6 inches thick. | SF | 100 |

9

| Building Name / Location | Task Description | | Quantity |
|---|---|---|---|
| Rock Creek Barracks (West)<br>Toms Place, CA | **Exterior Painting:** Includes all surface preparations, siding and drywall repairs. | SF | 1600 |
| | **Interior Painting:** .Includes all surface preparations and drywall repairs. | SF | 1600 |
| | **Install New Vent Stacks:** Vent stacks are currently installed on the following locations: bathroom (2), laundry, kitchen and HVAC unit. Contractor to confirm count. | LS | 5 |

10

| Building Name / Location | Task Description | Unit | Quantity |
|---|---|---|---|
| Rock Creek House<br>Toms Place, CA | **Exterior Painting:** Includes all surface preparations, siding and drywall repairs. | SF | 1400 |
| | **Interior Painting:** .Includes all surface preparations and drywall repairs. | SF | 1400 |
| | **Flooring Replacement**: Install new flooring, includes all work associated with removing the existing flooring and preparing the surface for new flooring. Existing flooring is made of carpet, replace in-kind commercial grade. | SF | 200 |
| | **Roof Replacement:** Install new roof, includes all work associated with removing existing roof and preparing the structure for the new roof. Existing roof is made of composite shingles, replace in-kind. | SF | 800 |
| | **Replace Ceiling Tiles**: Remove existing ceiling tiles and replace them with drywall. Includes all work associated with removing the existing tiles, preparing the ceiling and the disposal of existing ceiling tiles. | SF | 800 |
| | **Update Lighting Fixtures**: Update the lighting fixtures in the following spaces: Dining Room (1), Bedroom (1), Bathroom (1) and Living Room (1). | LS | 4 |
| | **Replace Bedroom Wall Heater:** Replace existing wall heater with a new heater. Exiting Cadet wall heater. | LS | 1 |
| | **Replace Bathroom Ceiling Heater** | LS | 1 |
| | **Replace Back Steps:** Existing concrete steps are approximately 3 ft wide, 3 steps. | LS | 1 |
| | **Install Weatherstripping on Front Door:** Existing standard 36 inch door. | LS | 1 |
| | **Install Door Sweep on Front Door:** Existing standard 36 inch door. | LS | 1 |
| | **Replace Windows:** Install new windows as shown in the window schedule. See attached window schedule for specific window count. Includes removal and disposal of existing windows and preparing the area for new windows. | LS | 1 |

11

| Building Name / Location | Task Description | Unit | Quantity |
|---|---|---|---|
| Rock Creek Exterior Bathroom<br>Toms Place, CA | **Exterior Painting:** Includes all surface preparations, siding and drywall repairs. | SF | 1000 |
| | **Interior Painting:** .Includes all surface preparations and drywall repairs. | SF | 1000 |
| | **Replace Door Casing:** Exiting door are approximately 36 inch wide, metal doors, replace in-kind. | LS | 1 |

| Building Name / Location | Task Description | Unit | Quantity |
|---|---|---|---|
| Mammoth Recreation Barracks<br>Mammoth Lakes, CA | **Exterior Painting:** Includes all surface preparations, siding and drywall repairs. | SF | 2000 |
| | **Interior Painting:** .Includes all surface preparations and drywall repairs. | SF | 2000 |
| | **Replace Siding:** Existing Siding is made of wood, damaged with Woodpecker holes. Replace in-kind and where needed. | SF | 320 |
| | **Demolish & Remodel Bathrooms:** Replace two vanities, two sinks, four faucets, and two shower installs, and two show fixtures. Chrome for all fixtures. Toilets are new and don't need to be replaced. Includes demolition and disposal of existing bathroom and preparing the area for the new bathroom. | LS | 2 |
| | **Install New Bathroom Fan/Light Combo:** Replace existing light and vent, with new fan/light combo. Must be vented to exterior. | LS | 2 |
| | **Repair Front Porch Awning:** Existing Front Porch is approximately 8 ft by 8 ft and has structural damage to snow loading. | LS | 1 |
| | **Front Porch Roof Replacement:** Existing roof is made of sheet metal, replace with corrugated metal roof. | SF | 200 |
| | **Bedroom Expansion:** Demolish wall between bedroom 1 and outside storage room to expand bedroom 1. Add insulation and drywall outer walls (26 ft), Includes removing outside storage door and replacing it will wall and new siding. Includes ceiling installation, matching flooring to existing bedroom flooring (carpet). | LS | 1 |
| | **Install Exterior Pest Exclusion Measures:** Shall include installing wire mesh around the building to exclude pests. | LF | 200 |
| | **Paint Back Entrance Railing:** Existing railing is approximately 10ft and made of wood. | LS | 1 |
| | **Flooring Replacement:** Existing flooring is made of carpet, replace in-kind commercial grade. Approximate area, contractor to verify flooring area. | SF | 1000 |
| | **Flooring Replacement:** Existing flooring is made of sheet vinyl, replace in-kind, commercial grade. Approximate area, contractor to verify flooring area. | SF | 800 |
| | **Replace Ceiling Tiles**: Remove existing ceiling tiles and replace them with drywall. Includes all work associated with removing the existing tiles, preparing the ceiling and the disposal of existing ceiling tiles. | SF | 1800 |

| Building Name / Location | Task Description | Unit | Quantity |
|---|---|---|---|
| Mammoth Fire Barracks<br>Mammoth Lakes, CA | **Exterior Painting:** Includes all surface preparations, siding and drywall repairs. | SF | 2000 |
| | **Interior Painting:** .Includes all surface preparations and drywall repairs. | SF | 2000 |
| | **Replace Kitchen Counter:** Existing sink is approximately 24 inch by 96 inch (Laminate, Formica), replace in-kind. | LS | 1 |
| | **Replace Cabinet Door:** Cabinet door is approximately 12 inch by 24 inch, Oak material, replace in-kind. | LS | 1 |
| | **Repair Cabinet Door:** Existing cabinet door does not close. | LS | 1 |
| | **Replace Window Trim:** Existing window is approximately 36 inch by 36 inch. | LS | 2 |
| | **Replace Kitchen Drawer:** Existing kitchen drawer is approximately 5 inch by 18 inch, Oak material, replace in-kind. | LS | 1 |
| | **Replace Double Sink** | LS | 2 |
| | **Replace Faucet** | LS | 2 |
| | **Replace Front and Rear Stairs:** Existing stairs have five steps and are approximately 3 ft wide. Replace in-kind. | LS | 2 |
| | **Install Roof Enclosure Over Stairs:** Enclosure to be constructed around front and back stairs and shall be made of composite shake roof to shade snow and shall extend over the new stairs. | LS | 2 |
| | **Roof Replacement:** Existing roof is made of composite shingles, replace in-kind, includes replacing existing roof vents. | SF | 1800 |
| | **Repair Bathroom Walls:** Existing bathroom walls have moisture damage/water damage. Includes replacing the cove base (vinyl). | SF | 512 |
| | **Seal Windows:** Seal front window exteriors to weatherproof them. Windows are approximately 24 inch by 36 inch. | LS | 2 |
| | **Flooring Replacement:** Existing flooring is made of carpet, replace in-kind commercial grade. Approximate measurements, contractor to verify flooring area. | SF | 1200 |
| | **Flooring Replacement:** Existing flooring is made of sheet vinyl, replace in-kind, commercial grade. Approximate area, contractor to verify flooring area. | SF | 300 |
| | **Install Exterior Pest Exclusion Measures:** Shall include installing wire mesh around the building to exclude pests. | LF | 200 |
| | **Install New Bathroom Fan/Light Combo:** Replace existing light and vent, with new fan/light combo. Must be vented to exterior. | LS | 2 |

14

| Building Name / Location | Task Description | Unit | Quantity |
|---|---|---|---|
| 103 Ritter House<br>Mammoth Lakes, CA | **Exterior Painting:** Includes all surface preparations, siding and drywall repairs. | SF | 1700 |
| | **Interior Painting:** .Includes all surface preparations and drywall repairs. | SF | 1700 |
| | **Minor Roof Repair:** Existing roof is made of metal, with minor roof damage due to snow. | SF | 200 |
| | **Install New Bathroom Fan/Light Combo:** Replace existing light and vent, with new fan/light combo. Must be vented to exterior. | LS | 2 |
| | **Update Bathroom Lighting:** Existing vanity light has two fixtures. | LS | 1 |
| | **Replace Bathroom Ceiling Heater** | LS | 1 |
| | **Replace Interior Ceiling Vents:** Existing vents are metal and approximately 6 inch by 12 inch. Contractor to confirm number of vents required for whole house. | LS | 6 |
| | **Replace Kitchen Light Fixture:** Existing fluorescent light fixture is approximately 12 inch by 48 inch | LS | 1 |
| | **Update Bedroom Lighting** | LS | 3 |

15

| Building Name / Location | Task Description | Unit | Quantity |
|---|---|---|---|
| 105 Ritter House<br>Mammoth Lakes, CA | **Exterior Painting:** Includes all surface preparations, siding and drywall repairs. | SF | 1700 |
| | **Interior Painting:** .Includes all surface preparations and drywall repairs. | SF | 1700 |
| | **Minor Roof Repair:** Existing roof is made of metal, with minor roof damage due to snow. | SF | 200 |
| | **Install New Bathroom Fan/Light Combo:** Replace existing light and vent, with new fan/light combo. Must be vented to exterior. | LS | 2 |
| | **Update Bathroom Lighting:** Existing vanity light has two fixtures. | LS | 1 |
| | **Replace Bathroom Ceiling Heater** | LS | 1 |
| | **Replace Interior Ceiling Vents:** Existing vents are metal and approximately 6 inch by 12 inch. Contractor to confirm number of vents required for whole house. | LS | 6 |
| | **Update Bedroom Lighting** | LS | 3 |
| | **Paint Kitchen Cabinets:** Existing cabinets are made of MDF. | SF | 300 |
| | **Flooring Replacement:** Existing flooring is made of carpet, replace in-kind commercial grade. Approximate measurements, contractor to verify flooring area. | SF | 1000 |
| | **Flooring Replacement:** Existing flooring is made of sheet vinyl, replace in-kind, commercial grade. Approximate area, contractor to verify flooring area. | SF | 200 |

16

| Building Name / Location | Task Description | Unit | Quantity |
|---|---|---|---|
| 106 Ritter House<br>Mammoth Lakes, CA | **Exterior Painting:** Includes all surface preparations, siding and drywall repairs. | SF | 1700 |
| | **Minor Roof Repair:** Existing roof is made of metal, with minor roof damage due to snow. | SF | 200 |

17

| Building Name / Location | Task Description | | Quantity |
|---|---|---|---|
| 1 Ediza House<br>Mammoth Lakes, CA | **Exterior Painting:** Includes all surface preparations, siding and drywall repairs. | SF | 1700 |
| | **Minor Roof Repair:** Existing roof is made of metal, with minor roof damage due to snow. | SF | 200 |
| | **Replace Window Trim:** Existing windows are approximately 36 inch by 48 inch. | LS | 7 |
| | **Replace Front Sidewalk and Steps:** Existing sidewalk is approximately 3 ft by 30 ft with two steps. | LS | 1 |

18

| Building Name / Location | Task Description | Unit | Quantity |
|---|---|---|---|
| 1 Murphy House<br>Mammoth Lakes, CA | **Exterior Painting:** Includes all surface preparations, siding and drywall repairs. | SF' | 2000 |
| | **Interior Painting:** .Includes all surface preparations and drywall repairs. | SF' | 2000 |
| | **Minor Roof Repair:** Existing roof is made of metal, with minor roof damage due to snow. | SF' | 200 |
| | **Update Bathroom Lighting**: Existing vanity light has two fixtures. | LS | 2 |
| | **Install New Bathroom Fan/Light Combo:** Replace existing light and vent, with new fan/light combo. Must be vented to exterior. | LS | 2 |
| | **Remove Wall Heater:** Remove existing wall heater in living room and repair wood wall. | LS | 1 |

19

| Building Name / Location | Task Description | Unit | Quantity |
|---|---|---|---|
| 6 Ruby House | **Exterior Painting:** Includes all surface preparations, siding and drywall repairs. | SF | 1700 |
| | **Replace Siding:** Existing Siding is made of wood, damaged with Woodpecker holes. Replace in-kind and where needed. | SF | 160 |
| | **Replace Window Trim:** Existing windows are approximately 36 inch by 48 inch | LS | 7 |
| | **Replace Front Steps:** Existing wooden steps are approximately 3 ft by 5 ft.; landing is approximately 3 ft by 4 ft. Includes painting existing railing and support beams. | LS | 1 |

20

| Building Name / Location | Task Description | Unit | Quantity |
|---|---|---|---|
| Trailer Pads<br><br>Mammoth Lakes, CA | **Construct New Concrete Trailer Pads:** Construct concrete trailer pad approximately 12 ft by 25 ft, with a minimum 10 ft separation from other trailer pads. | LS | 3 |
| | **Install New Water Service:** Install new frost-proof yard hydrants next to the new trailer pad and connect it to the existing water distribution system. | LS | 3 |
| | **Install New Sewer Service:** Install new sewer hookup next to the new trailer pad and connect it to the existing sewer system. | LS | 3 |
| | **Install New Electrical Service:** Install new RV power pedestal next to the new trailer pads and connect it to the existing power supply. | LS | 3 |

| Building Name / Location | Task Description | Unit | Quantity |
|---|---|---|---|
| Crestview Cabin 1120<br>Crestview, CA | **Exterior Painting:** Includes all surface preparations, siding and drywall repairs. | SF | 1000 |
| | **Interior Painting:** .Includes all surface preparations and drywall repairs. | SF | 1000 |
| | **Install Weather Stripping:** Install new weather stripping on front door and back door. Existing doors are 36 inch standard doors. | LS | 2 |
| | **Replace Vent Stacks:** Install new vent stacks. Contractor to confirm actual vent stack count. | LS | 2 |
| | **Replace Windows:** Install new windows as shown in the window schedule... See attached window schedule for specific window count. Includes removal and disposal of existing windows and preparing the area for new windows. | LS | 1 |
| | **Replace Bathroom Door:** Existing door is made of wood and is approximately 32 inch wide. | LS | 1 |
| | **Install New Vanity:** Replace existing sink with new sink vanity, approximately 44 inch, 36 inch, by 21 inch. | LS | 1 |
| | **Install New Faucet:** Contractor to install new bathroom faucet. | LS | 1 |
| | **Flooring Replacement:** Existing flooring is made of sheet vinyl, replace in-kind, commercial grade. Approximate area, contractor to verify flooring area. Includes repairing/replacing existing subflooring. | SF | 24 |
| | **Replace Bathroom Ceiling Heater** | LS | 1 |
| | **Install heat tape and Insulation:** Contractor to Install heat tape underneath cabin and insulate pipes. | LS | 1 |
| | **Install Exterior Pest Exclusion Measures:** Shall include installing wire mesh around the building to exclude pests. | LF | 200 |
| | **Insulate Water Heater and Pipe** | LS | 1 |
| | **Install Snow Bar:** Install Snow bar above utilities | LF | 25 |
| | **Roof Replacement:** Install new metal roof. Existing roof is made of metal replace in-kind, includes replacing existing roof vents. | SF | 600 |
| | **Wall and Structural Repairs:** Repair south facing cabin, which is leaning away from building due to snow loading damage. | LS | 1 |

| Building Name / Location | Task Description | | Quantity |
|---|---|---|---|
| Crestview Cabin 1119<br>Crestview, CA | **Exterior Painting:** Includes all surface preparations, siding and drywall repairs. | SF | 1000 |
| | **Interior Painting:** .Includes all surface preparations and drywall repairs. | SF | 1000 |
| | **Install Weather Stripping:** Install new weather stripping on front door and back door. Existing doors are 36 inch standard doors. | LS | 2 |
| | **Replace Windows:** Install new windows as shown in the window schedule. See attached window schedule for specific window count. Includes removal and disposal of existing windows and preparing the area for new windows. | LS | 1 |
| | **Flooring Replacement:** Existing flooring is made of sheet vinyl, replace in-kind, commercial grade. Approximate area, contractor to verify flooring area. | SF | 24 |
| | **Install heat tape and Insulation:** Contractor to install heat tape underneath cabin and insulate pipes. | LS | 1 |
| | **Install Exterior Pest Exclusion Measures:** Shall include installing wire mesh around the building to exclude pests. | LF | 200 |
| | **Insulate Water Heater and Pipe** | LS | 1 |
| | **Replace Shower Head** | LS | 1 |
| | **Install Front Porch Light Fixture** | LS | 1 |
| | **Install Bathroom Door Trim:** Existing door is approximately 32 inch | LS | 1 |
| | **Install Snow Bar:** Install Snow bar above utilities**.** | LF | 25 |

23

| Building Name / Location | Task Description | Unit | Quantity |
|---|---|---|---|
| Crestview Cabin 1122<br>Crestview, CA | **Exterior Painting:** Includes all surface preparations, siding and drywall repairs. | SF | 1000 |
| | **Interior Painting:** .Includes all surface preparations and drywall repairs. | SF | 1000 |
| | **Replace Front Door**: Install new door. Exiting doors are approximately 32 inch wide wood door, replace in-kind. | LS | 1 |
| | **Replace Windows:** Install new windows as shown in the window schedule. See attached window schedule for specific window count. Includes removal and disposal of existing windows and preparing the area for new windows. | LS | 1 |
| | **Replace Back Door:** Install new door. Exiting doors are approximately 32 inch wide wood door, replace in-kind. | LS | 1 |
| | **Replace Deck**: Contractor to replace the existing deck, in-kind. Existing deck is made of wood, approximately 6 ft by 8 ft. With 3ft high railing, with 4 steps and wraps around the front door area. | LS | 1 |
| | **Install heat tape and Insulation:** Contractor to install heat tape underneath cabin and insulate pipes. | LS | 1 |
| | **Install Exterior Pest Exclusion Measures:** Shall include installing wire mesh around the building to exclude pests. | LF | 200 |
| | **Insulate Water Heater and Pipe** | LS | 1 |
| | **Install New Vent Fan:** Install new vent fan in bathroom. | LS | 1 |
| | **Install Snow Bar:** Install Snow bar above utilities**.** | LF | 25 |

24

| Building Name / Location | Task Description | Unit | Quantity |
|---|---|---|---|
| Crestview Cabin 1121<br>Crestview, CA | **Building Inspection:** Building inspection shall include structural member inspections, roof inspections, flooring inspections, water and sewer inspections including foundation inspections. | LS | 1 |
| | | | |

25

| Building Name / Location | Task Description | | Quantity |
|---|---|---|---|
| Trailer Pads<br><br>Crestview, CA | **Construct New Concrete Trailer Pads:** Construct concrete trailer pad approximately 12 ft by 25 ft, with a minimum 10 ft separation from other trailer pads. | LS | 4 |
| | **Install New Water Service:** Install new frost-proof yard hydrants next to the new trailer pad and connect it to the existing water distribution system. | LS | 4 |
| | **Install New Sewer Service:** Install new sewer hookup next to the new trailer pad and connect it to the existing sewer system. | LS | 4 |
| | **Install New Electrical Service:** Install new RV power pedestal next to the new trailer pads and connect it to the existing power supply. | LS | 4 |

26

| Building Name / Location | Task Description | Unit | Quantity |
|---|---|---|---|
| Lee Vining Recreation Barracks<br>Lee Vining, CA | **Exterior Painting:** Includes all surface preparations, siding and drywall repairs. | SF | 2000 |
| | **Interior Painting:** .Includes all surface preparations and drywall repairs. | SF | 2000 |
| | **Replace Ceiling Tiles**: Remove existing ceiling tiles and replace them with drywall. Includes all work associated with removing the existing tiles, preparing the ceiling and the disposal of existing ceiling tiles. | SF | 1600 |
| | **Update Lighting:** Install new light fixtures in the following locations: Bedroom (5), Bathroom (3 ceiling lights and 2 vanity lights), Kitchen/Common Area (6)**.** Contractor to confirm light fixture count. | SF | 16 |
| | **Install Door Trim:** Install door trim on women's bathroom. Existing door is a 36 inch standard door. | LS | 1 |
| | **Install Screen Door:** Install screen door on main entrance door. Existing door is 36 inch standard door. | LS | 1 |
| | **Install Exterior Pest Exclusion Measures:** Shall include installing wire mesh around the building to exclude pests. | LF | 200 |

| Building Name / Location | Task Description | Unit | Quantity |
|---|---|---|---|
| Lee Vining Fire Barracks<br>Lee Vining, CA | **Exterior Painting:** Includes all surface preparations, siding and drywall repairs. | SF | 2000 |
| | **Interior Painting:** .Includes all surface preparations and drywall repairs. | SF | 2000 |
| | **Replace Front and Rear Stairs:** Existing stairs have five steps and are approximately 3 ft wide. Replace in-kind. | LS | 2 |
| | **Install Roof Enclosure Over Stairs:** Contractor to construct enclosure around front and back stairs, made of composite shingle roof to shade snow. Shall extend over the new stairs. | LS | 2 |
| | **Install Exterior Pest Exclusion Measures:** Shall include installing wire mesh around the building to exclude pests. | LF | 200 |
| | **Install New Bathroom Fan/Light Combo:** Replace existing light and vent, with new fan/light combo. Must be vented to exterior. | LS | 2 |
| | **Replace Storm Doors**: Install new storm doors on the front and back entrance. Existing door is 36 inch standard door. | LS | 2 |
| | **Replace Vent Stacks:** Install new vent stacks. Contractor to confirm actual vent stack count. | LS | 10 |
| | **Install Weather Stripping:** Install new weather stripping on front and back entrance doors. Existing door is 36 inch standard door. | LS | 2 |
| | **Install Door Sweeps:** Install door sweeps on front and back entrance doors. Existing door is 36 inch standard door. | LS | 2 |
| | **Replace Window Trim:** Install new window trim on bedroom window. Bedroom window is approximately 36 inch by 48 inch. | LS | 1 |
| | **Paint Main Entrance Ramp and Railing:** Existing stairs are approximately 3ft x 20ft, with a 3 ft by 4 ft landing. | LS | 1 |
| | **Paint Back Entrance Stairs and Railing:** Existing stairs are approximately 3ft x 5 ft, with a 3 ft by 5 ft landing. | LS | 1 |
| | **Repair Bathroom Walls:** Existing bathroom walls have moisture damage/water damage. Includes replacing the cove base (vinyl). | SF | 512 |
| | **Replace Kitchen Counter:** Install new kitchen counter. Existing counter is approximately 24 inch by 96 inch (Laminate, Formica), replace in-kind. | LS | 1 |
| | **Replace Double Sink** | LS | 2 |
| | **Replace Faucet** | LS | 2 |
| | **Flooring Replacement:** Existing flooring is made of carpet, replace in-kind commercial grade. Approximate measurements, contractor to verify flooring area. | SF | 1200 |
| | **Flooring Replacement:** Existing flooring is made of sheet vinyl, replace in-kind, commercial grade. Approximate area, contractor to verify flooring area. | SF | 300 |

| Building Name / Location | Task Description | Unit | Quantity |
|---|---|---|---|
| 1012 Lee Vining House<br>Lee Vining, CA | **Exterior Painting:** Includes all surface preparations, siding and drywall repairs. | SF | 2500 |
| | **Interior Painting:** .Includes all surface preparations and drywall repairs. | SF | 2500 |
| | **Replace Ceiling Tiles**: Remove existing ceiling tiles and replace them with drywall. Includes all work associated with removing the existing tiles, preparing the ceiling and the disposal of existing ceiling tiles. | SF | 2500 |
| | **Update Lighting:** Install new light fixtures in the following locations: Bedroom (3), Entryway (1) Bathroom (2 vanity lights), Hallway (2), Livingroom (1), Kitchen (2, 1 above sink), Laundry Room (1), Little dining room (1). Contractor to confirm light fixture count. | LS | 14 |
| | **Install New Bathroom Fan/Light Combo:** Replace existing light and vent, with new fan/light combo. Must be vented to exterior. | LS | 2 |
| | **Update Toilets:** Install new toilet in the main bathroom. | LS | 1 |
| | **Replace Faucet:** Install new faucets in the following locations: Bathroom (2), Laundry room (1), and kitchen (1) | LS | 4 |
| | **Replace Kitchen Counter:** Install new kitchen counter. Existing counter is approximately 24 inch by 180 inch (Laminate, Formica), replace in-kind. | LS | 1 |
| | **Replace Double Sink:** Install new double sink in kitchen. | LS | 1 |
| | **Replace Vent Stacks:** Install new vent stacks. Contractor to confirm vent stack count. | LS | 5 |
| | **Roof Replacement:** Existing roof is made of metal, replace in-kind. | SF | 2500 |
| | **Replace Deck:** Existing deck is made of wood, 10 ft by 20 ft. With 3ft high railing, with 3 steps and wraps around the back door area. | LS | 1 |
| | **Repair and Paint Front Steps:** Existing steps are approximately 4 ft by 8 ft , with a 4ft by 8 ft landing. | LS | 1 |
| | **Replace Back Door:** Exiting doors are approximately 36 inch wide wood door, replace in-kind. | LS | 1 |
| | **Install Weather Stripping:** Install new weather stripping on the laundry room doors (2) and garage door (1). Existing door is 36 inch standard door. | LS | 3 |
| | **Flooring Replacement:** Existing flooring is made of carpet, replace in-kind commercial grade. Approximate measurements, contractor to verify flooring area. | SF | 1500 |
| | **Flooring Replacement:** Existing flooring is made of sheet vinyl, replace in-kind, commercial grade. Approximate area, contractor to verify flooring area. | SF | 1000 |
| | **Replace Windows:** Install new windows as shown in the window schedule. See attached window schedule for specific window count. Includes removal and disposal of existing windows and preparing the area for new windows. | LS | 1 |
| | **Replace Bathroom Ceiling Heater:** Install new ceiling heater in small bathroom. | LS | 1 |

29

| Building Name / Location | Task Description | Unit | Quantity |
|---|---|---|---|
| 1006 Lee Vining Big House<br>Lee Vining, CA | **Exterior Painting:** Includes all surface preparations, siding and drywall repairs. | SF | 2300 |
| | **Replace Windows:** Install new windows as shown in the window schedule. See attached window schedule for specific window count. Includes removal and disposal of existing windows and preparing the area for new windows. | SF | 1 |
| | **Replace North Side Door:** Install new door on the north side of the building. Existing door is approximately 36 inch wide wooden door, replace in-kind. | LS | 1 |

30

| Building Name / Location | Task Description | | Quantity |
|---|---|---|---|
| 1025 Lee Vining Small House<br>Lee Vining, CA | **Exterior Painting:** Includes all surface preparations, siding and drywall repairs. | SF | 900 |
| | **Roof Replacement:** Install new roof. Existing roof is made of wood shakes, replace in kind. | SF | 900 |
| | **Install New Screen Door:** Install new screen door. Existing door is approximately 32 inch wide. | LS | 1 |
| | **Replace Siding:** Existing Siding is made of wood, damaged with Woodpecker holes. Replace in-kind and where needed. | SF | 40 |
| | **Repair and Paint Front Porch:** Existing porch is approximately 4 ft by 10 ft, with 3t railing, with two sets of stairs (4 steps and approximately 4 ft wide). Historic building and will need to be hand scrapped, paint color to match existing paint. | LS | 1 |

31

| Building Name / Location | Task Description | Unit | Quantity |
|---|---|---|---|
| Lee Vining Bathhouse<br>Lee Vining, CA | **Exterior Painting:** Includes all surface preparations, siding and drywall repairs. | SF | 450 |
| | **Interior Painting:** .Includes all surface preparations and drywall repairs. | SF | 450 |
| | **Realign Door:** Realign Bathhouse main entrance door. Existing door is 36 inch standard metal door. | LS | 1 |
| | **Install Weather Stripping**: Install new weather stripping on the bathhouse main entrance door. Existing door is 36 inch standard door. | LS | 1 |
| | **Install Exterior Pest Exclusion Measures:** Shall include installing wire mesh around the building to exclude pests. | LF | 36 |

32

| Building Name / Location | Task Description | Unit | Quantity |
|---|---|---|---|
| Lee Vining Ranger Station<br>Lee Vining, CA | **Exterior Painting:** Includes all surface preparations, siding and drywall repairs. | SF | 8000 |
| | **Interior Painting:** .Includes all surface preparations and drywall repairs. | SF | 8000 |
| | **Replace Windows:** Install new windows as shown in the window schedule. See attached window schedule for specific window count. Includes removal and disposal of existing windows and preparing the area for new windows. | LS | 1 |
| | **Replace Siding:** Existing Siding is made of wood, damaged with Woodpecker holes. Replace in-kind and where needed. | SF | 3350 |
| | **Install Exterior Pest Exclusion Measures:** Shall include installing wire mesh around the building to exclude pests. | LF | 400 |
| | **Walkway Repair:** Repair existing concrete porch walkway and ramp. Existing walkway is approximately 3 ft wide and approximately 100 ft long, with a spalling crumbling concrete surface. | SF | 300 |

33

| Building Name / Location | Task Description | Unit | Quantity |
|---|---|---|---|
| Trailer Pads<br><br>Lee Vining, CA | **Construct New Concrete Trailer Pads:** Construct concrete trailer pad approximately 12 ft by 25 ft, with a minimum 10 ft separation from other trailer pads. | LS | 7 |
| | **Install New Water Service:** Install new frost-proof yard hydrants next to the new trailer pad and connect it to the existing water distribution system. Existing dirt pad has hydrants that need to be updated. | LS | 7 |
| | **Install New Sewer Service:** Install new sewer hookup next to the new trailer pad and connect it to the existing sewer system. Existing dirt pad has sewer hookups that need to be updated. | LS | 7 |
| | **Install New Electrical Service:** Install new RV power pedestal next to the new trailer pads and connect it to the existing power supply. Existing dirt pad has electrical connection that needs to be updated. | LS | 7 |