US Department of Agriculture (USDA)



Statement of Work

West Side Vault Toilet Pumping & Septic Services

Contents

Project 3
General Information 3
1.0 Scope of Work 3
Contractor Requirements 3
2.0 Technical Requirements / Tasks 3
3.0 Deliverables / Schedule 7

Project

West Side Vault Toilet Pumping & Septic Services

General Information

1.0 Scope of Work

The purpose of this service contract is to provide portable restrooms facilities for forest visitors, vault toilet pumping services at rec sites, septic system pumping services at Forest Service facilities, and general plumbing services at Forest Service facilities on the Klamath National Forest.

Contractor Requirements

2.0 Technical Requirements / Tasks

Contractor shall complete the following tasks within the specified time constraints and in accordance with relevant FAR clauses and provisions.

2.1 Klamath River Portable Toilets

Contractor shall provide clean, safe, and convenient portable restroom facilities for forest visitors. The location and quantity of portable toilets to be ordered is displayed below. Any additional portable toilets will be determined by agency staff.

RIVER ACCESS & TOILET OWNER	NUMBER OF TOILETS	WEEKS OF SERVICE (ONE SERVICE PER WEEK)	LATITUDE	LONGITUDE
SKEAHAN BAR HC SEPTIC	1	20	41.858774	-122.703877
ROCKY POINT FOREST SERVICE	1	20	41.816325	-123.1283
SLUICE BOX FOREST SERVICE	1	20	41.842542	-123.218627
WINGATE BAR FOREST SERVICE	1	20	41.722618	-123.43844
COON CREEK HC SEPTIC	1	20	41.614575	-123.49547

Contractor shall furnish on a call when needed basis: portable toilet rentals, pumping, interior service, repairs, delivery, and pickup of rented units. Additionally, contractors shall place Forest Service owned portable toilets at designated river access sites on a call when needed basis. Contractor shall provide pumping, interior service, repairs, delivery, and pickup of Forest Service owned units.

Portable toilet interior service shall consist of pumping toilet's vault; sweeping interior floors; removing waste, paper, and debris from all surfaces; washing interior fixtures, walls and floor with water and disinfectant soap; restocking with seat covers, toilet paper and service date stamp (provided by the contractor); repairing seats, fixtures, springs, hinges and latches to a serviceable condition.

2.1.1 Maintenance

For contractor owned portable toilets, contractor shall be responsible for repairs and replacement of broken, inoperable or unsafe portable restroom components, roof leaks and ventilation systems. If a unit becomes irreparable as determined by the agency, the contractor shall replace the unit within one week of notification at the rate specified in the Schedule of Items.

2.1.2 Placement of portable toilets

Toilet placement location will be coordinated with agency personnel and confirmed when order is placed. The agency may move toilet units at its expense and discretion within the recreation site. Agency will notify contractor of toilet movement within one business day of change.

2.2 Happy Camp Ranger District Vault Toilets

Contractor shall provide vault toilet pumping services at Forest Service recreation sites on the Happy Camp Ranger District including, campgrounds, day use areas, river access sites, and trailheads. The location of Forest Service vault toilets is displayed below.

RECREATION SITE NAME	NUMBER OF VAULT TOILETS	VAULT CAPACITY (GALS)	SERVICE FREQUENCY	LATITUDE	LONGITUDE
HAPPY CAMP OAK KNOLL DISTRICT					
GOTTVILLE RIVER ACCESS	1	1000	Annual	41.858949	-122.749758
SARAH TOTTEN CAMPGROUND	4	4000	Annual	41.787612	-123.051811
FORT GOFF CAMPGROUND	1	1000	2 years	41.865136	-123.256153
INDIAN CREEK RIVER ACCESS	1	1000	Annual	41.79025	-123.379844
CURLY JACK CAMPGROUND	5	5000	Annual	41.785842	-123.389348
FERRY POINT RIVER ACCESS	2	2000	Annual	41.671336	-123.432506
INDEPENDENCE REST AREA	1	1000	Annual	41.661372	-123.448612
GRIDER CREEK CAMPGROUND	1	1000	2 years	41.80664	-123.216975
NO MAN'S TRAILHEAD	1	750	2 years	41.729191	-123.533062
KELLY LAKE TRAILHEAD	1	1000	2 years	41.913314	-123.511111
NORCROSS CAMPGROUND	1	1000	Annual	41.64626	-123.30819
SULPHUR SPRINGS CAMPGROUND	1	1000	Annual	41.660356	-123.319933
WEST BRANCH CAMPGROUND	1	1000	2 years	41.932169	-123.475498
POKER FLAT TRAILHEAD	1	1000	2 years	41.930179	-123.544473
BROWN BEAR RIVER ACCESS	1	1000	2 years	41.823729	-122.963378
O'NEILL CREEK CAMPGROUND	2	2000	2 years	41.809020	-123.116388
TREE OF HEAVEN CAMPGROUND	6	6000	Annual	41.830659	-122.660384
MT. ASHLAND CAMPGROUND	2	2000	Annual	42.075629	-122.714374

GROUSE GAP REC AREA	2	2000	Annual	42.078489	-122.737260
		SCOTT SALMON DISTRICT			
TAYLOR LAKE	1	1000	Annual	41.3677	-122.975
TRAIL CREEK	2	2000	Annual	41.22909	-122.971
CARTER MEADOWS	2	2000	Annual	41.22079	-122.911
HIDDEN HORSE	2	2000	Annual	41.21918	-122.912
FORKS REST AREA	1	1000	Annual	41.25841	-123.322
RED BANKS	1	1000	Annual	41.29834	-123.23
MULE BRIDGE TRAILHEAD	1	1000	Annual	41.35688	-123.075
IDLEWILD	3	3000	Annual	41.32955	-123.06
HOTELLING	1	1000	Annual	41.23936	-123.276
MATTHEW'S CREEK	2	2000	Annual	41.18717	-123.213
EAST FORK	1	1000	Annual	41.15408	-123.109
JONES BEACH	1	1000	Annual	41.64032	-123.059
LOVERS CAMP	2	2000	Annual	41.5931	-123.142
INDIAN SCOTTY	7	7000	Annual	41.63383	-123.08

Recreation site vault toilet interior service shall consist of pumping toilet vaults to empty them of human waste and removing trash from the vault to the extent practical. Contractor will clean any interior surfaces of the toilet building where human waste has spilled during the pumping process.

Happy Camp RD staff will obtain services on an as needed basis and will call Happy Camp Septic to arrange timing of vault toilet pumping. Toilet vaults are generally pumped once per season, with actual dates of pumping dependent on when the tanks become full. Not all vaults listed below will require pumping in 2026 because they were pumped late in the season during 2025.

2.3 Other Services and Requirements

Contractor shall provide septic system pumping services at Forest Service administrative sites on the Happy Camp Ranger District, including employee housing units.

Contractor shall provide general plumbing services at Forest Service administrative sites and buildings on an on-call basis.

Administrative site septic tank pumping service shall consist of pumping septic holding tank to empty them of human waste. Administrative site plumbing services shall consist of general plumbing system repairs.

Site Name	Coordinates
River View 1	41.785835, -123.387938

River View 2	41.785671, -123.388362
Seiad Oaks	41.847168, -123.197448
Seiad WC House	41.840787, -123.194349
Curly Jack Mobile Park	41.777330, -123.393023
Happy Camp Admin Site	41.789467, -123.393133

2.3.1 Ordering and servicing schedule

Toilets will be regularly serviced weekly on a weekday agreed upon by the contractor and the agency. Service time shall be between the hours of 6:00AM and 6:00PM unless another time is agreed upon when the order is placed.

Emergency/additional service requests shall be fulfilled within 12 hours of notification unless both parties agree to an alternate time. Emergency / additional service requests include extra service cleaning on short notice, spilled waste material, turnover of units etc.

This clause applies to items 1 and 2 of the schedule of items. Additional service requests may be ordered at the Agency's discretion. The projected holiday services will be completed on Sunday and Monday of the following holiday weekends, Memorial Day, Fourth of July, and Labor Day. For these identified holidays service would be required on Monday and Sunday. Service should be completed before 11:00AM to facilitate easy access to the units.

2.3.2 Offsite Disposal of Sewage

The Contractor shall be properly licensed by the state of California and shall be responsible for making disposal arrangements, including disposal of all effluent, debris, and trash, and payments of all fees. Disposal shall conform to all Federal, State, and local laws and ordinances. Contracting Officer Representative and Contracting Officer shall approve all disposal sites before pumping begins.

The Contractor shall be responsible to prevent spillage and to haul all waste material (sewage and debris) in watertight containers. Handling of all waste material shall be in accordance with all applicable health regulations.

2.3.3 Conduct of Personnel

The Contractor and his/her employees shall make every reasonable effort to prevent interference with the normal use and occupancy of recreational areas while engaged in the performance of the contract. Due to the nature of the duties under the contract, the Contractor and his/her employees shall keep themselves and equipment presentable at all times. The Contracting Officer may, in writing, require the Contractor to remove from the work site any employee the Contracting Officer deems incompetent, careless, discourteous to the public, or is otherwise objectionable, or for theft, possession and/or removal of materials, supplies, equipment, or any Government-owned property.

2.3.4 Pre-work Conference

Prior to the start of work, a meeting will be scheduled to be attended by the Contractor, the Contracting Officer and other Government personnel who may be involved in the administration of this contract. The meeting will be held at a time and place mutually agreeable to the Contractor and the Contracting Officer Representative and Contracting Officer. The purpose of this meeting is to thoroughly discuss the schedule of work, work performance, requirements, approved waste disposal sites, contract terms, and to familiarize both parties with the responsibilities of each under the terms of this contract.

2.3.5 Contractor's Representative

Prior to the start of work, the Contractor shall designate in writing a person to act for him/her during his/her absence from any work site and shall specify the scope of their authority.

2.3.6 Resource Damage

Any damage or defacement that occurs to government property or land resources during the Contractor's operations shall be repaired at the Contractor's expense to its original condition. Onsite inspection will be made by the Contracting Officer Representative prior to the acceptance of work.

3.0 Deliverables / Schedule

The contractor shall perform the following major items in the contract with the incentives and deductions for the work described.

Work Statement	**Performance Standard**	**Government Method of Assessment**	**Incentives and Deductions for Meeting the Standard**
Toilet rental and services.	Work meets specification requirements as stated in the PWS.	COR and Inspector conduct periodic random monitoring	The quality provided by the Contractor will be reflected in the performance evaluation either positive or negative. If the Contractor fails to meet standards, work may be suspended or terminated for Cause for failure to take corrective action immediately and result in adverse performance evaluation. If the Government does not receive the services as stated in the specifications, a deduction may be made in price.
Quality Control	Contractor maintains good quality control on all aspects of operation.	COR or Inspector randomly observe operations.	The Quality Control provided by the Contractor will be reflected in the performance evaluation either positive or negative. If the Contractor fails to meet standards, work may be suspended or terminated for Cause for failure to take corrective action immediately and result in adverse performance evaluation.
Work Plan Schedule, and Communications	Work meets schedule as per specifications. Contractor keeps COR/Inspector advised of where they can be reached by phone at all times of contract performance.	COR and Inspector conduct periodic random monitoring.	Contractor's ability to maintain the work schedule and complete work on schedule will be reflected in the performance evaluation as either positive or negative incentive. Contractor's work not completed on schedule is subject to default and may result in termination for cause including assessment of re-procurement costs and result in adverse performance evaluation.

Loss, damage or destruction of Government property	Contractor shall protect the Government property at the recreation sites while in service	COR and Inspector conduct periodic random monitoring	Contractor shall be responsible for loss; damage or destruction of Government property unless the Contractor can show the damage resulted from causes beyond the Contractor's control and without the Contractor's fault or negligence.