TECHNOLOGY EQUIPMENT SCHEDULE

THE EQUIPMENT LIST ABBREVIATIONS AND THE TECHNOLOGY EQUIPMENT SCHEDULE ARE FOR THE CONVENIENCE OF THE CONTRACTOR. EACH CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFICATION OF QUANTITIES AND SHALL FURNISH ALL MATERIAL REQUIRED, WHETHER SPECIFIED OR NOT, TO PRODUCE A SATISFACTORY WORKING SYSTEM.

CATALOG NUMBERS ARE NOT TO BE CONSIDERED COMPLETE BUT ARE GIVEN ONLY TO AID THE CONTRACTOR IN THE SEARCH FOR MATERIAL NO MATERIAL SHALL BE ORDERED BY MANUFACTURER AND CATALOG NUMBER ONLY. EACH CONTRACTOR SHALL FIRST READ THE COMPLETE DESCRIPTION OF THE MATERIAL ON THESE DRAWINGS AND SPECIFICATIONS. THE FIRST MANUFACTURER LISTED IS THE BASIS OF DESIGN. "STANDARD COLOR" INDICATES FACTORY FINISH AVAILABLE AT NO ADDITIONAL CHARGE.

EQUIPMENT LIST ABBREVIATION	EQUIPMENT LIST DESCRIPTION
AC-CR1-W	DUAL AUTHENTICATION CARD READER WITH KEYPAD. PROVIDED AS INTEGRAL PART OF SECURITY MANAGEMENT SYSTEM. REFER TO ACCESS CONTROL DOOR TYPE SCHEDULE ON T600 FOR ADDITIONAL INFORMATION. CARD READERS SHOWN ON PLANS TO IDENTIFY INTENDED MOUNTING LOCATION. REFER TO SPECIFICATION SECTION 28 13 00 FOR COMPLETE INFORMATION. PROVIDE PROGRAMMING FOR DUAL AUTHENTICATION. INTEGRATE WITH C-CURE 9000 MANAGEMENT.
AC-SCP-1	SECURITY MANAGEMENT SYSTEM CONTROL PANEL, FOR USE WITH INTEGRATED SECURITY MANAGEMENT SYSTEM. REFER TO SPECIFICATION SECTION 28 13 00 FOR COMPLETE INFORMATION.
PA-S1-W	WALL MOUNTED SPEAKER. MOUNT HORIZONTALLY AT +108" AFF. INSTALL 4" SQUARE BACKBOX WITH A 3/4"CONDUIT TO THE NEAREST ACCESSIBLE CEILING IN THE CORRIDOR. COORDINATE MOUNTING HEIGHT WITH ARCHITECTURAL DETAILS.
PA-S-C	CEILING MOUNTED SPEAKER. INSTALL 4" SQUARE BACKBOX WITH A 3/4"CONDUIT TO THE NEAREST ACCESSIBLE CEILING IN THE CORRIDOR.
PW-HH-1	HANDHOLE COMPOSITE POLYMER CONCRETE BODY AND COVER. STAINLESS STEEL HARDWARE BOLTED NON-SKID COVER RATED FOR 15,000LB. DESIGN LOAD OCCASIONAL NON-DELIBERATE VEHICULAR TRAFFIC. STACK UNITS TO ACIEVE DEPTH SHOWN ON PLANS. UNITS IN LANDSCAPED AREAS SHALL BE GREEN IN COLOR. "COMMUNICATIONS" LOGO ON HANHOLE COVER. CONTRACTOR SHALL FIELD VERIFY QUANTITY AND LOCATIONS. REFER TO F77/T400 FOR DETAIL. PW-HH-1 = 24"WX24"L.
PW-MH-1	MANHOLE, REFER TO C1/T401 FOR DETAIL.
SC-BLK-1	RACK BLANKING PANEL, ANGLED. 1RU, 19" RACK MOUNT.
SC-ER-1	4-POST EQUIPMENT RACK WITH CAGE NUT RAILS, 84" HIGH, 23.75" WIDE SUPPORTING STANDARD 19" MOUNTING SPACE, 30" CHANNEL DEPTH. PRINTED RACK SPACE IDENTIFICATION ON ALL EQUIPMENT RAILS. UL LISTED FOR 2000LBS, PROVIDES (45) 1.75 MOUNTING SPACES. PROVIDE IN WHITE POWDERCOAT FINISH. PROVIDE WITH FRONT AND REAR SECURITY DOORS WITH SECURITY DOOR MOUNTING HARDWARE. PROVIDE WITH (2) PDU MOUNTING BRACKETS.
SC-FDC-1	ANGLED OPTICAL FIBER DISTRIBUTION CABINET, RACK MOUNT. HIGH DENSITY 144 FIBER MAXIMUM CAPACITY. FOR PRE-TERMINATION TRUNKS FOR MCR-01 HDA DISTRIBUTION PROVIDE WITH OM4/OS1 MTP TYPE CASSETTES AS NECESSARY (LEVITON HDX ENTERPRISE SPMPH SERIES) FOR CAMPUS TR DISTRIBUTION PROVIDE WITH OM4/OS1 LC, FUSION SPLICE TYPE CASSETTES AS NECESSARY (LEVITON HDX ENTERPRISE SPLCH SERIES) REQUIRES (1) 19" X 1.75" RACK MOUNTING SPACES.
SC-GND-1	GROUNDING BUSBAR, WALL MOUNT. 4" H X 20" L X 1/4" D COPPER, ELECTRICALLY ISOLATED BY INSULATORS INTEGRAL TO MOUNTING BRACKETS. COPPER GROUND BAR IS 1/4" THICK AND STAND OFF 2.75" FROM WALL. THE 20" BUSBAR PROVIDES CONNECTION FOR EIGHTEEN (18) 2-HOLE COMPRESSION LUGS RESPECTIVELY WITH 5/8" OR 1" CENTERS. ANSI/TIA-607 AND BICSI COMPLIANT. UL LISTED. REFER TO GROUND BAR DETAIL ON 5/T400.
SC-GND-2	GROUNDING BUSBAR, RACK MOUNT.
SC-HWM-1	FLAT SINGLE-SIDED HORIZONTAL WIRE MANAGER WITH FRONT DOOR, (1) RU. 19" RACK MOUNT.
SC-HWM-2	FLAT SINGLE-SIDED HORIZONTAL WIRE MANAGER WITH FRONT DOOR, (2) RU. 19" RACK MOUNT.
SC-IO-C	INFORMATION OUTLET, CEILING MOUNT. 2-PORT SURFACE MOUNT BISCUIT. REFER TO DATA CONNECTION SCHEDULE ON T600 FOR PIN CONFIGURATION. " # " INDICATES INFORMATION OUTLET FACEPLATE CONFIGURATION AS INDICATED ON THE PLANS. REFER TO ABOVE CEILING INFORMATION OUTLET DETAIL ON C7/T400.
SC-IO-W	INFORMATION OUTLET, WALL MOUNT. COVERPLATE PORTS AS INDICATED ON DATA CONNECTION SCHEDULE, REFER TO DATA CONNECTION SCHEDULE ON T600 FOR ADDITIONAL INFORMATION. " # "INDICATES INFORMATION OUTLET FACEPLATE CONFIGURATION AS INDICATED ON THE DRAWINGS. " W " PROVIDE (1) RJ-45 JACK FOR VOICE AT +42" AFF FOR WALL HUNG PHONE. PROVIDE WITH STAINLESS STEEL FACEPLATE, MATING LUGS. (LEVITON 4108W-1SP) INSTALL INFORMATION OUTLET IN EXISTING ROUGH-IN UNLESS OTHERWISE NOTED. IF NEW ROUGH-IN IS REQUIRED, PROVIDE A 4" SQUARE BACKBOX WITH A SINGLE GANG PLASTER RING. INSTALL A 1.25" EMT CONDUIT TO NEAREST ACCESSIBLE CEILING.
SC-MPP-1	ANGLED MODULAR PATCH PANEL, 48 MODULAR RJ-45 TERMINATIONS, MOUNTS DIRECTLY TO EIA/TIA STANDARD 19" RELAY RACK, PORT IDENTIFICATION NUMBERS, U.L. LISTED. REQUIRES (1) 1.75" MOUNTING SPACES. PROVIDE WITH REAR CABLE MANAGER AND ANGLED PANEL COVER.
SC-PDU-1	POWER STRIP, VERTICALLY MOUNTS IN A STANDARD 19" RACK OR CABINET. 208V NOMINAL INPUT VOLTAGE, 120V/208V NOMINAL OUTPUT VOLTAGE. NEMA L21-20P INPUT CONNECTIONS. (36) IEC 60320 C13, (2) NEMA 5-20R, (6) IEC 60320 C19 OUTPUT CONNECTIONS. PROVIDE WITH (2) PDU FOR EACH FLOOR MOUNTED TR CHANNEL RACK.
SC-TTB	TELECOMMUNICATIONS TERMINAL BOARD, 4'X8'X3/4" A-C GRADE FIRE-RATED PLYWOOD. EXPOSED SIDE SHALL BE SMOOTH. MOUNT VERTICALLY WITH TOP OF PLYWOOD AT 8'-6" AFF. IN THE EVENT THE MANUFACTURER'S RATING STAMP IS NOT VISIBLE ON THE SMOOTH SIDE, THE CONTRACTOR SHALL PROVIDE A LAMINATED LETTER FROM THE MANUFACTURER OR SUPPLIER CERTIFYING THAT THE PLYWOOD IS FIRE-RATED AND ATTACH THE LETTER WITH A PICTURE OF THE RATING STAMP TO THE PLYWOOD. PAINT PLYWOOD WITH WHITE FINISH, REFER TO DIVISION 9. FIRE RATED PLYWOOD SHALL NOT BE PAINTED OR TREATED WITH ANY TYPE OF SEALANT THAT WOULD LESSEN THE INTEGRITY OF THE FIRE RATING.
SC-UPS-1	UNINTERRUPTED POWER SUPPLY.
SC-VWM-1	VERTICAL WIRE MANAGER, 76.94"H X 6.45"W X 10.26"D. REMOVABLE FRONT HINGED DOOR. SPOOLS FOR INTEGRAL BEND RADIUS CONTROL.
VS-CM-1	SINGLE LENS, SINGLE VARIFOCAL LENS, INTERIOR/EXTERIOR, IP CAMERA. 3.1 MEGAPIXEL, VARIFOCAL: 3.4-8.9 mm, MIN ILLUMINATION: COLOR: 0.1 LUX, B/W: 0.0 LUX. FEATURES: WIDE DYNAMIC RANGE, IR ILLUMINATION, VIDEO COMPRESSION: H.264, H.265, MOTION JPEG; CASING:IP52-RATED; IK RATING; IK10 IMPACT-RESISTANT CASING WITH HARD-COATED DOME; POWER: TYPICAL 6.4W, MAX 10.7W; OPERATING CONDITIONS: 0-50 DEG C.; INCLUDES VANDAL RESISTANT SCREWS. CAMERA COLOR: WHITE. (2) INFORMATION OUTLETS FOR CAMERA SHALL BE TERMINATED ON AN RJ-45 PLUG. ALL EXTERIOR CAMERAS TO BE BLACK IN COLOR.
VS-CM-2	360° MULTI-DIRECTIONAL LENS IP CAMERA. 4X3.1 MEGAPIXEL SENSORS, VARIFOCAL: 3.18-8.12 mm, MIN ILLUMINATION: COLOR: 0.14 LUX, B/W: 0 LUX. FEATURES: WIDE DYNAMIC RANGE, IR ILLUMINATION, TWO-WAY AUDIO, AND I/O CONNECTIVITY. VIDEO COMPRESSION: H.264, H.265, MOTION JPEG; CASING: IP66, IP67 -RATED; POWER: MAXIMUM VIDEO RESOLUTION 1920 X 1080; OPERATING CONDITIONS: -30 TO 50 DEG C.; INCLUDES VANDAL RESISTANT SCREWS. CAMERA COLOR: WHITE. (2) INFORMATION OUTLETS FOR CAMERA SHALL BE TERMINATED ON AN RJ-45 PLUG. ALL EXTERIOR CAMERAS TO BE BLACK IN COLOR.

DATA CONNECTION SCHEDULE

NOTES: 1. PROVIDE REMOVABLE BLANK INSERT(S) FOR ALL UNUSED PORTS. 2. LABEL INFORMATION OUTLET FACEPLATES PORTS STARTING TOP LEFT TO BOTTOM RIGHT.

LEGEND

FACEPLATE CONFIGURATION TYPE	CABLE TYPE	TERMINATION TYPE	CONNECTOR/CABLE COLOR
DATA:	CAT6A	RJ45 JACK	BLUE/BLUE
BLANK:	CAT6A		MATCH FACEPLATE/BLUE
NC:	BYN.C.C.	BY N.C.C.	BY N.C.C.
TV:	RG-6	F-CONNECTOR	
DEVICE CONNECTION TYPE			
WAP:	CAT6A	MPTL MALE RJ45	RED/NA
CAM:	CAT6A	MPTL MALE RJ45	GREEN/GREEN
AV:	CAT6A	MPTL MALE RJ45	ORANGE/NA

CONFIGURATION/ DEVICE CONNECTION	CABLE COUNT	DIRECT CONNECTION TYPE	NUMBER OF FACEPLATE(S)	FACEPLATE PORTS	FACEPLATE PORT IDENTIFICATION						NOTES
					POSITION 1	POSITION 2	POSITION 3	POSITION 4	POSITION 5	POSITION 6	
1D-WAP	1			1	DATA						
D1	1			1	DATA						
D2	2			2	DATA	DATA					
W	1			1	VOICE						

ACCESS CONTROL DOOR TYPE SCHEDULE

1. ELECTRONIC DOOR HARDWARE SUCH AS ELECTRIC STRIKES, ELECTRIC LATCH RETRACTION, ETC. SHALL BE PROVIDED AND INSTALLED BY THIS CONTRACT.
2. REFER TO THE TECHNOLOGY EQUIPMENT SCHEDULE FOR CREDENTIAL READER TYPE INFORMATION.

			CREDENTIAL READER				REQUEST TO EXIT		DOOR HARDWARE / MONITORING								INTEGRATION											OTHER (REFER TO NOTES)					
DOOR #	SECURITY DOOR TYPE	ROUGH IN ONLY	CREDENTIAL READER TYPE	MULTIPLE CREDENTIAL READERS OPERATES SINGLE DOOR	OPERATES MULTIPLE DOORS	INTERNAL ELECTRIFIED HARDWARE CONNECTION	MOTION DETECTOR	LOCAL PUSHBUTTON DOOR HARDWARE OVERRIDE	ELECTRONIC LOCKING HARDWARE	MAG LOCK	LOCAL ALARM HORN	LATCH STATUS DETECTION	MONITOR LATCH BOLT	MONITOR DOOR POSITION SWITCH SPDT	MONITOR DOOR POSITION SWITCH DPDT	MONITOR DOOR POSITION SWITCH - OVERHEAD DOOR	MONITOR DOOR POSITION SWITCH - ROOF HATCH	AUTOMATIC DOOR OPERATOR	ELEVATOR	LOCKED BY EMERGENCY/ DURESS SEQUENCE	INFANT PROTECTION	REMOTE UNLOCK VIA INTERCOM MASTER	REMOTE UNLOCK VIA PUSHBUTTON	INTRUSION DETECTION	REMOTE UNLOCK VIA FIRE COMMAND CENTER	VIDEO SURVEILLANCE	WANDER PREVENTION SYSTEM	DELAYED EGRESS	LOCAL 120VAC POWER SUPPLY	SCHEDULE BASED LOCKING	VISUAL STROBE/AUDIBLE ALARM	DETAIL REFERENCE	NOTES
000A	RIM		R1				•		•					•																		
000B	DPS													•																		
0S2A	RIM		R1				•		•					•																		
1S1A	RIM						•		•					•																		
100A	DPS													•																		
100B	DPS													•																		
100C	DPS													•																		
100D	DPS													•																		
100E	DPS													•																	2	DOUBLE DOOR
102C	RIM		R1				•		•					•																		
102D	DPS													•																		
203A	RIM		R1				•		•					•																		
203B	RIM		R1				•		•					•																		
208	RIE		R1			•			•					•				•														
WS101	RIM		R1				•		•					•																		
WS103	RIM		R1				•		•					•																		
WS104	RIM		R1				•		•					•																		
WS106A	RIM		R1				•		•					•																		

2

INDIVIDUAL CAMERA REQUIREMENTS SCHEDULE

CAMERA TYPE	CAMERA ENVIRONMENT	TELECOM ROOM #	FIELD OF VIEW DESCRIPTION	MOUNTING TYPE	DETAIL REFERENCE	ADDITIONAL INFORMATION	NOTES
CM-2	EXTERIOR	TR-1	EXTERIOR ROOF	PARAPET	2/T400		
CM-2	EXTERIOR	TR-1	EXTERIOR ROOF	PARAPET	2/T400		
CM-2	EXTERIOR	TR-1	EXTERIOR ROOF	PARAPET	2/T400		
CM-2	EXTERIOR	TR-1	EXTERIOR ROOF	PARAPET	2/T400		
CM-1	INTERIOR	TR-1	STAIRS	WALL	4/T401		
CM-1	INTERIOR	TR-1	STAIRS	WALL	4/T401		
CM-1	INTERIOR	TR-1	TR ENTRANCES	WALL	4/T401		
CM-2	EXTERIOR	TR-1	EXTERIOR ROOF	PARAPET	2/T400		
CM-1	INTERIOR	TR-1	DOOR ENTRANCES	CEILING	3/T401		
CM-1	INTERIOR	TR-2	TR ENTRANCES	WALL	4/T401		
CM-1	EXTERIOR	TR-2	DOOR ENTRANCES	WALL	4/T401		
CM-1	EXTERIOR	TR-2	DOOR ENTRANCES	WALL	4/T401		
CM-1	INTERIOR	TR-1	DOOR ENTRANCES	CEILING	3/T401		
CM-1	INTERIOR	TR-1	STAIRS	WALL	4/T401		
CM-1	INTERIOR	TR-1	DOOR ENTRANCES	WALL	4/T401		
CM-1	INTERIOR	TR-1	TR ENTRANCES	WALL	4/T401		
CM-2	EXTERIOR	TR-1	EXTERIOR ROOF	PARAPET	2/T400		

BIDDING RFIs	09/23/2026
Revisions:	Date:

CONSTRUCTION AGENT

US Army Corps of Engineers ®

New England District

CONSULTANT

IMEG
The FUTURE Built Smarter www.imegcorp.com
15 SUNNEN DRIVE
SUITE 104
ST. LOUIS, MO 63143
P: 314.645.1132 F: 314.645.1173
PROJECT #22000669.04

DESIGNER OF RECORD

A/E:
LEO A DALY
JOINT VENTURE
Perkins&Will

STAMP

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
DAVID LARSON
BICSI ID # 106098
EXPIRES 12-31-26
RCDD
2026-07-31

Office of Construction and Facilities Management

VA U.S. Department of Veterans Affairs

Drawing Title: TECHNOLOGY SCHEDULES

Approved:

Phase: READY TO ADVERTISE

FULLY SPRINKLERED

Project Title: CHILLED WATER PLANT REPLACEMENT AND SITE UTILITY IMPROVEMENTS PHASE A2

Location: 950 CAMPBELL AVENUE WEST HAVEN, CT 06516

Issue Date: 2026-07-31

Checked: ADAJUN

Drawn: DAVLAR

Project Number: 689-040

Building Number: 17

Drawing Number: T600

Autodesk Docs://001-10210-001_Phase_A2/689-040_VAWH BLDG-17_ET.rvt

9/25/2026 3:46:14 PM

VA FORM 08 - 6231