AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT

1. CONTRACT ID CODE	PAGE	OF	PAGES
J	1		7

2. AMENDMENT/MODIFICATION NUMBER	3. EFFECTIVE DATE	4. REQUISITION/PURCHASE REQUISITION NUMBER	5. PROJECT NUMBER *(If applicable)*
0006	10 NOV 2026		689-040

6. ISSUED BY	CODE	7. ADMINISTERED BY *(If other than Item 6)*	CODE
W912WJ			

W2SD ENDIST NEW ENGLAND
KO CONTRACTING DIVISION, 696 VIRGINIA ROAD
CONCORD, MA 01742-2751
UNITED STATES
TYLER MARYAK, EMAIL: TYLER.S.MARYAK@USACE.ARMY.MIL TELEPHONE: 978-318-8049

SCD: PAS:

8. NAME AND ADDRESS OF CONTRACTOR *(Number, street, county, State and ZIP Code)*

CODE | FACILITY CODE

(X)

☒ 9A. AMENDMENT OF SOLICITATION NUMBER: W912WJ26RA008

9B. DATED *(SEE ITEM 11)*: 24 AUG 2026

☐ 10A. MODIFICATION OF CONTRACT/ORDER NUMBER

10B. DATED *(SEE ITEM 13)*

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

☒ The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers ☐ is extended. ☒ is not extended.

Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing items 8 and 15, and returning 1 copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or electronic communication which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by letter or electronic communication, provided each letter or electronic communication makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA *(If required)*

SEE SECTION G - CONTRACT ADMINISTRATION DATA

13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NUMBER AS DESCRIBED IN ITEM 14.

CHECK ONE	
☐	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: *(Specify authority)* THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NUMBER IN ITEM 10A.
☐	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES *(such as changes in paying office, appropriation data, etc.)* SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).
☐	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:
☐	D. OTHER *(Specify type of modification and authority)*

E. IMPORTANT: Contractor ☐ is not ☐ is required to sign this document and return _____ copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (*Organized by UCF section headings, including solicitation/contract subject matter where feasible.*)

This amendment is necessary to add clauses for Government-Furnished Property and to respond to RFIs. All other aspects remain unchanged.

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER *(Type or print)*		16A. NAME AND TITLE OF CONTRACTING OFFICER *(Type or print)*	
		ERIN E. BRADLEY	
15B. CONTRACTOR/OFFEROR	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA	16C. DATE SIGNED
(Signature of person authorized to sign)		Erin E. Bradley *(Signature of Contracting Officer)*	10 NOV 2026

Previous edition unusable

STANDARD FORM 30 (REV. 11/2016)
Prescribed by GSA FAR (48 CFR) 53.243

SECTION SF 30 BLOCK 14 CONTINUATION PAGE

SUMMARY OF CHANGES

Section 00 21 16 - Instructions to Proposers

Miscellaneous text in this section has been added to:

Amendment 0006

Offerors are advised that any RFIs that have not received a response and been "closed" in ProjNet before the submission due date for Volume I will receive a response prior to the submission due date for Volume II and Volume III.

Requests for Information

1. **(ProjNet Inquiry ID 12018683)**
Ref. Government property - This paragraph assigns responsibility to the contractor to remove /relocate Government property. Please confirm if and where the extents of the property to be relocated is shown on the drawings and/or detailed in the specifications.

The plans and specifications identify existing Government property that will need to be removed, stored, and re-installed as part of the construction of this work. However, depending on the Contractor's exact means and methods to perform this work, it may become necessary to remove, store, and re-install additional pieces of Government property. It is the responsibility of the Contractor to identify those Government properties as part of the project phasing work plan for review and approval.

2. **(ProjNet Inquiry ID 12018737)**
Ref. Project Scheduler - Para. 1.3 requires an authorized representative be on the job site full-time, with no other duties. The project scale and scope cannot support a full-time scheduler on site. The limited work/staging space afforded will not support this individual on site full time either. This requirement may increase cost to the Government without corresponding value. Can this statement be revised to allow for remote access (teams/zoom) to the approved scheduler daily or at the Contracting Officer's request be on site within 24-48 hours instead?

Based on the scope and complexity of the work, an off-site scheduler is acceptable, provided the scheduler attends schedule-related meetings in person and remains actively engaged in project coordination and schedule management. See updated specification section 01 32 01.00 10 attached to this amendment.

3. **(ProjNet Inquiry ID 12040669)**

Please confirm if the project is tax exempt.

It is the contractor's responsibility to determine tax liability. After contract award, the contractor may complete and submit the applicable Sales Tax Exemption form and send it to the Contracting Officer for signature.

4. **(ProjNet Inquiry ID 12048052)**

1. What will the work hour requirements be for all phases of this project? Bid phasing drawings C-001 - C-011 note that "CONTRACTOR MAY ONLY WORK IN THIS AREA DURING FEDERAL HOLIDAYS, WEEKENDS OR NIGHT HOURS".
1a. Will this requirement be standard for all trades (i.e., CIP concrete), or will these work hour restrictions only apply to work occurring in and around road and pedestrian access routes? It is also noted that during all other hours, the road and pedestrian access must be open to vehicle and pedestrian traffic.
1b. If this note is standard for all trades, what hours will the contractors be allowed to work? Are nights defined as second shift (3:30 pm - 12:00 am) or third shift (10:00 pm - 6:00 am)?
1c. Weekends are listed in the allowable working hours note above. Will crews be required to work weekends, every weekend? Or, will weekends only be required if the contractor falls behind schedule?

Bid Phasing Note #4 ("Contractor may only work in this area during Federal holidays, weekends or night hours.") as shown on drawings C-003 to C-010 applies as identified in the plans, specifications, and appendices to any work in and around vehicular and/or pedestrian crossings only. This note would apply to all trades that perform work that would impact vehicular and/or pedestrian crossings. Specification Section 01 14 00, part 1.3.3 Work Outside Regular Hours, identifies hours of work outside of normal working hours.

5. **(ProjNet Inquiry ID 12045492)**

Amendment 0005 states that Offerors shall submit only Volume I prior to the current deadline, that the final design will be issued by amendment in February 2027 with a new deadline for Volumes II and III, and that all Offerors submitting Volume I will be invited to submit Volumes II and III. The redesign is expected to change chiller, pump, cooling tower and fuel oil storage quantities, which bear directly on the key subcontractors identified under Volume I - Factor 1 and on the summary schedule, phasing and durations under Volume I - Factor 2.

With the February 2027 amendment, will Offerors be permitted to submit a revised Volume I, in whole or in part, concurrent with Volumes II and III?

If revisions are permitted, please confirm the required method. Paragraph 4, "Revisions," directs that changed pages be a different color, marked by a vertical line in the right margin, and dated. Confirm whether Offerors should submit (a) a complete re-issued Volume I with changes so marked, or (b) replacement pages only, and confirm the file naming convention for the revised submission.

The design amendment planned for February 2027 will only reduce chilled water and fuel storage capacity, resulting in reduction of chiller(s), pump(s), cooling tower section(s), and fuel tank storage. It will not eliminate the scope or intent of this project; therefore, there is no direct bearing on the key subcontractor requirements. As such, Offerors will not be permitted to resubmit a revised Volume I concurrent with Volumes II and III.

6. **(ProjNet Inquiry ID 12040686)**
There is a note on 01-MP101 Column Line HH/6 referencing gate valves with a bleed valve typical for all double valves shown on the drawings for steam and condensate. This note points to the two future chilled water lines to the surgical tower. Please confirm this is correct.

Please see revised drawing 01-MP101 included as an attachment to this amendment.

7. **(ProjNet Inquiry ID 12040727)**
Flow diagram on M501 shows a control valve at each tower, the cooling tower north view elevation on M304 shows a butterfly valve, is there only a control valve with a manual operator or will a manual isolation valve be needed as well.

All components shown on M501 are required, including manual valves prior to control valves.

8. **(ProjNet Inquiry ID 12040757)**
M-503 note at FP-1 Automatic Fuel Polisher references a drawing detail 2/MP-605, there is no MP605 drawing. Please provide correct reference or missing drawing.

Please see revised drawing M-503 included as an attachment to this amendment.

9. **(ProjNet Inquiry ID 12040924)**
The responsibility matrix in the specification (23 09 23 1.1.e) does not call out who is to provide installation and wiring for the following system. Please provide who is responsible to provide and install this wiring?
a. Sump pump float switches and control panel wiring shown on P drawings
b. Fuel wiring system and sensors
c. Miscellaneous field sensors for chillers

The temperature controls contractor is to provide all low voltage control wiring unless noted otherwise. Temperature controls contractor is to provide all components required for monitoring, alarm, and control of systems to provide a complete and fully functional controls system as indicated in specification section 23 09 23 part 1.1. a.3.. This would include control panels, switches, and sensors for systems which do not come with manufacturer provided control panels, switches, and sensors. The controls contractor shall coordinate with the contractors providing the equipment to verify items which do and do not come with the equipment.

10. **(ProjNet Inquiry ID 12042488)**
Detail C6 and E5 on Sheet CK502 calls for high Security, Ornamental fencing to have "Impasse II "Gauntlet" Style" pickets and the drawing shows a spear tip at the end of the picket. However, the spec section 32 31 40 - 2.1.1 calls for a "tubular steel", typically found in Aegis Montage "Invincible" Style pickets. This "Invincible" style typically comes with the spear tip (as drawn), and the "Gauntlet Style" specified comes with a tri tip point. Please clarify which picket is needed?

Please see revised drawing CK-502 and CK-505 included as attachments to this amendment. The fencing picket style should be the "invincible/spear pointed" style as drawn and using tubular steel as indicated in the Specifications.

11. **(ProjNet Inquiry ID 12042747)**
M524 - Detail # C2 - Fuel Oil Heater Controls. Please clarify if the controls contractor, is to provide the low voltage control wiring for this fuel oil system or if the Division 26 Electrical Contractor will be responsible for this wiring? Also, who is responsible to provide the leak detectors for this system? This is not included in the responsibility table in spec 230923.

The temperature controls contractor is to provide all low voltage control wiring unless noted otherwise. Temperature controls contractor is to provide all components required for monitoring, alarm, and control of systems to provide a complete and fully functional controls system as indicated in specification section 23 09 23 part 1.1. a.3.. This would include control panels, switches, and sensors for systems which do not come with manufacturer provided control panels, switches, and sensors. Controls contractor shall coordinate with the contractors providing the equipment to verify items which do and do not come with the equipment. Specification section 23 10 00 paragraph 2.7 indicates the fuel oil polishing system calls for the control panel to have multiple indications to include "Rupture Basin Leak" alarm. Paragraph 2.9 indicates electric fuel oil heater calls for each outdoor electric fuel oil heater to come equipped with a hydrocarbon leak detector that's wired into the programmable logic controller to indicate an alarm in the event of a leak. Both panels should have leak detection as part of the equipment.

12. **(ProjNet Inquiry ID 12042752)**
DWG: M524 - Detail # D5 - Fuel Oil Polisher Controls. Please clarify if the controls contractor, is to provide the low voltage control wiring for this fuel oil system or if the Division 26 Electrical

Contractor will be responsible for this wiring? This is not included in the responsibility table in spec 23 09 23.

The temperature controls contractor is to provide all low voltage control wiring unless noted otherwise.

13. **(ProjNet Inquiry ID 12042755)**
DWG: M524 - Detail # D8 - Fuel Oil Tank Fill Controls. Please clarify if the controls contractor, is to provide the low voltage control wiring for this fuel oil system or if the Division 26 Electrical Contractor will be responsible for this wiring? Also, who is responsible to provide the 2-position control valves for this system? This is not included in the responsibility table in 23 09 23.

The temperature controls contractor is to provide all low voltage control wiring unless noted otherwise. Temperature controls contractor is to provide all components required for monitoring, alarm, and control of systems to provide a complete and fully functional controls system as indicated in specification section 23 09 23 part 1.1. a.3.. This would include control valves, switches, and sensors for systems which do not come with manufacturer provided control valves, switches, and sensors. Controls contractor shall coordinate with the contractors providing the equipment to verify items which do and do not come with the equipment.

14. **(ProjNet Inquiry ID 12043798)**
17-FA001 Fire Alarm Demo Note 1 states that the contractor is to field verify and field determine the scope of demolition work prior to bid. There was only one pre-bid site walk scheduled, and this work was not reviewed. In order to competitively bid all fire alarm demo work should be shown on the bid documents provided. Please confirm all fire alarm demo work is shown or provide additional drawings for review.

A site walk was performed by the fire protection engineering team to verify existing fire alarm conditions and document existing devices that are slated for demolition. While every effort was made to identify all fire alarm devices, experienced contractors may identify devices that were not observed by the FPE team during the brief survey. All known existing fire alarm devices to be removed are shown on the demolition drawings.

Section 00 72 00 - General Conditions

The following clauses were added:

FAR Clauses Incorporated by Reference

Number	Title	Effective Date	Alternate/ Deviation	Variation Effective Date
52.245-1	Government Property.	Sep 2021		
52.245-9	Use and Charges.	Apr 2012		

DFARS Clauses Incorporated by Reference

Number	Title	Effective Date	Alternate/ Deviation	Variation Effective Date
252.245-7003	Contractor Property Management System Administration	Jan 2025		
252.245-7005	Management and Reporting of Government Property.	Jan 2024		