

REPLACE FLOORING
RM 140

DEPARTMENT OF VETERANS AFFAIRS
PROJECT NO. 528A6-26-607
BUILDING 76
BATH, NY

Department of Veterans Affairs



SITE LOCATION
SCALE: NONE



SITE PLAN
SCALE: NONE

DRAWING INDEX

DISCIPLINE/ SHEET NO.	DESCRIPTION
G001	COVER SHEET & DRAWING INDEX
G002	GENERAL NOTES
A100	ARCHITECTURAL & DEMOLITON PLAN
A101	ICRA / LIFE SAFETY PLAN
A1	SITE LAYOUT
S1	FLOOR & WALLS SUPPORT LAYOUT
S2	CEILING SUPPORT LAYOUT - UNISTRUT
SD3	DETAIL - CEILING SUPPORT
SD4	DETAIL - WALL & FLOOR ANCHOR
SD5	DETAIL - WALL & FLOOR ANCHOR
EN	ELECTRICAL NOTES
EL	ELECTRICAL LEGEND
E1	ELECTRICAL LAYOUT
E2	RACEWAY DIAGRAM / CONDUIT LEGEND
ED1	ELECTRICAL DETAILS
ED2	ELECTRICAL DETAILS

Revisions: | Date:

CONSULTANT

ARCHITECT/ENGINEER OF RECORD

STAMP

Office of Construction and Facilities Management

VA U.S. Department of Veterans Affairs

Drawing Title: Cover Sheet
Phase: Construction Drawings
Project Title: Replace Flooring - RM 140
Project Number: 528A6-26-607
Building Number:
Approved: Project Director
NOTE: USERS OF THESE DRAWINGS ARE RESPONSIBLE FOR VERIFYING EXISTING DIMENSIONS AND CONDITIONS IN THE FIELD
Location: Bath, NY
Issue Date: Issue Date | Checked: AAA | Drawn: MCC
Drawing Number: G001

VA FORM 08 - 6231

S:\BAN-MES\WS-Eng-Projects\FY-2026\26-607 Replace Flooring RM 140\Design\528A6-26-607 - ES101.dwg 5-28-26 10:58:07 AM VHABANCAGLEM

one inch = one foot | three quarters inch = one foot | one half inch = one foot | three eighths inch = one foot | one quarter inch = one foot | one eighth inch = one foot | three inches = one foot | one and one half inches = one foot

GENERAL PROJECT NOTES:

1. CONTRACTOR SHALL PERFORM ALL WORK IN STRICT ACCORDANCE WITH ALL APPLICABLE LOCAL, STATE, AND FEDERAL RULES, REGULATIONS, AND GUIDELINES, AS OUTLINED WITHIN THE CONTRACT DOCUMENTS.
2. CONTRACTOR IS RESPONSIBLE FOR VERIFYING ALL EXISTING CONDITIONS (DIMENSION, QUANTITIES, ETC ..) AND ESTABLISHING THE COMPATIBILITY OF ALL NEW WORK WITH THE EXISTING CONDITIONS.
3. CONTRACTOR IS RESPONSIBLE FOR OBTAINING AND PAYING FOR ALL PERMITS, LICENSES, ETC .. REQUIRED BY REGULATING BODIES HAVING JURISDICTION.
4. CONTRACTOR IS RESPONSIBLE FOR ALL TOOLS, EQUIPMENT, AND SUPPLIES.
5. CONTRACTOR SHALL PROVIDE ALL NECESSARY SCAFFOLDING AND STAGING, INCLUDING ERECTION AND DISMANTLING AS REQUIRED FOR THE WORK AND OWNER OCCUPANCY.
6. CONTRACTOR IS RESPONSIBLE FOR KEEPING THE WORK AREA IN A CLEAN AND SAFE CONDITION. CONTRACTOR SHALL ENSURE THAT UNCERTIFIED PERSONNEL DO NOT ENTER ACTIVE WORK AREAS AT ANY TIME.
7. CONTRACTOR IS REQUIRED TO PROVIDE AND MAINTAIN ALL NECESSARY BARRICADES AND PROTECTIONS AS MAY BE NEEDED TO SAFELY MAINTAIN AND PROTECT THE EXISTING BUILDING, EQUIPMENT AND OCCUPANTS.
8. ALL WORK IS TO BE COMPLETED WITHIN OCCUPIED SPACE. CONTRACTOR SHALL TAKE EVERY PRECAUTION TO ELIMINATE THE TRAVEL OF DUST AND DEBRIS FROM THE CONSTRUCTION AREA INTO ADJACENT SPACES. TEMPORARY DUST PROTECTION SHALL BE ERECTED OUTSIDE OF NORMAL WORKING HOURS. INFECTION CONTROL MEASURES SHALL BE IMPLEMENTED.
9. CONTRACTOR IS RESPONSIBLE FOR THE PATCHING, REFINISHING & RESTORING EXISTING FINISHES TO MATCH ADJACENT SURFACES AS REQUIRED.
10. CONTRACTOR SHALL COORDINATE WITH THE OWNER THE LOCATION FOR ANY SITE STORAGE OF MATERIAL, EQUIPMENT, AND WASTE TRAILER/DUMPSTER.
11. CONTRACTOR IS RESPONSIBLE FOR COORDINATING WITH ALL TRADES PRIOR TO THE START OF ANY WORK.
12. CONTRACTOR IS RESPONSIBLE FOR SCHEDULING ALL WORK INCLUDING THE TEMPORARY DISCONNECTION OF UTILITIES WITH THE OWNER PRIOR TO THE START OF WORK, SO AS NOT TO DISRUPT OCCUPIED AREAS WITHIN AND SURROUNDING THE SCOPE OF WORK.
13. CONTRACTOR SHALL MAINTAIN EXISTING UTILITIES INDICATED TO REMAIN, KEEP IN SERVICE, AND PROTECT AGAINST DAMAGE DURING ALL WORK. CONTRACTOR TO COORDINATE CONSTRUCTION AROUND EXISTING EQUIPMENT, CONDUIT CABLING, ETC .. WITH OWNER AS REQUIRED.
14. CONTRACTOR SHALL COORDINATE EXACT LOCATION OF ALL NEW EQUIPMENT TO BE INSTALLED ABOVE CEILING WITH EXISTING MECHANICAL AND ELECTRICAL SERVICES.
15. CONTRACTOR SHALL PROTECT AND PRESERVE EXISTING ITEMS TO REMAIN, INCLUDING BUT NOT LIMITED TO WALLS, DOORS, WINDOWS, CASEWORK, FURNISHINGS AND EQUIPMENT. DAMAGE TO EXISTING ITEMS TO REMAIN SHALL BE PATCHED, REPAIRED AND/OR REPLACED AS NECESSARY TO MATCH EXISTING CONDITIONS AT NO ADDITIONAL COST TO THE OWNER.
16. CONTRACTOR SHALL OBTAIN OWNER'S DIRECTION AND APPROVAL PRIOR TO THE DEMOLITION/REMOVAL OF ALL ITEMS TO DETERMINE IF THE ITEMS WILL BE DISPOSED OF, REINSTALLED, OR SALVAGED AND RETURNED TO THE OWNER.
17. CONTRACTOR IS RESPONSIBLE FOR MAINTAINING ALL MEANS OF EGRESS AND LIFE SAFETY ROUTES FOR OCCUPIED AREAS DURING ALL PHASES OF CONSTRUCTION. FIRE ALARM AND SMOKE DETECTION SYSTEMS TO REMAIN OPERATIONAL AT ALL TIMES. ANY TEMPORARY EXCEPTIONS SHALL BE APPROVED BY THE LOCAL CODE OFFICIALS AND FIRE CHIEF.
18. CONTRACTOR SHALL REMOVE ALL SIGNAGE WITHIN SCOPE OF PROJECT. SALVAGE AND DELIVER TO OWNER, PATCH AND PREPARE WALLS AS REQUIRED TO RECEIVE SCHEDULED FINISH.
19. CONTRACTOR SHALL COMPLY WITH GOVERNING REGULATIONS PERTAINING TO ENVIRONMENTAL PROTECTION FOR POLLUTION CONTROL &HAZARDOUS MATERIALS. STOP WORK AND INFORM OWNER IMMEDIATELY IN WRITING OF ANY HAZARDOUS MATERIAL ENCOUNTERED OR THOUGHT TO BE OF HAZARDOUS MATERIAL. THE OWNER, AFTER RECEIVING WRITTEN NOTICE SHALL INSTRUCT CONTRACTOR ON HOW TO PROCEED.
20. CONTRACTOR SHALL PROVIDE PHILIPS WITH A SCHEDULE OF WORK TO ASSIST IN THE COORDINATION OF DELIVERY OH PHILIPS SUPPLIED PRODUCTS WHICH ARE TO E INSTALLED BY THE CONTRACTOR AND DELIVERY OF THE PRIMARY EQUIPMENT.


MINIMUM SITE PREPARATION REQUIREMENTS:

1. WALLS SHALL BE PAINTED OR COVERED, BASEBOARDS INSTALLED, FLOORS SHALL BE TILES AND/OR COVERED, CEILING SHALL HAVE GRID TILES AND LIGHTING FIXTURES INSTALLED AND OPERATIONAL.
2. ALL ELECTRICAL CONVENIENCE, CONDUIT, RACEWAY, KNOCKOUTS, CABLE OPENINGS, CHASE NIPPLES, AND JUNCTION BOXES INSTALLED AND OPERATIONAL.
3. INCOMING MAINS POWER OPERATIONAL AND CONNECTED TO ROOM X-RAY BREAKER.
4. ALL SUPPORT STRUCTURE CORRECTLY INSTALLED. ALL CHANNELS, PIPES, BEAMS AND/OR OTHER SUPPORTING DEVICES SHOULD BE LEVEL, PARALLEL, AND FREE OF LATERAL OR LONGITUDINAL MOVEMENTS.
5. ALL CONTRACTOR-SUPPLIED CABLES PULLED AND TERMINATED.
6. A DUST-FREE ENVIRONMENT IN AND AROUND THE PROCEDURE ROOM.
7. ARCHITECTURAL FEATURES SUCH AS COMPUTER FLOOR, WOOD FLOOR, CASEWORK, BULKHEADS, INSTALLED AND FINISHED.

ELECTRICAL REQUIREMENTS:

M-CABINET CXA 80

SUPPLY CONFIGURATION:	3 PHASE, 3 WIRE POWER, NEUTRAL AND GROUND. WYE. or 3 PHASE, 3 WIRE POWER,GROUND. DELTA
NORMAL LINE VOLTAGE:	400, 440, 460 or 480 VAC, 60 Hz
BRANCH POWER REQUIREMENT:	112.5 kVA MINIMUM
CIRCUIT BREAKER:	3 POLE, 50 Amps (@ 480V) (SLOW BLOW) RESIDUAL CURRENT DEVICE TO BE INSTALLED DEPENDING ON LOCAL REGULATIONS.



1 BUILDING KEY PLAN
SCALE: 1/16" = 1'0"

Revisions:	Date:

CONSULTANT

ARCHITECT/ENGINEER OF RECORD

STAMP


Office of Construction and Facilities Management

VA U.S. Department of Veterans Affairs

Drawing Title: General Notes	Phase: Construction Drawings	Project Title: Replace Flooring - RM 140	Project Number: 528A6-26-607
Approved: Project Director	NOTE: USERS OF THESE DRAWINGS ARE RESPONSIBLE FOR VERIFYING EXISTING DIMENSIONS AND CONDITIONS IN THE FIELD	Location: Bath, NY	Building Number:
		Issue Date: Issue Date / Checked: AAA / Drawn: MCC	Drawing Number: G002

S:\BIM-MES\MES-Eng-Projects\YY-2026\26-607 Replace Flooring RM 140\Design\528A6-26-607 - ES101.dwg 4-30-26 10:23:43 AM WHABNACKLEM

VA FORM 08 - 6231




1 NEW FLOORING PLAN
SCALE: N.T.S.

NEW CONSTRUCTION KEY NOTES: (#)

1. EXISTING FLOORING AND COVE BASE/TRIM TO BE DEMOLISHED/REMOVED.
2. INSTALL NEW LVT FLOORING WITH 6" FLASHCOVE. SEE FINISHED SCHEDULE.
3. WALL TO BE FURRED-OUT. PATCH AND PAINT WALLS WHERE ANY RELOCATED PANELS OR ELECTRICAL WORK HAS LEFT INCIDENTAL VOIDS OR OPENINGS.

FINISHED SCHEDULE		
RM NUMBER	FLOORING	REMARKS
140	LVT	BASIS OF DESIGN: SHAW NATURELIFE WOOD II 6" SHEET VINYL, COLOR "YOUNG HICKORY" WITH 6" FLASHCOVE AND STAINLESS COVE CAP
140A	LVT	BASIS OF DESIGN: SHAW NATURELIFE WOOD II 6" SHEET VINYL, COLOR "YOUNG HICKORY" WITH 6" FLASHCOVE AND STAINLESS COVE CAP



2 ELECTRICAL & SYSTEMS POWER DEMOLITION PLAN
SCALE: N.T.S.

KEYED DEMOLITION NOTES: (#)

1. REMOVE EXISTING CONDUIT AND POWER CABLES FROM (CB) TO (ME).
2. REMOVE EXISTING CONDUIT AND POWER CABLING FROM (CB) TO (ST).
3. REMOVE EXISTING CONDUIT AND POWER CABLING FROM (ME) TO (S1).
4. REMOVE EXISTING CONDUIT AND POWER CABLING FROM (S1) TO (WL).
5. REMOVE EXISTING CONDUIT AND POWER CABLING FROM (ME) TO (DS).
6. EXISTING CEILING TILES TO BE CAREFULLY REMOVED AS NOT CAUSE DAMAGE TO ACCOMMODATE THE DEMOLITION OF EXISTING CONDUITS. CONTRACTOR WILL BE RESPONSIBLE FOR REPLACING ANY DAMAGED CEILING TILES. CEILING GRID TO REMAIN IN PLACE.

GENERAL DEMOLITION NOTES:

1. SEE ELECTRICAL LEGEND ON DRAWING "EL".
2. ANY ITEM NOT SPECIFICALLY IDENTIFIED BUT REQUIRED TO BE REMOVED OR REPAIRED TO PREPARE THE BUILDING FOR THE NEW WORK OR TO OTHERWISE PRODUCE THE FINISHED PRODUCT SHOWN IN THE CONTRACT DOCUMENTS IS THE RESPONSIBILITY OF THE GENERAL CONTRACTOR.
3. SCHEDULE ALL SHUTDOWNS THAT AFFECT UTILITIES AND PORTIONS OF THE BUILDING THAT MUST REMAIN IN OPERATION WITH THE OWNER AND ALL LOCAL JURISDICTIONS HAVING AUTHORITY PRIOR TO IMPLEMENTING.
4. DEMOLITION WORK SHALL BE SCHEDULED AT ALL TIMES AND BE SUBJECT TO THE DIRECTION AND APPROVAL OF THE OWNER AND IMPLEMENTED WITHOUT DISRUPTION OF OCCUPIED AREAS SURROUNDING THE DEMOLITION ZONE.
5. EXISTING CONTRUCTION TO REMAIN SHALL BE PRESERVED AND PROTECTED DURING CONSTRUCTION. DAMAGE TO EXISTING CONSTRUCTION TO REMAIN SHALL BE PATCHED AND REPAIRED TO MATCH EXISTING CONDITIONS AT NO ADDITIONAL COST TO THE OWNER, INCLUDING THE MAINTENANCE OF ALL FIRE RATINGS AT STRUCTURAL MEMBERS, FLOORS, WALLS, CEILINGS, ETC.
6. PRIOR TO ANY DEMOLITION, THE GENERAL CONTRACTOR SHALL COORDINATE BRACING TO MAINTAIN THE STRUCTURAL INTEGRITY OF THE REMAINING ELEMENTS OF THE BUILDING AS REQUIRED.
7. CONTRACTOR SHALL REMOVE ALL MATERIALS IN A WORKMAN-LIKE MANNER APPROVED BY THE OWNER AND DISPOSE OF ALL MATERIALS PER APPLICABLE CODES.
8. FILL ANY OPENINGS IN FLOOR AND CEILING SLAB TO MATCH AND PRESERVE FIRE RATING.
9. COMPLY WITH GOVERNING REGULATIONS PERTAINING TO ENVIRONMENTAL PROTECTION FOR POLLUTION CONTROL & HAZARDOUS MATERIALS.
10. ALL MEANS OF EGRESS AND LIFE SAFETY ROUTES FOR OCCUPIED AREAS ARE TO REMAIN ACCESSIBLE DURING ALL PHASES OF CONSTRUCTION. FIRE ALARM AND SMOKE DETECTION SYSTEMS TO REMAIN OPERATIONAL AT ALL TIMES. ANY TEMPORARY EXCEPTIONS SHALL BE APPROVED BY THE LOCAL CODE OFFICIALS AND FIRE CHIEF.
11. CONTRACTOR TO PROVIDE TEMPORARY PARTITIONS (RATED AND/OR NON-RATED) AS REQUIRED. REVIEW LOCATIONS OF TEMPORARY PARTITIONS WITH OWNER & ARCHITECT PRIOR TO START OF WORK. ALL WORK IS TO BE DONE IN PROTECTED SPACE.
12. CONTRACTOR RESPONSIBLE FOR VERIFYING EXISTING CONDITIONS, CONDUIT SIZES, AND LENGTHS.

Revisions:	Date:

CONSULTANT

ARCHITECT/ENGINEER OF RECORD

STAMP

Office of Construction and Facilities Management

VA U.S. Department of Veterans Affairs

Drawing Title: Architectural & Demolition Plan

Phase: Construction Drawings

Project Title: Replace Flooring - RM 140

Project Number: 528A6-26-607

Building Number:

Approved: Project Director

NOTE: USERS OF THESE DRAWINGS ARE RESPONSIBLE FOR VERIFYING EXISTING DIMENSIONS AND CONDITIONS IN THE FIELD

Location: Bath, NY


Issue Date: Issue Date | Checked: AAA | Drawn: MCC

Drawing Number: A100

S:\BIM-MS\MS-Eng-Projects\Y1-2026\26-607 Replace Flooring RM 140\Design\528A6-26-607 - ES101.dwg 4-30-26 10:24:15 AM WHABNCAGLEM

one inch = one foot | one quarter inch = one foot | three eighths inch = one foot | one half inch = one foot | three quarters inch = one foot | one and one half inches = one foot | three inches = one foot | one eighth inch = one foot

VA FORM 08 - 6231



1 ICRA & Dust Control Plan
SCALE: N.T.S.

DUST CONTROL PLAN NOTES/DUST CONTROL PLAN HAZARD ASSESSMENT

PRIOR TO INITIATING WORK, CONTRACTOR WILL ASSESS THE SCOPE OF THE CONSTRUCTION ACTIVITIES AND DETERMINE THE POTENTIAL RISK GROUPS INVOLVED ON THE LOCATION OF ACTIVITIES AND EXTENT AND DURATION OF THE WORK. LOW RISK GROUPS ARE CONSIDERED "OFFICE WORKERS", MEDIUM RISK GROUPS ARE CONSIDERED ALL INPATIENT AND OUTPATIENT AREAS SUCH AS PEDIATRIC & ADULT OPERATING/DELIVERY ROOMS, CATH LABS, MYELO SUPPRESSIONS UNITS, ICU'S, DIALYSIS, NURSERIES AS WELL AS CLINIC AREAS (CLINICS ASSOCIATED WITH HEMATOLOGY, ONCOLOGY, PEDIATRIC INFECTION DISEASE, OR TRANSPLANT SERVICES) AND SERVICE AREAS (CENTRAL PROCESSING, STERILE PROCESSING, FOOD PREP & SERVICE AREA AND PHARMACIES. THE VAMC INFECTION CONTROL GROUP WILL CONFIRM AND APPROVE THE DESIGNATION PROVIDED IN THIS SUBMITTED DUST CONTROL PLAN. VAMC IS ALSO RESPONSIBLE FOR ANY AND ALL INFECTION CONTROL MEASURES DETERMINED & ESTABLISHED BY VAMC POLICY, SUCH AS THE RELOCATIONS OF HIGH RISK PATIENTS, APPROVING ALTERNATE TRAFFIC PATHS FOR CONSTRUCTION WORKERS OR ESTABLISH ALTERNATE TRAFFIC PATTERNS FOR STAFF, PATIENTS & VISITORS. THE PLAN SHOULD BE REVISED ACCORDING TO SPECIFIC VAMC POLICIES OR CHANGING CONDITIONS AT THE SITE AS THEY MAY OCCUR.

BATH RENOVATION
FOR THE PURPOSE OF THIS RENOVATION, THE CONSTRUCTION WORK IS CONSIDERED MEDIUM RISK AND COMPRISES WORK WHICH COULD GENERATE MODERATE TO HIGH LEVELS OF DUST NOT WITHIN THE CONFINES OF A SUITE OR OFFICE AND INCLUDES EXTENSIVE CONSTRUCTION WORK (DEMOLITION) THROUGHOUT THE FIRST FLOOR. THE DUST CONTROL PLAN MUST BE DISTRIBUTED AND REVIEWED BY ALL CONTRACTORS PERFORMING WORK ON THIS CONSTRUCTION PROJECT.

A. EXTERNAL DEMOLITION & CONSTRUCTION ACTIVITIES
- DETERMINE IF THE IMPACTED AREAS OF THE FACILITY CAN OPERATE TEMPORARILY ON RE-CIRCULATED AIR; IF FEASIBLE, SEAL OF ADJACENT AIR INTAKES.
- IF THIS IS NOT POSSIBLE OR PRACTICAL, CHECK THE LOW-EFFICIENCY FILTER BANKS FREQUENTLY & REPLACE AS NEEDED TO AVOID BUILDUP OF PARTICULATE.
- SEAL WINDOWS & REDUCE WHEREVER POSSIBLE OTHER SOURCES OF OUTSIDE AIR INTRUSION (OPEN DOORS IN CORRIDORS) ESPECIALLY IN PROTECTIVE ENVIRONMENT (PE) AREAS.

B. INTERNAL DEMOLITION & CONSTRUCTION ACTIVITIES DUST & DEBRIS CONTROL
- BARRIER SYSTEMS: THE AREA SHOULD BE ISOLATED. AS THE PROJECT REQUIRES. SMALL, SHORT DURATION PROJECTS GENERATING MINIMAL DUST MAY SE FIRE-RATED PLASTIC SHEETING, BUT SHOULD BE SEALED AT FULL CEILING HEIGHT WITH AT LEAST 2-FOOT OVERLAPPING FLAPS FOR ACCESS TO ENTRY. PROJECTS THAT PRODUCE MODERATE TO HIGH LEVELS OF DUST REQUIRE RIGID, DUST-PROOF, & FIRE-RATED BARRIERS WALLS (E.G DRYWALL) WITH CAULKED SEAMS FOR A TIGHT SEAL, EXTENDING FLOOR TO CEILING. SEAL OFF AND BLOCK AIR VENTS IF RIGID BARRIERS ARE USED FOR CONTAINMENT. LARGE DUST PROJECTS MAY NEED AN ENTRY VESTIBULE FOR CLOTHING CHANGES AND TOOL STORAGE AND TIGHT SEALS SHOULD BE MAINTAINED AT THE FULL PERIMETER OF WALLS & WALL PENETRATIONS. AN INTERIM PLASTIC DUST BARRIER (MINIMUM 4-MIL) MAY BE REQUIRED TO PROTECT THE AREA WHILE THE RIGID IMPERVIOUS BARRIER IS BEING CONSTRUCTED. ANY DUST MUST BE IMMEDIATELY CLEANED IF TRACKED OUTSIDE OF THE CONSTRUCTION BARRIER. UPON COMPLETION OF THE CONSTRUCTION PROJECT DUST BARRIER MUST BE REMOVED CAREFULLY TO MINIMIZE SPREADING OF DUST & THE CONTRACTOR PERSONNEL MUST MONITOR & PERFORM BARRIER MAINTENANCE & BE EDUCATED TO NOTICE SIMPLE CLUES SUCH AS ACCUMULATIONS OF VISIBLE DUST EVIDENCED BY FOOTPRINTS, OPENED DOORS/WINDOWS EVIDENCED BY PRESENCE OF INSECTS & FLIES, WET CEILING TILES, ETC.
- TRAFFIC CONTROL: DESIGNATED ENTRY & EXIT PROCEDURES MUST BE DEFINED. EGRESS PATHS SHOULD BE FREE OF DEBRIS; DESIGNATED ELEVATORS SHOULD BE USED DURING SCHEDULED TIMES; AND ONLY AUTHORIZED PERSONNEL SHOULD BE ALLOWED TO ENTER THE CONSTRUCTION ZONE. SIGNAGE SHOULD DIRECT PEDESTRIAN TRAFFIC AWAY FROM TH E CONSTRUCTION AREA & MATERIALS.
-DEMOLITION DEBRIS: DEBRIS SHOULD BE REMOVED IN CARTS WITH TIGHTLY FITTED COVERS, USING DESIGNATED TRAFFIC ROUTES. EFFORTS SHOULD BE REMOVED DAILY & AT TIMES SPECIFIED BY THE VAMC. IF CHUTES ARE USED TO DIRECT DEBRIS OUTSIDE, HIGH EFFICIENCY PARTICULATE AIR (HEPA) FILTERED NEGATIVE AIR MACHINES SHOULD BE USED, & THE CHUTE OPENING SHOULD BE SEALED WHEN NOT IN USE. FILTERS SHOULD BE BAGGED AND SEALED BEFORE BEING TRANSPORTED OUT OF THE CONSTRUCTION AREA. THE CONTRACTOR MUST NOT HAUL DEBRIS THROUGH PATIENT-CARE AREAS WITHOUT PRIOR APPROVAL FROM THE VAMC.
- EXTERIOR WINDOWS: WINDOWS SHOULD BE SEALED TO MINIMIZE INFILTRATION FROM ANY ADJACENT EXCAVATION DEBRIS.
- CEILINGS THAT ARE REMOVED/MODIFIED TO ALLOW CONSTRUCTION OF ICRA BARRIERS SHOULD BE REINSTALLED TO PRE-CONSTRUCTION CONDITIONS.

VENTILATION & ENVIRONMENTAL CONTROLS
- AIR SYSTEM FLOW: DETERMINE WHTHER THE CONSTRUTION AREA USES FRESH/OUTSIDE OR RE-CIRCULATED AIR. FILTERS SHOULD BE ADDED OR RETURN VENTS COVERED AS NEEDED WITH FILTER MATERIAL OR PLASTIC. AIR MUST FLOW FROM CLEAN TO DIRTY AREAS.
- NEGATIVE AIR PRESSURE: THE AIR WITHIN THE CONSTRUCTION AREA MUST BE NEGATIVE WITH RESPECT TO SURROUNDING AREAS & WITH NO DISRUPTION OF AIR SYSTEMS OF ADJACENT AREAS. USE OF THE NEGATIVE AIR PRESSURE SYSTEM WITHIN THE ENCLOSURE TO REMOVE DUST SHOULD PASS AIR THROUGH AN INDUSTRIAL GRADE, PORTABLE HEPA FILTER CAPABLE OF FILTRATION RATES OF 300-800 CUBIC FEET PER MINUTE (FT3/MIN), OR EXHAUST AIR DIRECTLY TO THE OUTSIDE IF APPROVED BY VAMC. IF EXHAUST MUST BE TIED INTO A RE-CIRCULATED AIR SYSTEM, A PRE-FILTER & HEPA FILTER SHOULD BE USED BEFORE EXHAUST TO PREVENT CONTAMINATION OF THE DUCTS.
- ADJACENT AREAS: THE STATUS OF SEALED PENETRATIONS & INTACT CEILING SHOULD BE VERIFIED DAILY.
- AIR EXCHANGE RATES & PRESSURE RELATIONSHIPS: VAMC AND/OR CONTRACTOR WILL VERIFY & MAINTAIN PROPER RATES IN CRITICAL AREAS NEAR CONSTRUCTION ACTIVITY & ENSURE AIR IS NOT BEING RE-CIRCULATED WITHOUT FILTRATION FROM THE CONSTRUCTION AREA ELSEWHERE. VAMC WILL MAKE DETERMINATION OF PROVIDING FOR THE ACCOUNTABILITY AND FREQUENCY OF TESTING AIR PRESSURE THROUGHOUT THE PROJECT.
- MANOMETERS SHOULD BE LOCATED ON ICRA PARTITION DOOR & ON THE NON-CONSTRUCTION SIDE OF THE PARTITION.

CONTAMINATION OF PATIENT ROOMS
- WORK SITE CLOTHING: CONTRACTOR PERSONNEL CLOTHING SHOULD BE FREE OF LOOSE SOIL & DEBRIS BEFORE LEAVING THE CONSTRUCTION AREA. IF PROTECTIVE APPAREL IS NOT WORK (E.G COVERALLS, FOOTGEAR & HEADGEAR) A HEPA-FILTERED VACUUM SHOULD BE USED TO REMOVE DUST FROM CLOTHING BEFORE LEAVING THE BARRICADE. IF PROTECTIVE APPAREL IS UTILIZED THE CONTRACTOR MUST CONSTRUCT A SPACE OR ANTEROOM FOR CHANGING CLOTHING & STORING EQUIPMENT (DESIGNATED AREA). ALL EQUIPMENT, TOOLS, TOOL CARTS, MATERIALS, ETC. TRANSPORTED THROUGH OCCUPIED AREAS MUST BE MADE FREE FROM DUST & MOISTURE BY VACUUMING & WET WIPING BEFORE THEIR REMOVAL FROM THE CONSTRUCTION ZONE OR WORK AREA.
- CONTRACTOR CLEANING: THE CONSTRUCTION ZONE SHOULD BE MAINTAINED IN A CLEAN MANNER BY CONTRACTORS & SWEPT OR HEPA-VACUUMED DAILY OR MORE FREQUENTLY AS NEEDED TO MINIMIZE DUST. ADJACENT AREAS THAT MAY BE IMPACTED BY THE CONSTRUTION SHOULD BE DAMP MOPPED DAILY OR MORE FREQUENTLY AS NEEDED. WALK-OFF MATS WITH TACKY OR ADHESIVE SURFACES SHOULD BE UTILIZED TO MINIMIZE TRACKING OF HEAVY DIRT & DUST FROM CONSTRUCTION AREAS.

NOTES:
1. ENSURE RENOVATED AREA IS COMPLETELY SEALED OFF FROM SURROUNDING AREAS.
2. MAINTAIN MEANS OF EGRESS DURING CONSTRUCTION. RESTRICT ACCESS TO WORK AREA DURING CONSTRUCTION.
3. PROVIDE AND MAINTAIN CLEAN TACKY MATS AT ENTRANCE / EXIT OF ICRA BARRIER TO MINIMIZE TRACKING CONSTRUCTION DEBRIS THROUGH THE BUILDING.
4. COORDINATE PHASING SCHEDULE WITH COR PRIOR TO STARTING CONSTRUCTION.
5. CEILINGS THAT ARE REMOVED/MODIFIED TO ALLOW CONSTRUCTION OF ICRA BARRIERS ARE THE CONTRACTOR'S RESPONSIBILITY TO BE REINSTALLED TO PRE CONSTRUCTION CONDITIONS.

EGRESS SYMBOL/RATED PARTITION KEY

EXIT ACCESS — EXISTING EXIT ACCESS

LIFE SAFETY / CONSTRUCTION WASTE REMOVAL PATH

Revisions:	Date:

CONSULTANT

ARCHITECT/ENGINEER OF RECORD

STAMP

Office of Construction and Facilities Management

VA U.S. Department of Veterans Affairs

Drawing Title: Dust Control / ICRA Plan & Life Safety Plan

Phase: Construction Drawings

Project Title: Replace Flooring - RM 140

Project Number: 528A6-26-607

Building Number:

Approved: Project Director

NOTE: USERS OF THESE DRAWINGS ARE RESPONSIBLE FOR VERIFYING EXISTING DIMENSIONS AND CONDITIONS IN THE FIELD

Location: Bath, NY


Issue Date	Checked	Drawn
Issue Date	AAA	MCC

Drawing Number: A101

S:\BIM-MS-Eng-Projects\PY-2026\26-607 Replace Flooring RM 140\Design\528A6-26-607 – ES101.dwg 5-28-26 11:00:39 AM VHABANCAOLEM

VA FORM 08 - 6231

© Koninklijke Philips Electronics N.V. 2019. All rights reserved. Reproduction in whole or in part is prohibited without prior written consent of the copyright holder.



Legend

- Walls
- Soffit
- Existing (to be removed)
- Beams or other building construction elements

Site Layout

1/4" = 1'-0"

Recommended Minimum Ceiling Height: 8'-9" (2667mm)
Recommended Maximum Ceiling Height: 10'-6" (3200mm)

Reported Ceiling Height: 9'-0" (2743mm)

Ceiling Heights (measured from finished floor to bottom of Unistrut) other than recommended may impact equipment functionality - see Ceiling Height Guide and consult with Philips.

General Notes

* Counters and cabinetry shown to be supplied and installed by contractor.
* Field to verify all room dimensions.
* Refer to A.D.A. Guidelines for doors and clearances. Verify all other applicable code(s) with the architect of record.

PHILIPS


Project
Radiography 7300 C Pro VS
VA Medical Center Bath
Bath, NY
Room: #2

Philips Contacts
Project Manager: Arian Hallanjaku
Contact Number: (716) 262-7394
Email: arian.hallanjaku@philips.com
Drawn By: Miguel Maldonado

Project Details
Drawing Number
N-EAS250499 B
Date Drawn: 1/28/2026
Quote: Q-00526625
Order: 6600754396.010000

A1

THE DRAWINGS AND RELATED INSTRUCTIONS PROVIDED BY PHILIPS ARE ACCEPTABLE FOR USE BY THE HOSPITAL'S ARCHITECT OR ENGINEER TO USE FOR THE DEVELOPMENT OF CONSTRUCTION DOCUMENTS.



Floor & Wall Support Legend

A Furnished and installed by Philips
B Furnished by customer/contractor and installed by customer/contractor
C Installed by customer/contractor
D Furnished by Philips and installed by contractor
E Existing
F Future
G Optional

	Item Number	Description	Detail Sheet
B	MS	Anchors in floor for Diagnost TH	SD5
B	DVS	Support in wall for BuckyDiagnost VS	SD4
B	DVS	Anchors in floor for BuckyDiagnost VS	SD4
A	DVS	Anchors in wall for BuckyDiagnost VS	SD4
A	VCS	Anchors in wall for BuckyDiagnost VS Connection Box (not shown)	SD4
A	WAP	Wi-Fi Access Point - optional wall mounting	SD5

All dimensions must be off of the finished wall.

If a wall is furred out to hide electrical duct or boxes, the dimensions included in this plan must come off of the finished furred wall.

Notes:
1. Anchors for items that are installed/anchored by customer/contractor shall be provided by customer/contractor.
2. Anchors for items that are installed/anchored by Philips shall be provided by Philips. If customer's engineering documents specify anchors other than those listed in this document, the anchors shall be provided by customer/contractor and installed by Philips.
3. In all instances, the wall and/or floor support are the sole responsibility of the customer/contractor. The customer's architect/engineer of record shall specify wall and/or floor support sufficient for the bolt forces shown on the details.

Floor & Walls Support Layout

1/4" = 1'-0"
Recommended Minimum Ceiling Height: 8'-9" (2667mm)
Recommended Maximum Ceiling Height: 10'-6" (3200mm)

Reported Ceiling Height: 9'-0" (2743mm)

Ceiling Heights (measured from finished floor to bottom of Unistrut) other than recommended may impact equipment functionality - see Ceiling Height Guide and consult with Philips.

PHILIPS

Project
Radiography 7300 C Pro VS
VA Medical Center Bath
Bath, NY
Room: #2


Philips Contacts
Project Manager: Arian Hallanjaku
Contact Number: (716) 262-7394
Email: arian.hallanjaku@philips.com
Drawn By: Miguel Maldonado

Project Details
Drawing Number
N-EAS250499 B
Date Drawn: 1/28/2026
Quote: Q-00526625
Order: 6600754396.010000

S1

© Koninklijke Philips Electronics N.V. 2019. All rights reserved. Reproduction in whole or in part is prohibited without prior written consent of the copyright holder.

THE DRAWINGS AND RELATED INSTRUCTIONS PROVIDED BY PHILIPS ARE ACCEPTABLE FOR USE BY THE HOSPITAL'S ARCHITECT OR ENGINEER TO USE FOR THE DEVELOPMENT OF CONSTRUCTION DOCUMENTS.



Ceiling Support Legend

A Furnished and installed by Philips
B Furnished by customer/contractor and installed by customer/contractor
C Installed by customer/contractor
D Furnished by Philips and installed by contractor
E Existing
F Future
G Optional

Item Number	Description	Detail Sheet
B UNI	Unistrut (P1001)	SD3

All dimensions must be off of the finished wall.

If a wall is furred out to hide electrical duct or boxes, the dimensions included in this plan must come off of the finished furred wall.

See Ceiling Clearance Detail (sheet SD2) for information on restricted areas for objects that project below the finished ceiling.

Ceiling Support Layout - Unistrut

1/4" = 1'-0"
Recommended Minimum Ceiling Height: 8'-9" (2667mm)
Recommended Maximum Ceiling Height: 10'-6" (3200mm)

Reported Ceiling Height: 9'-0" (2743mm)

Ceiling Heights (measured from finished floor to bottom of Unistrut) other than recommended may impact equipment functionality - see Ceiling Height Guide and consult with Philips.

PHILIPS

Project
Radiography 7300 C Pro VS
VA Medical Center Bath
Bath, NY
Room: #2

Philips Contacts
Project Manager: Arian Hallanjaku
Contact Number: (716) 262-7394
Email: arian.hallanjaku@philips.com
Drawn By: Miguel Maldonado

Project Details
Drawing Number
N-EAS250499 B
Date Drawn: 1/28/2026
Quote: Q-00526625
Order: 6600754396.010000

S2

© Koninklijke Philips Electronics N.V. 2019. All rights reserved. Reproduction in whole or in part is prohibited without prior written consent of the copyright holder.


THE DRAWINGS AND RELATED INSTRUCTIONS PROVIDED BY PHILIPS ARE ACCEPTABLE FOR USE BY THE HOSPITAL'S ARCHITECT OR ENGINEER TO USE FOR THE DEVELOPMENT OF CONSTRUCTION DOCUMENTS.

© Koninklijke Philips Electronics N.V. 2019. All rights reserved. Reproduction in whole or in part is prohibited without prior written consent of the copyright holder.


Detail - Ceiling Support

(Not to scale)

Fixing Block for Philips Ceiling Rails (Clip Rails) Detail



Clip Rail Detail



CSR UNI

- Philips does not specify the overhead equipment support structure. Unistrut (or equal) may or may not be used. If Unistrut are used, it is up to Unistrut and the structural engineer for the project to determine which of it's products are appropriate for each project.
- Finished ceiling must **NOT** be lower than the bottom of the Unistrut in order to prevent damage to the finished ceiling during the installation of clip rails.
- Finished ceiling height to be 1/4" above bottom of Unistrut.
- Nothing shall be attached to the Unistrut with any fastener that protrudes into the Unistrut which would interfere with positioning of the fixing block.
- Fixing blocks for Philips ceiling rails (clip rails) are designed to be installed in P1001 Unistrut.
- The inside of the Unistrut must be clear of obstructions (including paint).
- Unistrut elements must be rigid and comply with the ceiling structure requirements. See SN sheet, item #4 "Ceiling Support Apparatus".

Tube Crane Support Forces	Tension Forces	Compressive Forces
CSM III	956 lbs/support	192 lbs/support

(Support = 2 screws into each Fixing Block)

(25.0)

PHILIPS

Project
Radiography 7300 C Pro VS
VA Medical Center Bath
Bath, NY
Room: #2

Philips Contacts
Project Manager: Arian Hallanjaku
Contact Number: (716) 262-7394
Email: arian.hallanjaku@philips.com
Drawn By: Miguel Maldonado

Project Details
Drawing Number
N-EAS250499 B
Date Drawn: 1/28/2026
Quote: Q-00526625
Order: 6600754396.010000


SD3

THE DRAWINGS AND RELATED INSTRUCTIONS PROVIDED BY PHILIPS ARE ACCEPTABLE FOR USE BY THE HOSPITAL'S ARCHITECT OR ENGINEER TO USE FOR THE DEVELOPMENT OF CONSTRUCTION DOCUMENTS.

Detail - BuckyDiagnost VS Digital

(Not to scale)

Elevation View of Bolts and Backing for DVS
(not site specific)



Bolt Forces (Standard DVS)

Tmax (Tension)(Wall)	= 303 lbs/bolt (max)
Vmax (Shear)(Wall)	= 72 lbs/bolt (max)
Vmax (Shear)(Floor)	= 227 lbs/bolt (max)

Bolt Forces (Tilting DVS)

Tmax (Tension)(Wall)	= 604 lbs/bolt (max)
Vmax (Shear)(Wall)	= 89 lbs/bolt (max)
Vmax (Shear)(Floor)	= 283 lbs/bolt (max)

Wall mounting points must be suitable to tensile strength Fs ≥ 1500N (338 lbf) each anchor.

Floor mounting points must be suitable for tensile strength Fs ≥ 500N (113 lbf) for each screw.

DVS

(Seismic area forces - consult seismic calculation documents)


Wall Support Options

The customer's architect/engineer of record shall specify a wall support sufficient for the bolt forces specified. Anchors will be provided by Philips, and the wall support is the sole responsibility of the customer/contractor. Below are Philips' pre-evaluated and approved methods of providing support:


Option	Anchor Style (Provided by Philips)	Anchor Size	Anchor Quantity	Wall Support Size & Material (Provided & installed by customer/contractor)
A	Through Bolt	3/8" diameter	4	Minimum 10 Gauge Steel Plate[1], or Douglas Fir #2 Grade (minimum 4" x 4")
B	Self Drilling Tek Screw	#14	4	Minimum 10 Gauge Steel Plate[1]
C	Lag Screw	7/16"	4	Douglas Fir #2 Grade (minimum 4" x 4")
D	Toggler Snaptoggle Anchor	3/8" diameter expansion screw	4	Minimum 10 Gauge Steel Plate[1]

[1] Unistrut, angle, or c-chanel material is preferred.


Wall Holder / Bracket Details




Wall Anchoring Example
Illustration of Wall Support with Steel Plate and Toggler Anchor




Floor Anchoring Details
mounting holes at floor





(25.1)

Elevation View of Connection Box
Weight = 36 lbs



VSC

Detail - BuckyDiagnost VS Advanced Connection Box

(Not to scale)

Wall Support Options

The customer's architect/engineer of record shall specify a wall support sufficient for the bolt forces specified. Anchors will be provided by Philips, and the wall support is the sole responsibility of the customer/contractor. Below are Philips' pre-evaluated and approved methods of providing support:

Option	Anchor Style (Provided by Philips)	Anchor Size	Anchor Quantity	Wall Support Size & Material (Provided & installed by customer/contractor)
A	SPAX Multipurpose Flat Head Screw	#10 x 1½"L	4	Drywall with wood backing
B	Round Phillips Head Self Drilling Screw	#10-16 x 1½"L	4	Drywall with minimum 10 gauge steel backing
C	Toggler SnapToggle with Round Head Screw	#BA with #10-24 x 2½"L	4	Drywall (5/8"D min.)
D	Round Phillips Head Self Drilling Screw	#10-16 x 1½"L	4	Metal junction box or raceway

Bolt Forces
Tmax (Tension) = 39 lbs/bolt
Vmax (Shear) = 36 lbs/bolt
(Seismic area forces - consult seismic calculation documents)

(13.0)

PHILIPS

Project
Radiography 7300 C Pro VS
VA Medical Center Bath
Bath, NY
Room: #2

Philips Contacts
Project Manager: Arian Hallanjaku
Contact Number: (716) 262-7394
Email: arian.hallanjaku@philips.com
Drawn By: Miguel Maldonado

Project Details
Drawing Number
N-EAS250499 B
Date Drawn: 1/28/2026
Quote: Q-00526625
Order: 660075439 6.010000

SD4


© Koninklijke Philips Electronics N.V. 2019. All rights reserved. Reproduction in whole or in part is prohibited without prior written consent of the copyright holder.

THE DRAWINGS AND RELATED INSTRUCTIONS PROVIDED BY PHILIPS ARE ACCEPTABLE FOR USE BY THE HOSPITAL'S ARCHITECT OR ENGINEER TO USE FOR THE DEVELOPMENT OF CONSTRUCTION DOCUMENTS.

© Koninklijke Philips Electronics N.V. 2019. All rights reserved. Reproduction in whole or in part is prohibited without prior written consent of the copyright holder.

Detail - Wi-Fi Access Point - Wall Mounted)

(Not to scale)




WAP

(17.0)

Detail - Diagnost TH/TF Table Base

(Not to scale)



Bolt Forces
The mounting points on the floor must be suitable for a tensile strength of F> 3600N (810 lbf) each anchor. (Seismic area forces - consult seismic calculation documents)

MS

(25.0)

PHILIPS

Project
Radiography 7300 C Pro VS
VA Medical Center Bath
Bath, NY
Room: #2

Philips Contacts
Project Manager: Arian Hallanjaku
Contact Number: (716) 262-7394
Email: arian.hallanjaku@philips.com
Drawn By: Miguel Maldonado

Project Details
Drawing Number
N-EAS250499 B
Date Drawn: 1/28/2026
Quote: Q-00526625
Order: 6600754396.010000

SD5

THE DRAWINGS AND RELATED INSTRUCTIONS PROVIDED BY PHILIPS ARE ACCEPTABLE FOR USE BY THE HOSPITAL'S ARCHITECT OR ENGINEER TO USE FOR THE DEVELOPMENT OF CONSTRUCTION DOCUMENTS.

General Electrical Information

1. General
The customer shall be solely responsible, at its expense, for preparation of the site, including any required electrical alterations. The site preparation shall be in accordance with this plan and specifications, the architectural/construction drawings and in compliance with all safety and electrical codes, the customer shall be solely responsible for obtaining all electrical permits from jurisdictional authority.

2. Materials and Labor
The customer shall be solely responsible, at its expense, to provide and install all electrical ducts, boxes, conduit, cables, wires, fittings, bushing, etc., as separately specified herein.

3. Electrical Ducts and Boxes
Electrical ducts and boxes shall be accessible and have removable covers. Floor ducts and boxes shall have watertight covers. Ducts shall be divided into as many as three separate channels by metal dividers, separately specified herein, to separate wiring and/or cables into groups as follows: Group A: power wiring and/or cables, Group B: signal and/or data and protective ground wiring and/or cables, Group C: x-ray high voltage cables. The use of 90 degree ells is not acceptable. On ceiling duct and wall duct use 45 degree bends at all corners. All intersecting points in duct to have cross over tunnels supplied and installed by contractor to maintain separation of cables.

4. Raceway / Conduit
Raceway / Conduit point - to - point runs shall be as direct as possible. Empty conduit runs used for cables may require pull boxes located along the run. Consult with Philips. A Greenlee measuring tape (part no. 435) shall be installed in each conduit run. Best practice to name the physical conduit. All conduits which enter duct prior to their termination point must maintain separation from other cables via use of dividers, cross over tunnels, or conduit supplied and installed by contractor from entrance into duct to exit from duct.

5. Conductors
All conductors, separately specified, shall be 75°C stranded copper, rung out and marked.

6. Disconnecting Means
A disconnecting means shall be provided as separately specified.

7. Warning Lights and Door Switches
"X-ray on" warning lights and x-ray termination door switches should be provided at all entrances to x-ray rooms as required by code.

8. Dimmer Switches
X-ray room lights should be provided with dimmer switches.

(25.0)

Electrical Notes

1. The contractor will supply & install all breakers, shunt trip and incoming power to the breakers. The exact location of the breakers and shunt trips will be determined by the architect or contractor.
2. The contractor shall supply & install all pull boxes, raceways, conduit runs, stainless steel covers, etc. Conduit/raceways must be free from burrs and sharp edges over its entire length. A Greenlee pull string/measuring tape (part no. 435, or equivalent) shall be provided with conduit runs.
3. All pre-terminated, cut-to-length cables will be supplied and installed by Philips. See Conduit List for information regarding all other cables (e.g. cables to breakers, etc.).
4. Provide and install 4 - 2"(50mm) diameter chase nipples between adjacent wall boxes (not required if raceway installed above and below wall boxes).
5. Electrical raceway shall be installed with removable covers. The raceway should be accessible for the entire length. In case of non - accessible floors, walls and ceilings, an adequate number of access hatches should be supplied to enable installation of cabling. Approved conduits may be substituted. All raceways will be designed in a manner that will not allow cables to fall out of the raceway when the covers are removed. In most cases, this will require above-ceiling raceway to be installed with the covers removable from the top. Raceway system as illustrated on this drawing are based upon length of furnished cables. Any changes in routing of raceway system could exceed maximum allowable length of furnished cables. Conduit or raceway above-ceiling must be kept as near to finished ceiling as possible.
6. Conduit sizes shall be verified by the architect, electrical engineer or contractor, in accordance with local or National Electrical Codes, whichever governs.
7. Convenience outlets are not illustrated. Their number and location are to be specified by the customer/architect.
8. All sections of raceway and conduit shall be grounded with an independent #6AWG green wire that is to be attached using solderless lugs All ceiling mounted structural support members and ceiling plates shall also be grounded. All grounding connections, terminals, etc. shall be installed in a manner to provide accessibility for inspection, maintenance, repair, etc.
9. The contractor is to ensure system cables that run from the system cabinet to the table are not run under the slab in ground floor installations. They need to be run in a trough or a raceway in the floor per NEC section 390 Underfloor Raceway. Conduits may not be allowed in a basement slab. The cables from the cabinets to the table are not certified in a wet environment/area.
10. Applied cable connectors cannot be removed for installation. Site must select a suitable size for cable ducts and wall outlets so connectors and cables can pass through.
11. Flex conduit does not meet Philips installation requirement and is NOT ALLOWED for substitution for EMT/Rigid conduit materials. Any deviation for conduit material requires written permission from the Philips project manager.

(25.0)

Electrical Requirements

Electrical power distribution at the facility shall comply with:

- Utilization voltages per ANSI C84.1 - 1982 range A.
- Voltage to be supplied is 3 phase, 3 wire power and ground (delta or wye) unless otherwise noted in equipment specifications.
- Phase conductors to be sized for instantaneous voltage drop per NEC 517-73 and Philips recommendations.
- Neutral and ground conductors to be sized equivalently to phase conductors, unless otherwise noted.
- Metal conduit shall not be used as the equipment ground conductor.
- Clamping type surge suppressors are highly recommended in addition to standing facility lighting arrestors. Equipment to be protected from ANSI/IEEE C62.41-1980 location category B impulses.
- ANSI/NFPA 70 - National Electrical Code (NEC)
  Article 250 - Grounding
  Article 517 - Health Care Facilities
- ANSI/NFPA 99 - Health Care Facilities Code
- NEMA standard XR 9 - Power Supply Guidelines for X-Ray Machines
- A clearance of 3'-6 $\frac{1}{8}$" (1070mm) in front of all system cabinets is required for Philip' safe serviceability and to meet NEC requirements.

(25.0)

Power Quality Guidelines

1. Power supplied to medical imaging equipment must be separate from power feeds to air conditioning, elevators, outdoor lighting, and other frequently switched or motorized loads. Such loads can cause waveform distortion and voltage fluctuations that can hinder high quality imaging.
2. Equipment that utilizes the facility power system to transmit control signals (especially clock systems) may interfere with medical imaging equipment, thus requiring special filtering.
3. The following devices provide a high impedance, nonlinear voltage source, which may affect image quality: static UPS systems, series filters, power conditioners, voltage regulators.

   Do not install such devices at the mains supply to medical imaging equipment without consulting Philips installation or service personnel.
4. Line impedance is the combined resistance and inductance of the electrical system and includes the impedance of the power source, the facility distribution system, and all phase conductors between the source and the imaging equipment. The minimum conductor size is based on the total line impedance and NEC requirements. Impedance calculations are to be performed by an electrical engineer).

(21.0)

PHILIPS

Project
Radiography 7300 C Pro VS
VA Medical Center Bath
Bath, NY
Room: #2

Philips Contacts
Project Manager: Arian Hallanjaku
Contact Number: (716) 262-7394
Email: arian.hallanjaku@philips.com
Drawn By: Miguel Maldonado

Project Details
Drawing Number
N-EAS250499 B
Date Drawn: 1/28/2026
Quote: Q-00526625
Order: 6600754396.010000

EN

© Koninklijke Philips Electronics N.V. 2019. All rights reserved. Reproduction in whole or in part is prohibited without prior written consent of the copyright holder.

THE DRAWINGS AND RELATED INSTRUCTIONS PROVIDED BY PHILIPS ARE ACCEPTABLE FOR USE BY THE HOSPITAL'S ARCHITECT OR ENGINEER TO USE FOR THE DEVELOPMENT OF CONSTRUCTION DOCUMENTS.

Electrical Legend

A Furnished and installed by Philips
B Furnished by customer/contractor and installed by customer/contractor
C Installed by customer/contractor
D Furnished by Philips and installed by contractor
E Existing
F Future
G Optional

	Item Number	Description	Detail Sheet
		Floor	
B	MS	8" (203mm) W x 8" (203mm) L x 4" (102mm) D floor box, mounted below finished floor with a 5" (127mm) diameter core drill to cable inlet of table.	ED1
		Ceiling	
B	CS	8" (203mm) W x 8" (203mm) L x 6" (152mm) D ceiling box, flush mounted with removable screw-type cover plate.	
		Duplexes	
B		120V, 20A dedicated duplex outlet. Coordinate exact location with local Philips Service.	
		Network Connectors	
B	N	RJ45 type Ethernet 10/100/1000 Mbit network connector. Access through customer's network to VPN device capable of connecting to the Philips Remote Service Network (RSN) Datacenter is needed. Refer to page N1 for RSN connectivity options. Locate within 10' (3048mm) of network card. Network Fiber optic and Ethernet cabling, connectors, wall boxes, patch panels, etc, are the responsibility of the purchaser. Philips assumes no responsibility for procurement, installation, or maintenance of the components.	N1

Electrical Legend

A Furnished and installed by Philips
B Furnished by customer/contractor and installed by customer/contractor
C Installed by customer/contractor
D Furnished by Philips and installed by contractor
E Existing
F Future
G Optional

	Item Number	Description	Detail Sheet
		Wall	
B	CB	480V, 3 phase 50 AMP circuit breaker with shunt trip. Run power from breaker to ME, leaving an 8' (2438mm) tail. See Sheet ED1 for power quality requirements. Location per local code or owner requirements. (Not shown on plan)	ED1
B	ST	Shunt Trip (emergency off) Large mushroom-head button on remote control station with contacts to operate feature of CB. Location per local code or owner requirements (mandatory for VA and DOD installations). (Not shown on plan)	
B	WL	Warning Light - Provide an surface or flush mounted light fixture above door to indicate when X-Ray is on. (Not shown on plan)	ED1
B	DS	Door Switch - 120V, 5A switch limited to open when door is open. Mount in upper corner on strike side of main entry door(s) (Cooper no. 1665 or equivalent), if required by local code or physicist of record. (Not shown on plan)	ED1
B	S1	Single pole general purpose ON/OFF switch with red cover. Safety switch is required between scanner unit and "WL" for Philips Service, if a warning light is used. Locate near system disconnect if possible or near "ME" wall box. (Not shown on plan)	ED1
B	ME	19 1/4" (489mm) W x 67" (1702mm) H x 4" (102mm) D flanged-edge terminal wall box with removable screw-type cover plate, surface mounted 75" (1905mm) A.F.F. to top of box. Conduits to terminate at conduit knock outs provided on top, bottom, or sides of terminal wall box. If raceway is used at top and / or bottom of terminal wall box, remove panel(s) of terminal box by drilling out pop rivets. Top and bottom panels will slide out without the need for cutting. Cutting of the box is prohibited as it will void the UL listing. Weight is approximately 125lbs per box. See ED1 sheet for wall box ordering instructions.	ED1
B	TB	Three Terminal Blocks (one "A" Block, one "E" Block, and one "D" Block) with each Block assembled on a customer/contractor provided DIN rail. All Blocks to be mounted inside "ME" Back Box. Customer/contractor to supply and install cables to and from the Terminal Blocks. (See Sheet ED1 and ED2 for details)	ED1/ ED2
B	DVS	6" (152mm) W x 6" (152mm) L x 4" (102mm) D wall box with removable screw-type cover plate, flush mounted 39" (991mm) A.F.F. to bottom of box.	
B	WAP	4" (102mm) W x 4" (102mm) L x 4" (102mm) D wall box with removable screw-type cover plate, flush mounted 10" (254mm) below ceiling/top of wall to top of box. Location shown is recommended and may be changed - verify relocation with local Philips Service.	
B	WR1	4" (102mm) W x 4" (102mm) D wall raceway, surface mounted with removable screw-type cover plate, at 4" (102mm) A.F.F. to bottom of raceway. *	ED1
B	WR2	10" (254mm) W x 4" (102mm) D wall raceway, surface mounted with removable screw-type cover plate, at 75" (1905mm) A.F.F. to bottom of raceway. *	ED1
B	ELW	Grommet opening on WR3. Exact size to be determined by local Philips Service. Location shown is recommended and may be changed - verify relocation with local Philips Service. For cables to ELW.	
B	WR3	10" (254mm) W x 4" (102mm) D wall raceway, surface mounted 6" (152mm) above finished floor with removable screw-type cover plate.	ED1

*WR1 and / or WR2 are only needed if conduit knock outs within the terminal wall box are not the sufficient size, quantity, or in the proper locations as required. As noted for "ME", the top and bottom panels can be removed by drilling out the pop-rivets and pulling the panel out. Raceway size and length can be changed as needed as long as the raceway is a minimum of 19 ¼" (489mm) in length to cover the entire opening of the removed top or bottom panel(s) and the terminal wall box remains at a mounting height of 75" (1905mm) A.F.F. Raceways cannot be deeper than the terminal wall box, they must fit securely behind the terminal wall box flanged-edge.

PHILIPS

Project
Radiography 7300 C Pro VS
VA Medical Center Bath
Bath, NY
Room: #2

Philips Contacts
Project Manager: Arian Hallanjaku
Contact Number: (716) 262-7394
Email: arian.hallanjaku@philips.com
Drawn By: Miguel Maldonado


Project Details
Drawing Number
N-EAS250499 B
Date Drawn: 1/28/2026
Quote: Q-00526625
Order: 6600754396.010000


EL

© Koninklijke Philips Electronics N.V. 2019. All rights reserved. Reproduction in whole or in part is prohibited without prior written consent of the copyright holder.

THE DRAWINGS AND RELATED INSTRUCTIONS PROVIDED BY PHILIPS ARE ACCEPTABLE FOR USE BY THE HOSPITAL'S ARCHITECT OR ENGINEER TO USE FOR THE DEVELOPMENT OF CONSTRUCTION DOCUMENTS.

© Koninklijke Philips Electronics N.V. 2019. All rights reserved. Reproduction in whole or in part is prohibited without prior written consent of the copyright holder.





Electrical Layout

1/4" = 1'-0"
Recommended Minimum Ceiling Height: 8'-9" (2667mm)
Recommended Maximum Ceiling Height: 10'-6" (3200mm)

Reported Ceiling Height: 9'-0" (2743mm)

Ceiling Heights (measured from finished floor to bottom of Unistrut) other than recommended may impact equipment functionality - see Ceiling Height Guide and consult with Philips.

All conduit runs must have Greenlee Conduit Measuring Tape (part number 435 or equivalent) fed through entire length.

Note: The use of 90 degree ells is not acceptable. Use 45 degree bends at all raceway corners. For raceway (conduit) runs, use the minimum bending radius specific to the raceway (conduit) diameter. The use of crossover tunnels at all applicable locations is required. The above mentioned recommendations will help to ensure the integrity of the cables and fiber optic runs.

PHILIPS

Project
Radiography 7300 C Pro VS
VA Medical Center Bath
Bath, NY
Room: #2


Philips Contacts
Project Manager: Arian Hallanjaku
Contact Number: (716) 262-7394
Email: arian.hallanjaku@philips.com
Drawn By: Miguel Maldonado


Project Details
Drawing Number
N-EAS250499 B
Date Drawn: 1/28/2026
Quote: Q-00526625
Order: 6600754396.010000

E1

THE DRAWINGS AND RELATED INSTRUCTIONS PROVIDED BY PHILIPS ARE ACCEPTABLE FOR USE BY THE HOSPITAL'S ARCHITECT OR ENGINEER TO USE FOR THE DEVELOPMENT OF CONSTRUCTION DOCUMENTS.

Isometric Layout
(Not to scale)





Raceway Diagram
(Not to scale)

Refer to Electrical Legend and Layout - Sheet E1

Note: The use of 90 degree ells is not acceptable. Use 45 degree bends at all raceway corners. For raceway (conduit) runs, use the minimum bending radius specific to the raceway (conduit) diameter. The use of crossover tunnels at all applicable locations is required. The above mentioned recommendations will help to ensure the integrity of the cables and fiber optic runs.

Conduit Required

General Notes
1. All conduit runs must take most direct route point to point.
2. All conduit runs must have Greenlee Conduit Measuring Tape (part number 435 or equivalent)
3. For conduit use the minimum bending radius specific to the conduit diameter. All conduit and raceway shall be sweeps.

A Conduit supplied and installed by contractor - Philips cables installed by Philips.
B Conduit supplied and installed by contractor - Philips cables installed by contractor
C Conduit and cables supplied and installed by contractor
D Conduit existing - cables supplied and installed by Philips
E Conduit existing - cables supplied by Philips, installed by contractor
F Conduit existing - cables supplied and installed by contractor
G Conduit optional - for future upgrade. Verify with Philips Sales/Service.

* Cable Type
F Fiber Optic
H High Tension Power Cables
P Power / Ground
S Signal Cables
V Video Cables

	Conduit			Conduit Quantity	Cable Type *	Minimum Conduit Size	Maximum Conduit Length	Special Requirements
	Run No.	From	To					
C	1	Power Panel	CB	1	P	Per N.E.C.	Per N.E.C.	
C	2	CB	ME	1	P	2"	50'	8' of the 50' cable to be left as a tail. Contractor to supply and install cables from "CB" to "TB" inside "ME".
C	3	CB	ST	1	P	3/4"	50'	
C	4	ME	S1	1	P	1/2"	--	Contractor to supply and install cables to and from "TB" inside "ME". Max combined cable length = 50'
C	5	S1	WL	1	P	1/2"	--	
C	6	ME	DS	1	P	1/2"	50'	Contractor to supply and install cables to and from "TB" inside "ME".
A	7	ME	ELW	1	P	2"	88'	
A	8	ME	ELW	1	S	3"	88'	
A	9	ME	MS	1	P	2"	55'	
A	10	ME	MS	1	S	2"	55'	
A	11	ME	DVS	1	P	2"	55'	
A	12	ME	DVS	1	F/S	2"	55'	
A	13	ME	CS	1	H	3"	45'	
A	14	ME	CS	1	P	3"	45'	
A	15	ME	CS	1	S	3"	45'	
A	16	ELW	MS	1	F/S	2"	98'	
A	17	ELW	DVS	1	S	1"	98'	
A	18	WAP	ELW	1	S	1"	65'	Ethernet cable. Conduit if required by local code.

Note: Optional conduit intended for future upgrade to fixed detector. Conduit is **not** required for Table or Wall Stand with SkyPlate option. Verify with Philips Sales/Service.

Refer to Electrical Layout and Legend - Sheet E1

PHILIPS

Project
Radiography 7300 C Pro VS
VA Medical Center Bath
Bath, NY
Room: #2

Philips Contacts
Project Manager: Arian Hallanjaku
Contact Number: (716) 262-7394
Email: arian.hallanjaku@philips.com
Drawn By: Miguel Maldonado

Project Details
Drawing Number
N-EAS250499 B
Date Drawn: 1/28/2026
Quote: Q-00526625
Order: 6600754396.010000

E2

© Koninklijke Philips Electronics N.V. 2019. All rights reserved. Reproduction in whole or in part is prohibited without prior written consent of the copyright holder.


THE DRAWINGS AND RELATED INSTRUCTIONS PROVIDED BY PHILIPS ARE ACCEPTABLE FOR USE BY THE HOSPITAL'S ARCHITECT OR ENGINEER TO USE FOR THE DEVELOPMENT OF CONSTRUCTION DOCUMENTS.

Detail - Cable Trough Divisions

(Not to scale)

Troughs or ducts must be separated by metal barriers into three sections.

1. High voltage (H.T.) cables to be routed separately from all other cables.
2. Power cables and ground cables can be routed together.
3. Signal cables and data cables can be routed together but must be separated from power cables.
4. Video cables to be routed separately from all other cables.
5. It is important that all cables are placed in the appropriate trough and at no given point do any cables from one division cross with cables from another. Trough separation must be continuous from the beginning to the end of the run. Utilize crossover tunnels as appropriate.
6. Trough or ducts: steel with steel dividers grounded to building ground.
7. Contractor to provide cable restraints in all troughs.




WR1 WR2 WR3

(21.0)

Detail - X-Ray On Light and Door Switch

(CXA Generator)

Not to Scale



S1 WL DS

(25.1)


Power Quality Requirements

(M-Cabinet CXA 80)

Power Output:	80 kW
Supply Configuration:	3 phase, 3 wire power, neutral and ground. Wye. or 3 phase, 3 wire power, ground. Delta.
Nominal Line Voltage:	400, 440, 460, or 480 VAC, 60 Hz
Line Voltage Variation:	± 8% steady-state
Line Voltage Balance:	2% maximum of nominal voltage between phases
Frequency Variation:	± 1% (± 0.6 Hz)
Voltage Surges:	To 110% of steady-state voltage 100 msecs. maximum duration, 6 per hour maximum
Voltage Sags:	To 90% of steady-state voltage 100 msecs. maximum duration, 6 per hour maximum
Line Impulses:	1000 VPK above phase-neutral RMS absolute maximum. No more than 1 impulse per hour to exceed 500 VPK.
Neutral-ground Voltage:	2.0 volts maximum RMS value
Neutral-ground Impulses:	No more than 1 per hour that exceeds 25 volts and 1 Mjoule
High Frequency Noise:	3.0 volts steady-state maximum. Over 3.0 volts permitted for 100 msec. maximum, 1 per hour maximum
Ground and Neutral Conductor Impedance:	0.1 Ω @ 60Hz maximum

Detail - Wall Box Mounting

(Not to scale)



Pop-rivets on top and bottom can be removed for direct integration with raceway ducts. DO NOT remove top and bottom if conduit hubs are used.


Wall Ducts are only needed if conduit knock outs within the terminal wall box are not the sufficient size, quantity, or in the proper location to meet the siting requirements.

ME TB

(19.0)

Detail - Diagnost TH Table Base - Core Drill

Not to Scale



Provide a 5" diameter core drill if the floor cannot accommodate a standard 8"W x 8"L x 4"D floor box for "MS".

MS


(13.1)

Branch Circuit and Wire Gauge Requirements

Branch Power:	112.5 kVA minimum
Circuit Breaker:	3 pole, 50 amperes (@ 480V) (Slow Blow)
Maximum Instantaneous Power:	105 kVA (800 mA @ 100 kV) (Short-term), < 5 amperes (Long-term)

Recommended conductor sizes for 1% impedence of branch conductors to circuit breaker (CB), based on 20°C copper conductors:

	400 VAC	440 VAC	460 VAC	480 VAC
#2 AWG	80 feet	96 feet	105 feet	115 feet
#1 AWG	101 feet	122 feet	134 feet	146 feet
1/0 AWG	128 feet	154 feet	168 feet	184 feet
2/0 AWG	161 feet	194 feet	212 feet	232 feet
3/0 AWG	203 feet	244 feet	267 feet	292 feet
4/0 AWG	258 feet	311 feet	340 feet	372 feet
250 MCM	303 feet	364 feet	399 feet	436 feet
300 MCM	363 feet	437 feet	478 feet	523 feet
Instantaneous Current	160 A	--	--	135 A
Maximum Phase-Phase Impedance	0.2 Ω	--	--	0.3 Ω
Maximum Load Voltage Drop	45.6 V	42.0 V	40.0 V	38.0 V
Percent Regulation at Maximum Load	11.4%	9.5%	8.7%	7.9%



Minimum copper wire size, circuit breaker (CB) to equipment: #4 AWG, maximum 50' in length, (Customer/contractor provided).

*The ground conductor for the power feeder shall be the same size as the phase conductor wires.

**Residual current device to be installed depending on local regulations.

CB

(20.0)

Wall Box Ordering Details

Distinctive Manufacturing Group Method of Business
Transactions for Philips Customers

Part# 989801220367 Philips Xray Back Box

1) Three ordering methods:
-Email: backbox@thedmgusa.com
-Phone: 260-495-1818
-Fax: 260-495-1822

2) Payment Terms - Credit Card Only
-MasterCard
-Visa
-Discover
-American Express


3) Lead Time
-3 Week Lead time

4) Freight
-All shipments will be shipped on skid
-Freight will be Pre-paid and added (PP+) to the invoice at time of shipment

ME

Detail - M-Cabinet CXA Wall Box - Cable Outlet on Rear

(Not to scale)



Important Notes:
- New replacement backboxes must be installed at the standard height.
- Existing backboxes cannot be relocated or modified; doing so will void the UL rating.
- Existing backboxes that meet standard height requirements can be re-used.

Wall Box Cover
Bottom cover punch out to be used. Top of the cover punch out should not be higher than height of the cabinet.

Wall Box
General contractor to pop out top/bottom of box as required. Provided by customer/contractor (NA only).

(24.0)

PHILIPS

Project
Radiography 7300 C Pro VS
VA Medical Center Bath
Bath, NY
Room: #2

Philips Contacts
Project Manager: Arian Hallanjaku
Contact Number: (716) 262-7394
Email: arian.hallanjaku@philips.com
Drawn By: Miguel Maldonado

Project Details
Drawing Number
N-EAS250499 B
Date Drawn: 1/28/2026
Quote: Q-00526625
Order: 6600754396.010000


ED1

© Koninklijke Philips Electronics N.V. 2019. All rights reserved. Reproduction in whole or in part is prohibited without prior written consent of the copyright holder.


THE DRAWINGS AND RELATED INSTRUCTIONS PROVIDED BY PHILIPS ARE ACCEPTABLE FOR USE BY THE HOSPITAL'S ARCHITECT OR ENGINEER TO USE FOR THE DEVELOPMENT OF CONSTRUCTION DOCUMENTS.

Detail - Screw Connection Terminal Blocks


(Not to Scale)



A Block (Quantity = 1)		
Parts	Quantity	Wire Range
1492-J50 Yellow	4	#10 - 1/0 AWG, Yellow
1492-J50 Gray	2	#10 - 1/0 AWG, Gray
1492-J16 Gray	4	#18 - 4 AWG, Gray



D Block (Quantity = 1)		
Parts	Quantity	Wire Range
1492-J3 Yellow	6	#28 - 12 AWG, Yellow
1492-J16 Gray	1	#18 - 4 AWG, Gray



E Block (Quantity = 1)		
Parts	Quantity	Wire Range
1492-J16 Gray	4	#18 - 4 AWG, Gray

TB

(25.1)

Pre-Assembled Blocks are available through Anixter:

Supplier: Anixter, Inc. www.Anixter.com




- Anixter Phone Number: 860-282-5300
- Primary Sales Contact: Joe Digiovanni 860-282-5347 joe.digiovanni@anixter.com
- Secondary Sales Contact: Lori Perras 860-205-4095 Lori.perras@anixter.com

- Part# 800170 for “A” Block (Quantity: 1)
- Part# 800173 for “D” Block (Quantity: 1)
- Part# 800174 for “E” Block (Quantity: 1)

* Customer/Contractor to provide the three blocks (one A, one D, and one E). Contractor to show the Philips Service the three blocks are available at least one week prior to system delivery and installed inside the "ME" wall box prior to system delivery date. Each block must have its parts assembled on a customer/contractor supplied DIN rail as shown in pictures above.

Screw Connection Terminal Blocks

Standard Feed-Through Blocks

	1492-J16	1492-J50	1492-J3
Dimensions are not intended to be used for manufacturing purposes. **Note**: Height dimension is measured from top of rail to top of terminal block.			

Specifications	*Feed-through terminal block*			*Feed-through terminal block*				*Feed-through terminal block*			
Certifications	LR	CSA IEC ATEX		LR	CSA IEC ATEX			LR	CSA IEC ATEX		
Voltage Rating	600V AC/DC	1000V AC/DC	690V AC/DC	1000V AC/DC	600V AC/DC	1000V AC/DC	690V AC/DC	600V AC/DC		800V AC/DC	550V AC/DC
Maximum Current	85 A	76 A	66 A	150 A		150 A	126 A	25 A	20 A	24 A	21 A
Wire Range (Rated Cross Section)	#18…4 AWG	16 mm2	16 mm2 (#16…6 AWG)	#10… 1/0 AWG	#8… 1/0 AWG	50 mm2	#10… 1/0 AWG 50 mm2	#22…12 AWG	#26…12 AWG	2.5 mm2	2.5 mm2 (#20…14 AWG)
Wire Strip Length	0.63 in. (16 mm)			0.94 in. (24 mm)				0.39 in. (10 mm)			
Recommended Tightening Torque	35.0 lb•in (4.0 N•m)			31.5 lb•in (3.6 N•m)				4.5…7.1 lb•in (0.5…0.8 N•m)			
Density	25 pcs/ft (83 pcs/m)			16 pcs/ft (54 pcs/m)				59 pcs/ft (196 pcs/m)			
Housing Temperature Range	-58…+248 °F (-50…+120 °C)			-58…+248 °F (-50…+120 °C)				-58…+248 °F (-50…+120 °C)			

PHILIPS

Project
Radiography 7300 C Pro VS
VA Medical Center Bath
Bath, NY
Room: #2

Philips Contacts
Project Manager: Arian Hallanjaku
Contact Number: (716) 262-7394
Email: arian.hallanjaku@philips.com
Drawn By: Miguel Maldonado

Project Details
Drawing Number
N-EAS250499 B
Date Drawn: 1/28/2026
Quote: Q-00526625
Order: 6600754396.010000

ED2

© Koninklijke Philips Electronics N.V. 2019. All rights reserved. Reproduction in whole or in part is prohibited without prior written consent of the copyright holder.

THE DRAWINGS AND RELATED INSTRUCTIONS PROVIDED BY PHILIPS ARE ACCEPTABLE FOR USE BY THE HOSPITAL'S ARCHITECT OR ENGINEER TO USE FOR THE DEVELOPMENT OF CONSTRUCTION DOCUMENTS.