Flow Control Valve Sizes

Turnout Location	Flow Control Valve Size	Maximum Operating Pressure	Maximum Operating Flows	Yard Pipe Drawing	Interior Pipe Centerline Elevation	Site Plan
Sanostee	6 inch	233 psi	2.27 cfs	1695-D-62561	5571.75	1695-D-62528
Newcomb	6 inch	184 psi	1.52 cfs	1695-D-62562	5570.80	1695-D-62531
Naschitti	6 inch	210 psi	1.77 cfs	1695-D-62563	5877.50	1695-D-62533
BBN9	8 inch	123 psi	3.80 cfs	1695-D-62564	6056.30	1695-D-62535
Coyote Canyon	6 inch	230 psi	1.25 cfs	1695-D-62565	6259.75	1695-D-62537
Rock Springs	6 inch	148 psi	1.71 cfs	1695-D-62566	6858.85	1695-D-62539
Window Rock[1]	12 inch	138 psi	11.51 cfs	1695-D-62567	6795.70	1695-D-62541

Notes:

1. Future phase, not for construction

Location of Lateral Turnout

Lateral Turnout	Lateral Turnout Tie-In Location		Reference Drawing	Consecutive Distribution Entry Point	
	Northing[1]	Easting[1]		Northing[1]	Easting[1]
Sanostee	1976795.6044	2462216.8104	1695-D-60728	1976728.7800	2462184.4600
Newcomb	1925402.5175	2466258.7219	1695-D-60728	1925555.7300	2466211.6000
Naschitti	1845416.9037	2472035.7886	1695-D-60728	1845407.4200	2472005.3900
BBN9[2]	1773044.4500	2479055.1100	1695-D-62535	1772870.6700	2479016.7600
Coyote Canyon	1728154.7800	2453530.3800	1695-D-62537	1728015.9400	2453444.5400
Rock Springs	1688592.1811	2415237.0131	1695-D-60119	1688625.8900	2415142.2500
Window Rock	1698957.0600	2363086.8899	1695-D-60260	1699016.9700	2362980.6500

Notes:

1. Coordinate system code NM83-WF
2. Crownpoint is now BBN9

REFERENCE DRAWINGS

1695-D-60119 ------ STA. 121300+00 TO STA. 121350+00
1695-D-60260 ------ STA. 122280+00 TO END
1695-D-60326 ------ Sectionalizing Valve Installation
1695-D-60328 ------ Crownpoint Turnout
1695-D-60728 ------ Typical Turnout
1695-D-62535 ------ BBN9 Site Plan
1695-D-62537 ------ Coyote Canyon Site Plan
1695-D-62556 ------ Thrust Blocks and Misc. Site Concrete
1695-D-62590 ------ Galvanic Anode Cathodic Protection

GENERAL NOTES

1. Provide nuts, bolts and gaskets suitable for cold water service.
2. All flanges shall be AWWA Class F as shown unless otherwise noted.
3. Additional fittings, flanges, or welded joints added by the contractor to facilitate installation of the piping are subject to Government approval.
4. Set grooved coupling gap to half of manufacturer's maximum allowable pipe end separation.
5. Thead-O-Let type fittings may be substituted for the 3000 lb. steel threaded couplings and threaded half-couplings. Weld Thread-O-Let fittings to pipe as recommended by Thread-O-Let manufacturer.
6. Welding symbols apply to the joints of all members of similar identification.
7. Hydrostatic test pressure for the turnout building steel pipe: 1.5 times the maximum operating pressure, see table.
8. Dimensions marked with an asterisk (*) to be field verified.
9. All valves and equipment to be rated for a minimum 300 psi working pressure.
10. Provide control valve flange supports to match control valve flanges, round or flat bottomed.
11. All elbows shall be long radius unless otherwise noted.
12. At locations where fittings have a greater wall thickness than steel piping, machine to match lighter pipe wall and taper excess thickness internally to form transition zone.
13. All fillet welds shall be returned.

BUREAU OF RECLAMATION

ALWAYS THINK **SAFETY**

U.S. DEPARTMENT OF THE INTERIOR
BUREAU OF RECLAMATION
NAVAJO-GALLUP WATER SUPPLY PROJECT, NM
NEW MEXICO

SAN JUAN LATERAL

TURNOUT BUILDINGS

REV NO	STA.	DATE	BY	DESCRIPTION
2	D	2026-11-04	JEREMY HAMMOND, P.E.	UPDATED NEWCOMB FLOW CONTROL VALVE SIZE
1	STA. D	2026-09-30	JEREMY HAMMOND, P.E.	ADDED NOTE TO FLOW CONTROL VALVE SIZES TABLE

CHRISTOPHER BELLECI
DESIGNED
CHRISTOPHER BELLECI
DRAWN
KYLE TAYLOR
CHECKED
JEREMY HAMMOND, P.E.
TECH. APPR. JEREMY HAMMOND, P.E.
CODY YOUNG, P.E.
APPROVED CODY YOUNG, P.E.
Peer Reviewer - Supervisor, Mechanical Piping and Systems

DENVER, CO 2026-06-19

COVERSHEET

DETAILS

1695-D-62558