PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	A.1

U. S. DEPARTMENT OF TRANSPORTATION
FEDERAL HIGHWAY ADMINISTRATION

ALASKA KEY MAP

TYPE OF CONSTRUCTION:

Clearing, excavation, grading, roadway aggregate, bridge construction, boardwalk construction, and drainage

SPECIFICATION:

Standard Specifications for Construction of Roads and Bridges on Federal Highway Projects, FP-24

PLANS PREPARED BY

DJ&A AND PND ENGINEERS, INC.

FOR

U.S. DEPARTMENT OF TRANSPORTATION
FEDERAL HIGHWAY ADMINISTRATION
WESTERN FEDERAL LANDS HIGHWAY DIVISION
VANCOUVER, WASHINGTON

PROJECT MANAGER
T. YEOMAN

PLANS FOR PROPOSED PROJECT

AK FLAP ANCHORAGE 2021(1)

FAR NORTH BICENTENNIAL PARK ENHANCEMENTS

FAR NORTH BICENTENNIAL PARK
MUNICIPALITY OF ANCHORAGE
ALASKA

BASE LENGTH: 0.16 MILES
OPTION Z LENGTH: 0.04 MILES

Scale in miles
0.5 0 0.5 1 1.5

SECTION INDEX

A. GENERAL INFORMATION
B. SUMMARY OF QUANTITIES
C. TYPICAL SECTIONS
D. PLAN-PROFILE
E. SOIL EROSION AND SEDIMENT CONTROL
F. LANDSCAPING
G. TEMPORARY TRAFFIC CONTROL
H. DRAINAGE
S. BRIDGE
T. NORTH BOARDWALK
U. SOUTH BOARDWALK

See Sheet A.2 for complete Sheet Index.

PROJECT LOCATIONS
See Sheet A.4

OPTION Z LOCATION
See Sheet A.4

APPROVED:

BRENT LEE COE Digitally signed by BRENT LEE COE
Date: 2026.10.08 08:06:27 -07'00'

Chief of Engineering, Western Federal Lands Highway Division — *DATE*

c:\djfa-nwwork\djfa-prod\d02966521\100% A sheets.dgn [Title Sheet]
8 September 2026 12:12 PM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	A.2

SHEET INDEX

FIRM		
		A. GENERAL INFORMATION
DJ&A	A.1	TITLE SHEET
DJ&A	A.2	SHEET INDEX
DJ&A	A.3	PLAN SYMBOLS AND ABBREVIATIONS
DJ&A	A.4	VICINITY MAP
		B. SUMMARY OF QUANTITIES
BOTH	B.1	SCHEDULE A
DJ&A	B.2	OPTION Z
		C. TYPICAL SECTIONS
PND	C.1	BRIDGE APPROACHES TYPICAL SECTION
DJ&A	C.2	BOARDWALK APPROACHES TYPICAL SECTIONS
		D. PLAN-PROFILE
PND	D.1	SURVEY CONTROL
PND	D.2	TABULATION OF BRIDGE SITE QUANTITIES
PND	D.3	BRIDGE PLAN AND PROFILE
DJ&A	D.4	TABULATION OF BOARDWALK SITE QUANTITIES
DJ&A	D.5	NORTH BOARDWALK PLAN AND PROFILE
DJ&A	D.6	SOUTH BOARDWALK PLAN AND PROFILE
		E. SOIL EROSION AND SEDIMENT CONTROL
PND	E.1	TABULATION OF BRIDGE SITE QUANTITIES
PND	E.2	BRIDGE SITE EROSION CONTROL PLAN
DJ&A	E.3	TABULATION OF BOARDWALK SITE QUANTITIES
DJ&A	E.4	NORTH BOARDWALK EROSION CONTROL PLAN
DJ&A	E.5	SOUTH BOARDWALK EROSION CONTROL PLAN
DJ&A	E.6-7	STANDARD DETAILS
		F. LANDSCAPING
PND	F.1	TABULATION OF BRIDGE SITE QUANTITIES
PND	F.2	BRIDGE SITE LANDSCAPING PLAN
DJ&A	F.3	TABULATION OF BOARDWALK SITE QUANTITIES
DJ&A	F.4	NORTH BOARDWALK LANDSCAPING PLAN
DJ&A	F.5	SOUTH BOARDWALK LANDSCAPING PLAN

NOTE:

1. *Plans prepared by multiple engineering firms. Firm responsible for each sheet indicated above.*

DJ&A

PND ENGINEERS, INC.

SHEET INDEX (CONTINUED)

FIRM		
		G. TEMPORARY TRAFFIC CONTROL
PND	G.1	TABULATION OF BRIDGE SITE QUANTITIES
PND	G.2	BRIDGE SITE TEMPORARY TRAFFIC CONTROL PLAN
DJ&A	G.3	TABULATION OF BOARDWALK SITE QUANTITIES
DJ&A	G.4	BOARDWALK SITE TEMPORARY TRAFFIC CONTROL
PND	G.5	SPECIAL SIGN PANEL DETAILS
DJ&A	G.6	NOTICE BOARD DETAILS
		H. DRAINAGE
DJ&A	H.1	TABULATION OF DRAINAGE QUANTITIES
DJ&A	H.2-4	STANDARD DETAILS
		S. BRIDGE
PND	S.1	NORTH FORK CAMPBELL CREEK BRIDGE
PND	S.2	BRIDGE GENERAL NOTES
PND	S.3	ABUTMENT DETAILS
PND	S.4	BAR LIST
PND	S.5	TYPICAL BRIDGE SECTION
PND	S.6	APPROACH RAIL DETAILS
		T. NORTH BOARDWALK
DJ&A	T.1	NORTH BOARDWALK GENERAL LAYOUT
DJ&A	T.2	TABULATION OF NORTH BOARDWALK QUANTITIES
DJ&A	T.3	BOARDWALK GENERAL NOTES
DJ&A	T.4	NORTH BOARDWALK FOUNDATION PLAN
DJ&A	T.5	NORTH BOARDWALK APPROACH SOIL RAMP PLAN AND ELEVATION
DJ&A	T.6	APPROACH SOIL RAMP DETAILS
DJ&A	T.7	NORTH BOARDWALK ABUTMENT PLAN AND ELEVATION
DJ&A	T.8	NORTH BOARDWALK PIER PLAN AND ELEVATION
DJ&A	T.9	BOARDWALK SUBSTRUCTURE DETAILS
DJ&A	T.10	NORTH BOARDWALK FRAMING PLAN
DJ&A	T.11	NORTH BOARDWALK DECKING PLAN
DJ&A	T.12	BOARDWALK SUPERSTRUCTURE DETAILS
FIRM		**U. SOUTH BOARDWALK (OPTION Z)**
DJ&A	U.1	SOUTH BOARDWALK GENERAL LAYOUT
DJ&A	U.2	TABULATION OF SOUTH BOARDWALK QUANTITIES
DJ&A	U.3	SOUTH BOARDWALK FOUNDATION PLAN
DJ&A	U.4	SOUTH BOARDWALK APPROACH SOIL RAMP PLAN AND ELEVATION
DJ&A	U.5	SOUTH BOARDWALK ABUTMENT PLAN AND ELEVATION
DJ&A	U.6	SOUTH BOARDWALK PIER PLAN AND ELEVATION
DJ&A	U.7	SOUTH BOARDWALK FRAMING PLAN
DJ&A	U.8	SOUTH BOARDWALK DECKING PLAN

STATE OF ALASKA
49TH
AMMON SCOTT GROESBECK
No. CE170425
REGISTERED PROFESSIONAL ENGINEER
9/21/2026

ENGINEERS OF RECORD:

1. *Ammon Groesbeck*
   License # 170425
   Firm - DJ&A

2. *Alexandra Jefferies*
   License # 106241
   Firm - PND

3. *Bryan Hudson*
   License # 12004
   Firm - PND

c:\dja-pwwork\dja-prod\d02966521\100% A sheets.dgn [Sheet Index]
9 September 2026 6:15 PM

SHEET INDEX

Δ	total central angle
Δc	curve central angle
Ø	diameter
θs	spiral central angle
abut.	abutment
ADT	average daily traffic
AH	ahead
appr.	approach
BK	back
b.f.	back face
BM	bench mark
BP	balance point
br.	bridge
brg.	bearing
btwn	between
cc or c. to c.	center to center
℄	centerline
clr.	clear
CMP	corrugated metal pipe
col.	column
conc.	concrete
conn.	connection
constr. jt.	construction joint
cont.	continuous
CS	point of curve to spiral
ctrs.	centers
CUFT	cubic foot (feet)
culv.	culvert
CUYD	cubic yard(s)
D	diameter
DHV	design hourly volume
dia.	diameter
diaph.	diaphragm
dist.	distance
drwg(s).	drawing(s)
E	east
e	superelevation rate
e.f.	each face
El. 94.16	elevation in feet
elev.	elevation
emb.	embankment
EOP	edge of pavement
EQ or eq.	equation
EW	edge of water
exc.	excavation
exp. jt.	expansion joint
f.f.	front face
fin.	finish
flg.	flange
ftg.	footing
ga.	gage (gauge)
galv.	galvanized
ID	inside diameter
IE	invert elevation
jt.	joint
KSI	thousand pounds per square inch
L	length of curve
lat.	latitude
LNFT	linear foot (feet)
long.	longitudinal
LPSM	lump sum
Ls	length of spiral
lt. or LT	left
LW	low water

M.L.	main line
M.P.	mile post
matl.	material
max.	maximum
MGAL	thousand gallon
min.	minimum
mon.	monument
N	north
NC	normal crown
o.c.	on center
o. to o.	out to out
OD	outside diameter
OG	original ground
OHWM	ordinary high water mark
PC	point of curve
PCC	point of compound curve
PCS	point of curve to spiral
PI	point of intersection
pl.	plate
POC	point on curve
POS	point on spiral
POT	point on tangent
PS	point of tangent to spiral
PSF	pounds per square foot
PSI	pounds per square inch
PSC	point of spiral to curve
PST	point of spiral to tangent
PT	point of tangent
pvmt.	pavement
R	radius
R.	range
R/W	right-of-way
rdwy.	roadway
reinf.	reinforcement
reqd.	required
rt. or RT	right
rte.	route
S	south
SADT	seasonal average daily traffic
SC	point of spiral to curve
sect.	section
shldr.	shoulder
SLRY	slurry unit
spa.	spacing, spaces or spaced
SQFT	square foot
SQYD	square yard
SRS	point of spiral to reverse spiral
SS	point of spiral to spiral (no curve)
ST	point of spiral to tangent
STA, Sta.	station
std.	standard
stgr.	stringer
stiff.	stiffener
struc.	structural
STS	point of spiral to tangent spiral
T	tangent distance
T.	township
TBM	temporary bench mark
thd.	thread
TS	point of tangent to spiral
Ts	tangent distance (spiraled curve)
typ.	typical
V	design speed (velocity)
vph	vehicles per hour
VPI	vertical point of intersection
W	west

NOTE:

1. Other symbols used in the plans will be shown in a legend on the appropriate plan sheet.

National Boundary
State Boundary
County Boundary
City Boundary
Township or Range Line
Section Line
Section Corner (Found, Projected)
¼ Section Line
¼ Section Corner (Found, Projected)
1/16 Section Line
1/16 Section Corner (Found, Projected)
Property Line
Parcel Number
National Park Boundary
National Forest Boundary
National Wildlife Refuge Boundary
BLM Lands Boundary
Indian Reservation Boundary
Existing Roadway (Paved, Gravel)
Railroad
Trail
Fiber Roll
Silt Fence
Sandbag
Intermittent Drainage or Small Creek
Large Creek or River
Lake, Pond or Reservoir; Marshland
Spring or Seep
Treeline; Individual Trees
Material Source; Bore Hole; Test Pit
Spot Elevation; Coordinate Grid Tick
Above Ground Tank; Underground Tank
Boulder; Well; Antenna; Grave
Cooking Grate; Garbage Can; Picnic Table
Flagpole; Fire Hydrant
Gas & Water Meter; Gas & Water Valve
Control Point (Terrestrial and GPS)



		EXISTING / PROPOSED
North Arrow		
Slope Stake Limits	Top of Cut / Toe of Fill	
Construction Limits	- no symbol -	
Bottom of Ditch		
Fence		
Gate with Fence		
Cattleguard		
Guardrail		
Concrete Barrier and Guard Wall		
Retaining Wall		wall face
Signs (single, double post; portable)		
Delineators		
Pipe Culvert (arrow shows flow)		
Pipe Culvert with End Section		
Pipe Culvert with Headwall		
Pipe Culvert with Drop Inlet	DI	DI
Box Culvert		
Underdrain	UD	UD
Overhead/Above Ground Utilities	P	P
Underground Utilities	W	W
Poles (Power, Telephone, Joint Use, Light, Support w/Anchor)		
Miscellaneous Utility Features	TP	TP
Building		
Right-of-Way Line	r/w	R/W
Permanent Easement	P/E	P/E
Construction Easement	- no symbol -	TCE
Riprap		

FM = force main, FO = fiber optic, G = gas, IRR = irrigation, O = oil, P = power, SA = sanitary sewer, SD = storm drain, SS = storm sewer, STEAM = steam, T = telephone, TV = CATV, W = water

EM = electric meter, TP = telephone pedestal, TV = CATV pedestal, UP = transformer or junction box, WF = water fountain

Section A-A

NO SCALE

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	A.3

U.S. DEPARTMENT OF TRANSPORTATION, FHWA
OFFICE OF FEDERAL LANDS HIGHWAY

PLAN SYMBOLS AND ABBREVIATIONS

WFLHD DETAIL W101-1
SPECIFICATION FP-24
APPROVED FOR USE 6/2022

30 June 2026 9:58 AM c:\fja-pwwork\fja-prod\0026719?\W101-1.dgn [Det W101-1]

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	A.4

FAR NORTH BICENTENNIAL PARK

BEGIN PROJECT
"NORTH 01" 30+00

BEGIN OPTION Z
"SOUTH 01" 40+00

END OPTION Z
"SOUTH 01" 42+03

Tank trail

SUSPEND PROJECT
"NORTH 01" 33+76

North Fork Campbell Creek

RESUME PROJECT
"BRIDGE 01" 100+00

END PROJECT
"BRIDGE 01" 105+00

Staging area

Property Line

Section Line

To Basher Drive

North Gasline trail

North Gasline trail

To Klutina Drive

Staging area

Stuckagain Creek

Staging area at intersection of Tank Trail and North Gasline Trail

JOINT BASE ELMENDORF-RICHARDSON

STATE OF ALASKA
49TH
AMMON SCOTT GROESBECK
No. CE170425
REGISTERED PROFESSIONAL ENGINEER
9/21/2026

Scale in feet
300 0 300 600 900

VICINITY MAP

c:\dja-pwwork\dja-prod\d0296652\100% A sheets.dgn [Vicinity Map]
14 July 2026 3:28 PM

© 2026 Microsoft Corporation Earthstar Geographics SIO © Mapbox

SUMMARY OF QUANTITIES - Schedule A

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	B.1

AMEND	LINE ITEM NO.	PAY ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT	Sheet and Description							ALLOW-ANCE	Estimated Quantities	Remarks and/or Determination of Estimated Quantity
					D	E	F	G	H	S	T			
					Plan-Profile	Erosion Control	Landscaping Plans	Temporary Traffic Control	Drainage	Trail Bridge	North Boardwalk		BID SCHEDULE	
	A0020	15101-0000	MOBILIZATION	LPSM									ALL	
	A0040	15201-0000	CONSTRUCTION SURVEY AND STAKING	LPSM									ALL	
	A0060	15301-0010	CONTRACTOR QUALITY CONTROL AND ASSURANCE	LPSM									ALL	
	A0080	15401-0000	CONTRACTOR TESTING	LPSM									ALL	
	A0100	15501-0000	CONSTRUCTION SCHEDULE	LPSM									ALL	
	A0120	15701-0000	SOIL EROSION CONTROL	LPSM									ALL	
	A0140	20101-0000	CLEARING AND GRUBBING	ACRE	0.38							0.02	0.4	
	A0160	20301-0400	REMOVAL OF BRIDGE	EACH	1								1	
	A0180	20401-0000	ROADWAY EXCAVATION	CUYD	526							54	580	
	A0200	20410-0000	SELECT BORROW	CUYD	1113					8		379	1500	
	A0220	20701-1000	SEPARATION GEOTEXTILE, WOVEN,(CLASS 2, TYPE B)	SQYD	1204							121	1325	
	A0240	20803-0000	STRUCTURAL BACKFILL	CUYD							31	4	35	
	A0260	25301-0000	GABIONS	SQFT							90	10	100	
	A0280	30202-2100	ROADWAY AGGREGATE, METHOD 2, SURFACE COURSE	TON	156							9	165	
	A0300	55201-0800	STRUCTURAL CONCRETE, CLASS D (AE)	CUYD						10			10	
	A0320	55401-2000	REINFORCING STEEL, EPOXY-COATED	LB						1850			1850	
	A0340	55504-0000	PREFABRICATED STEEL BRIDGE	LPSM									ALL	
	A0360	55601-1300	BRIDGE RAILING, TIMBER,(BOARDWALK)	LNFT							122	8	130	
	A0380	55601-1300	BRIDGE RAILING, TIMBER,(BRIDGE)	LNFT						100			100	
	A0400	55701-2000	STRUCTURAL TIMBER AND LUMBER, TREATED	MFBM							2.4	0.1	2.5	
	A0420	55703-2000	STRUCTURAL TIMBER AND LUMBER, TREATED, DECKING	SQYD							56	4	60	
	A0440	57302-0000	HELICAL PILE	EACH							14		14	
	A0460	60201-0600	18-INCH PIPE CULVERT	LNFT					26			4	30	
	A0500	62201-2370	VACUUM TRUCK	HOUR									8	
	A0520	62301-0000	GENERAL LABOR	HOUR									8	
	A0540	62502-0000	TURF ESTABLISHMENT	SQYD			2568					132	2700	
	A0560	63501-3500	TEMPORARY TRAFFIC CONTROL, PUBLIC INFORMATION PROGRAM	LPSM									ALL	
	A0580	63502-0600	TEMPORARY TRAFFIC CONTROL, BARRICADE TYPE 3	EACH				7					7	
	A0600	63504-1000	TEMPORARY TRAFFIC CONTROL, CONSTRUCTION SIGN	SQFT				60					60	

STATE OF ALASKA
49TH
AMMON SCOTT GROESBECK
No. CE170425
REGISTERED PROFESSIONAL ENGINEER
9/21/2026

Milestone: Signoff; Date Completed: 09/10/2026

10-Sep-2026 5:31 PM https://djanda1.sharepoint.com/sites/ActiveProjects/Shared Documents/7233.19 WFL AK FLAP Bicentennial Park/Engineering/Docs/Cost Estimates/[mw-summary-quantities202509.xlsm]Sheet

SUMMARY OF QUANTITIES - Option Z

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	B.2

AMEND	LINE ITEM NO.	PAY ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT	Sheet and Description D Plan-Profile	E Erosion Control	F Landscaping Plans	G Temporary Traffic Control	H Drainage	U South Boardwalk	ALLOW-ANCE	Estimated Quantities BID SCHEDULE	Remarks and/or Determination of Estimated Quantity
	Z0020	15101-0000	MOBILIZATION	LPSM								ALL	
	Z0040	15201-0000	CONSTRUCTION SURVEY AND STAKING	LPSM								ALL	
	Z0060	15301-0010	CONTRACTOR QUALITY CONTROL AND ASSURANCE	LPSM								ALL	
	Z0080	15401-0000	CONTRACTOR TESTING	LPSM								ALL	
	Z0100	15501-0000	CONSTRUCTION SCHEDULE	LPSM								ALL	
	Z0120	15701-0000	SOIL EROSION CONTROL	LPSM								ALL	
	Z0140	20101-0000	CLEARING AND GRUBBING	ACRE	0.11							0.11	
	Z0160	20401-0000	ROADWAY EXCAVATION	CUYD	192						18	210	
	Z0180	20410-0000	SELECT BORROW	CUYD	262						28	290	
	Z0200	20701-1000	SEPARATION GEOTEXTILE, WOVEN,(CLASS 2, TYPE B)	SQYD	485						50	535	
	Z0220	20803-0000	STRUCTURAL BACKFILL	CUYD						22	3	25	
	Z0240	25301-0000	GABIONS	SQFT						63	37	100	
	Z0260	30202-2100	ROADWAY AGGREGATE, METHOD 2, SURFACE COURSE	TON	16						4	20	
	Z0280	55601-1300	BRIDGE RAILING, TIMBER,(BOARDWALK)	LNFT						102	8	110	
	Z0300	55701-2000	STRUCTURAL TIMBER AND LUMBER, TREATED	MFBM						1.2	0.1	1.3	
	Z0320	55703-2000	STRUCTURAL TIMBER AND LUMBER, TREATED, DECKING	SQYD						25	5	30	
	Z0340	57302-0000	HELICAL PILE	EACH						12		12	
	Z0360	62201-2370	VACUUM TRUCK	HOUR								8	
	Z0380	62301-0000	GENERAL LABOR	HOUR								8	
	Z0400	62502-0000	TURF ESTABLISHMENT	SQYD			636				64	700	
	Z0420	63502-0600	TEMPORARY TRAFFIC CONTROL, BARRICADE TYPE 3	EACH				3				3	
	Z0440	63504-1000	TEMPORARY TRAFFIC CONTROL, CONSTRUCTION SIGN	SQFT				30				30	

Milestone: 100% Design; Date Completed: 09/10/2026

22-Jul-2026 11:44 AM https://djanda1.sharepoint.com/sites/ActiveProjects/Shared Documents/7233.19 WFL AK FLAP Bicentennial Park/Engineering/Docs/Cost Estimates/[mw-summary-quantities202509.xlsm]Sheet (2)

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	C.1



"BRIDGE 01"
100+93.00 TO 102+12.07 [2]
102+92.07 TO 104+50.00

FOOTNOTE:

[1] The slope behind all bridge rails is 1V:2H. Transition the slope over 10 feet prior to or after the rail.

[2] See sheet S.5 for Bridge typical section.

[3] 5' except where shown on plans.

[4] Transition slope to match bridge slope. Transition over 15 feet prior to or after the bridge.

STATE OF ALASKA
49 TH
Alexandra Jefferies
Alexandra Jefferies
CE-106241
9/21/2026
REGISTERED PROFESSIONAL ENGINEER

BRIDGE APPROACHES TYPICAL SECTION

J:\2025\251087 Far North Bicentennial Park Enhancements\Drawings\aka-anchorage2021-2_pln_typ.dgn [Typical Section]
11 September 2026 6:23 AM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	C.2



"NORTH 01"

30+00.00 to 31+45.06
32+06.06 to 33+75.91



"SOUTH 01"

40+00.00 to 41+00.49
41+51.49 to 42+02.79

BOARDWALK APPROACHES TYPICAL SECTIONS

c:\djs-pwwork\djs-prod\d0260488\aka-anchorage2021-1_TYP.dgn [Typical Section]
10 September 2026 3:53 PM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	D.1

PROJECT : AK FLAP ANCHORAGE 2021(1)
DATE OF FIELD WORK : 08/13/25 - 08/14/25, 09/09/25
DATE OF FINAL ADJUSTMENT : 09/09/25

COORDINATE SYSTEM : ANC BOWL 2000
VERTICAL DATUM : MOA 72
EPOCH DATE : N/A

POINT NUMBER	STATE PLANE COORDINATES			GEO COORDINATES				DESCRIPTION
	NORTH	EAST	ORTHOMETRIC ELEVATION	LATITUDE	LONGITUDE	ELLIPSOID HEIGHT	COMBINED FACTOR	
3000	326465.239	367548.222	235.603	N 61° 10' 45.771"	W 149° 46' 35.019"	259.776	0.999889382	FBD [SSDR, NGS HC, DOT GPS OPTICS 1993]
3008	323963.942	377782.299	437.253	N 61° 10' 20.752"	W 149° 43' 6.521"	462.804	0.999879672	CP20107 [2.25" AL CAP, FHA WFLHD]
3009	323258.744	377789.374	435.779	N 61° 10' 13.807"	W 149° 43' 6.438"	461.326	0.999879743	CP20108 [2.25" AL CAP, FHA WFLHD]
3010	321617.645	377795.950	439.887	N 61° 9' 57.647"	W 149° 43' 6.448"	465.498	0.999879543	CP20109 [2.25" AL CAP, FHA WFLHD]
3011	322055.185	377786.766	436.507	N 61° 10' 1.956"	W 149° 43' 6.597"	462.111	0.999879705	CP20110 [2.25" AL CAP, FHA WFLHD]
3012	319471.174	377810.284	559.490	N 61° 9' 36.511"	W 149° 43' 6.345"	585.184	0.999873819	CP20211 [2.25" AL CAP, FHA WFLHD]
3013	319201.747	377812.373	556.115	N 61° 9' 33.858"	W 149° 43' 6.326"	581.79	0.999873981	CP20112 [2.25" AL CAP, FHA WFLHD]

NOTE:

1. *Anchorage (ANC) Bowl 2000 is a local surface grid coordinate system expressed in U.S. Survey Feet developed by the Alaska Department of Transportation and Public Facilities (ADOT&PF), as a modification to Alaska State Plane Zone 4 (ASP Z4), NAD83(92). Anchorage Bowl 2000 preserves a State Plane Bearing Basis while providing ground distances at the project location.*

2. *To convert from the local ANC Bowl 2000 ground coordinates to NAD83 State Plane Alaska Zone 4 perform the following:*
   ADD +2296868.6878' N, +1312517.4904' E to ANC Bowl 2000 local ground coordinates.
   SCALE the resultant using 0.9998910192

   To convert from NAD83 State Plane Alaska Zone 4 to local ANC Bowl 2000 ground coordinates perform the following:
   SCALE the State Plane Coordinates Using 1.000108993
   SUBTRACT +2296868.6878' N, +1312517.4904' E from the resultant.

3. *All elevations for the project are based upon the MOA 72 vertical control network. The Datum is Mean Sea Level (MSL) Greater Anchorage Area Borough (GAAB) 1972 adjustment, and the unit of measure is U.S. Survey feet.*

STATE OF ALASKA
49 TH
Alexandra Jefferies
Alexandra Jefferies
CE-106241
9/21/2026
REGISTERED PROFESSIONAL ENGINEER

SURVEY CONTROL

J:\2025\251087 Far North Bicentennial Park Enhancements\Drawings\[D.1 Survey Control Sheet.xlsx]Sheet
3-Sep-2026 6:47 AM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	D.2

EARTHWORK SUMMARY TABLE

LOCATION	RAW DATA				CUT						FILL				TOTALS				
	Volumes_Cut (Total Cut volume excluding topsoil)	**Volumes_Fill** (Total Fill volume including Topsoil)	**Exist Topsoil (removed)** (existing topsoils in cut)	**Exist Topsoil (removed and replaced)** (existing topsoil in fill)	**Item 20401-0000 ROADWAY EXCAVATION**	(+) Additional Excavation for info only	(-) Topsoil Stripped from Cuts for info only	(-) Estimate of Unsuitable Material for info only	Total Unadjusted Excavation Available for Fill for info only	Total Adjusted Available for Embankment (adjusted based on shrink/swell factor) for info only	Embankment for info only	(+) Additional Backfill Needed for info only	(+) Topsoil stripped from embankment foundation areas for info only	Total Embankment Needed for info only	Total Fill needed for info only	(-) Excess Available Fill (Total Adjusted Available For Embankment minus Total Embankment Needed) for info only	(=) **Item 20410-0000 SELECT BORROW**	Waste for info only	
UNITS	CUYD	CUYD	CUYD	CUYD	CUYD	CUYD	CUYD	CUYD	CUYD	CUYD	CUYD	CUYD	CUYD	CUYD	CUYD	CUYD	CUYD	CUYD in situ	CUYD Compacted
"BRIDGE 01" 100+93 to 102+12.07	7	416			7		-	-	7	7	416		-	416	409	0	409	0	0
"BRIDGE 01" 102+92.07 to 104+50	2	2			2		-	-	2	2	2		-	2	0	0	0	0	0
TOTALS	9	418	0	0	**9**	0	0	0	9	9	418	0	0	418	409	0	**409**	0	0

NOTE:

1. All volumes are in-place cubic yards (i.e. in situ or compacted in place).

SCHEDULE A - BRIDGE SITE QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	LOCATION	REMARKS
			BASE "BRIDGE 01"	
20101-0000	CLEARING AND GRUBBING	ACRE	0.16	
20301-0400	REMOVAL OF BRIDGE	EACH	1	
20401-0000	ROADWAY EXCAVATION	CUYD	9	
20410-0000	SELECT BORROW	CUYD	409	
20701-1000	SEPARATION GEOTEXTILE, WOVEN, (CLASS 2, TYPE B)	SQYD	719	
30202-2100	ROADWAY AGGREGATE, METHOD 2, SURFACE COURSE	TON	94	Based on 1.97 TONS/CUYD

STATE OF ALASKA
49 TH
Alexandra Jefferies
Alexandra Jefferies
CE-106241
9/21/2026
REGISTERED PROFESSIONAL ENGINEER

TABULATION OF BRIDGE SITE QUANTITIES

J:\2025\251087 Far North Bicentennial Park Enhancements\Drawings\aka-anchorage2021-2_plh_pp.dgn [Plan Quantities]
11 September 2026 12:03 PM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	D.3

100 101 102 103 104 105

N

Overhead power, see SCR section 107.02

RESUME PROJECT
"BRIDGE 01" 100+00.00
N = 323318.982
E = 377775.516

N01°26'56"W

"Bridge 01"
Line to be constructed

PI 101+11.37
Δ = 20°14'55" (LT)
R = 100.00'
T = 17.86'
L = 35.34'
e = 2.0%

North Gasline Bridge
Removal of bridge

4" Gas
(relocate by others)

N21°41'51"W

N00°11'03"W

Construction limit
Slope stake limits

PI 103+73.79
Δ = 07°15'58" (LT)
R = 250.00'
T = 15.87'
L = 31.70'
e = -2.0%

N07°48'19"E

END PROJECT
"BRIDGE 01" 105+00.00
N = 323814.492
E = 377758.022

N00°32'20"E

PC 100+93.5
PT 101+28.85
PC 101+49.0
PT 101+87.45
PC 103+11.72
PT 103+46.58
PC 103+57.91
PT 103+89.62

Campbell Creek

12" High pressure gas
(existing)
Preserve and protect
in place.

PI 103+29.17
Δ = 07°59'21" (RT)
R = 250.00'
T = 17.46'
L = 34.86'
e = 2.0%

Construction Limit
STA 101+17.84
OFF 11.33'

Construction Limit
STA 100+93.03
OFF 7.50'

PI 101+68.90
Δ = 21°30'48" (RT)
R = 100.00'
T = 19.00'
L = 37.55'
e = -2.0%

North Fork

BEGIN CONSTRUCTION
"BRIDGE 01" 100+93.00
N = 323411.953
E = 377773.165

END CONSTRUCTION
"BRIDGE 01" 104+50.00
N = 323765.345
E = 377757.559

gas
3009

450
440
430
420

435.99
K = 24
30' VC
+1.629%
+2.895%
101+86
438.43
+0.484%
103+18
439.07
-3.790%
K = 9
30' VC
-0.543%
101+13
436.31
SSD = 151.45'
K = 12.44
30' VC
102+12.07
Install prefabricated steel bridge.
See Section S for details
102+92.07
SSD = 91.97'
K = 7.02
30' VC
104+09
435.63

Profile Grade
Existing Ground

100+00 101+00 102+00 103+00 104+00

STATE OF ALASKA
49 TH
Alexandra Jefferies
Alexandra Jefferies
CE-106241
9/21/2026
REGISTERED PROFESSIONAL ENGINEER

J:\2025\251087 Far North Bicentennial Park Enhancements\Drawings\aka-anchorage2021-2_pln_pp.dgn [ALL_MAIN_BRIDGE1 - Plan 1-2 [Sheet]]
18 September 2026 3:43 PM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	D.4

EARTHWORK SUMMARY TABLE

	RAW DATA				ASSUMPTIONS					CUT						FILL				TOTALS				
LOCATION	**Volumes_Cut** (Total Cut volume excluding topsoil)	**Volumes_Fill** (Total Fill volume including Topsoil)	**Exist Topsoil (removed)** (existing topsoils in cut)	**Exist Topsoil (removed and replaced)** (existing topsoil in fill)	Shrink (-) / Swell (+) Factor	Specific areas with unsuitable material	Assumed percent unsuitable (0%=Suitable to 100%=Unsuitable)	Unsuitable material based on Volumes_Cut and Assumed Percent Unsuitable	Assumed Topsoil Removal / Conserved Depth	**Item 20401-0000 ROADWAY EXCAVATION**	(+) Additional Excavation for info only	(-) Topsoil Stripped from Cuts for info only	(-) Estimate of Unsuitable Material for info only	Total Unadjusted Excavation Available for Fill for info only	Total Adjusted Available for Embankment (adjusted based on shrink/swell factor) for info only	Embankment for info only	(+) Additional Backfill Needed for info only	(+) Topsoil stripped from embankment foundation areas for info only	Total Embankment Needed for info only	Total Fill needed for info only	(-) Excess Available Fill (Total Adjusted Available For Embankment minus Total Embankment Needed) for info only	(=) **Item 20410-0000 SELECT BORROW**	Waste for info only	
UNITS	CUYD	CUYD	CUYD	CUYD	%	CUYD	%	CUYD	INCH	CUYD	CUYD	CUYD	CUYD	CUYD	CUYD	CUYD	CUYD	CUYD	CUYD	CUYD	CUYD	CUYD	CUYD in situ	CUYD Compacted
"NORTH 01" 30+00 to 33+75.91	513	704	-	-		-	100%	513	0	513	-	-	513	-	-	704	-	-	704	704	0	704	0	0
"SOUTH 01" 40+00 to 42+02.79	192	262	-	-		-	100%	192	0	192	-	-	192	-	-	262	-	-	262	262	0	262	0	0
TOTALS	705	966	0	0		0		705		**705**	0	0	705	0	0	966	0	0	966	966	0	**966**	0	0

TABULATION OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	LOCATION		REMARKS
			BASE "NORTH 01"	OPTION Z "SOUTH 01"	
20101-0000	CLEARING AND GRUBBING	ACRE	0.22	0.11	
20401-0000	ROADWAY EXCAVATION	CUYD	513	192	
20410-0000	SELECT BORROW	CUYD	705	262	
20701-1000	SEPARATION GEOTEXTILE, WOVEN, (CLASS 2, TYPE B)	SQYD	485	485	
30202-2100	ROADWAY AGGREGATE, METHOD 2, SURFACE COURSE	TON	62	16	Based on 1.97 TONS/CUYD

STATE OF ALASKA
49TH
AMMON SCOTT GROESBECK
No. CE170425
REGISTERED PROFESSIONAL ENGINEER
9/21/2026

TABULATION OF BOARDWALK SITE QUANTITIES

c:\dja-pwwork\dja-prod\d0296652\100% Quantity Table Sheets.dgn [TABULATION OF BOARDWALK SITE QUANTITIES]
9 September 2026 4:13 PM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	D.5

PI 30+16.81
Δ = 45°20'17" (LT)
R = 25.00'
T = 10.44'
L = 19.78'
e = 4.0%

PT 30+26.15
PC 30+06.37
N37°01'20"W
N08°18'57"E
PC 30+72.35
PT 31+20.97
PI 30+97.55
Δ = 37°08'42" (RT)
R = 75.00'
T = 25.20'
L = 48.62'
e = -2.0%

North Boardwalk
N00°07'22"E
18-inch pipe culvert
32+17
PC 32+46.66
PT 32+78.39
PI 32+62.59
Δ = 12°07'13" (RT)
R = 150.00'
T = 15.92'
L = 31.73'
e = -2.0%

PI 33+48.27
Δ = 12°47'54" (LT)
R = 50.00'
T = 5.61'
L = 11.17'
e = 2.0%
PC 33+42.66
PT 33+53.83
N12°14'35"E
N00°33'19"W

"NORTH 01" Line to be constructed
Slope stake limits
Construction limits

BEGIN PROJECT
"NORTH 01" 30+00.00
N= 321649.6928
E= 377799.8161

SUSPEND PROJECT
"NORTH 01" 33+75.91
N= 322010.1286
E= 377771.2334

STATE OF ALASKA 49TH
AMMON SCOTT GROESBECK
No. CE170425
REGISTERED PROFESSIONAL ENGINEER
9/21/2026



c:\dja-pwwork\dja-prod\d0296652\100% sheet prints.dgn [ALI - North - Plan 1 [Sheet]]
22 July 2026 10:53 AM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	D.6



BEGIN OPTION Z

"SOUTH 01" 40+00.00
N= 319247.9261
E= 377811.4424

PI 40+23.18
Δ = 11°35'00" (RT)
R = 100.00'
T = 10.14'
L = 20.22'
e = -2.0%

PI 41+59.74
Δ = 23°44'32" (RT)
R = 25.00'
T = 5.26'
L = 10.36'
e = -2.0%

END OPTION Z

"SOUTH 01" 42+02.79
N= 319447.8972
E= 377819.4491



STATE OF ALASKA
49TH
AMMON SCOTT GROESBECK
No. CE170425
REGISTERED PROFESSIONAL ENGINEER
9/21/2026

c:\dja-pwwork\dja-prod\d0296652\100% sheet prints.dgn [ALI - South - Plan 2 (Sheet)]
20 July 2026 2:13 PM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	E.1

SOIL EROSION CONTROL, SILT FENCE FOR INFORMATION ONLY			
LOCATION	*LT/RT*	*QUANTITY (FT)*	*REMARKS*
"BRIDGE 01" 102+12	*-*	*50*	*South bridge abutment*
"BRIDGE 01" 102+92	*-*	*50*	*North bridge abutment*
BASE SCHEDULE TOTAL		***100***	

SOIL EROSION CONTROL, FIBER ROLL FOR INFORMATION ONLY			
LOCATION	*LT/RT*	*QUANTITY (FT)*	*REMARKS*
"BRIDGE 01" 101+67 to 102+12	*LT*	*51*	*Along toe of slope*
"BRIDGE 01" 101+50 to 102+10	*RT*	*48*	*Along toe of slope*
"BRIDGE 01" 102+92 to 103+41	*LT*	*52*	*Along toe of slope*
"BRIDGE 01" 102+89 to 103+40	*RT*	*52*	*Along toe of slope*
BASE SCHEDULE TOTAL		***203***	

TABULATION OF BRIDGE SITE QUANTITIES

J:\2025\251087 Far North Bicentennial Park Enhancements\Drawings\aka-anchorage2021-2_plh_ec.dgn [Tabulation of Qtys]
3 September 2026 7:33 AM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	E.2

BEGIN CONSTRUCTION
"BRIDGE 01" 100+93.00

END CONSTRUCTION
"BRIDGE 01" 104+50.00



LEGEND:

Install soil erosion control, silt fence. See Sheet E.6 for details.

Install soil erosion control, fiber rolls. See Sheet E.7 for details.

STATE OF ALASKA
49 TH
Alexandra Jefferies
Alexandra Jefferies
CE-106241
3/21/2026
REGISTERED PROFESSIONAL ENGINEER

BRIDGE SITE EROSION CONTROL PLAN

J:\2025\251087 Far North Bicentennial Park Enhancements\Drawings\aka-anchorage2021-2_plh_ec.dgn [Plan]
21 July 2026 9:50 AM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	E.3

SOIL EROSION CONTROL, SILT FENCE FOR INFORMATION ONLY	
ALIGNMENT	*QUANTITY (LNFT)*
"NORTH 01"	*723*
BASE SCHEDULE TOTAL	*723*
"SOUTH 01"	*390*
OPTION Z TOTAL	*390*

SOIL EROSION CONTROL, FIBER ROLL FOR INFORMATION ONLY	
ALIGNMENT	*QUANTITY (LNFT)*
"NORTH 01"	*518*
BASE SCHEDULE TOTAL	*518*
"SOUTH 01"	*281*
OPTION Z TOTAL	*281*

9/21/2026

TABULATION OF BOARDWALK SITE QUANTITIES

c:\dfa-pwwork\dfa-prod\d02966521\100% Quantity Table Sheets.dgn [TABULATION OF EROSION CONTROL QUANTITIES]
21 July 2026 3:25 PM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	E.4



LEGEND:

Install soil erosion control, silt fence. See Sheet E.6 for details.

Install soil erosion control, fiber roll. See sheet E.7 for details.

STATE OF ALASKA
49TH
AMMON SCOTT GROESBECK
No. CE170425
REGISTERED PROFESSIONAL ENGINEER
9/21/2026

NORTH BOARDWALK EROSION CONTROL PLAN

c:\dla-pw\work\dla-prod\d02966521\100% ESC and landscaping prints.dgn [North ESC (Sheet)]
9 September 2026 5:59 PM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	E.5



LEGEND:

Install soil erosion control, silt fence. See Sheet E.6 for details.

Install soil erosion control, fiber roll. See sheet E.7 for details.

STATE OF ALASKA
49TH
AMMON SCOTT GROESBECK
No. CE170425
REGISTERED PROFESSIONAL ENGINEER
9/21/2026

SOUTH BOARDWALK EROSION CONTROL PLAN

c:\dja-pwwork\dja-prod\d0296652\100% ESC and landscaping prints.dgn [South ESC (Sheet)]
9 September 2026 5:55 PM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	E.6



POST AND GEOTEXTILE INSTALLATION DETAIL



PLAN

NOTE:

1. *Alternate preassembled silt fence options will be allowed as long as specified dimensions are satisfied. Follow manufacturer's recommendations for installation procedures. All types must ensure silt fence remains attached to, and does not slide down, supporting posts.*
2. *Install silt fence to follow the ground contours as closely as possible.*
3. *Curve ends of silt fence upgrade to prevent water from running around the ends.*
4. *10-foot maximum spacing with silt fence reinforcement. 6-foot maximum spacing without silt fence reinforcement.*



PLAN



ELEVATION

END DETAIL



ELEVATION

SILT FENCE INSTALLATION AT TOE OF FILL



PLAN

POSTS AT JOINTS



PLAN

END POSTS DETAIL

NO SCALE

U.S. DEPARTMENT OF TRANSPORTATION, FHWA OFFICE OF FEDERAL LANDS HIGHWAY	WFL STANDARD W157-1
SILT FENCE	SPECIFICATION FP-24, FP-14
	APPROVED FOR USE 10/2016

J:\2025\251087 Far North Bicentennial Park Enhancements\Drawings\W157-1.dgn [Std W157-1]
3 June 2026 4:23 PM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	E.7



ELEVATION



PLAN

INSTALLATION BEYOND TOE OF SLOPE



Step 1: Excavate trench and install fiber rolls



Step 2: Backfill soil against fiber rolls

PROPERLY STAKED AND ENTRENCHED FIBER ROLL

FIBER ROLL SPACING	
Slope	Spacing (FT)
1:4 or flatter	40
1:3	30
1:2	20
1:1	10

STAKES REQUIRED	
Fiber roll length (FT)	Stakes required for each roll
25	8
20	6
12	4

NOTE:

1. Drive stakes at each end and at 4-foot spacing until fiber roll is secure to slope. Live stakes may be used for permanent installations. Do not crush fiber roll while staking.
2. Overlap fiber rolls 12-inch minimum. Drive stakes at 6-inches from fiber roll end angles towards the adjacent fiber roll and space stakes at 4-foot maximum.



FIBER ROLL STAKING DETAIL



ALTERNATE FIBER ROLL JOINT DETAIL
SLOPE PROTECTION INSTALLATION



INSTALLATION ALONG SLOPES



FIBER ROLL LAPPING DETAIL

NO SCALE

U.S. DEPARTMENT OF TRANSPORTATION, FHWA OFFICE OF FEDERAL LANDS HIGHWAY	WFL STANDARD W157-21
FIBER ROLL	SPECIFICATION FP-24, FP-14
	APPROVED FOR USE 7/2016

J:\2025\251087 Far North Bicentennial Park Enhancements\Drawings\W157-21.dgn [Std:W157-21]
18 June 2026 10:12 AM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	F.1

LANDSCAPING QUANTITIES				
ITEM NO.	*DESCRIPTION*	*UNIT*	*LOCATION*	*REMARKS*
			BASE "BRIDGE 01"	
62502-0000	*TURF ESTABLISHMENT*	*SQYD*	*1340*	*Two applications, one in fall and one in spring.*

TABULATION OF BRIDGE SITE QUANTITIES

J:\2025\251087 Far North Bicentennial Park Enhancements\Drawings\aka-anchorage2021-2_plh_lscp.dgn [Tabulation of Qtys]
3 September 2026 7:48 AM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	F.2

BEGIN CONSTRUCTION
"BRIDGE 01" 100+93.00

END CONSTRUCTION
"BRIDGE 01" 104+50.00



LEGEND:

Turf Establishment

STATE OF ALASKA
49 TH
Alexandra Jefferies
Alexandra Jefferies
CE-106241
9/21/2026
REGISTERED PROFESSIONAL ENGINEER

BRIDGE SITE LANDSCAPING PLAN

J:\2025\2510B7 Far North Bicentennial Park Enhancements\Drawings\aka-anchorage2021-2_pln_lscp.dgn [Plan]
8 September 2026 8:29 AM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	F.3

LANDSCAPING QUANTITIES					
ITEM NO.	DESCRIPTION	UNIT	LOCATION		
			BASE "NORTH 01"	OPTION Z "SOUTH 01"	REMARKS
62502-0000	TURF ESTABLISHMENT	SQYD	1228	636	Two applications at each location, one in fall and one in spring



TABULATION OF BOARDWALK SITE QUANTITIES

8 September 2026 10:12 AM c:\dla-pwwork\dla-prod\d0296652\100% Quantity Table Sheets.dgn [TABULATION OF LANDSCAPING AND REVEGETATION QUANTITIES]

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	F.4



LEGEND:

Turf establishment

STATE OF ALASKA
49TH
AMMON SCOTT GROESBECK
No. CE170425
REGISTERED PROFESSIONAL ENGINEER
9/21/2026

NORTH BOARDWALK LANDSCAPING PLAN

c:\dja-pwwork\dja-prod\d0296652\100% ESC and landscaping prints.dgn {North Landscaping [Sheet]}
16 July 2026 6:46 AM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	F.5



LEGEND:

Turf establishment

Turf establishment, wetland

STATE OF ALASKA
49TH
AMMON SCOTT GROESBECK
No. CE170425
REGISTERED PROFESSIONAL ENGINEER
9/21/2026

SOUTH BOARDWALK LANDSCAPING PLAN

c:\dja-pwwork\dja-proof\d0296652\100% ESC and landscaping prints.dgn [South Landscaping [Sheet]]
21 July 2026 12:30 PM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	G.1

TABULATION OF TEMPORARY TRAFFIC CONTROL DEVICE QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	LOCATION
			BASE "BRIDGE 01"
63502-0600	TEMPORARY TRAFFIC CONTROL, BARRICADE TYPE 3	EACH	5
63504-1000	TEMPORARY TRAFFIC CONTROL, CONSTRUCTION SIGN	SQFT	40

ITEM 63504-1000
TEMPORARY TRAFFIC CONTROL, CONSTRUCTION SIGN
FOR INFORMATION ONLY

MUTCD REF. NO.	SIGN LEGEND	REMARKS	SIGN SIZE (IN)	NO. OF SIGNS	QUANTITY (SQFT)
REF-1, SEE G.5	TRAIL CLOSED	BASE "BRIDGE 01"	48 x 30	4	40
				BASE SCHEDULE TOTAL	40

TABULATION OF BRIDGE SITE QUANTITIES

J:\2025\251087 Far North Bicentennial Park Enhancements\Drawings\aka-anchorage2021-2_pln_ttc.dgn [Tabulation of Traffic Control Quantities]
3 September 2026 8:07 AM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	G.2

N

NOTE:

1. Do not drive below existing guy wires. Install Barricade, type 3, below guy wires to block construction traffic.

LEGEND:

- Allowable Access Route
- Barricade, Type 3
- Staging Area

Muldoon Rd

Tikishla St.

Resurrection Dr.

Majestic Dr.

Resurrection Dr.

Butte Cir.

Pioneer Dr.

Gannett Cir.

Rendezvous Cir.

Klutina Dr.

Beaver Dam Trail

Muldoon Swamp Trail

TRAIL CLOSED Ref - 1

Barricade, Type 3

Utility Substation

Klutina Drive Gated Access

See Detail Below

Allowable access route.

Existing guy wires, See note 1.

Utility Substation

North Fork Campbell Creek

North Gasline Trail

North Gasline Bridge

Utility Substation

TRAIL CLOSED Ref - 1

Barricade, Type 3

North Fork Campbell Creek

Staging area

North Gasline Bridge

Allowable access route

TRAIL CLOSED Ref - 1

Barricade, Type 3

TRAIL CLOSED Ref - 1

Barricade, Type 3

Existing Trails / Access Roads

Utility Substation

Existing Stream Crossing Location

RESUME PROJECT
"BRIDGE 01" 100+00.00

END PROJECT
"BRIDGE 01" 105+00.00

STATE OF ALASKA
49 TH
Alexandra Jefferies
Alexandra Jefferies
CE-106241
9/21/2026
REGISTERED PROFESSIONAL ENGINEER

BRIDGE SITE TEMPORARY TRAFFIC CONTROL PLAN

J:\2025\251087 Far North Bicentennial Park Enhancements\Drawings\ake-anchorage2021-2_plh_ttc.dgn [Traffic Control Plan]

21 July 2026 10:55 AM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	G.3

TABULATION OF TEMPORARY TRAFFIC CONTROL DEVICE QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	LOCATION	
			"NORTH 01"	"SOUTH 01"
63502-0600	TEMPORARY TRAFFIC CONTROL, BARRICADE TYPE 3	EACH	2	3
63504-1000	TEMPORARY TRAFFIC CONTROL, CONSTRUCTION SIGN	SQFT	20	30

TEMPORARY TRAFFIC CONTROL, CONSTRUCTION SIGN FOR INFORMATION ONLY

MUTCD REF. NO.	SIGN LEGEND	REMARKS	SIGN SIZE (IN)	NO. OF SIGNS	QUANTITY (SQFT)
REF-1, SEE G.5	TRAIL CLOSED	"NORTH 01"	48 x 30	2	20
				BASE SCHEDULE TOTAL	20
REF-1, SEE G.5	TRAIL CLOSED	"SOUTH 01"	48 x 30	3	30
				OPTION Z TOTAL	30

PUBLIC INFORMATION PROGRAM FOR INFORMATION ONLY

REF. NO.	BULLITEN BOARD EXHIBIT	MAP SIZE (IN)	NO. OF MAPS
REF-2, SEE G.6	Park map with trail closure locations	8.5 X 11	4

STATE OF ALASKA
49TH
AMMON SCOTT GROESBECK
No. CE170425
REGISTERED PROFESSIONAL ENGINEER
9/21/2026

TABULATION OF BOARDWALK SITE QUANTITIES

8 September 2026 10:12 AM c:\dja-pwwork\dja-prod\d0296652\100% Quantity Table Sheets.dgn [TABULATION OF TEMPORARY TRAFFIC CONTROL QUANTITIES]

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	G.4



STATE OF ALASKA
49TH
AMMON SCOTT GROESBECK
No. CE170425
REGISTERED PROFESSIONAL ENGINEER
9/21/2026

BOARDWALK SITE TEMPORARY TRAFFIC CONTROL PLAN

c:\dja-pwwork\dja-prod\d0296652\100% TTC sheets.dgn [Vicinity Map - Plan 2 (Sheet)]
8 September 2026 10:25 AM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	G.5

REF - 1
(Black lettering and borders on a white background)

STATE OF ALASKA
49 TH
Alexandra Jefferies
Alexandra Jefferies
CE-106241
9/21/2026
REGISTERED PROFESSIONAL ENGINEER

SPECIAL SIGN PANEL DETAILS

10 July 2026 11:04 AM J:\2025\2511087 Far North Bicentennial Park Enhancements\Drawings\aka-anchorage2021-2_afh_ttc.dgn [Special Sign Panel Details]

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	G.6



8.5"

11"

REF-2
(Park map with shading designating construction areas)

STATE OF ALASKA
49TH
AMMON SCOTT GROESBECK
No. CE170425
REGISTERED PROFESSIONAL ENGINEER
9/21/2026

c:\dja-pwwork\dja-prod\d0296652\1009% TTC sheets.dgn [Notice Board Details]
8 September 2026 10:40 AM

NOTICE BOARD DETAILS

Note: The quantities shown hereon are approximate and are subject to field adjustments.

TABULATION OF DRAINAGE QUANTITIES

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	H.1

PAY ITEM NUMBER			60201 -0600																							
Station	ESTIMATED MAXIMUM COVER	STRUCTURAL EXCAVATION	18-INCH PIPE CULVERT																				SKEW ANGLE	Allowable Pipe Material (See key below)	BEVELS 1V:nH	BEVELS 1V:nH	REMARKS See below for numbered notes
	FEET	CUYD	LNFT																						Lt	Rt	
32+17	3		26																					GS			NORTH 01
PROJECT TOTAL	**0**		**26**																								



Allowable Pipe Material

A	Aluminum
AS	Aluminized steel
C	Concrete
GS	Galvanized steel
P	Plastic
(blank)	Any appropriate material
x/__	Any appropriate material except __

C:\Users\Stephen.henry\Downloads\[Drainage24-202512 (1).xlsx]Sheet
21-Jul-2026 10:37 AM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	H.2

METAL ROUND PIPE CULVERT

FILL HEIGHT AND METAL THICKNESS TABLE FOR HELICAL LOCKSEAM AND WELDED SEAM PIPE CULVERT

STEEL

PIPE SIZE DIAMETER INCHES	MINIMUM COVER INCHES	2⅔" x ½" CORRUGATIONS					3" x 1" CORRUGATIONS					5" x 1" CORRUGATIONS				
		METAL THICKNESS (INCH/GAGE)														
		0.064/16	0.079/14	0.109/12	0.138/10	0.168/8	0.064/16	0.079/14	0.109/12	0.138/10	0.168/8	0.064/16	0.079/14	0.109/12	0.138/10	0.168/8
		MAXIMUM FILL HEIGHT ABOVE TOP OF PIPE (FEET)														
12	12	100	100	100	100	100										
15	12	100	100	100	100	100										
18	12	100	100	100	100	100										
21	12	100	100	100	100	100										
24	12	100	100	100	100	100										
30	12	85	100	100	100	100										
36	12	71	89	100	100	100	81	100	100	100	100					
42	12	61	76	100	100	100	70	87	100	100	100					
48	12	53	66	93	100	100	61	76	100	100	100	54	68	95	100	100
54	12		59	83	100	100	54	68	95	100	100	48	60	85	100	100
60	12			74	97	100	49	61	86	100	100	43	54	76	98	100
66	12				87	100	44	55	78	100	100	39	49	69	89	100
72	12				80	97	40	51	71	92	100	36	45	63	82	100
78	12					87	37	47	66	85	100	33	42	58	75	92
84	12					75	35	43	61	78	96	31	39	54	70	86
90	12						32	40	57	73	90	29	36	51	65	80
96	12							38	53	69	84		34	48	61	75
102	18							36	50	65	79		32	45	57	71
108	18								47	61	75			42	54	67
114	18								45	58	71			40	52	63
120	18								43	55	67			38	49	60
126	18									52	64				47	57
132	18									50	61				44	54
138	18									48	58				42	52
144	18										56					50

ALUMINUM

PIPE SIZE DIAMETER INCHES	MINIMUM COVER INCHES	2⅔" x ½" CORRUGATIONS					3" x 1" CORRUGATIONS				
		METAL THICKNESS (INCH/GAGE)									
		0.060/16	0.075/14	0.105/12	0.135/10	0.164/8	0.060/16	0.075/14	0.105/12	0.135/10	0.164/8
		MAXIMUM FILL HEIGHT ABOVE TOP OF PIPE (FEET)									
12	12	100	100	100	100	100					
15	12	100	100	100	100	100					
18	12	100	100	100	100	100					
21	12	88	100	100	100	100					
24	12	77	97	100	100	100					
30	12	62	77	100	100	100	71	89	100	100	100
36	12	52	64	90	100	100	59	74	100	100	100
42	12	44	55	77	99	100	51	64	89	100	100
48	12			67	87	100	44	56	78	100	100
54	18			54	71	88	39	50	69	93	100
60	18				57	72	35	45	62	83	98
66	18					58	32	40	56	76	89
72	18					45	30	37	55	70	82
78	24							34	48	64	75
84	24								44	59	70
90	24								41	62	65
96	24								38	51	61
102	24									46	55
108	24									42	50
114	24										45
120	24										40

NOTE:

1. When directed, camber pipe culverts upward from a chord through the inlet and outlet inverts an ordinate amount equal to 1% of the pipe length. Develop camber on a parabolic curve. If the midpoint elevation on the parabolic curve as designed exceeds the elevation of the inlet invert, reduce the amount of camber or increase the pipe culvert gradient.
2. Fill heights exceeding 100 feet require special analysis by the CO.
3. The fill heights in the table are for helical lockseam and welded seam pipe only. Fill heights for culvert pipe with annular corrugations are more restrictive than those of helical lockseam and welded seam pipe. Obtain approval before furnishing annular corrugation pipe.
4. For flexible pavement and aggregate surface roadways, measure minimum cover from the top of the pipe culvert to the bottom of the roadway subgrade. For rigid pavements, measure minimum cover from the top of the pipe culvert to the top of the pavement. For all roadway surface types, measure maximum fill height from the top of the pipe culvert to the top of the pavement.

METAL PIPE ARCH CULVERT

FILL HEIGHT AND METAL THICKNESS TABLE FOR HELICAL LOCKSEAM AND WELDED SEAM PIPE CULVERT

STEEL

PIPE ARCH SIZE SPAN x RISE INCHES	EQUI-VALENT DIAMETER INCHES	MINIMUM CORNER RADIUS INCHES	MINIMUM COVER INCHES	2⅔" x ½" CORRUGATIONS					3" x 1" CORRUGATIONS					5" x 1" CORRUGATIONS				
				METAL THICKNESS (INCH/GAGE)														
				0.064/16	0.079/14	0.109/12	0.138/10	0.168/8	0.079/14	0.109/12	0.138/10	0.168/8		0.079/14	0.109/12	0.138/10	0.168/8
				MAXIMUM FILL HEIGHT ABOVE TOP OF PIPE (FEET)														
17 x 13	15	3	12	13														
21 x 15	18	3	12	12														
24 x 18	21	3	12	13														
28 x 20	24	3	12	13														
35 x 24	30	3	12	12														
42 x 29	36	3.5	12	12														
49 x 33	42	4	12		12													
57 x 38	48	5	12			12												
60 x 46	54	8	15							21					21			
64 x 43	54	6	12			12												
66 x 51	60	9	15							21					21			
71 x 47	60	7	12				12											
73 x 55	66	12	18							20					20			
77 x 52	66	8	12					12										
81 x 59	72	14	18						17					17				
83 x 57	72	9	12					12										
87 x 63	78	14	18						17					17				
95 x 67	84	16	18						17					17				
103 x 71	90	16	18							17				17				
112 x 75	96	18	21							16					16			
117 x 79	102	18	21							16					16			
128 x 83	108	18	24								16					16		
137 x 87	114	18	24								16					16		
142 x 91	120	18	24									16						16

ALUMINUM

PIPE ARCH SIZE SPAN x RISE INCHES	EQUI-VALENT DIAMETER INCHES	MINIMUM CORNER RADIUS INCHES	MINIMUM COVER INCHES	2⅔" x ½" CORRUGATIONS				3" x 1" CORRUGATIONS			
				METAL THICKNESS (INCH/GAGE)							
				0.060/16	0.075/14	0.105/12	0.135/10	0.060/16	0.075/14	0.105/12	0.135/10
				MAXIMUM FILL HEIGHT ABOVE TOP OF PIPE (FEET)							
17 x 13	15	3	12	13							
21 x 15	18	3	12	12							
24 x 18	21	3	12	13							
28 x 20	24	3	12		13						
35 x 24	30	3	12		12						
42 x 29	36	3.5	15			12					
49 x 33	42	4	15			12					
57 x 38	48	5	15				12				
60 x 46	54	8	15					21			
64 x 43	54	6	18				12				
66 x 51	60	9	18					21			
73 x 55	66	12	18						20		
81 x 59	72	14	21							17	
87 x 63	78	14	21							17	
95 x 67	84	16	24							17	
103 x 71	90	16	24								17

NO SCALE

U.S. DEPARTMENT OF TRANSPORTATION, FHWA OFFICE OF FEDERAL LANDS HIGHWAY	FLH STANDARD 602-1
METAL PIPE CULVERT	SPECIFICATION FP-24, FP-14
	APPROVED FOR USE 8/2024

c:\dja-pwwork\dja-prod\d0292724\Std602-1.dgn [Std 602-1]
12 August 2024 3:15 PM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	H.3

COUPLING BANDS FOR METAL PIPE CULVERT [1]

CORRUGATION SIZE [2] INCHES	ROUND PIPE DIAMETER INCHES	PIPE ARCH SPAN × RISE INCHES	MINIMUM BAND WIDTH (INCHES)		
			ANNULAR CORRUGATED BANDS [3]	HELICALLY CORRUGATED BANDS [4]	SEMI-CORRUGATED BANDS [5]
1½ × ¼	underline [6]	-	10.5	7	10.5
2⅔ × ½	12 to 36	17 × 13 to 42 × 29	7	12	
	42 to 72	49 × 33 to 83 × 57	10.5	12	
	78 to 84	-	10.5	12	10.5
3 × 1	36 to 72	60 × 46 to 81 × 59	12	14	10.5
	78 to 144	87 × 64 to 142 × 91	12	14	10.5
5 × 1	36 to 72	60 × 46 to 81 × 59	20	22	
	78 to 144	87 × 64 to 142 × 91	20	22	

[1] Fabricate annular, helical and semi-corrugated type coupling bands from the same metal as the connecting pipe. Provide coupling bands not more than 3 nominal sheet thicknesses thinner than the thickness of the pipe to be connected, and no thinner than 0.052 inch for steel or 0.048 inch for aluminum. Fasten coupling bands with the following diameter of bolt:
⅜" for 18" round culvert (21" × 15" pipe arch) or less
½" for 21" round culvert (24" × 18" pipe arch) or more

[2] For helically corrugated pipe with rerolled ends, the nominal corrugations size refers to the dimension of the end corrugation in the pipe.

[3] Use annular corrugated bands with pipes having annular corrugations or with helical pipe having rerolled end to form annular corrugations. A 10.5 inch band is acceptable on pipe ends rerolled with 2⅔" × ½" corrugations. A 12 inch band is acceptable on pipe ends rerolled with 3" × 1" pipe corrugations.

[4] Use helical corrugated bands with pipes having helically corrugated ends.

[5] The minimum band widths shown for 3" × 1" and 5" × 1" corrugated sizes apply to 2⅔" × ½" corrugations on rerolled pipe ends.

[6] Smooth sleeve-type couplers and flat bands may be used for pipe diameters of 12" or less. Use a matching metal having a nominal thickness of not less than 0.040 inch for steel, or 0.036 inch for aluminum, or a plastic with an equivalent strength to metal.



SLEEVE JOINT

Smoother sleeve with center stop.
Stab type joint

SMOOTH SLEEVE BAND



FLAT BAND

NOTE:

1. Other types of coupling bands or fastening devices that comply with the joint performance criteria of AASHTO Standard specifications for Highway Bridges, Division II Section 26 may be used.



SIDE VIEW



SIDE VIEW



SIDE VIEW



Band Angle



Oval Lug



Bar & Strap



Integral Flange



Wedge and Strap

STANDARD BAND CONNECTIONS



END VIEW

Second angle connection optional to 42" diameter, required above 42" diameter

ANNULAR BAND



END VIEW

Second angle connection optional to 42" diameter, required above 42" diameter

HELICAL BAND



END VIEW

SEMI-CORRUGATED BAND

NO SCALE

U.S. DEPARTMENT OF TRANSPORTATION, FHWA OFFICE OF FEDERAL LANDS HIGHWAY	FLH STANDARD 602-2
METAL PIPE CULVERT COUPLING BAND	SPECIFICATION FP-24, FP-14
	APPROVED FOR USE 1/2024

c:\dfa-pwwork\dfa-prod\d0292724\Std602-2.dgn [Std 602-2]
18 June 2026 7:22 AM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	H.4



ABOVE NATURAL GROUND



ON UNYIELDING MATERIAL



ON NATURAL GROUND



ON UNSTABLE MATERIAL



ABOVE AND BELOW NATURAL GROUND



BELOW NATURAL GROUND OR TRENCH EXCAVATION IN EMBANKMENT

LEGEND:

- Bedding material (uncompacted)
- Embankment material placed in layers not exceeding 6" compacted depth.
- Compacted backfill material placed in layers not exceeding 6" compacted depth; or flowable backfill according to Section 614.
- Impermeable backfill material.

BEDDING DEPTH	
PIPE SIZE (H)	DEPTH
12" to 54"	4"
> 54"	6"



PIPE BEDDING

NOTE:

1. When directed, camber pipe culverts upward from a chord through the inlet and outlet inverts an ordinate amount equal to 1% of the pipe length. Develop camber on a parabolic curve. If the midpoint elevation on the parabolic curve as designed exceeds the elevation of the inlet invert, reduce the amount of camber or increase the pipe culvert gradient.
2. H equals the diameter of all round pipe culverts or the rise dimension of all pipe arch culverts.
3. See Section 704 for bedding and backfill requirements.

MINIMUM SPACING	
DIAMETER or SPAN	SPACING
UP to 48"	24"
48" and UP	Half diameter or span or 36", whichever is less



ELEVATION

MULTIPLE PIPE INSTALLATION





SECTION A-A

Construct piping plug of impermeable backfill material at the pipe culvert inlet where granular material is used for backfill. Width may be adjusted to tie into impervious material.

PIPING PLUG

NO SCALE

U.S. DEPARTMENT OF TRANSPORTATION, FHWA
OFFICE OF FEDERAL LANDS HIGHWAY

METAL AND PLASTIC PIPE CULVERT BEDDING

FLH STANDARD	
602-3	
SPECIFICATION	
FP-24	
APPROVED FOR USE	
1/2024	

c:\dfa-pwwork\dfa-prod\d0292724\Std602-3.dgn [Std 602-3]
24 July 2024 11:18 AM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	S.1



PLAN

HYDRAULICS			
	Q	Vm	WS EL.
Q_2	60 cfs	3.2	432.3'
Q_{50}	120 cfs	4.2	432.7'
Q_{100}	130 cfs	4.3	432.8'
Q_{500}	170 cfs	8.5	433.0'



ELEVATION

NOTE:

1. Remove existing ground beneath bridge to a minimum depth of 6 inches below the low chord elevation. Grade to drain way from the footing.

STATE OF ALASKA
49 TH
Bryan Hudson
Bryan K. Hudson
SE-14290
9/21/26
REGISTERED PROFESSIONAL ENGINEER

NO.	DATE	BY	REVISIONS

STRUCTURE NO.	STRUCTURE NAME		LOCATION			U.S. DEPARTMENT OF TRANSPORTATION FEDERAL HIGHWAY ADMINISTRATION OFFICE OF FEDERAL LANDS HIGHWAY	
	NORTH GASLINE BRIDGE		FAR NORTH BICENTENNIAL PARK				
DESIGNED BY	DRAWN BY	CHECKED BY	PROJECT TEAM LEAD	SCALE	BRIDGE PLAN	DATE	RG NO.
PND	OR	MK	BH	1" = 10'	Sheet 1 of 6	9/11/2026	RG3339-A

NORTH FORK CAMPBELL CREEK BRIDGE

J:\2025\251087 Far North Bicentennial Park Enhancements\Drawings\aka-anchorage2021-2_pln_bdg.dgn [North Gasline Trail - Plan 1 (Sheet)]
18 September 2026 3:45 PM

BRIDGES GENERAL NOTES

SPECIFICATIONS:

Construction:
Standard Specifications for Construction of Roads and Bridges on Federal Highway Projects, FP-24.

Design:
AASHTO LRFD Bridge Design Specifications 9th Edition.
AASHTO LRFD Guide Specifications for the Design of Pedestrian Bridges 2nd Edition, with 2015 Interim Revisions.

Camber:
Provide bridges cambered to account for dead load of structure and deck plus an additional 0.2% of total bridge span at the midpoint of the span.

DESIGN LOADS:

Dead Loads:
Concrete: 150 pcf
Lateral Earth Pressure: soil unit weight, 0.120 kcf
Snow: 50 psf (Apply 1.75 Strength Load Factor, 1.0 Extreme Event Load Factor)

Live Loads:
Pedestrian live load: 90 pcf
AASHTO H-10
PistenBully 100 (16.5k total)



PISTENBULLY 100

Seismic Design Criteria:
PGA 0.55g
S_s 1.25g
S_1 0.5g
Site class C
Liquefaction potential: low
AASHTO 7% probability of exceedance in 75 years

MATERIALS:

Cast-in-place Concrete:
Provide class D (AE) for abutments.
F'c = 5,000 psi at 28 days.
Chamfer exposed edges of all concrete 1" unless noted otherwise on the plans.

Reinforcing Steel:
Provide reinforcing steel conforming to AASHTO M31, Grade 60 deformed, epoxy coated.
Provide 2" cover for reinforcing steel unless noted otherwise.

Structural Steel:
Provide high-strength low alloy structural steel conforming to section 717 or ASTM A847 Gr50.

Timber:
Use timber members conforming to the requirements of the grading rules agency for the the species, type, and grade specified below:

Provide timber conforming to Subsection 716.01 of FP-24. Use timber members conforming to the requirements of the grading rules agency for the species, type and grade specified below:
- Douglas Fir - Coastal Region, in accordance with WCLIB Grading Rules.
- No. 2 or better, or No. 1 or better.
- Surface four sides (S4S)

Preservative Treatment:
Treat all timber members as follows:
- Fabricate (cut, drill, and incise) prior to treatment.
- Where field cuts or holes are required, apply treatment in accordance with AWPA M-4 using three saturating applications of copper naphthenate.
- Treat in accordance with AWPA U1 (Use Category System) and AWPA T1 (Processing and Treatment Standard).
- Pressure treat with ACZA to a minimum retention of 0.60 pcf.
- Provide a quality mark approved by the American Lumber Standards Comittee indicating compliance with applicable AWPA standards for each piece or pallet.

Timber Hardware:
- Use galvanized ASTM A307 timber (economy) bolts with hex nut and malleable iron washer for all timber-to-timber connections.
- Use galvanized ASTM A325 bolts with hex nut and malleable iron washer for all timber-to-steel connections.
- Tighten timber-to-steel and timber-to-timber connections to snug tight condition.

Welding:
Perform all welding in accordance with the current AASHTO/AWS D1.5 Bridge Welding Code.

GEOTECHNICAL REPORT:

For boring logs and other geotechnical information, see Final Geotechnical Report number WFL GR15-20, dated January 2021, and GM39-25 Limited Geotechnical Site Investigation Findings and Recommendations, dated September 2025.

TABULATION OF BRIDGE QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	QUANTITY	REMARKS
20410-0000	SELECT BORROW	CUYD	8	
20801-0000	STRUCTURE EXCAVATION	CUYD	4	
55201-0800	STRUCTURAL CONCRETE, CLASS D (AE)	CUYD	10	Foundation & Backwall
55401-2000	REINFORCING STEEL, EPOXY-COATED	LB	1850	
55504-0000	PRE-FABRICATED STEEL BRIDGE	LPSM	ALL	North Fork Campbell Creek
55601-1300	BRIDGE RAILING, TIMBER, (BRIDGE)	LNFT	100	Approach Railing

SHEET INDEX

SHEET NO.	DRAWING TITLE
S.1	North Fork Campbell Creek Bridge
S.2	Bridge General Notes
S.3	Abutment Details
S.4	Bar List
S.5	Typical Bridge Section
S.6	Approach Rail Details

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	S.2

STATE OF ALASKA
49 TH
Bryan K. Hudson
SE-14290
9/11/26
REGISTERED PROFESSIONAL ENGINEER

NO.	DATE	BY	REVISIONS

STRUCTURE NO.	STRUCTURE NAME	LOCATION
	NORTH GASLINE BRIDGE	FAR NORTH BICENTENNIAL PARK

DESIGNED BY	DRAWN BY	CHECKED BY	PROJECT TEAM LEAD	SCALE	BRIDGE PLAN
PND	OR	MK	BH	NO SCALE	Sheet 2 of 6

U.S. DEPARTMENT OF TRANSPORTATION
FEDERAL HIGHWAY ADMINISTRATION
OFFICE OF FEDERAL LANDS HIGHWAY

DATE	RG NO.
9/11/2026	RG3339-B

BRIDGES GENERAL NOTES

J:\2025\251087 Far North Bicentennial Park Enhancements\Drawings\eka-anchorage2021-2_pln_bdg.dgn [Bridges General Notes]
11 September 2026 1:47 PM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	S.3

SHEET NOTES:

Coordinate footing dimensions and quantities with the selected bridge. Submit any required footing design revisions for CO approval.

Footing design:
Bridge reactions estimated from pre-manufactured pedestrian bridges of similar spans.

North Fork Campbell Creek North Gasline = DC+LL = 47 kip / bridge reaction (70 kip factored)

Factored Bearing Resistance:
North Fork Campbell Creek North Gasline = 12.3 ksf (in-situ)



FOOTING & BACKWALL PLAN







PARTIAL ELEVATION

NOTE:

1. *Provide all bearings and bridge-to-footing connection hardware. Install bearings in accordance with the manufacturer's recommendations.*
2. *#6EA5 Rebar not shown in section detail.*

FOOTING & BACKWALL SECTION

STATE OF ALASKA
49 TH
Bryan K. Hudson
SE-14290
9/21/26
REGISTERED PROFESSIONAL ENGINEER

NO.	DATE	BY	REVISIONS

STRUCTURE NO.	STRUCTURE NAME	LOCATION
	NORTH GASLINE BRIDGE	FAR NORTH BICENTENNIAL PARK

DESIGNED BY	DRAWN BY	CHECKED BY	PROJECT TEAM LEAD	SCALE	BRIDGE PLAN
PND	OR	MK	BH	VARIES	Sheet 3 of 6

U.S. DEPARTMENT OF TRANSPORTATION
FEDERAL HIGHWAY ADMINISTRATION
OFFICE OF FEDERAL LANDS HIGHWAY

DATE	RG NO.
9/11/2026	RG3339-C

ABUTMENT DETAILS

J:\2025\251087 Far North Bicentennial Park Enhancements\Drawings\ak-anchorage2021-2_plh_bdg.dgn [Abut Details]
3 September 2026 12:10 PM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	S.4

Rebar Bill of Materials

Bridge	Label #	Quantity†	Overall Length (ft-in)*
North Fork North Gasline	#6EA1	20	15'-8"
	#6EA2	34	3'-8"
	#6EA3	34	3'-3"
	#6EA4	34	3'-3"
	#6EA5a	8	2'-4"
	#6EA5b	8	2'-10"
	#6EA5c	8	3'-3"
	#6EB1a	4	17'-10.75"
	#6EB1b	4	20'-8"
	#6EB1c	12	21'-8"

Notes:

**Overall length is the length after bending, not the full length of the rebar.*

†Quantities and lengths are based on a 2'-4" top of footing to top of backwall height. Coordinate footing dimensions and quantities with the selected bridge. Submit any required footing design revisions for CO approval.

STATE OF ALASKA
49 TH
Bryan K. Hudson
SE-14290
9/21/26
REGISTERED PROFESSIONAL ENGINEER

NO.	DATE	BY	REVISIONS

STRUCTURE NO.	STRUCTURE NAME	LOCATION
	NORTH GASLINE BRIDGE	FAR NORTH BICENTENNIAL PARK

DESIGNED BY	DRAWN BY	CHECKED BY	PROJECT TEAM LEAD	SCALE	BRIDGE PLAN
PND	OR	MK	BH	NO SCALE	Sheet 4 of 6

U.S. DEPARTMENT OF TRANSPORTATION
FEDERAL HIGHWAY ADMINISTRATION
OFFICE OF FEDERAL LANDS HIGHWAY

DATE	RG NO.
9/11/2026	RG3339-D

BAR LIST

J:\2025\251087 Far North Bicentennial Park Enhancements\Drawings\aka-anchorage2021-2_pdh_bdg.dgn [Bar List]
3 September 2026 12:27 PM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	S.5

NOTE:

1. *All elements are steel unless noted otherwise.*
2. *Submit design calculations and shop drawings to the CO for approval before fabrication including superstructure type, member size and truss height in submittal according to Section 104.*
3. *After superstructure installation and deck placement, repair any damage to coating due to shipping, handling, and erecting the bridge.*



STATE OF ALASKA
49 TH
Bryan K. Hudson
SE-14290
9/21/26
REGISTERED PROFESSIONAL ENGINEER

NO.	DATE	BY	REVISIONS

STRUCTURE NO.	STRUCTURE NAME		LOCATION			U.S. DEPARTMENT OF TRANSPORTATION FEDERAL HIGHWAY ADMINISTRATION OFFICE OF FEDERAL LANDS HIGHWAY	
	NORTH GASLINE BRIDGE		FAR NORTH BICENTENNIAL PARK				
DESIGNED BY	DRAWN BY	CHECKED BY	PROJECT TEAM LEAD	SCALE	BRIDGE PLAN	DATE	RG NO.
PND	OR	MK	BH	1" = 20'	Sheet 5 of 6	9/11/2026	RG3339-E

TYPICAL BRIDGE SECTION

J:\2025\251087 Far North Bicentennial Park Enhancements\Drawings\aka-anchorage2021-2_pln_bdg.dgn [Typical Bridge Section]
8 September 2026 9:22 AM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	S.6



APPROACH RAIL PLAN



BOLT DETAIL



APPROACH RAIL ELEVATION

NO.	DATE	BY	REVISIONS

STRUCTURE NO.	STRUCTURE NAME	LOCATION
	NORTH GASLINE BRIDGE	FAR NORTH BICENTENNIAL PARK

DESIGNED BY	DRAWN BY	CHECKED BY	PROJECT TEAM LEAD	SCALE	BRIDGE PLAN
PND	OR	MK	BH	VARIES	Sheet 6 of 6

U.S. DEPARTMENT OF TRANSPORTATION
FEDERAL HIGHWAY ADMINISTRATION
OFFICE OF FEDERAL LANDS HIGHWAY

DATE	RG NO.
9/11/2026	RG3339-F

APPROACH RAIL DETAILS

J:\2025\251087 Far North Bicentennial Park Enhancements\Drawings\aka-anchorage2021-2_pln_bdg.dgn [Approach Rail Details]
3 September 2026 12:45 PM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	T.1



PLAN



ELEVATION



TYPICAL SECTION

Scale: 1/4" = 1'-0"



PROFILE GRADE DIAGRAM

No Scale

Elevations are at profile grade @ ℄ Trail

STATE OF ALASKA
49TH
AMMON SCOTT GROESBECK
No. CE170425
REGISTERED PROFESSIONAL ENGINEER
9/21/2026

NORTH BOARDWALK GENERAL LAYOUT

10 September 2026 10:57 AM c:\dja-pwwork\dja-prod\d0296652\100% Boardwalk layout.dgn [NORTH BOARDWALK GENERAL LAYOUT]

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	T.2

BOARDWALK GENERAL NOTES

See T.3 for boardwalk general notes.

SHEET INDEX

SHEET NO.	DRAWING TITLE
T.1	North Boardwalk General Layout
T.2	Tabulation of North Boardwalk Quantities
T.3	Boardwalk General Notes
T.4	North Boardwalk Foundation Plan
T.5	North Boardwalk Approach Soil Ramp Plan and Elevation
T.6	Approach Soil Ramp Details
T.7	North Boardwalk Abutment Plan and Elevation
T.8	North Boardwalk Pier Plan and Elevation
T.9	Boardwalk Substructure Details
T.10	North Boardwalk Framing Plan
T.11	North Boardwalk Decking Plan
T.12	Boardwalk Superstructure Details

TABULATION OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	QUANTITY	REMARKS
20803-0000	STRUCTURAL BACKFILL	CUYD	31	Includes Class 2, Type A non-woven Geotextile
25301-0000	GABIONS	SQFT	90	
55601-1300	BRIDGE RAILING, TIMBER, (BOARDWALK)	LNFT	122	Boardwalk Timber Railing
55701-2000	STRUCTURAL TIMBER AND LUMBER, TREATED	MFBM	2.4	Stringers, Backwall and Pile Caps
55703-2000	STRUCTURAL TIMBER AND LUMBER, TREATED, DECKING	SQYD	56	Timber Decking
57302-0000	HELICAL PILE	EACH	14	

STATE OF ALASKA
49TH
AMMON SCOTT GROESBECK
No. CE170425
REGISTERED PROFESSIONAL ENGINEER
9/21/2026

TABULATION OF NORTH BOARDWALK QUANTITIES

c:\dla-pwwork\dla-prod\d0296652\100% boardwalk details.dgn [TABULATION OF NORTH BOARDWALK QUANTITIES]
9 September 2026 4:33 PM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	T.3

BOARDWALK GENERAL NOTES

SPECIFICATIONS:
DESIGN: AASHTO LRFD Guide Specification for Design of Pedestrian Bridges, 2nd edition with 2015 Interims, AASHTO LRFD Bridge Design Specifications 9th Edition with Interims, and Forest Service Handbook 7709.56B Transportation Structures Handbook Chapter 80 Trail Bridge Design.

CONSTRUCTION: Standard Specifications for Construction of Road and Bridges on Federal Highway Projects FP-24.

DEAD LOAD:
Timber: 50 lb per cubic foot
Soil: 130 lb per cubic foot

	8 ft Boardwalk	4 ft Boardwalk
LIVE LOAD:		
Pedestrian Live Load:	*90 lb per square foot*	*90 lb per square foot*
Snow Load:	*55 lb per square foot*	*55 lb per square foot*
Vehicle Load:	*Snowmobile (500 lbf + 300 lbf person)*	
	H5 Design Vehicle	
	Dynamic Load Allowance (impact), IM = 0%	

SEISMIC:
Site Class = D
Peak Ground Acceleration, PGA = 0.536 g
Horizontal Response Spectral Aceeleration Coefficient at 0.2-sec Period, SS = 1.183g
Site Factor at Zero-Period on Acceleration Response Spectrum, FPGA = 1
Site Factor at Short-Period Range of Acceleration Response Spectrum, Fa = 1.027
Site Factor for Long-Period Range of Acceleration Response Spectrum, Fv = 1.538
Horizontal Response Spectral Acceleration Coeffiecient at 0.2-s Period Modified by Short-Period Site Factor, SDS = 1.215 g
Horizontal Response Spectral Acceleration Coefficient at 1.0-s Period Modified by Long-Period Site Factor, SD1 = 0.71 g
Peak Seismic ground Acceleration Coefficient Modified by Short-Period Site Factor, AS = 0.536 g
Seismic Zone = 4

WIND: 130 miles per hour

TIMBER & LUMBER: Use Solid Sawn Timber Member Conforming to the Requirements of the Grading Rules Agency for the Species, Type and Grade Specified Below:

Stringer	*- Coastal Region Douglas Fir-Larch Full Sawn, Select Structural Grading Rules Agency - WWPA, WCLIB*
Decking, Diaphragms, Backwall Planks and Posts, and Pile Caps	*- Coastal Region Douglas Fir-Larch Full Sawn, No. 1 or Better Grading Rules Agency - WWPA, WCLIB*
Pedestrian Handrail and Railing Posts	*- Coastal Region Douglas Fir-Larch S4S, Select Structural Grading Rules Agency - WWPA, WCLIB*

TIMBER TREATMENT: Treat all timber members after fabrication. Preservative Treatment Shall be in Accordance with the Current AWPA Specifications using the treatment material listed below. Treatment will comply with the requirements of the Current Edition of WWPI's "Best Management Practices for the use of Treated Wood in Aquatic Environments".

Decking, Joist, Diaphragms, Backwall Planks and Posts, Railing Posts, and Pile Caps	*- AWPA U1 Using UC4B Copper Naphthenate in Hydrocarbon Solvent A Alternate Oil-Based Products when Approved Equal*
Pedestrian Handrail	*- AWPA U1 Using UC3B Copper Naphthenate in Hydrocarbon Solvent A Alternate Oil-Based Products when Approved Equal*

FIELD TREATMENT: Furnish Copper Naphthenate (2% Solution) for Field Treating of Wood. All abrasion and field cuts are to be carefully trimmed and given three Brush Coats of the Field Treatment Solution. Where Field Drilling of Bolt or Nail Holes is required, the Holes are to be poured full of Preservative Prior to Inserting the Fasteners.

HARDWARE: Steel Shapes, plates and Bars shall conform to ASTM A36. Use galvanized hardware meeting the requirements of AASHTO M270, Grade A36, with Nuts and Bolts conforming to ASTM A307, Grade A. Use galvanized Malleable Iron Washers against Wood unless otherwise noted. Wood screws will conform to ANSI/ASME Standard B18.6.1. Holes in members with bolt connections will be 1/16 inch larger than bolt size. Predrill all screw connections with pilot holes to avoid splitting. All plates and fasteners used in construction of timber bridge will be galvanized according to AASHTO M232.

PILES: Material for helical pile will be ASTM 500 Grade C. All parts of the helical pile system will be galvanized per ASTM 123.

FABRICATOR: Submit Shop Drawings for all Timber Components, Structural Steel, and Hardware. Show all Dimensions and Fabrication Details for all cut or bored Timber members. Do not field drill bolt holes unless otherwise noted on the Plans.

STATE OF ALASKA
49TH
AMMON SCOTT GROESBECK
No. CE170425
REGISTERED PROFESSIONAL ENGINEER
9/21/2026

c:\dja-nwwork\dja-prod\d0296652\100% boardwalk details.dgn [BOARDWALK GENERAL NOTES]
10 September 2026 5:11 PM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	T.4



PLAN



ELEVATION

FOUNDATION LOCATIONS			
Location	*Station*	*Top of Deck Elevation*	*Pile Cut Off Elevation*
Abut. 1	31+45.56	El. 439.83	El. 437.56
Pier ①	31+55.56	El. 439.83	El. 437.56
Pier ②	31+65.56	El. 439.83	El. 437.56
Pier ③	31+75.56	El. 439.83	El. 437.56
Pier ④	31+85.56	El. 439.83	El. 437.56
Pier ⑤	31+95.56	El. 439.83	El. 437.56
Abut. 2	32+05.56	El. 439.83	El. 437.56



PROFILE GRADE DIAGRAM

No Scale

Elevations are at profile grade @ ℄ Trail

STATE OF ALASKA
49TH
AMMON SCOTT GROESBECK
No. CE170425
REGISTERED PROFESSIONAL ENGINEER
9/21/2026

NORTH BOARDWALK FOUNDATION PLAN

c:\dja-pwwork\dja-prod\d0296652\100% Boardwalk layout.dgn [NORTH BOARDWALK FOUNDATION]
10 September 2026 10:56 AM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	T.5



PLAN

Scale: 3/8" = 1'-0"



ELEVATION

Scale: 3/8" = 1'-0"

STATE OF ALASKA
49TH
AMMON SCOTT GROESBECK
No. CE170425
REGISTERED PROFESSIONAL ENGINEER
9/21/2026

NORTH BOARDWALK APPROACH SOIL RAMP PLAN AND ELEVATION

c:\dja-pwwork\dja-prod\d0296652\100% boardwalk details.dgn [NORTH BOARDWALK APPROACH SOIL RAMP PLAN AND ELEVATION]
9 September 2026 5:47 PM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	T.6



1 / T.6 **SECTION**

Scale: 3/8" = 1'-0"



STRUCTURE EXCAVATION DETAIL

Scale: 3/8" = 1'-0"

(4) #10x5" Wood screws, typ. Connected at each Timber Backwall Post

Note: Gabion Basket to be continuous on the front face. Cut Welded Wire on top of the Gabion Basket on the sides and back of post, as shown, to slide Post into Gabion Basket. Welded wire to be tight to post.



PLAN

(4) #10x5" Wood screws connected at each Timber Backwall Post



ELEVATION

Note: Backwall to End Handrail Post, Pile Caps, Stringers, or Decking.

TIMBER PLANK BACKWALL DETAIL

Scale: 3/4" = 1'-0"

STATE OF ALASKA
49th
AMMON SCOTT GROESBECK
No. CE170425
REGISTERED PROFESSIONAL ENGINEER
9/21/2026

Gabion Basket Notes:

1. *Gabion Baskets to be 3 feet wide and 3 feet tall, unless otherwise called out on plan.*
2. *Gabion Baskets shall be assembled according to Manufacturers instructions.*
3. *Remove and dispose of Duff and Top Organic Layers down to Mineral Soil. Place Gabion Basket on 2 feet of wrapped Structural Backfill.*
4. *In-fill Rock Material shall be Heavy Rock 8-inch plus.*
5. *Welded Wire to be 9 gauge, 3"x3" Galvanized*

APPROACH SOIL RAMP DETAILS

c:\dfa-pwwork\dfa-prod\d0296652\100% boardwalk details.dgn [APPROACH SOIL RAMP DETAILS]
10 September 2026 11:11 AM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	T.7



PLAN

Scale: 1/2" = 1'-0"

Note: Abutment 1 shown, abutment 2 similar.



ELEVATION

Scale: 1/2" = 1'-0"



1 / T.7

SECTION

Scale: 3/4" = 1'-0"

STATE OF ALASKA
49TH
AMMON SCOTT GROESBECK
No. CE170425
REGISTERED PROFESSIONAL ENGINEER
9/21/2026

NORTH BOARDWALK ABUTMENT PLAN AND ELEVATION

c:\djs-pwwork\djs-prod\d0296652\100% boardwalk details.dgn [NORTH BOARDWALK ABUTMENT PLAN AND ELEVATION]
8 September 2026 11:01 AM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	T.8



PLAN

Scale: 1/2" = 1'-0"

Note: Pier 1 shown, all other piers similar



ELEVATION

Scale: 1/2" = 1'-0"



1 T.8

SECTION

Scale: 3/4" = 1'-0"

STATE OF ALASKA
49TH
AMMON SCOTT GROESBECK
No. CE170425
REGISTERED PROFESSIONAL ENGINEER
9/21/2026

NORTH BOARDWALK PIER PLAN AND ELEVATION

8 September 2026 11:04 AM c:\dja-pwwork\dja-prod\d02966521\100% boardwalk details.dgn [NORTH BOARDWALK PIER PLAN AND ELEVATION]

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	T.9



U-BRACKET SECTION

Scale: 1" = 1'-0"



SECTION A-A

Scale: 1"= 1'-0"



BRACKET DETAIL

Scale: 1-1/2" = 1'-0"



SUPPORT BRACKET DETAIL

Scale: 3/4 = 1'-0"

STATE OF ALASKA
49TH
AMMON SCOTT GROESBECK
No. CE170425
REGISTERED PROFESSIONAL ENGINEER

9/21/2026



HELICAL PILE SECTION

Scale: Not to Scale

	Embedment Depth (ft)	Depth to 1st Helix (ft)	Helix Count per Pile Shaft	Post Size (in)	Helix Diameter (in)	Required Axial Capacity - Strength I (kips)	Required Lateral Capacity - Strength I (kips)
8-ft Boardwalk	13	7	2	3.5Øx0.375 min.	12	17	0.5
4-ft Boardwalk	10	5	2	3.5Øx0.375 min.	8	6	0.5

Notes: Provide timber support bracket assembly as recommended by helical pile manufacturer. Material for bracket must be galvanized per ASTM123.

Material for helical pile shall be ASTM 500, Grade C and galvanized per ASTM 123.

Material for abutment bracket shall be ASTM A36 steel.

Bolts used in connection of timber support bracket assembly to timber beams shall be domehead or carriage type bolts with round plate washers and nuts conforming to ASTM A307, Grade A.

BOARDWALK SUBSTRUCTURE DETAILS

11 September 2026 11:45 AM c:\dja-pwwork\dja-prod\d0296652\100% boardwalk details.dgn [BOARDWALK SUBSTRUCTURE DETAILS]

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	T.10



FRAMING PLAN

Scale: 3/16" = 1'-0"

STATE OF ALASKA
49TH
AMMON SCOTT GROESBECK
No. CE170425
REGISTERED PROFESSIONAL ENGINEER
9/21/2026

NORTH BOARDWALK FRAMING PLAN

10 September 2026 10:38 AM c:\dja-pwwork\dja-prod\d0296652\100% boardwalk details.dgn {NORTH BOARDWALK FRAMING PLAN}

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	T.11



DECKING PLAN

Scale: 3/16" = 1'-0"

STATE OF ALASKA
49TH
AMMON SCOTT GROESBECK
No. CE170425
REGISTERED PROFESSIONAL ENGINEER
9/21/2026

NORTH BOARDWALK DECKING PLAN

8 September 2026 11:03 AM c:\dja-pw\work\dja-prod\d0296652\100% boardwalk details.dgn [NORTH BOARDWALK DECKING PLAN]

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	T.12

Note: Backwall not Shown for Clarity. Do not Attach Backwall to End Handrail Post, Pile Caps, Stringers, or Decking.



HANDRAIL ELEVATION

Scale: 3/4" = 1'-0"

Note: Handrail Elevation is looking in in between the Exterior Stringer towards the Timber Handrail.



1 / T.11 **HANDRAIL SECTION**

Scale: 3/4" = 1'-0"



TIMBER BLOCKING CONNECTION DETAIL

Scale: 3/4" = 1'-0"



SECTION A-A

Scale: 3/4" = 1'-0"



END HANDRAIL POST DETAIL

Scale: 3/4" = 1'-0"



Schematic example of End Condition.

Schematic example of End Condition without End Deck Plank.

END HANDRAIL SCHEMATIC

Scale: Not to Scale

STATE OF ALASKA
49TH
AMMON SCOTT GROESBECK
No. CE170425
REGISTERED PROFESSIONAL ENGINEER
9/21/2026

BOARDWALK SUPERSTRUCTURE DETAILS

c:\djs-pwwork\djs-prod\d02966521\100% boardwalk details.dgn [BOARDWALK SUPERSTRUCTURE DETAILS]
8 September 2026 11:44 AM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	U.1



PLAN



ELEVATION



TYPICAL SECTION

Scale: 1/4" = 1'-0"



PROFILE GRADE DIAGRAM

No Scale

Elevations are at profile grade @ ℄ Trail

STATE OF ALASKA
49TH
AMMON SCOTT GROESBECK
No. CE170425
REGISTERED PROFESSIONAL ENGINEER
9/21/2026

SOUTH BOARDWALK GENERAL LAYOUT

10 September 2026 10:57 AM c:\dja-pwwork\dja-prod\d0296652\100% Boardwalk layout.dgn [SOUTH BOARDWALK GENERAL LAYOUT]

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	U.2

BOARDWALK GENERAL NOTES

See T.3 for boardwalk general notes.

SHEET INDEX

SHEET NO.	DRAWING TITLE
U.1	South Boardwalk General Layout
U.2	Tabulation of South Boardwalk Quantities
U.3	South Boardwalk Foundation Plan
U.4	South Boardwalk Approach Soil Ramp Plan and Elevation
U.5	South Boardwalk Abutment Plan and Elevation
U.6	South Boardwalk Pier Plan and Elevation
U.7	South Boardwalk Framing Plan
U.8	South Boardwalk Decking Plan

TABULATION OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	QUANTITY	REMARKS
20803-0000	STRUCTURAL BACKFILL	CUYD	22	Includes Class 2, Type A non-woven Geotextile
25301-0000	GABIONS	SQFT	63	
55601-1300	BRIDGE RAILING, TIMBER, (BOARDWALK)	LNFT	102	Boardwalk Timber Railing
55701-2000	STRUCTURAL TIMBER AND LUMBER, TREATED	MFBM	1.2	Stringers, Backwall and Pile Caps
55703-2000	STRUCTURAL TIMBER AND LUMBER, TREATED, DECKING	SQYD	25	Timber Decking
57302-0000	HELICAL PILE	EACH	12	

STATE OF ALASKA
49TH
AMMON SCOTT GROESBECK
No. CE170425
REGISTERED PROFESSIONAL ENGINEER
9/21/2026

TABULATION OF SOUTH BOARDWALK QUANTITIES

9 September 2026 5:45 PM c:\dja-pwwork\dja-prod\d0296652\100% boardwalk details.dgn [TABULATION OF SOUTH BOARDWALK QUANTITIES]

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	U.3



PLAN



ELEVATION

FOUNDATION LOCATIONS			
Location	*Station*	*Top of Deck Elevation*	*Pile Cut Off Elevation*
Abut. 1	41+00.99	El. 550.43	El. 548.16
Pier ①	41+10.99	El. 550.43	El. 548.16
Pier ②	41+20.99	El. 550.43	El. 548.16
Pier ③	41+30.99	El. 550.43	El. 548.16
Pier ④	41+40.99	El. 550.43	El. 548.16
Abut. 2	41+50.99	El. 550.43	El. 548.16



PROFILE GRADE DIAGRAM

No Scale

Elevations are at profile grade @ ℄ Trail

STATE OF ALASKA
49TH
AMMON SCOTT GROESBECK
No. CE170425
REGISTERED PROFESSIONAL ENGINEER
9/21/2026

SOUTH BOARDWALK FOUNDATION PLAN

10 September 2026 10:57 AM c:\dja-pwwork\dja-prod\d0296652\100% Boardwalk layout.dgn [SOUTH BOARDWALK FOUNDATION]

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	U.4



PLAN

Scale: 3/8" = 1'-0"



ELEVATION

Scale: 3/8" = 1'-0"

Note: See Sheet T.6 for Soil Ramp Details.

STATE OF ALASKA
49TH
AMMON SCOTT GROESBECK
No. CE170425
REGISTERED PROFESSIONAL ENGINEER
9/21/2026

SOUTH BOARDWALK APPROACH SOIL RAMP PLAN AND ELEVATION

c:\dja-pwwork\dja-prod\d0296652\100% boardwalk details.dgn [SOUTH BOARDWALK APPROACH SOIL RAMP PLAN AND ELEVATION]
9 September 2026 5:46 PM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	U.5



Note: Abutment 1 shown, abutment 2 similar.

PLAN

Scale: 1/2" = 1'-0"



ELEVATION

Scale: 1/2" = 1'-0"



1/U.5 **SECTION**

Scale: 3/4" = 1'-0"

Note: See Sheet T.9 for Substructure Details.

STATE OF ALASKA
49TH
AMMON SCOTT GROESBECK
No. CE170425
REGISTERED PROFESSIONAL ENGINEER
9/21/2026

SOUTH BOARDWALK ABUTMENT PLAN AND ELEVATION

9 September 2026 5:43 PM c:\djfa-pwwork\djfa-prod\d0296652\100% boardwalk details.dgn [SOUTH BOARDWALK ABUTMENT PLAN AND ELEVATION]

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	U.6



PLAN

Scale: 1/2" = 1'-0"

Note: Pier 1 shown, all other piers similar



ELEVATION

Scale: 1/2" = 1'-0"



1 / U.6 **SECTION**

Scale: 3/4" = 1'-0"

Note: See Sheet T.9 for Substructure Details.

STATE OF ALASKA
49TH
AMMON SCOTT GROESBECK
No. CE170425
REGISTERED PROFESSIONAL ENGINEER
9/21/2026

SOUTH BOARDWALK PIER PLAN AND ELEVATION

c:\dja-pwwork\dja-prod\d02966521\100% boardwalk details.dgn [SOUTH BOARDWALK PIER PLAN AND ELEVATION]
9 September 2026 5:43 PM

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	U.7



Note: See Sheet T.12 for Superstructure Details.

FRAMING PLAN

Scale: 3/16" = 1'-0"

STATE OF ALASKA
49TH
AMMON SCOTT GROESBECK
No. CE170425
REGISTERED PROFESSIONAL ENGINEER
9/21/2026

SOUTH BOARDWALK FRAMING PLAN

8 September 2026 10:58 AM c:\dja-pwwork\dja-prod\d0296652\100% boardwalk details.dgn [SOUTH BOARDWALK FRAMING PLAN]

PROJECT	SHEET NUMBER
AK FLAP ANCHORAGE 2021(1)	U.8



DECKING PLAN

Scale: 3/16" = 1'-0"

Note: See Sheet T.12 for Superstructure Details.

STATE OF ALASKA
49TH
AMMON SCOTT GROESBECK
No. CE170425
REGISTERED PROFESSIONAL ENGINEER
9/21/2026

SOUTH BOARDWALK DECKING PLAN

c:\dla-pwwork\dla-prod\d0296652\100% boardwalk details.dgn [SOUTH BOARDWALK DECKING PLAN]
8 September 2026 10:57 AM