SECTION C- DESCRIPTION/SPECIFICATIONS/WORK STATEMENT

C.1.0 GENERAL: Department of the Interior (DOI); U. S. Fish & Wildlife Service (FWS), Shiawassee National Wildlife Refuge, Saginaw, MI.

Project: Maintenance Shop – HVAC/Heat Replacement

C.1.1 FACILITY BACKGROUND INFORMATION

C.1.1.1 The Government maintenance shop was constructed in 1985 and is using outdated heating systems which is causing the refuge issues. Partial electrical outages cause the air compressor to shut down and the system reacts to loss of air pressure by overruling the thermostat and turning on the heaters, which will run continuously until they are manually turned off or pressure is restored which causes excessive heat in the building when nobody is on site to turn off the system. The building is also equipped with a wood fired boiler which is seldomly used and needs to be replaced.

C.1.2 PROJECT DESCRIPTION

C.1.2.1 FWS requires Vendor services to do the following work:
- Remove the wood fired boiler.
- Wood boiler was installed in series with the gas boiler. Install piping as needed to connect the existing piping to the gas boiler piping.
- Replace the existing L.P. gas fired boiler with a new 150,000 BUT, L.P. gas, cast iron, natural draft, 84-86% efficient boiler. Vent through the existing chimney with new vent pipe as needed.
- Update all boiler piping and boiler trim to current standards.
- Update circulator, expansion tank, water feed and air elimination system.
- Replace pneumatic controls with electronic zone valves connected to standard low voltage thermostats in the service space. Remove the compressor and pneumatic controls.
- Install a voltage monitor to protect the boiler electronics in the event of a power outage or brownout.

C.2.0 LOCATION OF WORK

C.2.1 Shiawassee National Wildlife Refuge - Maintenance Building
5299 Bartel Rd,
Saginaw, MI 48601
Ph. 989-385-5800

C.3.0 DEFINITIONS

C.3.1 Contracting Officer (CO): The Officer signing the contract on behalf of the Government. The Contracting Officer has overall responsibility for the contract and is the only one who has the authority to terminate a contract, to authorize changes or modifications, and to issue a final decision.

C.3.2 Contracting Officer's Representative (COR): The Government Engineer who will have the following authority under the Task Order:

- Represent the Contracting Officer for all technical matters that may arise under the contract.
- Shall remain cognizant of the Vendor's technical efforts and progress and discuss these matters with him as appropriately.
- Respond to the Vendor's inquiries on purely technical aspects of the contract.
- Review payment requests from the Vendor.

C.4.0 DESIGNATED PROJECT PERSONNEL

C.4.1 Contracting Officer (CO):

TBD

C.4.2 The Contracting Officer's Representative (COR):

Gerrick Prine
U.S. Fish and Wildlife Service
Division of Engineering
5600 American Blvd West, Suite 990
Bloomington, MN 55437-1458
Phone: (612) 544-0536
Gerrick_prine@fws.gov

C.4.3 Site Contacts:

Scott Simmons – Project Leader
Shiawassee National Wildlife Refuge
6975 Mower Road
Saginaw, MI 48601-9783

Ph. 989-385-5800

C.5.0 GOVERNMENT-FURNISHED PROPERTY/ITEMS

C.5.1 The Government will provide the following documents:

- Maintenance Shop Drawings
- Any other documents can be provided upon vendor's request.

C.6.0 SCOPE OF WORK OF VENDOR

C.6.1 Review scope of work information, coordinate any questions with Government.

C.6.2 Visit site to review in-place physical conditions of equipment, status of building's existing furnace and HVAC system and replace the equipment, piping, and controls. Vendor will take care of disposing of the old furnace, boiler, piping and other equipment and make sure the replacement equipment is tied into the new controls and test to make sure everything works properly.

C.6.3 Provide summary of any findings and recommendations for immediate improvements to the Government.

C.7.0 DELIVERABLES

C.7.1 Vendor to provide new equipment, owner's manual of the new equipment and any warranty information. Vendor shall also train staff on new equipment and controls.

C.8.0 ANTICIPATED PROJECT SCHEDULE

C.8.1 Immediately upon award visit site to meet staff and review condition assessment.

C.8.2 As soon as possible, contractor will have thirty (60) days to include lead times for the new equipment, installation, and testing.

C.8.5 Total contract period of performance of work depends on equipment lead times. Vendor will coordinate time requirements with FWS.

C.9.0 PAYMENT

C.9.1 The Vendor shall submit for final payment.