SOLICITATION, OFFER, AND AWARD (Construction, Alteration, or Repair)	1. SOLICITATION NO. 12445127B0002	2. TYPE OF SOLICITATION: [x] SEALED BID (IFB) INVITATION FOR BID; [ ] NEGOTIATED (RFP) REQUEST FOR PROPOSAL	3. DATE ISSUED 11/02/2026	PAGE 1 OF PAGES 47

IMPORTANT -- The "offer" section on the reverse must be fully completed by offeror.

4. CONTRACT NO.	5. REQUISITION/PURCHASE REQUEST NO. 1166742	6. PROJECT NO.

7. ISSUED BY CODE 4451	8. ADDRESS OFFER TO
USDA-FS CSA EAST 11 1720 PEACHTREE ST NW STE 876S ATLANTA GA 30309-2449	Adam Doyle / adam.doyle@usda.gov cc: Charles Cotton / charles.cotton@usda.gov SUBJECT LINE SHALL READ: SOLICITATION_12445127B0002

9. FOR INFORMATION CALL	a. NAME ADAM DOYLE	b. TELEPHONE NO. (Include area code) (NO COLLECT CALLS)

SOLICITATION

NOTE: In sealed bid solicitations "offer" and "offeror" mean "bid" and "bidder."

10. THE GOVERNMENT REQUIRES PERFORMANCE OF THE WORK DESCRIBED IN THESE DOCUMENTS (Title, identifying no., date)

Project Title: AZ Halfmoon Ranch House HVAC Installation
Original Set Aside: The project is set-aside 100% for small businesses per FAR 19.5.
NAICS Code: 238220 - Plumbing, Heating, and Air-Conditioning Contractors (size standard $19m).
PSC: N041 - Installation of Equipment - Refrigeration, Air Cond.
Location: Coronado National Forest, Douglas Ranger District (Cochise County, AZ). See Attachment 003 Statement of Work and Specifications for specific location.
Scope of Work (summarized): See Attachment 003 Statement of Work and Specifications for specific details not included under this paragraph. The contractor shall supply all material, labor, tools, equipment, supplies, incidentals, supervision, and safety measures necessary to complete this project. This project involves installing three ductless, split unit climate control system in Halfmoon Ranch, a historic house located in a remote and rural location. Currently there is no climate control system in the building.
Award of Contract: A single award will be made to the overall lowest priced responsive/responsible bidder.
Tentative Dates:
Site(s) Visit/Pre-Bid Conference (if needed): 11/10/2026 - POC Lauren Atkinson, lauren.atkinson@usda.gov
Date for Questions: 11/30/2026.
Bid Submittal Deadline: 12/07/2026, 1300 CT.
Delivery: 60 Days After Notice to Proceed Period of
Performance: 60 Days After Notice to Proceed
Submittal Method: All proposals will be emailed to adam.doyle@usda.gov and cc charles.cotton@usda.gov

***Payment and Performance Bonds MUST be Furnished if bid exceeds $35,000.00**

Continued ...

11. The Contractor shall begin performance within 10 calendar days and complete it within 60 calendar days after receiving [ ] award, [x] notice to proceed. The performance period is [ ] mandatory [x] negotiable. (See _____.)

12a. THE CONTRACTOR MUST FURNISH ANY REQUIRED PERFORMANCE AND PAYMENT BONDS? (If "YES", indicate within how many calendar days after award in Item 12b.)	[x] YES * [ ] NO	12b. CALENDAR DAYS 0

13. ADDITIONAL SOLICITATION REQUIREMENTS:

a. Sealed offers in original and 1 copies to perform the work required are due at the place specified in Item 8 by 1300 (hour) local time 12/07/2026 (date). If this is a sealed bid solicitation, offers will be publicly opened at that time. Sealed envelopes containing offers shall be marked to show the offeror's name and address, the solicitation number, and the date and time offers are due.

b. An offer guarantee [ ] is, [x] is not required.

c. All offers are subject to the (1) work requirements, and (2) other provisions and clauses incorporated in the solicitation in full text or by reference.

d. Offers providing less than 90 calendar days for Government acceptance after the date offers are due will not be considered and will be rejected .

OFFER *(Must be fully completed by offeror)*

14. NAME AND ADDRESS OF OFFEROR *(Include ZIP Code)*	15. TELEPHONE NO. *(Include area code)*
	16. REMITTANCE ADDRESS *(Include only if different than item 14.)*
CODE FACILITY CODE	

17. The offeror agrees to perform the work required at the prices specified below in strict accordance with the terms of this solicitation, if this offer is accepted by the Government in writing within _____ calendar days after the date offers are due. *(Insert any number equal to or greater than the minimum requirement stated in item 13d. Failure to insert any number means the offeror accepts the minimum in item 13d.)*

AMOUNTS ▶

18. The offeror agrees to furnish any required performance and payment bonds.

19. ACKNOWLEDGEMENT OF AMENDMENTS

(The offeror acknowledges receipt of amendments to the solicitation -- give number and date of each)

AMENDMENT NO.										
DATE.										

20a. NAME AND TITLE OF PERSON AUTHORIZED TO SIGN OFFER *(Type or print)*	20b. SIGNATURE	20c. OFFER DATE

AWARD *(To be completed by Government)*

21. ITEMS ACCEPTED:

Continued...

22. AMOUNT	23. ACCOUNTING AND APPROPRIATION DATA

24. SUBMIT INVOICES TO ADDRESS SHOWN IN *(4 copies unless otherwise specified)* ▶	ITEM	25. OTHER THAN FULL AND OPEN COMPETITION PURSUANT TO THE UNITED STATES CODE AT ☐ 10 U.S.C. 3204(a) ( ) ☐ 41 U.S.C. 3304(a) ( )

26. ADMINISTERED BY CODE 4451	27. PAYMENT WILL BE MADE BY
USDA-FS CSA EAST 11 1720 PEACHTREE ST NW STE 876S ATLANTA GA 30309-2449	

CONTRACTING OFFICER WILL COMPLETE ITEM 28 OR 29 AS APPLICABLE

☐ 28. NEGOTIATED AGREEMENT *(Contractor is required to sign this document and return* 1 *copies to issuing office.) Contractor agrees to furnish and deliver all items or perform all work requirements identified on this form and any continuation sheets for the consideration stated in this contract. The rights and obligations of the parties to this contract shall be governed by (a) this contract award, (b) the solicitation, and (c) the clauses, representations,certifications, and specifications incorporated by reference in or attached to this contract.*

☐ 29. AWARD *(Contractor is not required to sign this document.) Your offer on this solicitation is hereby accepted as to the items listed. This award consummates the contract, which consists of (a) the Government solicitation and your offer, and (b) this contract award. No further contractual document is necessary.*

30a. NAME AND TITLE OF CONTRACTOR OR PERSON AUTHORIZED TO SIGN *(Type or print)*		31a. NAME OF CONTRACTING OFFICER *(Type or print)* CHARLES C. COTTON	
30b. SIGNATURE	30c. DATE	31b. UNITED STATES OF AMERICA BY	31c. DATE

ITEM NO. (A)	SUPPLIES/SERVICES (B)	QUANTITY (C)	UNIT (D)	UNIT PRICE (E)	AMOUNT (F)
	Delivery: 60 Days After Notice to Proceed Delivery Location Code: 8160 USDA FOREST SERVICE DOUGLAS RANGER DISTRICT 1192 W SADDLE VIEW RD DOUGLAS AZ 85607 US Period of Performance: 60 Days After Notice to Proceed				
0001	Supply and Install HVAC Ductless Split Unit System Product/Service Code: N041 Product/Service Description: INSTALLATION OF EQUIPMENT-REFRIGERATION, AIR CONDITIONING, AND AIR CIRCULATING EQUIPMENT Attachments: C04 Attachment 001 CSS Commercial Construction C04 Attachment 002 Statement of Work and Specifications C04 Attachment 003 Schedule of Items Fillable C04 Attachment 004 DBA AZ20260038 Cochise				

Statement of Requirement - See Attachment 002 Statement of Work and Specifications for a complete list of requirements.

Schedule of Items - See Attachment 003 Schedule of Items Fillable.

Technical Data - Technical data and supporting documentation associated with this solicitation are available through the following sources:

NFPA 70, Article 100
Utility Company published standards.
ASHRAE/IESNA 90.1, "Energy Efficient Design of New Buildings except Low-Rise Residential Buildings."

Project Location -
USDA Forest Service, Coronado National Forest
Douglas Ranger District (Cochise County, AZ)
Halfmoon Ranch House
Coordinates - Latitude: 31.94729 / Longitude: -109.95445.

Definitization of Equitable Adjustments for Change Orders -
Pursuant to FAR 36.101-4(b), information regarding USDA's definitization of equitable adjustments for change orders under construction contracts may be found at Contracting with USDA under "Federal Acquisition Regulation 36.101-4". USDA's procedures that apply to the definitization of equitable adjustments for change orders under construction contracts may be found in AGAR 443.304 -70.

Federal Acquisition Regulation (FAR) and United States Department of Agriculture Acquisition Regulation (AGAR) Clauses and Provisions
The clauses and provisions contained herein are applicable to any order awarded as a result of this solicitation. The terms and conditions set forth herein supersede all other terms and conditions. Acceptance of the order in accordance with (IAW) FAR 12.201-1(b)(2) constitutes acceptance of all terms and conditions contained herein.

As part of the Revolutionary FAR Overhaul (RFO), system updates may lag policy updates. The System for Award Management (SAM) may continue to require entities to complete representations based on provisions that are not included in this solicitation. Contracting officers will rely on representations from offers based on provisions in the solicitation. Entities are not required to, nor are they able to, update their entity registration to remove these representations in SAM.

52.252-2 Clauses Incorporated by Reference Feb 1998
This solicitation incorporates one or more clauses by reference, with the same force and effect as if they were given in full text. Upon request, the Contracting Officer will make their full text available. Also the full text of the clause may be accessed electronically at Internet address https://www.acquisition.gov/far-overhaul/far-part-deviation-guide/far-overhaul-part-52

52.212-4 Terms and Conditions—Commercial Products and Commercial Services (Nov 2025)
☐ Alternate I (Nov 2025) of 52.212-4

This is a commercial construction acquisition. FAR 52.212-4 is amended as follows:

(b) *Inspection/Acceptance*. Inspection and Acceptance will be conducted in accordance with FAR 52.246-12, Inspection of Construction (Aug 1996).

(d) *Changes.* Changes will be handled in accordance with the following FAR clause(s):
☐ FAR 52.243-4, Changes (Nov 2025)
☒ FAR 52.243-5, Changes and Changed Conditions (Nov 2025)

(o) *Warranty.* FAR 52.246-21, Warranty of Construction is applicable to this contract.

52.203-17 Contractor Employee Whistleblower Rights (Nov 2023)
52.203-19 Prohibition on Requiring Certain Internal Confidentiality Agreements or Statements (Jan 2017)
52.222-50 Combating Trafficking in Persons (Nov 2025)
☐ Alternate I (Nov 2025) of 52.222-50
52.226-8 Encouraging Contractor Policies to Ban Text Messaging While Driving (May 2024)
52.232-39 Unenforceability of Unauthorized Obligations (Jun 2013)
52.232-40 Providing Accelerated Payments to Small Business Subcontractors (Mar 2023)
52.233-3 Protest After Award (Sep 2025)
52.233-4 Applicable Law for Breach of Contract Claim (Sep 2025)
52.240-91 Security Prohibitions and Exclusions (Nov 2025)
☐ Alternate I (Nov 2025) of 52.240-91
52.244-6 Subcontracts for Commercial Products and Commercial Services (Nov 2025)

The following clauses are applicable if checked:

☐ 52.203-6 Restrictions on Subcontractor Sales to the Government (Jun 2020) with Alternate I (Nov 2021) of 52.203-6
☐ 52.203-13 Contractor Code of Business Ethics and Conduct (Nov 2021)
☐ 52.204-9 Personal Identity Verification of Contractor Personnel Jan 2011
☒ 52.204-13 System for Award Management—Maintenance (Nov 2025)
☐ 52.204-91 Contractor identification (Nov 2025)
☐ 52.209-6 Protecting the Government's Interest When Subcontracting with Contractors Debarred, Suspended, or Proposed for Debarment (Sep 2025)
☐ 52.209-9 Updates of Publicly Available Information Regarding Responsibility Matters (Sep 2025)
☒ 52.209-10 Prohibition on Contracting with Inverted Domestic Corporations (Sep 2025)

☐ 52.219-4 Notice of Price Evaluation Preference for HUBZone Small Business Concerns (Nov 2025)
☒ 52.219-6 Notice of Total Small Business Aside (Nov 2025)
☐ Alternate I (Mar 2020).
☐ 52.219-8 Utilization of Small Business Concerns (Nov 2025)
☐ 52.219-9 Small Business Subcontracting Plan (Nov 2025)
☐ Alternate III (Nov 2025) of 52.219-9.
☐ Alternate IV (Nov 2025) of 52.219-9
☐ 52.219-14 Limitations on Subcontracting (Nov 2025)
☐ 52.219-16 Liquidated Damages—Subcontracting Plan (Nov 2025)
☐ 52.219-33 Nonmanufacturer Rule (Nov 2025)
☒ 52.222-3 Convict Labor (June 2003)
☐ 52.222-19 Child Labor—Cooperation with Authorities and Remedies (Nov 2025)
☐ 52.222-35 Equal Opportunity for Veterans (Nov 2025)
☐ Alternate I (Jul 2014) of 52.222-35
☐ 52.222-36 Equal Opportunity for Workers with Disabilities (Nov 2025)
☐ Alternate I (Jul 2014) of 52.222-36
☐ 52.222-37 Employment Reports on Veterans (Nov 2025)
☒ 52.222-40 Notification of Employee Rights Under the National Labor Relations Act (Dec 2010)
☒ 52.222-41 Service Contract Labor Standards (Aug 2018)
☒ 52.222-42 Statement of Equivalent Rates for Federal Hires (May 2014)

This Statement is for Information Only:
It is not a Wage Determination

Employee Class	Monetary Wage -- Fringe Benefits
Aircraft Mechanic	$XX.XX

☐ 52.222-43 Fair Labor Standards Act and Service Contract Labor Standards -- Price Adjustment (Multiple Year and Option Contracts) (Aug 2018)
☐ 52.222-44 Fair Labor Standards Act and Service Contract Labor Standards -- Price Adjustment (May 2014)
☐ 52.222-51 Exemption from Application of the Service Contract Labor Standards to Contracts for Maintenance, Calibration, or Repair of Certain Equipment-Requirements (May 2014)
☐ 52.222-53 Exemption from Application of the Service Contract Labor Standards to Contracts for Certain Services-Requirements (Nov 2025)
☐ 52.222-54 Employment Eligibility Verification (Nov 2025)
☒ 52.222-62 Paid Sick Leave Under Executive Order 13706 (Jan 2022)
☒ 52.222-90 Addressing DEI Discrimination by Federal Contractors (Apr 2026)

☒ 52.223-2 Reporting of Biobased Products Under Service and Construction Contracts (Nov 2025)
☐ 52.223-9 Estimate of Percentage of Recovered Material Content for EPA-Designated Items (May 2008)
☐ Alternate I (May 2008) of 52.223-9
☒ 52.223-11 Ozone-Depleting Substances and High Global Warming Potential Hydrofluorocarbons (Nov 2025)
☒ 52.223-12 Maintenance, Service, Repair, or Disposal of Refrigeration Equipment and Air Conditioners (Nov 2025)
☒ 52.223-23 Sustainable Products and Services (Nov 2025)
☐ 52.224-3 Privacy Training (Jan 2017)
☐ Alternate I (Jan 2017) of 52.224-3
☒ 52.225-1 Buy American-Supplies (Nov 2025)
☐ Alternate I (Oct 2022) of 52.225-1
☐ 52.225-3 Buy American--Free Trade Agreements--Israeli Trade Act (Nov 2025)
☐ Alternate II (Nov 2025) of 52.225-3.
☐ Alternate III (Nov 2025) of 52.225-3.
☐ Alternate IV (Oct 2022) of 52.225-3
☐ 52.225-5 Trade Agreements (Nov 2023)
☐ 52.225-19 Contractor Personnel in a Designated Operational Area or Supporting a Diplomatic or Consular Mission outside the United States (May 2020)
☐ 52.225-26 Contractors Performing Private Security Functions Outside the United States (Oct 2016)
☐ 52.226-4 Notice of Disaster or Emergency Area Set-Aside (Nov 2007)
☐ 52.226-5 Restrictions on Subcontracting Outside Disaster or Emergency Area (Aug 2025)
☐ 52.229-12 Tax on Certain Foreign Procurements
☐ 52.232-29 Terms for Financing of Purchases of Commercial Products and Commercial Services (Nov 2021)
☐ 52.232-30 Installment Payments for Commercial Products and Commercial Services (Nov 2021)
☒ 52.232-33 Payment by Electronic Funds Transfer— System for Award Management (Oct 2018)
☐ 52.232-34 Payment by Electronic Funds Transfer—Other Than System for Award Management (Jul 2013)
☐ 52.232-36 Payment by Third Party (Nov 2025)
☐ 52.240-92 Security Requirements (Nov 2025)
☐ Alternate II (Nov 2025) of 52.240-92
☐ 52.240-93 Basic Safeguarding of Covered Contractor Information Systems (Nov 2025)
☐ 52.242-13 Bankruptcy (July 1995)
☒ 52.246-21 Warranty of Construction (Mar 1994)
☐ 52.247-64 Preference for Privately Owned U.S.-Flag Commercial Vessels (Nov 2025)
☐ Alternate I (Apr 2023) of 52.247-64.

☐ Alternate II (Nov 2021) of 52.247-64

The Contractor shall comply with the following FAR Clauses for Commercial Construction.

52.222-6 Construction Wage Rate Requirements (Nov 2025)
52.222-7 Withholding of Funds (Nov 2025)
52.222-8 Payrolls and Basic Records (Nov 2025)
52.222-9 Apprentices and Trainees (Nov 2025)
52.222-10 Compliance with Copeland Act Requirements (Nov 2025)
52.222-11 Subcontracts (Labor Standards) (Nov 2025)
52.222-12 Contract Termination-Debarment (May 2014)
52.222-13 Compliance with Construction Wage Rate Requirements and Related Regulations. (May 2014)
52.222-14 Disputes Concerning Labor Standards (Nov 2025)
52.222-15 Certificate of Eligibility (May 2014)
52.236-5 Material and Workmanship (Jul 2025)

The following clauses are applicable when checked:

☒ 52.222-30 Construction Wage Rate Requirements-Price Adjustment (None or Separately Specified Pricing Method (Aug 2018)
☐ 52.222-31 Construction Wage Rate Requirements-Price Adjustment (Percentage Method) (Aug 2018)
☐ 52.222-32 Construction Wage Rate Requirements-Price Adjustment (Actual Method) (Nov 2025)
☒ 52.225-9 Buy American-Construction Materials (Nov 2025)
☐ Alternate I (Oct 2022) of 52.25-9
☐ 52.225-11 Notice of Buy American Requirement-Construction Materials under Trade Agreements (Nov 2025)
☐ Alternate I (Nov 2025) (of 52.225-11
☐ Alternate II (Oct 2022) of 52.225-11
☐ 52.228-2 Additional Bond Security (Oct 1997)
☐ 52.228-5 Insurance-Work on Government Installation (Jan 1997)
☐ 52.228-11 Individual Surety-Pledge of Assets (Feb 2021)
☐ 52.228-13 Alternative Payment Protections (Jul 2020)
☐ 52.228-14 Irrevocable Letter of Credit (Nov 2014)
☐ 52.228-15 Performance and Payment Bonds-Construction (Jun 2020)
☐ 52.228-17 Individual Surety-Pledge of Assets (Bid Guarantee) (Feb 2021)
☐ 52.236-2 Differing Site Conditions (Jul 2025)
☐ 52.236-3 Site Investigation and Conditions Affecting the Work (Jul 2025)
☐ 52.236-6 Superintendent by the Contractor (Jul 2025)
☒ 52.236-7 Permits and Responsibilities (Jul 2025)
☐ 52.236-8 Other Contracts (Jul 2025)

☐ 52.236-9 Protection of Existing Vegetation, Structures, Equipment, Utilities, and Improvements (Jul 2025)
☐ 52.236-10 Operations and Storage Areas (Jul 2025)
☐ 52.236-11 Use and Possession Prior to Completion (Jul 2025)
☐ 52.236-12 Cleaning Up (Jul 2025)
☐ 52.236-13 Accident Prevention (Jul 2025)
☐ Alternate I (Nov 1991) of 52.236-13
☒ 52.236-14 Availability and Use of Utility Services (Jul 2025)
☐ 52.236-15 Schedules for Construction Contracts (Jul 2025)
☐ 52.236-16 Quantity Surveys (Jul 2025)
☐ Alternate I (Apr 1984) of 52.236-16
☒ 52.236-17 Layout of Work (Jul 2025)
☐ 52.236-21 Specifications and Drawings for Construction (Jul 2025)
☐ Alternate I (Apr 1984) of 52.236-21
☐ Alternate II (Apr 1984) of 52.236-21
☐ 52.242-14 Suspension of Work (Apr 1984)
☐ 52.248-3 Value Engineering (Oct 2025)
☐ Alternate I (Apr 1984) of 52.248-3

Other Applicable Clauses

AGAR Clauses

This solicitation incorporates one or more clauses by reference, with the same force and effect as if they were given in full text. Upon request, the Contracting Officer will make their full text available. Also, the full text of the clause may be accessed electronically at Internet address https://www.usda.gov/guidance-documents/acquisition-policy/ocp/usda-agar30-sept-26pdf

AGAR 452.203-70 Unenforceable Supplier Terms (Sep 2026)

AGAR 452.204–70 Modification for Contract Closeout (Apr 2026)

AGAR 452.204-71 Personal Identity Verification and Workforce Integrity of Contractor Employees (Apr 2026)

AGAR 452.232-71 Progress Payments for Commercial Construction Contracts (May 2026)

AGAR 452.236-70 Electronic Submission of Payment Requests (Sep 2026)

Solicitation Information –

Award Type
It is anticipated that a Firm, Fixed Price Contract will be awarded as a result of this synopsis/solicitation. The Government intends to make one award from this solicitation. Therefore, to be considered responsive, contractors must submit pricing for all items.

Period of Performance
The Contractor is required to commence work under this contract within 10 calendar days after the date the Contractor receives the notice to proceed, and complete within 60 days after the Contractor receives the notice to proceed. The time stated for completion shall include final cleanup of the premises.

Organized Site Visit - Tuesday November 10, 2026, At Halfmoon Ranch House.
Contact Lauren Atkinson for more information.
Phone: 520-388-8427
Email: lauren.atkinson@usda.gov

Questions Deadline: 30 November 2026. Questions shall be submitted via email to adam.doyle@usda.gov and cc: charles.cotton@usda.gov and are due no later than November 30th, 2026. The subject line should read: *12445127B0002 QUESTION.*

Evaluation and Basis for Award
The provision at FAR 52.212-2, Evaluation—Commercial Products and Commercial Services is not applicable to this solicitation. In lieu of this provision, quotes will be evaluated in accordance with FAR 12.203 based on the criteria listed below. Award will be made to the offeror representing the best value to the Government.

Evaluation Method:
Award will be made to the lowest price that is:
FAR 14.306-1 Responsive
FAR 14.306-2 Responsible

52.252-1 Solicitation Provisions Incorporated by Reference Feb 1998
This solicitation incorporates one or more solicitation provisions by reference, with the same force and effect as if they were given in full text. Upon request, the Contracting Officer will make their full text available. The offeror is cautioned that the listed provisions may include blocks that must be completed by the offeror and submitted with its quotation or offer. In lieu of submitting the full text of those provisions, the offeror may identify the provision by paragraph identifier and provide the appropriate information with its quotation or offer. Also, the full text of a solicitation provision may be accessed electronically at this/these address(es): https://www.acquisition.gov/far-overhaul/far-part-deviation-guide/far-overhaul-part-52

52.212-1 Instructions to Offerors - Commercial Products and Commercial Services (Nov 2025) FAR 52.212-1 is amended as follows:

Period for acceptance of offers -
The Offeror agrees to hold the prices in its offer firm for **90 calendar days** from the date specified for receipt of offers.

General Instructions -
Each of the parts shall be separate and complete so that evaluation of one may be accomplished independently from evaluation of the other. Bids submitted in response to this solicitation shall be furnished as specified below:
The bids must include the following:

a. SF-1442, Solicitation, Offer & Award, Pages 1 and 2
b. Acknowledgement of solicitation amendments (if any). This can be accomplished by submitting the signed SF-30(s).
c. Attachment 003 Schedule of Items Fillable

52.203-18 Prohibition on Contracting with Entities that Require Certain Internal Confidentiality Agreements or Statements-Representation (Jan 2017)
52.209-2 Prohibition on Contracting with Inverted Domestic Corporations - Representation (Sep 2025)
52.209-11 Representation by Corporations Regarding Delinquent Tax Liability or a Felony Conviction under any Federal Law (Sep 2025)
52.240-90 Security Prohibitions and Exclusions Representations and Certifications (Nov 2025)

The following provisions are applicable if checked:

☐ 52.203-11 Certification and Disclosure Regarding Payments to Influence Certain Federal Transactions (Sep 2024)
☒ 52.204-7 System for Award Management—Registration (Nov 2025)
☐ Alternate I (Nov 2025) to 52.204-7
☐ 52.204-90 Offeror Identification (Nov 2025)
☐ 52.207-6 Solicitation of Offers from Small Business Concerns and Small Business Teaming Arrangements or Joint Ventures (Multiple-Award Contracts) (Aug 2024)
☐ 52.209-12 Certification Regarding Tax Matters (Oct 2025)
☐ 52.219-2 Equal Low Bids (Nov 2025)
☒ 52.222-5 Construction Wage Requirements, Secondary Site of the Work (Nov 2025)
☒ 52.222-18 Certification Regarding Knowledge of Child Labor for Listed End Products (Feb 2021)
☐ 52.222-48 Exemption from Application of the Service Contract Labor Standards for Maintenance, Calibration, or Repair of Certain Equipment–Certification (Nov 2025)
☐ 52.222-52 Exemption from Application of the Service Contract Labor Standards for Certain Services-Certification (Nov 2025)
☐ 52.222-56 Certification Regarding Trafficking in Persons Compliance Plan (Oct 2020)
☒ 52.223-4 Recovered Material Certification (May 2008)
☒ 52.225-2 Buy American Certificate (Oct 2022)

☐ 52.225-4 Buy American-Free Trade Agreements-Israeli Trade Act Certificate (Nov 2025)
☐ 52.225-6 Trade Agreements-Certificate (Feb 2021)
☐ 52.225-10 Notice of Buy American Requirement- Construction Materials (May 2014)
☐ Alternate I (May 2014) of 52.225-10
☐ 52.225-12 Notice of Buy American Requirement-Construction Materials under Trade Agreements (May 2014)
☐ Alternate I (May 2014) of 52.225-12
☐ Alternate II (Nov 2023) of 52.225-12

☐ 52.226-3 Disaster or Emergency Area Representation (Nov 2007)
☐ 52.228-1 Bid Guarantee (Sep 1996)
☐ 52.229-11 Tax on Certain Foreign Procurements—Notice and Representation (Jul 2025)

Other Applicable FAR Provisions

AGAR Provisions
This solicitation incorporates one or more provisions by reference, with the same force and effect as if they were given in full text. Upon request, the Contracting Officer will make their full text available. Also, the full text of the clause may be accessed electronically at Internet address https://www.usda.gov/guidance-documents/acquisition-policy/ocp/usda-agar30-sept-26pdf

NOTICE FOR FILING AGENCY PROTESTS
United States Department of Agriculture (USDA) Protest Procedures

The United States Department of Agriculture (USDA) is committed to fair, transparent, and efficient acquisitions. Interested parties with concerns about this solicitation are encouraged to seek resolution through the following USDA procedures.

Tier 1: Contracting Officer Concern Resolution

Submission: Interested parties with concerns about either the solicitation or subsequent award should first submit their concern directly to the Contracting Officer, providing sufficient detail to allow the Contracting Officer to understand and assess the issue.

Process: The Contracting Officer will review the concern, seek clarification as needed, and engage with the interested party to attempt prompt resolution.

Review Timeline: The Contracting Officer will make every effort to provide a response or resolution within 10 business days of receiving the concern.

Effect on Award or Performance: Tier 1 engagement is not considered an official notification of filing an agency protest and does not pause solicitation deadlines, delay award decisions, or suspend contract performance.

Next Steps: If the matter cannot be resolved at Tier 1, the interested party may file a written agency protest under Tier 2. USDA encourages all parties to seek resolution with the Contracting Officer before filing an agency protest.

Tier 2: Agency Protest
If concerns cannot be resolved at Tier 1, an interested party may file a written agency protest with either the Contracting Officer or the USDA Independent Review Authority. The decision by the USDA Independent Review Authority is an alternative to a decision by the Contracting Officer. The USDA Independent Review Authority will not consider an appeal of the Contracting Officer's decision on an agency protest.

The protest must state whether the protester elects review by the Contracting Officer, by the UDSA Independent Review Authority. If no election is stated, the Contracting Officer will decide the protest.

Required Information: Protests shall include the information set forth in FAR 33.104-4 (a)(3). Failure to submit the required information may result in a delay or dismissal of the protest.

Submission: Agency protests should be submitted electronically to SPE.inquiry@usda.gov and the Contracting Officer.

Timeliness: Protests must be filed within the timeframes specified in FAR 33.104.

Effect on Award or Performance: Contract awards or performance will be suspended during the protest period unless justified in writing for urgent and compelling reasons or determined to be in the best interest of the Government.

Review Timeline: USDA strives to resolve agency-level protests within 35 business days of receipt.

Election of Forum: By filing a protest with USDA, the protesters agree not to file a protest on the same matter with the Government Accountability Office (GAO) or any other external forum while the agency protest is pending. If such a protest is filed externally, the USDA agency protest will be dismissed.

Questions: Questions regarding this notice or protest procedures should be directed to the Contracting Officer identified in this solicitation.

Halfmoon HVAC Installation
STATEMENT of WORK
March 2026

Project Location: Work will take place at the Halfmoon Ranch which is located west of the town of Sunsites and is within the Douglas Ranger District of the Coronado National Forest in Cochise County, Arizona. From Tucson: Halfmoon Ranch House may be accessed by using I-10 east approximately 61 miles to Exit #318 (Dragoon Road). Turning right onto Dragoon Road and traveling for approximately 10 miles to the Cochise Stronghold Road. Turn right on Cochise Stronghold Road and travel for approximately 6 miles to Ironwood Road. Turn right on Ironwood Road, towards the Dragoon Mountains and travel for approximately 3 miles to arrive at the Halfmoon Ranch. Halfmoon Ranch is the long ranch house located off to the left of Ironwood Road behind a locked gate. Legal description: Township 17 South, Range 23 East, and Section 24. The coordinates for the site are Latitude: 31.94729 and the Longitude: -109.95445.

Planned Work: The work associated with this project entails installing a ductless climate control system in Halfmoon Ranch, a historic house located in a remote and rural location. Currently there is no climate control system in the building. Halfmoon Ranch is currently one of the properties which is part of the Rooms With A View Cabin Rental Program.

Half Moon Ranch (Residence):

1. Installing three (3) HVAC Ductless split unit systems.

All electrical, plumbing, sheet-metal, duct work, registers, thermostats, electrical lines, refrigerant lines, etc. work shall be considered incidental to the installation of the climate control system equipment.

Planned Disturbance: Construction activities associated with this project will be limited to the inside of the Halfmoon Ranch House. Any ground disturbance shall be limited to previously disturbed areas directly adjacent the buildings/structures.

SPECIFICATIONS

FOR

Halfmoon Ranch House

HVAC INSTALLATION

March 12, 2026

TABLE OF CONTENTS

DIVISION 01 – GENERAL REQUIREMENTS 1

01010 - SCOPE OF WORK 2

1.1 – Definitions 2

1.2 – Description 2

1.3 – Location and Conditions 2

1.4 – Schedule 3

1.5 – Contract Administration 3

1.6 – Quality of Work 3

1.7 – Codes and Standards 3

1.8 – Special Construction Requirements 4

1.9 – Contract Closeout 5

01020 – MEASUREMENT & PAYMENT 6

1.1 – Measurement & Payment 6

01030 - MOBILIZATION 7

1.1 - Summary 7

01050 – SUBMITTALS 8

1.1 - General 8

2.1 - Description 8

2.2 - Products 8

DIVISION 02 – SITE WORK 9

02010 – DEMOLITION 10

1.1 – Description 10

2.1 – Not Used 10

3.1 - Preparation 10

3.2 – Protection 10

3.4 – Removal 10

DIVISION 15 – MECHANICAL 11

15740 – DUCTLESS SPLIT SYSTEM AIR CONDITIONERS 12

1.1 - Summary 12

1.2 – Submittals 12
1.3 – Quality Assurance 12
2.1 – Ductless Split System Air Conditioners 13
2.2 – Accessories 13
3.1 – Installation 13
3.2 – Connections 14
3.3 – Field Quality Control 14
DIVISION 16 – ELECTRICAL 15
16050 – BASIC ELECTRICAL MATERIALS AND METHODS 16
1.1 – Summary 16
1.2 – Submittals 16
1.3 – Quality Assurance 16
1.4 – Coordination 16
2.1 – Raceways 17
2.2 – Wires, Cables and Connections 17
2.3 – Supporting Devices 17
2.4 – Electrical Identification 18
2.5 – Equipment for Utility Company's Electricity Metering 19
2.6 – Concrete Bases 19
3.1 – Electrical Equipment Installation 19
3.2 – Raceway Application 20
3.3 – Raceway and Cable Installation 20
3.4 – Wiring Methods for Power, Lighting and Control Circuits 21
3.5 – Wiring Installation 21
3.6 – Electrical Supporting Device Application 22
3.7 – Support Installation 22
3.8 – Identification Materials and Devices 23
3.9 – Firestopping 23
3.10 – Concrete Bases 24
3.11 – Demolition 24
3.12 – Cutting and Patching 24

DIVISION 01 – GENERAL REQUIREMENTS

01010 - SCOPE OF WORK

PART 1 – GENERAL

1.1 – Definitions

Contractor – the successful bidder who is awarded the contract.

Government – the Contracting Officer (CO) or designated Contracting Officer's Representative (COR) of the Coronado National Forest.

1.2 – Description

Contractor shall furnish all materials, equipment, transportation, labor, supervision, and other associated work necessary to complete work according to the specifications.

The work associated with this project entails installing a climate control system in the Shaw House. Currently there is no climate control system in the building. The Shaw House is currently one of the properties which is part of the Cabin Rental Program.

Scope of work includes:

Half Moon Ranch

1. Installing three (3) HVAC Ductless split unit systems.

*All electrical, plumbing, sheet-metal, duct work, registers, thermostats, electrical lines, refrigerant lines, etc. work shall be considered incidental to the installation of the climate control system equipment. Other infrastructure shall remain in place as part of the system to the maximum extent possible.

1.3 – Location and Conditions

Work will take place at the Half Moon Ranch which is located west of the town of Sunsites and is within the Douglas Ranger District of the Coronado National Forest in Cochise County, Arizona. From Tucson: Half Moon Ranch House may be accessed by using I-10 east approximately 61 miles to Exit #318 (Dragoon Road). Turning right onto Dragoon Road and traveling for approximately 10 miles to the Cochise Stronghold Road. Turn right on Cochise Stronghold Road and travel for approximately 6 miles to Ironwood Road. Turn right on Ironwood Road, towards the Dragoon Mountains and travel for approximately 3 miles to arrive at the Half Moon Ranch. Half Moon Ranch is the long ranch house located off to the left of Ironwood Road behind a locked gate. Legal description: Township 17 South, Range 23 East, and Section 24. The coordinates for the site are Latitude: 31.94729 and the Longitude: -109.95445.

It will be the Contractor's responsibility to familiarize themselves with the existing conditions and notify the Government of any discrepancies shown in these documents.

For delivery of materials and other construction-related items, the Contractor shall coordinate with Contracting Officers Representative (COR) and is advised to determine safe vehicle lengths and load limits for roads that access the site.

1.4 – Schedule

A pre-work meeting for clarification of the project will be held if needed or desired by either the contractor or the Government.

A schedule for all work must be submitted to and approved by the Government prior to construction beginning.

The Contractor shall notify the Forest Service three (5) days in advance of any survey work and seven (14) days in advance of any construction work.

All work shall be completed within 60 days of award.

1.5 – Contract Administration

The Contractor shall be fully responsible for seeing that construction activities conform to the specifications and provisions of this contract. The Government will provide timely reviews as requested by the Contractor and may periodically review work at any time.

Construction quality control shall include supplying all the personnel, equipment, and documentation necessary to ensure that construction is completed in compliance with the specifications and provisions of the contract.

The Contractor shall clearly stake limits of construction and maintain marks throughout construction. The Government will review all staking.

1.6 – Quality of Work

The products listed in the specifications are preferred products chosen for building compatibility and quality. However, equal or better alternatives submitted by the Contractor will be considered and are encouraged.

Use recovered materials, recyclable materials, and environmentally preferable products and services where possible as per Executive Order 13423.

1.7 – Codes and Standards

Codes and standards of the following associations and listed publications will become part of this contract:

1. International Building Code (IBC)
2. National Electrical Code (NEC)
3. National Electrical Manufacturers Association (NEMA)

4. Underwriters' Laboratories, Incorporated (UL)
5. International Mechanical Code (IMC)
6. International Fire Code (IFC)
7. Americans with Disability Act Standards (ADA) for Accessible Design
8. Occupational Health and Safety Administration (OSHA) Standards
9. American Society for Testing and Materials (ASTM)
10. American National Standards Institute (ANSI)
11. National Sanitary Foundation (NSF)

All materials, workmanship, and designs shall meet specified requirements of the standards referenced in this section and other local or state codes, related to this type of work, whichever is more stringent.

If a particular item is not covered by a standard, it shall be proven by certified test by a reputable laboratory to be capable of performing satisfactorily, at no additional cost to the Government.

1.8 – Special Construction Requirements

Upon completion of the project, all demolished improvements and other construction materials shall be removed from Government land and disposed of in accordance with State and County standards.

All site features to remain shall be protected from damage during the project. Any damage to site features shall be repaired to their original condition at the cost of the Contractor.

Construction Access and Protection: The Contractor shall be responsible for securing the project area from the public and government personnel. This includes providing the necessary security for protection of the Contractor's materials, equipment, tools and work until final acceptance by the Government. The Contractor shall also provide sufficient signs, barriers, barricades, markers, etc. to warn of hazardous conditions and to protect people from injury.

Equipment and Material Storage: The Contractor shall obtain permission from the Government for equipment and material storage, and for other areas needed for construction.

Utilities: Electricity and water are available on site.

1.9 – Contract Closeout

Remove temporary facilities and provide final cleaning and touch-up. Restore portions of buildings, site improvements, landscaping, and other items damaged by construction operations to the satisfaction of the Government at no additional expense to the Government.

***** END OF SPECIFICATION 01010 *****

01020 – MEASUREMENT & PAYMENT

PART 1 – GENERAL

1.1 – Measurement & Payment

Measurement and payment for contract work will be made only for and under those pay items included in the SCHEDULE OF ITEMS. All other work and materials will be considered incidental to the completion of the items shown and no separate payment will be made.

***** END OF SPECIFICATION 01020 *****

01030 - MOBILIZATION

PART 1 – GENERAL

1.1 - Summary

Section Includes: Preparatory work and operations, including those necessary to the movement of personnel, equipment, supplies and incidentals to the project site; and for other work and operations which must be performed or costs incurred prior to beginning work on the various items on the project site. This specification does not include moves between project sites.

*****END OF SPECIFICATION 01030*****

01050 – SUBMITTALS

PART 1 – REQUIREMENTS

1.1 - General

It will be the Contractor's responsibility to submit all items with such promptness as to cause no delay in the work. Approvals must be obtained before starting work which involves the item. Contractor shall allow 5 days for processing of submittals by the Government. Submittals may also be referred to as shop drawings.

PART 2 – MANUFACTURER'S LITERATURE AND SHOP DRAWINGS

2.1 - Description

The Contractor shall submit one copy of all submittals to the Government for approval on the items required herein. For each submittal, the Contractor must receive written approval from the Government to use the item before incorporating it into the project work. Literature must be marked or otherwise designated to show the exact model, size, etc. the Contractor proposes to use. Information must be adequate to determine compliance with the specifications. Approvals must be received for products differing from those described in the Government-supplied specifications.

2.2 - Products

Certificates of compliance are required for the following:

1. HVAC Ductless Split Unit System
2. Programmable Thermostat

*****END OF SPECIFICATION 01050*****

*****END OF DIVISION 1*****

DIVISION 02 – SITE WORK

02010 – DEMOLITION

PART 1 – GENERAL

1.1 – Description

The work of this section consists of the following: only minimal demolition associated with installation of the ductless split system components is expected.

PART 2 – PRODUCTS

2.1 – Not Used

PART 3 – EXECUTION

3.1 - Preparation

Coordinate removal work with the Government.

3.2 – Protection

Protect existing structures and features not required to be removed by construction from damage or displacement.

3.4 – Removal

A. All facilities and materials scheduled for demolition must be completely removed off Government lands and disposed of legally by the Contractor.

B. All work shall be performed in a workman like manner, to the quality and standard of the industry. Contractor shall be an experienced firm that has expertise in demolition work similar in material and extent to that indicated for this Project.

*****END OF SPECIFICATION 02010*****

***** END DIVISION 2 *****

DIVISION 15 – MECHANICAL

15740 – DUCTLESS SPLIT SYSTEM AIR CONDITIONERS

PART 1 – GENERAL

1.1 - Summary

This Section includes all labor, equipment, tools, materials, supervision

and transportation to accomplish the following work which consists of but is not limited to

the installation of Ductless Split System Air Conditioners, their accessories, and controls in BTU/HR ratings indicated for each air conditioner:

A. Shaw House

1. Three (3) 1 TON R410A single stage outdoor condensers

2. Three (3) 1 TON indoor wall-mounted units.

The systems shall be equipped with wall mounted digital thermostats. The systems shall have a certified Energy Star Rating and a minimum 20 SEER. System sizing requirements are estimated and the Contractor shall field verify all dimensions, sizes and quantities prior to ordering materials.

1.2 – Submittals

A. Manufacturers Product Data: Include rated capacities, furnished specialties, and accessories for each unit indicated. Include performance data in terms of capacities, outlet velocities, static pressures, sound power characteristics, motor requirements, and electrical characteristics.

B. Wiring Diagrams: Power, signal, and control wiring.

C. Operation and maintenance data.

1.3 – Quality Assurance

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.

B. Energy-Efficiency Ratio: Equal to or greater than prescribed by ASHRAE/IESNA 90.1, "Energy Efficient Design of New Buildings except Low-Rise Residential Buildings. "

C. Coefficient of Performance: Equal to or greater than prescribed by ASHRAE/IESNA 90.1, "Energy Efficient Design of New Buildings except Low-Rise Residential Buildings. "

PART 2 – PRODUCTS

2.1 – Ductless Split System Air Conditioners

A. Daikin 1 TON outdoor air-cooled heat pump unit. Model: RXC24AXVJU (208-230V/1PH, 18 SEER).

B. Daikin indoor wall-mounted unit. Model: FTXC24AXVJU.

2.2 – Accessories

A. Programmable Thermostat/Controller: Microcomputer based with automatic changeover from cooling to heating. Low voltage with subbase to control compressor and evaporator fan.

B. Refrigerant Line Kits: Soft-annealed copper suction and liquid lines factory cleaned, dried, pressurized, and sealed; factory-insulated suction line with flared fittings at both ends.

PART 3 – EXECUTION

3.1 – Installation

A. Install and secure units level and plumb in accordance with requirements required by the building code, maintaining manufacturer's recommended clearances and tolerances.

B. Install evaporator-fan components using manufacturer's standard mounting devices securely fastened to building structure.

C. Install ground-mounted, compressor-condenser components on 4-inch thick, reinforced concrete base; 4 inches larger on each side than unit.

D. This installation will require new electrical connections to include breaker, new conduit, new wiring, disconnect switch and digital thermostats.

E. All electrical work shall be completed by an electrician in accordance with all State and Local electrical codes.

F. Insulation shall be provided and installed on all line sets.

G. All condensate lines shall run to the exterior of the facility, sleeved in PVC and run down to ground level.

H. All penetrations through walls shall be sealed with approved fire sealer.

I. All electrical, plumbing, sheet-metal, duct work, registers, thermostats, electrical lines, refrigerant lines, etc. work shall be considered incidental to the replacement/installation of the equipment. Other infrastructure shall remain in place as part of the system to the maximum extent possible.

3.2 – Connections

A. Connect precharged refrigerant tubing to component's quick-connect fittings. Install tubing to allow access to unit.

B. Install piping adjacent to unit to allow service and maintenance.

C. Unless otherwise indicated, connect piping with unions and shutoff valves to allow units to be disconnected without draining piping.

D. Electrical System Connections: Comply with applicable requirements required by building code for power wiring, switches, and motor controls.

E. Ground equipment in accordance with requirements required by building code for "Grounding and Bonding. "

3.3 – Field Quality Control

A. Installation Inspection: Engage a factory-authorized service representative to inspect field-assembled components and equipment installation, including piping and electrical connections, and to prepare a written report of inspection.

B. Leak Test: After installation, charge system and test for leaks. Repair leaks and retest until no leaks exist.

C. Operational Test: After electrical circuitry has been energized, start units to confirm proper motor rotation and unit operation. Remove malfunctioning units, replace with new components, and retest.

D. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.

*****END OF SPECIFICATION 15740*****

***** END DIVISION 15 *****

DIVISION 16 – ELECTRICAL

16050 – BASIC ELECTRICAL MATERIALS AND METHODS

1.1 – Summary

A. This Section includes the following:

1. Raceways.
2. Building wire and connectors.
3. Supporting devices for electrical components.
4. Electrical identification.
5. Utility company electricity-metering components.
6. Concrete equipment bases.
7. Electrical demolition.
8. Cutting and patching for electrical construction.

1.2 – Submittals

A. Product Data: For utility company electricity-metering components.

B. Shop Drawings: Dimensioned plans and sections or elevation layouts and single-line diagram of electricity-metering component assemblies specific to this Project Codes and Standards:

1.3 – Quality Assurance

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.

B. Devices for Utility Company Electricity Metering: Comply with utility company published standards.

C. Comply with NFPA 70

1.4 – Coordination

A. Coordinate chases, slots, inserts, sleeves, and openings for electrical supports, raceways, and cable with general construction work.

B. Sequence, coordinate, and integrate installing electrical materials and equipment for efficient flow of the Work. Coordinate installing large equipment that requires positioning before closing in the building.

C. Where electrical identification devices are applied to field-finished surfaces, coordinate installation of identification devices with completion of finished surface.

PART 2 – PRODUCTS

2.1 – Raceways

A. EMT: Electrical metallic tubing; ANSI C80.3, zinc-coated steel, with set-screw or compression fittings.

B. FMC: Flexible metal conduit; zinc-coated steel.

C. IMC: Intermediate metal conduit; ANSI C80.6, zinc-coated steel, with threaded fittings.

D. LFMC: Liquid tight flexible metal conduit; zinc-coated steel with sunlight-resistant and mineral-oil-resistant plastic jacket.

E. RMC: Rigid metal conduit; galvanized rigid steel; ANSI C80.1.

F. RNC: Rigid nonmetallic conduit; NEMA TC 2, Schedule 40 PVC, with NEMA TC3 fittings.

G. Raceway Fittings: Specifically designed for raceway type with which used.

2.2 – Wires, Cables and Connections

A. Conductors, No. 10 AWG and Smaller: Solid or stranded copper.

B. Conductors, Larger Than No. 10 AWG: Stranded copper.

C. Insulation: Thermoplastic, rated 600 V, 75 deg C minimum, Type THW, THHN-THWN, or USE depending on application..

D. Cable: Type MC, ACTH,NM-B and NMC-B with ground wire.

E. Wire Connectors and Splices: Units of size, ampacity rating, material, type, and class suitable for service indicated.

2.3 – Supporting Devices

A. Material: Cold-formed steel, with corrosion-resistant coating.

B. Metal Items for Use Outdoors or in Damp Locations: Hot-dip galvanized steel.

C. Slotted-Steel Channel: Flange edges turned toward web, and 9/16-inch- (14-mm-) diameter slotted holes at a maximum of 2 inches (50 mm) o.c., in webs. Strength rating to suit structural loading.

D. Nonmetallic Slotted Channel and Angle: Structural-grade, factory-formed, glass-fiber-resin channels and angles with 9/16-inch- (14-mm-) diameter holes at a maximum of 8 inches (203 mm) o.c., in at least one surface. Strength rating to suit structural loading.

E. Slotted Channel Fittings and Accessories: Recommended by the manufacturer for use with the type and size of channel with which used.

    1. Materials: Same as channels and angles, except metal items may be stainless steel.

F. Raceway and Cable Supports: Manufactured clevis hangers, riser clamps, straps, threaded C-clamps with retainers, ceiling trapeze hangers, wall brackets, and spring-steel clamps or click-type hangers.

G. Pipe Sleeves: ASTM A 53, Type E, Grade A, Schedule 40, galvanized steel, plain ends.

H. Cable Supports for Vertical Conduit: Factory-fabricated assembly consisting of threaded body and insulating wedging plug for nonarmored electrical cables in riser conduits. Plugs have number and size of conductor gripping holes as required to suit individual risers. Body constructed of malleable-iron casting with hot-dip galvanized finish.

I. Expansion Anchors: Carbon-steel wedge or sleeve type.

J. Toggle Bolts: All-steel springhead type.

K. Powder-Driven Threaded Studs: Heat-treated steel.

2.4 – Electrical Identification

A. Identification Device Colors: Use those prescribed by ANSI A13.1, NFPA 70, and these Specifications.

B. Colored Adhesive Marking Tape for Raceways, Wires, and Cables: Self-adhesive vinyl tape, not less than 1 inch wide by 3 mils thick (25 mm wide by 0.08 mm thick).

C. Tape Markers for Conductors: Vinyl or vinyl-cloth, self-adhesive, wraparound type with preprinted numbers and letters.

D. Color-Coding Cable Ties: Type 6/6 nylon, self-locking type. Colors to suit coding scheme.

E. Underground Warning Tape: Permanent, bright-colored, continuous-printed, vinyl tape compounded for permanent direct-burial service, and with the following features:

1. Not less than 6 inches wide by 4 mils thick (150 mm wide by 0.102 mm thick).

2. Embedded continuous metallic strip or core.

3. Printed legend that indicates type of underground line.

F. Engraved-Plastic Labels, Signs, and Instruction Plates: Engraving stock, melamine plastic laminate punched or drilled for mechanical fasteners 1/16-inch (1.6-mm) minimum thickness for signs up to 20 sq. in. (129 sq. cm) and 1/8-inch (3.2-mm) minimum thickness for larger sizes. Engraved legend in black letters on white background.

G. Warning and Caution Signs: Preprinted; comply with 29 CFR 1910.145, Chapter XVII. Colors, legend, and size appropriate to each application.

1. Interior Units: Aluminum, baked-enamel-finish, punched or drilled for mechanical fasteners.

2. Exterior Units: Weather-resistant, nonfading, preprinted, cellulose-acetate butyrate with 0.0396-inch (1-mm), galvanized-steel backing. 1/4-inch (6-mm) grommets in corners for mounting

H. Fasteners for Nameplates and Signs: Self-tapping, stainless-steel screws or No. 10/32 stainless-steel machine screws with nuts and flat and lock washers.

2.5 – Equipment for Utility Company's Electricity Metering

A. Comply with requirements of electrical power utility company for current transformer cabinets, meter sockets, modular meter centers.

2.6 – Concrete Bases

A. Concrete: 3000-psi (20.7-MPa), 28-day compressive strength.

PART 3 – EXECUTION

3.1 – Electrical Equipment Installation

A. Headroom Maintenance: If mounting heights or other location criteria are not indicated, arrange and install components and equipment to provide maximum possible headroom.

B. Materials and Components: Install level, plumb, and parallel and perpendicular to other building systems and components, unless otherwise indicated.

C. Equipment: Install to facilitate service, maintenance, and repair or replacement of components. Connect for ease of disconnecting, with minimum interference with other installations.

D. Right of Way: Give to raceways and piping systems installed at a required slope.

3.2 – Raceway Application

A. Outdoor Installations:

1. Exposed: IMC, RMC or RNC.
2. Concealed: IMC, RMC or RNC.
3. Underground, Single Run: RMC or RNC.
4. Underground, Grouped: RNC.
5. Connection to Vibrating Equipment: LFMC.
6. Boxes and Enclosures: NEMA 250, Type 3R or Type 4, unless otherwise indicated.

B. Indoor Installations:

1. Exposed: EMT except in wet or damp locations, use IMC.
2. Concealed in Walls or Ceilings: EMT.
3. In Concrete Slab: IMC, RMC, RNC or EMT.
4. Below Slab on Grade or in Crawlspace: IMC, RMC or RNC.
5. Connection to Vibrating Equipment: FMC; except in wet or damp locations: LFMC.
6. Boxes and Enclosures: NEMA 250, Type 1, unless otherwise indicated.

3.3 – Raceway and Cable Installation

A. Conceal raceways and cables, unless otherwise indicated, within finished walls, ceilings, and floors.

B. Keep legs of raceway bends in the same plane and keep straight legs of offsets parallel.

C. Use RMC elbows where RNC turns out of slab.

D. Install pull wires in empty raceways. Use No. 14 AWG zinc-coated steel or woven polypropylene or monofilament plastic line with not less than 200-lb (90-kg) tensile strength. Leave at least 12 inches (300 mm) of slack at each end of pull wires.

E. Install telephone and signal system raceways, 2-inch trade size (DN 53) and smaller, in maximum lengths of 150 feet (45 m) and with a maximum of two 90-degree bends or equivalent. Add pull boxes where necessary to accomplish this.

F. Connect motors and equipment subject to vibration, noise transmission, or movement with a maximum of 72-inches (1830-mm) flexible conduit. Install LFMC in wet or damp locations. Install separate ground conductor across flexible connections.

G. Set floor boxes level and trim after installation to fit flush to finished floor surface.

3.4 – Wiring Methods for Power, Lighting and Control Circuits

A. Application: Use wiring methods specified below to the extent permitted by applicable codes as interpreted by authorities having jurisdiction.

B. Exposed Feeders: Insulated single conductors in raceway, Metal-clad cable, Armored cable or Nonmetallic sheathed cable.

C. Concealed Feeders in Ceilings, Walls, Gypsum Board Partitions: Insulated single conductors in raceway, Metal-clad cable, Armored cable or Nonmetallic sheathed cable.

D. Concealed Feeders in Concrete, below Floors on Grade, in Crawlspaces: Insulated single conductors in raceway.

E. Exposed Branch Circuits Including in Crawlspaces: Insulated single conductors in raceway, Metal-clad cable, Armored cable or Nonmetallic sheathed cable.

F. Concealed Branch Circuits in Ceilings, Walls, Gypsum Board Partitions: Insulated single conductors in raceway, Metal-clad cable, Armored cable or Nonmetallic sheathed cable.

G. Concealed Branch Circuits in Concrete, below Floors on Grade: Insulated single conductors in raceway.

H. Underground Feeders and Branch Circuits: Insulated single conductors in raceway.

I. Remote-Control Signaling and Power-Limited Circuits, Classes 1, 2, and 3: Insulated conductors in raceway unless otherwise indicated.

3.5 – Wiring Installation

A. Make splices and taps that are compatible with conductor material and that possess equivalent or better mechanical strength and insulation ratings than unspliced conductors.

3.6 – Electrical Supporting Device Application

A. Damp Locations and Outdoors: Hot-dip galvanized materials or nonmetallic, slotted channel system components.

B. Dry Locations: Steel materials.

C. Strength of Supports: Adequate to carry present and future loads, times a safety factor of at least four with, 200-lb (90-kg) minimum design load for each support element.

3.7 – Support Installation

A. Support parallel runs of horizontal raceways together on trapeze- or bracket-type hangers.

B. Size supports for multiple raceway or cable runs so capacity can be increased by a 25 percent minimum in the future.

C. Support individual horizontal single raceways with separate, malleable-iron pipe hangers or clamps.

D. Install sleeves for cable and raceway penetrations of concrete slabs and walls unless core-drilled holes are used. Install sleeves for cable and raceway penetrations of masonry and fire-rated gypsum walls and of all other fire-rated floor and wall assemblies. Install sleeves during erection of concrete and masonry walls.

E. Secure electrical items and their supports to building structure, using the following methods unless other fastening methods are indicated:

1. Wood: Wood screws or screw-type nails.

2. Gypsum Board: Toggle bolts. Seal around sleeves with joint compound, both sides of wall.

3. Masonry: Toggle bolts on hollow block and expansion bolts on solid block. Seal around sleeves with mortar, both sides of wall.

4. New Concrete: Concrete inserts with machine screws and bolts.

5. Existing Concrete: Expansion bolts or threaded studs driven by powder charge and provided with lock washers.

6. Structural Steel: Welded threaded studs, Spring-tension clamps or Threaded studs driven by powder charge and provided with lock washers.

    i. Comply with AWS D1.1 for field welding.

7. Light Steel Framing: Sheet metal screws.

8. Fasteners for Damp, Wet, or Weather-Exposed Locations: Stainless steel.

9. Light Steel: Sheet-metal screws.

10. Fasteners: Select so load applied to each fastener does not exceed 25 percent of its proof-test load.

3.8 – Identification Materials and Devices

A. Install at locations for most convenient viewing without interference with operation and maintenance of equipment.

B. Coordinate names, abbreviations, colors, and other designations used for electrical identification with corresponding designations indicated in the Contract Documents or required by codes and standards. Use consistent designations throughout Project.

C. Self-Adhesive Identification Products: Clean surfaces before applying.

D. Tag and label circuits designated to be extended in the future. Identify source and circuit numbers in each cabinet, pull and junction box, and outlet box. Color-coding may be used for voltage and phase identification.

E. Install continuous underground plastic markers during trench backfilling, for exterior underground power, control, signal, and communication lines located directly above power and communication lines. Locate 6 to 8 inches (150 to 200 mm) below finished grade. If width of multiple lines installed in a common trench or concrete envelope does not exceed 16 inches (400 mm), overall, use a single line marker.

F. Install warning, caution, and instruction signs where required to comply with 29 CFR 1910.145, Chapter XVII, and where needed to ensure safe operation and maintenance of electrical systems and of items to which they connect. Indoors install engraved plastic-laminated instruction signs with approved legend where instructions are needed for system or equipment operation. Install metal-backed butyrate signs for outdoor items.

G. Install engraved-laminated emergency-operating signs with white letters on red background with minimum 3/8-inch- (9-mm-) high lettering for emergency instructions on power transfer, load shedding, and other emergency operations.

3.9 – Firestopping

A. Apply Firestopping to cable and raceway sleeves and other penetrations of fire-rated floor and wall assemblies to restore original undisturbed fire-resistance ratings of assemblies.

3.10 – Concrete Bases

A. Construct concrete bases of dimensions indicated, but not less than 4 inches (100 mm) larger, in both directions, than supported unit. Follow supported equipment manufacturer's anchorage recommendations and setting templates for anchor-bolt and tie locations, unless otherwise indicated.

3.11 – Demolition

A. Protect existing electrical equipment and installations indicated to remain. If damaged or disturbed in the course of the Work, remove damaged portions and install new products of equal capacity, quality, and functionality.

B. Accessible Work: Remove exposed electrical equipment and installations, indicated to be demolished, in their entirety.

C. Abandoned Work: Cut and remove buried raceway and wiring, indicated to be abandoned in place, 2 inches (50 mm) below the surface of adjacent construction. Cap raceways and patch surface to match existing finish.

D. Remove, store, clean, reinstall, reconnect, and make operational components indicated for relocation.

3.12 – Cutting and Patching

A. Cut, channel, chase, and drill floors, walls, partitions, ceilings, and other surfaces required to permit electrical installations. Perform cutting by skilled mechanics of trades involved.

B. Repair, refinish and touch up disturbed finish materials and other surfaces to match adjacent undisturbed surfaces.

*****END OF SPECIFICATION 16050*****

*****END OF SPECIFICATIONS*****

Schedule of Items

Pay Item	Description	Method of Measurement	Est. Quantity	Unit Price	Total
1.00	Supply and Install HVAC Ductless split unit system	EA	3		

Total

Vendor Name:_____

Unique SAM ID:_____

Period of Performance Date Available:_____

SIGNATURE:_____

"General Decision Number: AZ20260038 05/18/2026

State: Arizona

Construction Types: Building

Counties: Arizona Counties of
Cochise

Modification Number	Publication Date
0	01/02/2026
1	05/18/2026

BRAZ0003-001 07/01/2024

	Rates	Fringes
BRICKLAYER	$ 32.29	9.97

CARP1912-001 07/01/2025

	Rates	Fringes
CARPENTER	$ 33.19	19.20

ELEC0570-001 06/01/2025

	Rates	Fringes
ELECTRICIAN (EXCLUDES LOW VOLTAGE WIRING)	$ 33.00	13.04

ENGI0428-016 06/01/2023

	Rates	Fringes
POWER EQUIPMENT OPERATOR: CRANE	$ 36.04	13.52
POWER EQUIPMENT OPERATOR: BULLDOZER	$ 31.69	13.52

IRON0075-007 08/01/2025

	Rates	Fringes
IRONWORKER, STRUCTURAL	$ 33.00	19.91

PLUM0469-009 07/01/2025

	Rates	Fringes
PIPEFITTER	$ 51.15	21.00

SHEE0359-001 07/01/2025

	Rates	Fringes
SHEET METAL WORKER	$ 49.39	19.86

SUAZ2019-001 06/12/2023

	Rates	Fringes
TILE SETTER	$ 21.50	0.00
PLUMBER	$ 28.51	0.00
PAINTER	$ 15.00	0.00

OPERATOR: ROLLER	$ 23.62	6.44
OPERATOR: LOADER	$ 15.00	4.15
OPERATOR: BACKHOE/EXCAVATOR/TRACKHOE	$ 19.58	3.79
LABORER: PIPELAYER	$ 16.77	1.05
LABORER: MASON TENDER - CEMENT/CONCRETE	$ 19.79	0.00
LABORER: COMMON OR GENERAL	$ 12.00	0.00
IRONWORKER, REINFORCING	$ 22.04	0.00
ELECTRICIAN (LOW VOLTAGE WIRING)	$ 26.16	9.91
DRYWALL FINISHER/TAPER	$ 22.47	0.00
CEMENT MASON/CONCRETE FINISHER	$ 21.00	0.00

WELDERS - Receive rate prescribed for craft performing operation to which welding is incidental.

==========

Note: Executive Order (EO) 13706, Establishing Paid Sick Leave for Federal Contractors applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2017. If this contract is covered by the EO, the contractor must provide employees with 1 hour of paid sick leave for every 30 hours they work, up to 56 hours of paid sick leave each year. Employees must be permitted to use paid sick leave for their own illness, injury or other health-related needs, including preventive care; to assist a family member (or person who is like family to the employee) who is ill, injured, or has other health-related needs, including preventive care; or for reasons resulting from, or to assist a family member (or person who is like family to the employee) who is a victim of, domestic violence, sexual assault, or stalking. Additional information on contractor requirements and worker protections under the EO is available at https://www.dol.gov/agencies/whd/government-contracts.

Note: Executive Order 13658 generally applies to contracts subject to the Davis-Bacon Act that were awarded on or between January 1, 2015 and January 29, 2022, and that have not been renewed or extended on or after January 30, 2022. Executive Order 13658 does not apply to contracts subject only to the Davis-Bacon Related Acts regardless of when they were awarded. If a contract is subject to Executive Order 13658, the contractor must pay all covered workers at least $13.65 per hour (or the applicable wage rate listed on this wage determination, if it is higher) for all hours spent performing on the contract from May 11, 2026, through December 31, 2026. The applicable Executive Order minimum wage rate will be adjusted annually. Additional information on contractor requirements and worker protections under Executive Order 13658 is available at www.dol.gov/whd/govcontracts.

Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29CFR 5.5 (a) (1) (iii)).

The body of each wage determination lists the classifications and wage rates that have been found to be prevailing for the type(s) of construction and geographic area covered by the wage determination. The classifications are listed in alphabetical order under rate identifiers indicating whether the particular rate is a union rate (current union negotiated rate), a survey rate, a weighted union average rate, a state adopted rate, or a supplemental classification rate.

Union Rate Identifiers

A four-letter identifier beginning with characters other than
�SU�, �UAVG�, �SA�, or �SC� denotes that a union rate was
prevailing for that classification in the survey. Example:
PLUM0198-005 07/01/2024. PLUM is an identifier of the union
whose collectively bargained rate prevailed in the survey for
this classification, which in this example would be Plumbers.
0198 indicates the local union number or district council
number where applicable, i.e., Plumbers Local 0198. The next
number, 005 in the example, is an internal number used in
processing the wage determination. The date, 07/01/2024 in the
example, is the effective date of the most current negotiated
rate.

Union prevailing wage rates are updated to reflect all changes
over time that are reported to WHD in the rates
in the collective bargaining agreement (CBA) governing the
classification.

Union Average Rate Identifiers

The UAVG identifier indicates that no single rate prevailed for
those classifications, but that 100% of the data reported for
the classifications reflected union rates. EXAMPLE:
UAVG-OH-0010 01/01/2024. UAVG indicates that the rate is a
weighted union average rate. OH indicates the State of Ohio.
The next number, 0010 in the example, is an internal number
used in producing the wage determination. The date, 01/01/2024
in the example, indicates the date the wage determination was
updated to reflect the most current union average rate.

A UAVG rate will be updated once a year, usually in January, to
reflect a weighted average of the current rates in the
collective bargaining agreements on which the rate is based.

Survey Rate Identifiers

The �SU� identifier indicates that either a single non-union
rate prevailed (as defined in 29 CFR 1.2) for this
classification in the survey or that the rate was derived by
computing a weighted average rate based on all the rates
reported in the survey for that classification. As a weighted
average rate includes all rates reported in the survey, it may
include both union and non-union rates. Example: SUFL2022-007
6/27/2024. SU indicates the rate is a single non-union
prevailing rate or a weighted average of survey data for that
classification. FL indicates the State of Florida. 2022 is the
year of the survey on which these classifications and rates are
based. The next number, 007 in the example, is an internal
number used in producing the wage determination. The date,
6/27/2024 in the example, indicates the survey completion date
for the classifications and rates under that identifier.

�SU� wage rates typically remain in effect until a new survey
is conducted. However, the Wage and Hour Division (WHD) has the
discretion to update such rates under 29 CFR 1.6(c)(1).

State Adopted Rate Identifiers

The �SA� identifier indicates that the classifications and
prevailing wage rates set by a state (or local) government were
adopted under 29 C.F.R 1.3(g)-(h). Example: SAME2023-007
01/03/2024. SA reflects that the rates are state adopted. ME
refers to the State of Maine. 2023 is the year during which the
state completed the survey on which the listed classifications
and rates are based. The next number, 007 in the example, is an

internal number used in producing the wage determination.
The date, 01/03/2024 in the example, reflects the date on which
the classifications and rates under the "SA" identifier took
effect under state law in the state from which the rates were
adopted.

WAGE DETERMINATION APPEALS PROCESS

1) Has there been an initial decision in the matter? This can be:

a) a survey underlying a wage determination
b) an existing published wage determination
c) an initial WHD letter setting forth a position on a wage determination matter
d) an initial conformance (additional classification and rate) determination

On survey related matters, initial contact, including requests for summaries of surveys, should be directed to the WHD Branch of Wage Surveys. Requests can be submitted via email to davisbaconinfo@dol.gov or by mail to:

Branch of Wage Surveys
Wage and Hour Division
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

Regarding any other wage determination matter such as conformance decisions, requests for initial decisions should be directed to the WHD Branch of Construction Wage Determinations. Requests can be submitted via email to BCWD-Office@dol.gov or by mail to:

Branch of Construction Wage Determinations
Wage and Hour Division
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

2) If an initial decision has been issued, then any interested party (those affected by the action) that disagrees with the decision can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Requests for review and reconsideration can be submitted via email to dba.reconsideration@dol.gov or by mail to:

Wage and Hour Administrator
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

The request should be accompanied by a full statement of the interested party's position and any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210.

==========

END OF GENERAL DECISION

"