STATEMENT OF WORK

Project PBXP272018

B422 Kitchenette Renovation

MANSFIELD LAHM ANG BASE

MANSFIELD, OHIO

Table of Contents	1
General Requirements	2-3
Project Description	3-5

1. General Requirements

1.1. The contractor shall provide all labor, materials, equipment, supervision, and incidentals necessary to expand and renovate the existing second-floor kitchenette/breakroom in the Wing Headquarters building at Mansfield Lahm ANGB, Ohio. Work shall be performed in accordance with this Statement of Work, the accompanying drawings, and the referenced specifications.

1.2. The location of the proposed work is within the main cantonment area of the Mansfield Lahm ANG Base, Mansfield, Ohio.

1.3. The contractor shall not exceed the scope of work without prior approval from the Contracting Officer.

1.4. The contractor shall protect all government property from damage. Any damages incurred in pursuance of this project shall be replaced and/or restored to original condition.

1.5. The contractor shall maintain a clean and safe job site at all times to prevent damage to other existing utilities, and surrounding facilities that may be affected; this is intended to protect building occupants from potential health hazard associated with the proposed work. This shall include dust, debris, and waste created in performance of this project; along with tools, and equipment located at the job site. The contractor shall comply with the provisions of the Occupational Safety and Health Act of 1972 and all provisions thereto.

1.6. The Contractor is responsible for properly laying out the work, and for lines and measurements for the work executed under the Contract Documents.

1.6.1. The Contractor, not the Government, is responsible to field verify all utilities within the project limits and/or as shown on the Drawings, before laying out the work. The Contractor is to report errors or inaccuracies in writing to the Contracting Officer's Representative before commencing work.

1.6.2. The Contracting Officer or his Representative will in no case assume the responsibility for any layout of the work or damages while performance of work is underway.

1.7. The Contractor shall field verify all dimensions. The dimensions provided by the Government are only approximations and they are not responsible for their precision or accuracy. This includes but is not limited to blueprints, drawings, schedules, and statements of work.

1.8. The contractor shall provide a one-year warranty for the work contained herein. They shall pass along extended guarantees for equipment and products.

1.9. All trash, waste, and construction debris generated from this project shall become property of the contractor and shall be removed from the base. The disposal of these materials shall follow the appropriate Federal and State laws. This includes the disposal or recycling of hazardous materials. The contractor shall report the disposition of all waste to the COR. Report shall detail weights of waste landfilled, diverted, and recycled.

1.10. Bids for this project shall be valid for 90 days.

1.11. Point of Contact for this project is Captain Clayton McCarthy at (419)-520-6158 or Mr. Joe Logan at (419)520-6051.

2. Project Description

2.1. The contractor shall demolish and reconfigure the existing interior partition walls as indicated on the drawings to expand the kitchenette footprint, including demolition of the existing half-height wall and construction of new full-height wall assembly to match adjacent construction.

2.1.1. The contractor shall furnish and install new commercial/institutional-grade base cabinets, wall cabinets, solid surface countertop, and 4-inch backsplash as indicated on the drawings and approved submittals.

2.1.2. The contractor shall furnish and install one (1) new single-bowl sink and one (1) new gooseneck faucet in the existing general location. The sink shall be a minimum of 24-inches wide. The contractor shall provide all required plumbing modifications, trim, connections, and appurtenances necessary for a complete and operational installation.

2.1.3. The contractor shall furnish and install new resilient flooring and new cove base throughout the renovated kitchenette footprint.

2.1.3.1. Provide transitions as required between new flooring and adjacent existing finishes.

2.1.4. The contractor shall prepare and paint all new wall construction and all existing wall surfaces within the renovated kitchenette area.

2.1.5. The contractor shall modify the existing suspended ceiling system as required to accommodate the revised wall layout, including relocation or replacement of ceiling grid members and ceiling tiles as required.

2.1.6. The contractor shall provide all required electrical work associated with the kitchenette renovation, including demolition, relocation, modification, and installation of receptacles, branch circuitry, lighting, and associated devices required for the revised layout.

2.1.6.1. The contractor shall provide code-compliant countertop receptacles, including GFCI protection where required, for a complete and operational installation.

2.1.6.2. The contractor shall provide one (1) additional branch circuit for countertop/appliance receptacles as required to support breakroom equipment loads.

2.1.6.3. The contractor shall furnish and install four (4) new 2x2 LED light fixtures in the renovated kitchenette and provide all associated wiring, connections, and minor ceiling modifications required for a complete installation.

2.1.7. The contractor shall relocate, modify, or reconnect existing communications outlets and associated devices if impacted by demolition or the revised room configuration.

2.1.8. The contractor shall provide minor mechanical modifications as required to accommodate the revised room layout, including adjustment or relocation of ceiling diffusers and associated components if impacted by the work.

2.1.9. The contractor shall modify fire alarm devices and associated components only if impacted by demolition or new construction, and shall restore the system to proper operation upon completion of the work.

2.2. Demolition and Disposal

2.2.1. The contractor shall be responsible for selective demolition, removal, and off-site disposal of all materials and debris generated by this project.

2.2.2. The contractor shall protect adjacent building finishes and building systems from damage during construction and shall repair any damage caused by the contractor at no additional cost to the Government.

2.2.3. The contractor shall maintain dust control and housekeeping measures sufficient to contain debris and minimize migration of dust to adjacent areas during demolition and construction.

2.2.4. The contractor shall field verify existing conditions and dimensions affecting the work prior to fabrication, procurement, and installation of materials.

2.3. Closeout

2.3.1. The contractor shall ensure all installed systems, fixtures, devices, and finishes are complete, properly connected, and fully operational.

2.3.2. The contractor shall patch and restore all disturbed architectural, electrical, communications, mechanical, and fire alarm elements affected by the work to a finished condition matching adjacent surfaces where applicable.

2.3.3. The contractor shall leave the work area clean and ready for Government use upon completion of the project.

2.4. Special Considerations: There are NO special project considerations other than requirements on the drawings and as required in specification sections of the project documents.

2.5. Government Furnished Property: There is NO Government furnished property provided for this project.

End Statement of Work