

GENERAL NOTES:

A. DISTURBED ROCK/RIPRAP NOT TO EXCEED EXIST GRADE ALONG SLOPE.

B. REFER TO SPECIFICATION 32 32 16 – PRECAST MODULAR BLOCK RETAINING WALL FOR MODULAR BLOCK WALL DESIGN AND CONSTRUCTION.

KEYNOTES (X)

1. WIRE MESH TO BE INSTALLED ACROSS EXTENTS OF RIPRAP SLOPE USING ROCK ANCHOR ASSEMBLIES FASTENED TO SPIKE PLATES. SEE DETAIL 1, SHEET 051C503 FOR PROPOSED ROCK FOUNDATION ANCHOR ARRANGEMENT.

2. REPLACE EXISTING TIMBER WALL WITH MODULAR BLOCK WALL. TOP OF MODULAR BLOCK WALL TO BE 4961.58'.

5 0 5 10
SCALE OF FEET
1" = 5'

Registered Professional Engineer (Civil)
CERTIFICATE NO.
76139
NICHOLAS
HUMPHREY
10-9-2026
Date Signed
ARIZONA, U.S.A.

Nicholas Humphrey

A/E FIRM PRIME: HDR ENGINEERING, INC. DENVER, CO 80202	DESIGNED: S. RACE CADD C. WITTENMEIER TECH. REVIEW: GOUGH/GLOVER DATE: JUNE 2026	SUB SHEET NO. 051 C401	TITLE OF SHEET SITEWORK SLOPE STABILIZATION ENLARGED SITE PLAN NORTH RIM - GRAND CANYON NATIONAL PARK	DRAWING NO. 113 182752 PMIS/PKG NO. 318719 SHEET 20 OF 113

10/12/2026 Green, Jake C:\Users\jagreen\DC\ACCDocs\HDR\10350545_NPS_GRCA_N_Rim_Utility_2022\Project Files\CAD_HDR\DRAWINGS\CIVIL\051-C401.dwg