
Solicitation 140P2026R0098		GRTE 237343 - Rehabilitate 4 Lazy 4 Ranch	
Question No.	**Sheet or Reference**	**Question**	**Response**
1		Force Main Installation Method: Section 33 14 15 subsection 1.1.A.2.C and Note 6 on Sheet C300 indicates the sewer force main to be plowed. Section 33 14 15 subsection 3.2.F.3 indicates “To keep within the proposed limits of disturbance, contractors may utilize alternative construction techniques such as plowing the force main”. Please confirm if open-cut trenching per Detail 1/C205 is acceptable provided work remains within the 15-ft limit of disturbance (Detail 3/C305) and one 10-ft travel lane is maintained (33 14 15 subsection 3.2.F.2).	Plowing is required for force main installation to expedite installation and minimize impact to Park operations and wildlife. Plowing is the required method for force main installation in roadways; performance-based standards must be met.
2		Plowed Sections: If plowing is required, please confirm the bedding, compaction testing (33 14 15 subsection 3.2.G), and blue board insulation (33 14 15 subsection 3.2.F.7; Detail 2/C205) requirements for plowed sections.	Plowing is required for force main installation to expedite installation and minimize impact to Park operations and wildlife. Pipe installation requirements per Details 1&2/C205 are applicable to open trench installation as required for gravity mains. Avoid force main insulation by ensuring minimum 6' cover over all force main pipe. If minimum cover is not possible, insulate above plowed pipe with minimum 2" thickness of overlapping blue board per foot of difference in cover between 6' and installed depth.
3		Cobbles and Boulders: The Geotechnical-Engineering Report (Section J, Attachment 6) identifies 5–45% cobbles and boulders. Please confirm whether open cut is permitted where cobbles or boulders prevent plowing.	Plowing will occur in roadway. This method has been previously employed successfully in the park. Pipe installation must comply with performance-based standards per Wyoming DEQ. Plowing; deflection and leakage requirements must be met.
4		Fiber in Common Trench: The area will be disturbed twice if the force main is plowed and the fiber is trenched in the same 15-ft strip (C300). Please confirm if the fiber can go in the same trench and the required separation if NPS approves open cut for the force main.	Yes, fiber to be installed in separate open cut trench.
5		Will contractors be able to camp or will NPS provide an RV/camper spots for contractors?	Contractors cannot camp on site and NPS does not have any RV/camper spots available for contractor use.
6		On the main lodge, is there a species of wood spec'd for the wall base and/or the interior wood paneling? I assume this specification would be applicable to all cabin renovations.	WOOD BASE: See section 062000 "Finish Carpentry" 2.1.C.1. and 2.2.B. for wood base description and material type. See Room Finish Schedule on A905 sheets for wood base (WB-1) locations. See 000 A901 for profile. Contractor to test and match existing trim materials but for bidding purposes, assume a Douglas fir. WOOD PANELING: There are two wood paneling materials used in the project (WP-1 & WP-2). See section 064200 "Wood Paneling" 2.1.B. & C. for description of both paneling types. See Room Finish Schedule on A905 sheets for wood paneling locations. See 000 A901 for profile. Contractor to test and match existing materials but for bidding purposes, assume a knotty pine for WP-1 and a Douglas fir for WP-2.

Question No.	Sheet or Reference	Question	Response
7		Government provided materials- (see spec section 01 11 00-3 B 3) Can we get clarification on if they plan to provide all site conduits including conduit for fiber optic, fire alarm system, power conduits and all associated handholes for each system? Or is it just for the Fiber Optics?	Materials will only be provided for the Fiber Optics system. See notes 7 & 8 on sheet C202.
8		Is there any order of importance regarding which cabins need to be renovated? Are there certain cabins you would like us to start rehabbing first?	The Bid Options are generally listed in order of priority, as reflected on the bid sheet, with the lodge as the first choice. This order may shift based on proposal pricing, but that is the intended priority.
9		Is there a bath accessories/fixtures schedule?	Bathroom accessories are shown on interior bathroom elevations and interior elevations. They are identified with abbreviated callouts that correspond to products in specification section 10 28 00. Minor clarifications at bathroom elevations and in the specification will be included in a forthcoming addendum. Bathroom fixtures are scheduled on plumbing drawings.
10		Reference: Div 28 (fire alarm) The specifications require a minimum ¾" conduit to fire alarm devices. Is cable-only wiring to devices acceptable? If so, please revise the device wiring requirement.	All fire alarm system conductors shall be run in conduit.
11		Reference: E100 Keynotes 8-9 Please provide additional information for the grinder pump motor electrical connection.	See updated plans issued based on DEQ comments clouded as Revision 1. Specifically, see detail 4 on sheet 000 E004, and detail 4 on sheet 000 C204.
12		Who will accept the existing light fixtures retained for rehabilitation?	Suggest coordinating with local lighting reps for this scope of work, including but not limited to: TLA North, Quantum Lighting, MH Lighting, and Northern Rockies Agency.
13		Reference: Div 26 a. Is NM (nonmetallic) cable approved for crawl spaces and protected areas? b. Is wiring to devices (outlets, switches, lighting) required in painted EMT conduit for vertical runs?	a. Yes b. Where exposed, yes painted EMT conduit shall be used.
14		Reference: E100 Keynote 4 Please confirm the existing feeder conductors and conduit from the LVE CT can to the existing disconnects are code compliant and reusable. Unless directed otherwise, no replacement of these conductors will be included without additional information.	Confirmed. Intent is to reuse these existing direct-bury feeders as shown in documents.

Question No.	Sheet or Reference	Question	Response
15		What is the intent for outlets on log walls? a. Recessed in the logs, with holes bored to the crawl space? This requires NM or MC cable with access holes; conduit is very difficult to conceal in log walls. b. Surface boxes mounted on the log face? Surface boxes (1-5/8" deep four-square or single-gang handy boxes) have visible knockouts and an industrial look, with conduit surface-mounted to the crawl space. Varying log diameters will make the installation look uneven.	See detail 3 on sheet 000 E003. As noted, preference is concealed. New wiring shall be concealed within walls, crawl space, and ceiling cavity to greatest extent possible. Where removal and replacement of log wall chinking is feasible, cabling shall be concealed behind interior wall chinking. NM or MC cable is allowed where concealed. Reuse existing path where possible. All routing shall be planned and approved by the Contracting Officer prior to implementation. Existing historic building components, including logs, may not be drilled or otherwise damaged to create pathway for electrical cabling. Where exposed surface mount routing is necessary, wiring shall be provided in painted EMT conduit, run vertically from crawl space or ceiling. Surface mount boxes shall be painted too.
16		Reference: Div 26 (grounding and bonding); Div 22 a. Is the existing water service to the cabins and lodge metal or PVC? b. If metal, are service bonding jumpers required across dielectric connections? c. Interior domestic water is copper per the specifications. Please confirm bonding requirements.	a. All existing water services to the cabins are being removed and replaced per contract documents. See civil and plumbing documents. b. Yes, as per NEC 250.68(B) and specification 260526 part 3.4.D. c. Bonding is required per NEC 250.104(A)**.**
17		a. Section 26 05 44 lists several acceptable products. Which is preferred for this project? b. What is required at conduit penetrations through cabin floors to surface-mounted outlets on log walls? Is silicone around the conduit acceptable? c. Is silicone acceptable at NM cable penetrations through 2x4 plates to the crawl space?	a. Varies by application. See "Part 3 - Execution" portion of specification section 260544 for application of products depending on wall type, penetration location, etc. b. Yes, unless any fire ratings require fire caulking. Coordinate with GC for flooring finish around exposed conduit penetrations and also provide escutcheon plates around exposed conduit penetrations. c. Yes, unless any fire ratings require fire caulking.

Question No.	Sheet or Reference	Question	Response
18		Are the exposed ceilings that remain to be stripped and/or refinished? I assume this would be the same requirement for all cabins? Reference: Main Lodge - 399/A601	Reflected ceiling plan notes require all interior ceiling components to be cleaned; finish shedule notes describe the cleaning method. Finish schedule notes specify that all interior beams and purlins are to be finished. The exposed underside of interior wood plank roof decking is to remain unfinished. All exterior exposed decking shall be finished. Please see drawings references below. *Per A601, Reflected Ceiling Plan Note #7:* *CLEAN AND FINISH ALL EXPOSED STRUCTURE INCLUDING BEAMS, JOIST, AND DECKING AT BUILDING INTERIOR & EXTERIOR.* *Per A905, Finish Schedule General Note #1:* *ICL-1 (GENERAL INTERIOR CLEANING TREATMENT) AT ALL (E) INTERIOR SURFACES.* *Per A905, Finish Schedule General Note #2:* *ST-1 AT ALL INTERIOR LOG AND LB-1 SURFACES INCLUDING WALLS, COLUMNS, BEAMS, AND PERLINS. APPLY FINISH PRIOR TO ANY CONSTRUCTION THAT WOULD BLOCK ACCESS TO SUCH SURFACES.*
19		RFI: I don't believe the crawls depths are called out. We understand that the bottom of footer needs to be 34" below grade per 399/S201. Is there a minimum stem wall height for the Main Lodge? I assume this height will be applicable to all cabins.	The height of the stem wall shall be as required to meet minimum depth requirements *and* top of stem wall to grade requirements as shown on the architectural drawings including sheet 000 A803.
20		the specs 33 14 15 and plans for the Sewer and Water force main's don't specify the SDR or if the hdpe needs to be CTS or IPS sized. There is one mention that the grinder/lift station piping is to be "HDPE PE 4710 CTS". CTS sizing stops at 2" max. IPS is more common and available, would IPS SDR 11 PE 4710 HDPE be acceptable for all hdpe sewer service?	Yes, IPS SDR 11 HDPE is acceptable for force main piping and the pressure sewer service from the Caretaker's Cabin.
21		Pipe size and material on C300 to the caretakers cabin is not specified. Should we assume 3" hdpe to the grinder and 2" hdpe to the 4" force main?	Specify 4" PVC to the grinder as per gravity sewer piping. Pressure service to be 2" SDR11 HDPE.
22		Spec 33 14 15 indicates water service to be "HDPE PE 4710 CTS", however CTS sizing stops at 2" max. IPS is more common and available, would IPS SDR 11 PE 4710 HDPE be acceptable for the wall water pipe?	IPS SDR 11 HDPE is acceptable for water services.
23		Can you confirm the size of pipe for water service to buildings is 2" HDPE?	Water services are to be 2" HDPE
24		Are there limitations/closures due to Elk calving season?	Yes. Refer to Summary of Work (01 11 00 -6) Wildlife- Related Work Schedule chart and Environmental Protection (01 35 13.05-3) Wildlife Protection section, for additonal information.
25	Water main	Water main symbols (C400, sheet 35). Two symbols resembling a “Z” or “N” appear near the valves at Sta. 3+42.29 and 4+69.90. Are these part of the valve notation or separate items we should include in the bid? If separate, please identify the required items and applicable detail.	Symbol (shown below) is the tracer wire termination block on 3/C203. 

Question No.	Sheet or Reference	Question	Response
26		What is the power situation going to look like? I noticed at the site walk that there were outlets in the buildings, but I understand that there is currently not power. Will that be turned on at any point? Will a generator be necessary for the entire duration? I also understand if that is yet to be determined, but whatever information you have would be greatly appreciated.	Please see specification section 01 50 00 - TEMPORARY FACILITIES AND CONTROLS for information regarding construction power sources and associated general contractor requirements.
27	Water and sewer design scope	Water and sewer design scope. The solicitation calls for contractor design, but the issued drawings already show pipe sizes, alignments, profiles, and details. Can we bid the systems as drawn, with field verification and standard submittals? If additional engineering is required, please clarify what remains to be designed and whether we should include sealed drawings, calculations, or permit revisions	Yes, bid water and sewer systems as designed. Additional engineering is not required.
28	Site utility permit question	Section C (page 10 of 67); specification 01 11 00 section 1.2.B.2, and C201 notes require the Contractor to design and permit the site utilities. Specification 01 31 00 section 1.9 states the Government acquired the WYDEQ Permit to Construct. Please confirm Contractor is not required to design and permit site utilities and that contractor design is limited to field investigations, submittals, CO-approved adjustments, as-built drawings, and closeout documents	Confirmed. Contractor is not required to design and permit site water and waste utilities. WYDEQ permit is acquired.
29	Specialize consultants	Are bidders required to include all specialized consultants. Could you clarify whether one person must be dedicated to each of these roles for the full lifecycle of the project. Historic Preservation Specialist Environmental Manager Wildlife compliance specialist Safety officer Testing agencies	a. The Superintendent cannot serve as the Safety Officer or Quality Control Representative. One individual may serve as both Safety Officer and Quality Control Representative. Both positions must be staffed on site at all times during construction. b. Historic Preservation, Environmental Manager, Wildlife Compliance Specialist are consultants to contractor. These posittions may serve in collateral roles, provided the individual is qualified. These responsibilities may be shared among personnel or assigned as additional duties to an individual's primary position. c. Third party testing agencies are to sub-contracted by contractor as per plans and specifications
30	Roles	Can project Superintendent play the role of Safety Manager?	No. The Superintendent cannot serve as the Safety Officer or Quality Control Representative. One individual may serve as both Safety Officer and Quality Control Representative. Both positions must be staffed on site at all times during construction.
31	Snow removal	Can you clarify the limits of where NPS will complete snow removal and access road maintenance throughout the project and where Contractor will be responsible?	Snow is typically plowed by the park to the area around the Menors Crossing vault toilet. Contractor is responsible for all snow plowing required for site access.
32	Schedule	Regarding the Proposal Schedule, with the base bid and optional bid items, does NPS want three separate schedules or one holistic schedule assuming all options are awarded?	Contractors shall provide one comprehensive schedule that includes the base bid and all options, assuming all options are awarded. The schedule must fall into the period of performance specified in the specifications.
33	Storage	Will Government-owned buildings be available for storage?	No

Question No.	Sheet or Reference	Question	Response
34	Site	How will the property development (parking lot and other dirt work) be covered with the bid schedule? There isn't any separate call out for that.	Reference 01 27 00 Definition of Contract Line Items. CLIN 11 Sitework - Parking Lot. CLIN 12 Sitework - Roadway and Staging Area Restoration. Note: Each facility has site work included within their associated CLINs. Staging Area restoration in CLIN 12 would only be for staging established on roads and remaining site work not captured in other CLINs. Staging areas, established in areas other than existing parking areas or roads, would be expected to be restored if CLIN 12 was not awarded.
35	CO answer	In the event of conflicts between drawings and specifications, which governs?	See clause FAR 52.236-21. Specs govern over drawings, but the order or precedence is described in this FAR cluase.
36	Change orders	How will unforeseen structural deterioration be handled (Change order or is it Contractor Full Responsibility)? Examples include (Hidden rot, Insect damage, Concealed water damage, Deteriorated logs, Damaged framing and Unknown utility conditions)	Some structural deterioration is called out in the contract documents, so please pay close attention to these details. Anything not described in the contract documents would be handled pursuant to FAR 52.236-2 Differing Site Conditions.
37	CMR	Will NPS provide direct oversight during historic restoration activities?	No. Direct oversight during historic restoration activities is contractor's responsibility.
38	Foundations	During the walkthrough it was mentioned that the River Cabin and the New Cabin are the only structures that are not getting a new foundation, can you clarify that the Ice House and Mouse House are also not getting a new foundations?	The River Cabin and the New Cabin are the only housing structures that are not getting a new foundation. The Ice House and Mouse House (storage buildings) are also not getting new foundations. All other buildings are getting new foundations.
39	Cabin leech fields	Where are the existing leech fields and what happens to them once the cabins are connected to the sewer line?	The cabins and lodge abandoned leech fields are not surveyed. NPS assumes they exit the back of the cabins. These are abandoned in place. Given the site's historic significance, the contractor will encounter undocumented abandoned utilities during construction and is expected to identify to CMR/Park staff and resolve/work though conflicts.
40	sewer	Do the Force Main services need to be plowed as well?	Force main service laterals for caretaker and new cabin do not need to be plowed.
41	CO	Reference: Att. 01 Dwgs 000 S001 General Requirements – Discrepancies (Dwg p.65); FAR 52.236-21 Sheet S001 states that where documents conflict the Contractor is "deemed to have included in the price the most expensive way of completing the work" and that conflicts are not a basis for adjustment. Please confirm that FAR 52.236-21 governs the resolution of discrepancies, that the Contracting Officer determines which document governs, and that the S001 paragraph is deleted.	Please ignore that statement at the top of pg 65 (sheet 000 S001) of the drawings. FAR 52.236-21 will govern here.
42	Personnel roles	Reference: Section H SR 6 Key Personnel (Sol. p.19); FAR 52.236-6; Att. 02 Specs 01 40 00 ¶1.5.B.1–3 (p.102); 01 35 23 ¶1.4.B (p.88); 01 74 19 ¶3.1.B (p.178) SR 6 lists four key personnel (Project Manager, Superintendent, QC Manager, Safety Manager); 01 40 00 states the QC Supervisor "shall be assigned no other duties"; and 01 74 19 requires a full-time Waste Management Coordinator. Given the remote site and residential-scale buildings, please confirm whether (a) the Project Manager may be off-site with periodic visits; (b) the Superintendent may also serve as Safety Manager/SSHO; (c) one qualified individual may serve as Superintendent, QC Manager and SSHO, with a named alternate; and (d) the Waste Management Coordinator may be a collateral duty. Additional Questions – Listed in Descending Order of Priority	The Project Manager may be off-site but must make periodic site visits. The Superintendent cannot serve as the Safety Officer or Quality Control Officer. However, one individual may fulfill both the Safety Officer and Quality Control Officer roles. The Waste Management Coordinator may be assigned as a collateral duty in addition to an individual's primary responsibilities.

Question No.	Sheet or Reference	Question	Response
43	Spec 28 46 21-fire alarm	Specification section 28 46 21 paragraph 1.13 mentions an annual service contract to the Owner. What should be included in the service contract? Is this to cover system monitoring and/ or annual testing services?	Annual service contract to the Owner will not required.
44	Spec 28 46 21-fire alarm	Specification section 28 46 21 paragraph 3.7G requires the contractor to provide the first annual test one year after substantial completion. However, Grand Teton park has a maintenance contract for all fire alarm and fire suppression maintenance. Will this contract cover the first annual inspection or will the maintenance of these fire systems be added to the existing maintenance contract?	First annual test after substantial completion will not required. A final integrated fire alarm and sprinkler test, to include all facilities reabilitated by contract, will be required by AHJ for acceptance and occupancy.
45		When removing asbestos vinyl flooring and mastic, it is often necessary to remove floor sub straight. Does this have a historical impact or is sub straight removal an approved method for eliminating hazardous materials?	Generally, removal of historic building substrates, currently scheduled to remain, should be avoided. However, substrate removal is an acceptable means of abatement should other methods not be feasible. Prior to removal of asbestos containing flooring material, determine the extent of substrate removal required. As new flooring will be installed at all locations where asbestos containing flooring material exists, substrate removal will be allowed with Contracting Officer approval. If substrates are removed, contractor will be required to replace them with new plywood floor decking.
46	Roof shingles	The current specification for shingles is for GAF HDZ RS. I believe the RS version of those shingles is unavailable in our market. I wanted to confirm that standard GAF HDZ shingles can be used here.	Standard GAF HDZ shingles appear to meet the requirements of specification section 07 3113. Follow procedures for substitutions; see Section 01 67 00 – Product Requirements.
47	Roof detail	The plans show a Reglet counterflashing detail for roof to wall flashing at the logs. I wanted to confirm that this is also the intended detail for roof to wall flashing at the chimneys? This would require us to cut a kerf into the existing chimney masonry to install counterflashing.	Please see detail 3/399 A801 illustrating roof to wall flashing at chimneys.
48		Removal of lead-based paint (LBP) components May all components identified as having LBP be removed and disposed of in their entirety rather than stripped of paint? Please identify any components that must be retained, stripped, or otherwise treated in place, including any salvage or historic preservation requirements.	Lead paint shall be removed without removal or damage to existing historic building components that are scheduled to remain, to be salvaged, or to be refinished or restored, per plans and documents. Only building components that are scheduled for removal may be removed and disposed of.
49		Removal of subfloor beneath asbestos-containing sheet vinyl May the abatement contractor remove and dispose of the sheet vinyl, inseparable mastic, and underlying subfloor together as asbestos-containing waste, rather than removing the flooring and mastic from the subfloor? Please identify any areas where the subfloor must remain and confirm who is responsible for replacement if removal is permitted.	Generally, removal of historic building substrates, currently scheduled to remain, should be avoided. However, substrate removal is an acceptable means of abatement should other methods not be feasible. Prior to removal of asbestos containing flooring material, determine the extent of substrate removal required. As new flooring will be installed at all locations where asbestos containing flooring material exists, substrate removal will be allowed with Contracting Officer approval. If substrates are removed, contractor will be required to replace them with new plywood floor decking.
50	Temp power	Temporary power. Will electrical power be available for contractor use at each building, or must contractors provide their own generators and temporary power distribution? If power is available, please confirm the connection locations, voltage, and available amperage.	Power is available on site for the Contractor to use. Contractor may establish temporay power distribution as needed to execute work.

Question No.	Sheet or Reference	Question	Response
51	Structural - 411	The schedule on 000 - G008 states that cabin 411 requires structural upgrades to the foundation. Sheet 411 - S201 does not call out any structural upgrades. 1) Can you please clarify whether there are structural upgrades to the foundation on cabin 411. 2) If there are upgrades, please clarify what they entail.	1&2) Structural upgrades are limited to connections between the existing floor system and the existing foundation as illustrated on 8/000 S402.
52	Building foundation	Regarding cabin 404, the south side of the building sits on an existing foundation. Is the existing foundation to be demolished and receive a new foundation along with the rest of the building?	At Cabin 404, the entire existing foundation is to be removed and replaced per the architectural and structural drawings.
53	Base/Bid options pricing	Reference: Att. 02 Specs 01 27 00 ¶3.1.A–D (utilities "to within 5 feet of each structure"); Att. 01 Dwgs 000 F004 Riser Legend 1–2 ("site contractor" to tee inside building, Dwg p.91); 000 E100 KN 5 Base utility CLINs terminate 5 ft outside each building, while F004 has the "site contractor" carrying the service to a tee inside the building. Please confirm the work from 5 ft outside through the new foundation to the interior connection (sleeves, insulation, penetrations) for water, sewer, power, fiber and FA conduit is included in each building's option CLIN, and that the Base CLINs terminate with capped, marked stubs 5 ft outside.	The division of work between CLINs, as described in the question, is correct.
54	Lead paint	There are several places in which lead paint was identified. There are a few ways to remove said paint, but I wanted to know if you have any preferences to methods used. For example, the cleanest and most permanent option is to just remove the wood/trim that is painted, but if that wood has to be preserved, an option like using a solvent works well but has the potential to stain the wood.	Lead paint shall be removed without removal or damage to existing historic building components, including trims and doors, that are scheduled to remain, to be salvaged, or to be refinished or restored. Only building components that are scheduled for removal may be removed and disposed of.
55		RFI: Is trenching an acceptable excavation alternative to "plowing method?" Per 33 14 15 - 1 "Construction technique for the sewer force main along the gravel road alignment from Moose to 4 Lazy F as noted on the drawings shall be constructed via plowing methods"	Plowing is required for force main installation to expedite installation and minimize impact to Park operations and wildlife. Plowing is the required method for force main installation in roadways; performance-based standards must be met.