CLIMATE CONTROL
A UNIT OF SNYDER GENERAL CORPORATION

Refrigerant


R410A



Garage door

Electric panel


Honeywell


Setpoint and Differential Settings. Diagram indicates relay on and off points in either the heating or cooling modes.
Programming Steps and Display
The ETC can be programmed in four simple steps using the LCD display and the three keys on the face of the control.
Step 1- To start programming, press the SET key once to access the Fahrenheit/Celsius mode. The display will show the current status, either F for degrees Fahrenheit or C for degrees Celsius. Then press either the up ▮ or down ▮ arrow key to toggle between the F or C designation.
Step 2- Press the SET key again to access the setpoint. The LCD will display the current setpoint and the S1 annunciator will be blinking on and off to indicate that the control is in the setpoint mode. Then press either the up ▮ key to increase or the down ▮ key to decrease the setpoint to the desired temperature.
Step 3- Press the SET key again to access the differential. The LCD will display the current differential and the DIF 1 annunciator will be blinking on and off to indicate that the control is in the differential mode. Then press either the up ▮ key to increase or the down ▮ key to decrease the differential to the desired setting.
Step 4- Press the SET key again to access the cooling or heating mode. The LCD will display the current mode, either C1 for cooling or H1 for heating. Then press either the up ▮ or down ▮ key to toggle between the C1 or H1 designation. Press the SET key once more and programming is complete.
Step
Annunciator
Description
Display
1
F or C
Fahrenheit or Celsius Scale
F
2
S1 (blinking)
Setpoint Temperature
10
3
DIF 1 (blinking)
Differential Temperature
5
4
C1/H1
Cooling or Heating Mode
C1
NOTE: The ETC will automatically end programming if no keys are pressed for a period of thirty seconds. Any settings that have been in the control will be accepted at that point.
SET
RANCO
ELECTRONIC TEMPERATURE CONTROL
MODEL 8145-20
D-FROST-O-MATIC TIME CONTROL
A-357-20
B-176
C-2679
24 Hour Dial
2 Hour Dial
TIMER RELEASE SOLENOID
208-240V 60Hz
NORMALLY OPEN LOAD
NORMALLY CLOSED LOAD
CYCLE LIMIT SWITCH (TEMP OR PRESSURE CONTROL) CLOSES ON TEMP OR PRESSURE RISE
LISTED REFRIGERATION CONTROLLER 516H
INSTALLING AND OPERATING DIRECTIONS:
Place start pins in outer (24 Hour) dial at the time of day that switch contacts are to be reverse from shown above when dial pins are opposite time pointer. CAUTION: (Leave at least 1 hole between each adjacent pin).
TO SET BACK-UP DEFROST TERMINATION: Push down and rotate pointer on inside (2 Hour) dial until it is opposite desired time.
TO SET TIME OF DAY: Grasp knob in the center of the inner (2 Hour) dial and rotate it in a counter-clockwise direction. This will revolve the outer dial. Line up the correct time of day on the outer dial with the time pointer. Do not try to set the time control by grasping the outer dial. Rotate the inner dial only.
FOR REPLACEMENT of this control contact refrigerator manufacturer.
FOR REPAIR contact nearest Paragon service station.
MAXIMUM CONTACT RATING
40A NON-INDUCTIVE 208-240Vac
2hp 208-240Vac
690VA PILOT DUTY 208-240Vac
Timing Motor 208-240V 60Hz
Made in the U.S.A. by
PARAGON ELECTRIC COMPANY, INC.
606 Parkway Blvd. P.O. Box 28, Two Rivers, WI 54241
Subsidiary of AMF INCORPORATED
MODEL 8145-20
TIME
LINE
PINETREE POND REFRIGERATION
ST. MARIES
208-245-4806
Galaxy Tab Active3

CLIMATE CONTROL

A UNIT OF SNYDER GENERAL CORPORATION

REFRIGERATION/COILS DIVISION

WILMINGTON, N.C.

MODEL NO.	SERIAL NO.
LVD-2100-2	

MOTOR CIRCUIT				
VOLTS	PH	HZ	QTY	HP EA.
230	1	60	2	

FLA EA.	MIN. CIRC. AMPACITY	MAX. OVER CURRENT PROTECTIVE DEVICE RATING
.70	19	AMP.


(DEFROST) HEATER CIRCUIT			
VOLTS	PH	AMPS	WATTS
230	1	16.7	
230	3	9.6	

DEFROST CONTROL RATING			REFRIGERANT	DESIGN PRESSURE P.S.I.G.
FLA	LRA	(PILOT DUTY) VA		
12	72	120	12,22,502	500

DANGER

HAZARDOUS MOVING PARTS


CLIMATE CONTROL
A UNIT OF SNYDER GENERAL CORPORATION
MODEL NO.
SERIAL NO.
VOLTS
PH.
MAX. FUSE SIZE - AMPS
COMPRESSOR
MOTOR
CRANKCASE HTR. - WATTS
KIT
EVAP. FAN MTR. MAX. AMPS
REFRIGERANT
TEST
FOR USE
400
150
DOOR
Date
Refrigera
Contracto
800-245-800


This system charged with
Refrigerant 417.C.
Date 9-7-22 Lubricant Hot shot 2
Refrigerant Charge 37 lbs
Contractor Air Dixon
RSD
REFRIGERATION SUPPLIES DISTRIBUTOR
Forane
800-245-8007 - www.rsd.net/refrigerantsuite/index.php

outside Compressor on
Other side of this wall

STATE OF IDAHO
Dept. of Labor & Industrial Services
ELECTRICAL BUREAU
Date: 2/29/84
Permit No.: C107886
Inspected By: EE
DO NOT REMOVE

IDAHO DEPARTMENT OF LABOR AND INDUSTRIAL SERVICES
Electrical Bureau
CONTRACTOR JOB IDENTIFICATION
To be placed on job site at panel location or as temporary service at time electrical work starts.
Contractor's Name Baker Electric
Tag Number C107886 Date 2-21-84
Signed

MAIN
MAIN
WARNING
BRYANT
AUTOMATIC TRIP IS INDICATED BY HANDLE POSITION MIDWAY BETWEEN (ON) & (OFF) RESTORE SERVICE BY MOVING HANDLE TO (OFF) THEN (ON) POSITION.
INSTALLED BY:
TEL.
CLASS CTL ENCLOSED PANELBOARD
ISSUE NO.
Includes warning light

Emergency Light


Garage Door


Cooler is
← Inside →

CONDENSING UNITS

Built on the same rigid base as the indoor SK Series, but encased in an all aluminum weather housing, our SC units are complete, all ambient outdoor models, completely pre-wired, pre-piped and factory shipped. Included are ball bearing fan motors, low ambient winter control system, weather proof, hinged electrical panel, hinged compressor compartment cover, suction and discharge line vibration absorbers, liquid line assembly, etc., all provided to assure the reliability and quality that are synonymous with Climate Control-Wilmington Coil. For complete technical data see bulletin #129-A.

SERIES SC
OUTDOOR
ALL AMBIENT





HP	Model*	Temp. Range and Refrigerant*	Dimensions (Inches) Width	Depth	Height	No. Fans	Line Sizes (O.D. Inches) Suct.	Liq.	Disch.	Approx. 90% Pump Down Cap. (Lb.)	Approx. Ship. Wt. (Lb.)
¾	SC-0075	M1	34¼	40³⁄₁₆	35⅝	1	⅞	½	½	36	370
1	SC-0100	M1, L5	34¼	40³⁄₁₆	35⅝	1	⅞	½	½	36	380
1½	SC-0150	M1, L5	34¼	40³⁄₁₆	35⅝	1	⅞	½	½	36	390
	SC-0200	H1,H2,M1,L5	34¼	40³⁄₁₆	35⅝	1	⅞	½	½	36	475
	SC-0300	H1,H2,M1,L5,EL5	34¼	40³⁄₁₆	35⅝	1	1⅛	½	⅝	36	520
5	SC-0500	H1,L5,EL5	34¼	40³⁄₁₆	35⅝	1	1⅜	½	⅞	36	575
5	SC-5MRB	M1	34¼	40³⁄₁₆	35⅝	1	1⅜	½	⅞	36	575
5	SC-0500	H2,M1	50¼	44⁵⁄₁₆	43⅛	2	1⅜	⅝	⅞	55	800
7½	SC-0750	H1,H2,M1,L5,EL5	50¼	44⁵⁄₁₆	43⅛	2	1⅜	⅝	1⅛	55	830
10	SC-1000	H1,L5	50¼	44⁵⁄₁₆	43⅛	2	1⅝	⅝	1⅛	55	860
10	SC-1000	H2	74½	44⁵⁄₁₆	43⅛	3	1⅝	⅞	1⅛	155	1220
15	SC-1500	H1,H2,L5	74½	44⁵⁄₁₆	43⅛	3	1⅝	⅞	1⅛	155	1220
20	SC-2000	H1,L5,H2	74½	44⁵⁄₁₆	43⅛	3	1⅝	⅞	1⅛	155	1260
25	SC-2500	L5	74½	44⁵⁄₁₆	43⅛	3	2⅛	⅞	1⅛	155	1340

SC/SK/SR *NOMENCLATURE**

UNIT STYLE — CAPACITY — APPLICATION RANGE — REFRIGERANT — ELECTRICAL CHARACTERISTICS — TYPE (SK & SR ONLY)

SC — 0300 — M — 1 — B — 2

UNIT/HP
"0075" = ¾
"0100" = 1
"0150" = 1
"0200" = 2
"0300" = 3
5MRB = 5
"0500" = 5
"0750" = 7
"1000" = 10
"1500" = 15
"2000" = 20
"2500" = 25

"H" - High-Med. Temp. ..... +10° F thru +40° F Evap.
"M" - Medium Temp. ..... 0° F thru +25° F Evap.
"L" - Low Temp. ..... 0° F thru -30° F Evap.
"EL" - Extra Low Temp. ..... -10° F thru -40° F Evap.

"1" = R-12
"2" = R-22
"5" = R-502

"A" - 230 V. 1ϕ (207-253 Volts; thru 5 HP only)
"B" - 208/230 V. 3ϕ (187-264 Volts, available on all units)
"D" - 460 V. 3ϕ, Includes 460 Volt compressor & 230 V. Control Circuit Transformer. No transformer is provided with a type-1 unit.

-1 = WITHOUT ELECTRICAL PANEL
-2 = WITH ELECTRICAL PANEL

SEE PRICE BULLETIN FOR MANY OPTIONS AVAILABLE WITH THE SC, SK & SR UNITS (MOST FACTORY INSTALLED); INCLUDING DEFROST CONTROL KITS, HEAT RECLAIM VALVES, ETC.

APPROVED FROM 1-20 HP, R12, R22 & R-502, 208-230/1/60, 208-230/3/60


SC/SK CAPACITY TABLES

HIGH & MEDIUM TEMPERATURE CONDENSING UNITS							
CLIMATE CONTROL	MIN. CIRCUIT AMPACITY			BTUH			
	"A"	"B"	"D"	SUCTION TEMPERATURE			
MODEL NO.	230/1ϕ	208/230/3ϕ	460/3ϕ	+40	+25	+20	+10
SC/SK 0075M1	12.0	9.0	—		6650	6050	4950
0100M1	13.7	11.1			9590	8680	7060
0150M1	14.6	13.2	10.1		14510	13010	10540
0200H1	21.6	17.3	10.9	22500	16830	15130	
0200M1	19.9	17.9	11.1		19220	17340	14020
0200H2	22.1	17.3	10.9	22950	15600	13250	
0300H1	27.9	22.4	13.6	33510	25490	23030	
0300M1	28.3	21.8	13.6		28450	25550	20940
0300H2	30.3	23.7	14.5	35130	25710	22890	
0500H1	38.4	35.3	16.9	48140	35990	32340	26000
0500M1		31.9	19.5		44120	39940	32390
5MRBM1		35.6	21.6		42030	37900	31750
0500H2		35	20.8	58760	43700	39040	30660
0750H1		53.9	28.5	73780	54270	48020	36060
0750M1		52.3	28.6		65510	60590	51080
0750H2		53.5	25.6	86700	64270	57460	45330
1000H1		86.2	43.0	111600	84200	76240	62600
1000M1		86.2	43.0		84200	76240	62600
1000H2		71.2	39.3	121600	91260	82250	66493
1500H1		99.9	52.4	150900	112500	101800	83900
1500H2		99.7	50.2	156700	116500	103900	84400
2000H1		105.3	55.1	174700	135800	124000	102610
2000H2		109.8	55.1	200800	149300	134000	107100

LOW TEMPERATURE CONDENSING UNITS							
CLIMATE CONTROL	MIN. CIRCUIT AMPACITY			SUCTION TEMPERATURE			
	"A"	"B"	"D"				
MODEL NO.	230/1ϕ	208/230/3ϕ	460/3ϕ	-10	-20	-30	-40
0100L5	13.7	11.7	7.1	5920	4620	3440	2440
0150L5	18.2	14.4	9.6	8380	6620	4970	3430
0200L5	21.6	17.3	10.9	11920	9450	7290	5430
0300L5	27.9	22.4	13.6	17710	14010	10470	7240
0300EL5	28.3	21.8	13.6	18410	15680	12170	9190
0500L5	38.4	35.3	16.9	27210	21040	16380	13680
0500EL5		35.6	21.6	30160	24410	18840	13410
0750L5		53.0	27.7	42790	34390	27230	21290
0750EL5		52.3	28.6	52140	42080	32230	22720
1000L5		86.2	43.0	64140	50690	38480	27400
1500L5		97.9	52.1	78480	62490	48890	37930
2000L5		105.3	55.1	92230	72860	55050	39200
2500L5		132.6	66.6	105200	84700	66900	51700

NOTE: RATINGS ARE FOR 90° AMBIENT. ADD APPROXIMATELY 6% FOR EACH 10° LOWER AMBIENT. DECREASE CAPACITY 6% FOR EACH 10° HIGHER AMBIENT.

WALK-IN UNITS/LOW VELOCITY



SERIES LVC

LOW VELOCITY

(35° to 55°)

The LVC units have heavy gauge aluminum casings with baked-on white finish. Channel type hanger bars provide built-in slope and provide easy hanging. Copper tubes with specially designed circuitry for low pressure-drop are expanded into wide spaced aluminum fins for longer operating time at full capacity. Aluminum inner drain pans under each coil prevent condensation on outer pan. Two-piece, reversible main drain pan construction allows easy removal without disturbing drain connection. Drain through collects condensate run-off and assures complete unit drainage. For additional data see Evaporator Bulletin No. 129-41.

Model No.	Capacity BTUH			Fans		Motors		Approx. R-12 Charge	Dimensions			Approx. Ship. Wt. Lbs.
	10° TD	12° TD	15° TD	CFM	Diam.	HP 115/1/60	RPM		Length	Depth	Height	
LVC-500	5,000	6,000	7,500	650	8" (2)	1/30 (2)	1,550	4.7	68 3/8	24	9 3/4	140
LVC-700	7,000	8,400	10,500	650	8" (2)	1/30 (2)	1,500	7.0	68 3/8	24	9 3/4	150
LVC-900	9,000	10,800	13,500	850	8" (2)	1/30 (2)	1,500	9.1	80 3/8	24	9 3/4	210
LVC-1200	12,000	14,400	18,000	1,100	10" (2)	1/30 (2)	1,500	11.9	89 3/8	26	11 1/4	220
LVC-1600	16,000	19,200	24,000	1,500	12" (2)	1/15 (2)	1,050	15.9	105 3/8	28	12 3/4	300
LVC-2100	21,000	25,200	31,500	2,000	14" (2)	1/15 (2)	1,050	20.7	116 3/8	28	14 1/4	340
LVC-2700	27,000	32,400	40,500	2,500	14" (2)	1/15 (2)	1,050	26.6	129 3/8	30	15 3/4	430

SERIES LVD

LOW VELOCITY
ELECTRIC DEFROST

(28° to 34°)

The time proven electric defrost system is completely automatic: time initiated, the multiple low-watt density heaters provide rapid and complete defrost, terminated by a factory set temperature sensor control, the defrost time is regulated only by the coil frost load and is protected by the inherently equipped fail-safe feature of the timer. To insure complete condensate run-off all models incorporate an individual heater in each inner drain pan. Internally wired to an external junction box, it is necessary for the installer to mount only the timer and interconnecting field wiring. For additional data see Evaporator Bulletin No. 129-41.

Model No.	Capacity BTUH			Fans		Motors		Approx. R-12 Charge	Dimensions			Approx. Ship. Wt. Lbs.
	10° TD	12° TD	15° TD	CFM	Diam.	HP 230/1/60	RPM		Length	Depth	Height	
LVD-900	9,000	10,800	13,500	850	8" (2)	1/30 (2)	1,500	9.1	80 3/8	24	9 3/4	210
LVD-1200	12,000	14,400	18,000	1,000	10" (2)	1/30 (2)	1,500	11.9	89 3/8	26	11 1/4	220
LVD-1600	16,000	19,200	24,000	1,500	12" (2)	1/15 (2)	1,050	15.9	105 3/8	28	12 3/4	300
LVD-2100	21,000	25,200	31,500	2,000	14" (2)	1/15 (2)	1,050	20.7	116 3/8	28	14 1/4	340
LVD-2700	27,000	32,400	40,500	2,500	14" (2)	1/15 (2)	1,050	26.6	129 3/8	30	15 3/4	430

Model No. SW-2

Centrifugal Atomizing

For small in-space applications

CAPACITY: Water Vapor Output: 2 lbs./hr. (0.9 kg/hr.)



Capable of producing quantities of water vapor up to two pounds (0.9 kg.) hourly, the Model SW-2 has a directional dome which may be fixed to any position enabling the discharged moisture to travel only a few feet while being completely evaporated into the surrounding atmosphere. It uses the force that is generated by centrifugal action to produce the finest moisture particles, and the simple rotating assembly which is responsible for this is carefully balanced for quiet, dependable and continuous service with little more than occassional cleaning maintenance required.

Typical applications include small, high humidity chambers, compact well-enclosed laboratory-type rooms, tobacco humidors or somewhat larger spaces in which a small amount of humidification will be beneficial.

SPECIFICATIONS


ELECTRIC MOTOR
50 watts
115 volts-1 ph-60 hz


WEIGHT
Unfilled 10 lbs (4 5 kg)
Operating 15 lbs (6 8 kg)

WATER CONNECTIONS & PRESSURES
Supply ⅛" (0 32 cm) Male Pipe Thread
Overflow ¼" (0 64cm) Female Pipe Thread
Operating Pressure Range: 10-150 psig. (.70-10.5 kg/cm²)

No.	Package	Carton Size	Shpg. Wt.	Shpg Case Cube
SW-2	Indiv Carton	15½" x 12¼" x 15¼" (39 4 cm x 31 1 cm x 38 7 cm)	13 lbs (5 9 kg)	1 68 cu ft (.048m³)

INSTALLATION DIMENSIONS AND SUGGESTIONS





ENVIROTECH

BAHNSON®

Catalog 7-A

ELECTRIC HUMIDISTATS

TYPES MB AND MBW

For Precise Control of Humidity


The Type MB Humidistat is essentially a single pole, double throw switch, operated by an actuating element that is extremely sensitive to changes in relative humidity. When the relative humidity drops below the control setting, the switch is thrown in one direction and when the relative humidity rises above the setting, the switch is thrown in the opposite direction.

The Type MBW Humidistat operates in the same way as the Type MB, but has a week-end control lever. This feature allows the humidity to be lowered a specified percentage for shut-down periods without changing the normal control setting. The week-end setting is adjustable so that the humidity may be lowered to any point between one and 30 per cent below the normal setting.

The construction of Type MB and Type MBW Humidistats allows the original setting to be made with extreme accuracy. When changes are desired, the control is adjusted by rotating the movable cap at the top. This cap has graduations on the rim, and pointers indicate the direction in which the cap should be turned to raise or lower the relative humidity. Movement of one graduation represents a change in relative humidity of approximately 1 per cent.

A great variety of operating conditions are found in the industrial and commercial application of humidistats. The Type MB Humidistat was designed with the extreme conditions in mind, so that Bahnson Controls will not be limited to a particular type of application. The Type MB Humidistat has been successfully used for several years in spaces where extreme conditions prevail and has proven to be completely dependable. The opening and closing of an electric circuit makes it applicable to the regulation of innumerable types of equipment where a positive control is desired.

Type MB and MBW Humidistats are available for independent mounting and in various types of control cabinets. All Bahnson Controls which have the Type MB Electric Humidistat will have the letters MB as the first letters in the control designation. Similarly, all controls which have the Type MBW Electric Humidistat will have the letters MBW as the first letters in the control designation.



- **SENSITIVE**
- **ACCURATE**
- **ADJUSTABLE**
- **DEPENDABLE**
- **POSITIVE CONTROL**
- **FLEXIBLE APPLICATION**

BAHNSON TYPE MB
ELECTRIC HUMIDISTAT

SPECIFICATIONS

Type: Bahnson Type MB or Type MBW Electric Humidistat
Element: Continuous strip of hygroscopic paper.
Operating Range: 20 to 95 per cent relative humidity.
Operating Temperatures: Up to 150° F.
Operating Differential: 2-3 per cent relative humidity.
Scale Increments: 1 per cent relative humidity.
Dimensions: 2⅝" Wide, 2⅞" Deep, 10¾" High.
Adjustment Means: Movable Cap.
Electrical Characteristics: Switch has normally open and normally closed circuits. Rated 10 Amps at 125 Volts, 5 Amps at 250 Volts. This humidistat is normally used in 24 Volt or 110 Volt control circuits.




BAHNSON TYPE MBW
ELECTRIC HUMIDISTAT
SHOWING WEEK-END
ADJUSTMENT LEVER


Copyright 1977 by Envirotech Corporation

BAHNSON®

TYPE MBEI HUMIDISTAT




FRONT VIEW



ELEVATION

TYPICAL WIRING DIAGRAM



THE ABBEON

CERTIFIED HYGROMETER

AND TEMPERATURE INDICATOR

Shows RELATIVE HUMIDITY and TEMPERATURE at a Glance
LARGE 5 INCH DIAL — NO SQUINT — NO CALCULATIONS



6" overall diameter

Model HTAB169

The Abbeon Certified Hygrometer Model No. HTAB-169 is certified to be accurate within 3% plus or minus. The dial indicates the complete range of 0 to 100% relative humidity. Each instrument has been tested at three different positions of the dial at temperatures ranging from 32 degs. to 230 degs. F. The original calibration and certification is done under the supervision of Dr. Helmut Brauckhoff of the G. Lufft Metallbarometerfabrik, GmbH-Stuttgart, under the standard conditions of the Federal Republic Test Society.

Each instrument is rechecked before shipment. If it varies from test accuracy during field use it can be brought into calibration by checking it against a known standard and if need be resetting to the correct reading by turning the calibration screw, located inside the wide bottom slit.

Specifications for the Model No. HTAB-169 are as follows: Casing solid brass with gleaming finish, black dial with white numbers and lettering, red tipped pointer, casing is drilled for wall mounting. Temperature dial range minus 10 degs. F. to 190 degs. F. Dial is direct reading without any calculations whatsoever. Size 6 inches overall, dial face 5 inches in diameter. Shipping weight 4 pounds.

Model No. HTAB-169

Delivered Price $89.00


THE ABBEON

CERTIFIED HYGROMETER

Shows Relative Humidity at a Glanc

LARGE 5 INCH DIAL — NO SQUINT —NO CALCULATIONS

Certified Hygrometer No. AB-167 is certified to be accurate wit 3% plus or minus. The dial indicates the complete range of 0 100% relative humidity and each instrument has been tested three different positions of the dial at temperatures ranging fr 32° to 230°F. The original calibration and certification is do under the supervision of Dr. Helmut Brauckhoff to the G. L Metallbarometerfabrik. GmbH Stuttgart, under the standard con tions of the Federal Republic Test Society.



6" overall diameter.
SOLID BRASS CASING

$77.9(
Delivered Price
Model AB-167

IRONCLAD GUARANTEE
No ifs, ands or buts in our guarantee — here it is — 100% absolute satisfaction guaranteed or your money back within 10 days without question or quibble.

Abbeon Cal. Inc. 123 Gray Ave., Santa Barbara, Ca. 93101 Phone (805) 963-7646


Please Mail Printed Blank On Your Order Catalog No. and Page No. — Catalog No. 783 — Pag

VAPOR PROOF LIGHTING FIXTURES

FRANKLIN F MACHINE

NFPA No. 96 APPROVED LIGHTING FIXTURES

"GUARDIAN" VAPORPROOF LIGHTING FIXTURE



The First NFPA No. 96 Approved Fixture
A must for a Complete NFPA Hood

- For Pre-Wired hoods — complete with wire leads for easy installation.
- For use with standard 100 watt bulb.
- Fits 4" or 3½" junction box.

No. 5250 PX	Fixture with shatterproof globe.
No. 5250 PX WG	Fixture with shatterproof globe and wire guard.

U.L. Listing "Commercial Cooking Hood Fixture"—
File No. E66663 Guide MZLR

CONVENTIONAL LIGHTING FIXTURES

VFC Series
- Without junction box for pre-wired hoods.



VFP Adaptor Assembly to fit Std. Junction Box

MODEL No. Without Junction Box	DESCRIPTION	MODEL No. With Junction Box
VFC-100	Glass globe without guard	VXS-100
VFC-100-PX	Shatterproof globe without guard	VXS-100-PX
VFC-100-WG	Glass globe with guard	VXS-100-WG
VFC-100-PX-WG	Shatterproof globe with guard.	VXS-100-PX-WG

VXS Series
- With junction box




- Fits standard 100 Watt bulb
- Shatterproof models are NSF approved
- U.L. Listing - "Enclosed & Gasketed" File #E31782


For Replacement Globes and Guards see page E-5.

No. VXS-200 Similar to VXS-100 except larger to accomodate a 200 Watt bulb.

RECESSED LIGHTING FIXTURES

No. 5300 "CENTURION" RECESSED FLUORESCENT LIGHTING FIXTURE.





- Designed specifically for Canopy hoods.
- All Stainless Steel trim and hinge.
- U.L. Listing — "Enclosed & Gasketed" File #E31782
- Unbreakable, heat resistant Lexan polycarbonate diffuser.
- Vaporproof conduit hubs.
- Bracket or stud mounted — Specify when ordering.
- Stock sizes: 24", 36", and 48"

Diffuser available in other materials.

notification... covering design, service and price information

To all sales personnel and dealers

N-79-112
March 1979
Replaces
Bulletin No. 116-68
January 20, 1969

SUBJECT: INSTALLING REMOTE REFRIGERATION SYSTEMS

Under no circumstances is it permissable to hang evaportor coils or to support condensing units weighing more than one hundred pounds directly on Bally prefab ceiling sections. All remote refrigeration systems weighing more than one hundred pounds must be supported as described below.


Mounting Evaporator Coils in Outdoor or Indoor Installations. If the ceiling sections are supported by interior structural steel the evaporator coil can be supported as shown in figure 1. If the walk-in does not have interior structural steel, special hangers must be used as shown in figure 2. If the walk-in has one center beam it can be supported as shown in figure 3. Cost of required steel supports and fastening devices will be listed on price quotation.

Support Condensing Units on Outdoor or Indoor Installations: *(up to and including 2 H.P.)* All condensing units must be mounted on steel channels which will distribute the weight to the side walls clear of the ceiling sections as shown in figure 3. Compressors larger than 2 H.P. must be supported independently of the walk-in or refrigerated building because of excessive vibration.


NOTE: *All evaporator coils weighing less than one hundred pounds can be hung directly on Bally ceiling panels by using steel rods secured to 6" x 6" x 1/8" thick steel plates on exterior of panel (For detail, see Instruction Manual IM-111-69, pg. 5, Fig. 6.).*

Bally

Bally Case & Cooler, Inc., Bally, Pa.




FRONT ELEVATION




SECTION A-A


FIGURE 1



FRONT ELEVATION




DETAIL "A"




SECTION A-A


FIGURE 2



FRONT ELEVATION



SECTION A-A



DETAIL "B"

FIGURE 3

Honeywell

Recorders, Indicators and Controllers
45-61-03-01
1/80

Model 61
Relative Humidity and Temperature Recorders

Specifications

Function

Honeywell Model 61 hygrometers monitor and permanently record on a circular chart the relative humidity and temperature of the ambient atmosphere without the use of psychrometric charts or tables. These hygrometers are ideal for monitoring performance of industrial and commercial heating, ventilating and air conditioning systems.

Description

Enclosure

The instrument is housed in a fabricated steel case with a picture frame cast aluminum door. A grid enclosed rear permits free air circulation to the measuring elements. The case has a cutout carrying handle on the rear and four rubber support feet for portable applications. The case can also be mounted in a panel or an air duct, or surface mounted to a wall.

Chassis

Inside the case, all components are mounted on the chart plate. On the front are the circular chart and one (humidity) or two pen(s) (humidity and temperature). There is a screw-type chart retaining hub. The pen assemblies are disposable fiber-tip ink cartridges each capable of producing more than 1000 feet of recorded trace on the chart. On the back of the chart plate are the spring-wound or electric chart drive motor, the nylon hygrometer element, and a bi-metal temperature spiral.

The nylon hydroscopic element responds to a change in relative humidity by a change in its length. A suitable linkage connects the element to a recording pen. On two pen models, a bi-metallic spiral senses temperature and actuates the temperature pen.



Figure 1 – Single Pen RH Recorder, handwound chart drive model with optional door lock



d Temperature Recorder,

ington, PA 19034

CUSTOMER IDENTIFICATIC
TRANSFER TAPE
ADHESIVE
ISFER TAPE
NOTICE: TH
TESTED AR
PLEASE USE CARE IN
ING SHIPPING CLAM
INSPECT
INSPECTOR
PLEASE ENC
WITH ANY C
CONCERNING
ington, PA 19034

Specifications

Operating Conditions

	Reference Conditions	Rated Conditions	Extreme Conditions	Transporation and Storage Conditions
Ambient Temperature	25 ± 3°C 77 ± 5°F	0 to 66°C 0 to 130°F	– 29 to 66°C – 20 to 150°F	– 29 to 66°C – 20 to 150°F
Relative Humidity	50 ± 5%	15 to 95%	5 to 98%	0 to 98%

Performance

Accuracy	*Relative Humidity:* ± 3% of total span from 15 to 95% RH. *Temperature:* ± 2% of span throughout range. Can be calibrated in the field to ± 1°F from 60° to 80°F on 0–100 range chart.
Actuation	*Relative Humidity:* Special treated nylon element. *Temperature:* Bi-metal spiral (available on two-pen models only).
Temperature Effect on RH	± 2% per 22°C (40°F)
Voltage and Frequency	120 or 220 Vac, 50 or 60 Hz (electric chart drives only).

Design

Chart	Diameter 203 mm (8 inch). Calibrated width 76.2 mm (3 inch). 24-hr or 7-day revolution (see Table 1).
Chart Drive	Spring wound, or electric motor drive. 24-hr or 7-day revolution.
Records	*Humidity:* Red *Temperature:* Purple
Mounting	Table, flush (duct or panel) or surface
Weight	*Net:* 5.5 kg (12 lb) *Shipping:* 11.3 kg (25 lb)
Dimensions	Refer to Figure 3.
Standard Accessories	1 box of 100 charts, 2 sets of disposable ink cartridges, 7 ft power cord (electric chart drive) or 1 key (handwound chart drive), 1 instruction and maintenance manual.

TABLE 1 - Chart Ranges

Chart Numbers			
24-hour	**7-day**	**Range**	**Valve per Division**
1565	1571	0–100% RH & °F	2
1610T	1639T	0 to 50°C	1
		0 to 100% RH	2
1628T	1634T	0 to 130°F	2
		0 to 100% RH	2

Ordering Information

Please specify:

Refer to Model Selection Guide
Model 612X9
Voltage and frequency (if electric chart drive)
Number of pens (humidity only or humidity and temperature)
Range and chart number (see Table 1)
Chart drive (electric or hand wound) and speed (24 hr or 7 day)
Optional door lock (if desired)

For more information, contact the nearest Honeywell Sales Office, or Honeywell Process Control Division, 1100 Virginia Drive, Fort Washington, PA, 19034. In Canada, Honeywell Limited 740 Ellesmere Road, Scarborough, Ontario M1P 2V9.

Specifications are subject to change without notice.

Dimensions: millimetres / inches




Figure 3


LHF

MULTIPLE UNIT - SINGLE PHASE DEFROST

CIRCUIT	FROM	TO
1	24D-2	24D-2
2		
3	1-2	1-2
4		
5	12-2	12-2
6	36-2	36-2
10	24-2, 45-2	24-2, 45-2
QTY.	WIRE	


REFRIGERATED TREE COOLER
AVERY RANGER STATION
IDAHO
AVERY, ,


M.J. MERRICK & ASSOCIATES
10 INVERNESS DRIVE EAST
ENGLEWOOD, COLORADO



PLAN

SCALE: 3/4" = 1'-0"





SECTION THRU WALL


SCALE: 3/4" = 1'-0"


M. J. MEEDLICK & ASSOCIATES
ENGLEWOOD, COLORADO

REFRIG. PIPE DIAGRAM


ISOMETRIC DRAWING of REFRIGERATION PIPING

AS BUILT





SIDE VIEW FRONT VIEW



WIRING SCHEMATIC

TEMPERATURE ALARM
MODEL #BB 8455

FOREST SERVICE COOLERS