AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT

1. CONTRACT ID CODE	PAGE	OF	PAGES
	1		8

2. AMENDMENT/MODIFICATION NO.	3. EFFECTIVE DATE	4. REQUISITION/PURCHASE REQ.NO.	5. PROJECT NO. *(If applicable)*
0004	11/13/2026		

6. ISSUED BY CODE AAQ510ATL-AFN

FEDERAL AVIATION ADMINISTRATION
AAQ-500 - REGIONAL ACQUISITIONS
1701 COLUMBIA AVENUE
COLLEGE PARK GA 30337

7. ADMINISTERED BY *(If other than Item 6)* CODE

8. NAME AND ADDRESS OF CONTRACTOR *(No., street, county, State and ZIP Code)*

CODE FACILITY CODE

(X) 9A. AMENDMENT OF SOLICITATION NO. 697DCK-27-R-00022A

[X] 9B. DATED *(SEE ITEM 11)* 10/07/2026

[ ] 10A. MODIFICATION OF CONTRACT/ORDER NO.

10B. DATED *(SEE ITEM 13)*

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

[X] The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers [X] is extended. [ ] is not extended.

Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing items 8 and 15, and returning 1 copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment number. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA *(If required.)*

13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.

(x)	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: *(Specify authority)* THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.
[ ]	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES *(such as changes in paying office, appropriation data, etc.)* SET FORTH IN ITEM 14.
[ ]	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:
[ ]	D. OTHER *(Specify type of modification and authority)*

E. IMPORTANT: Contractor [ ] is not [ ] is required to sign this document and return _____ copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (*Organized by UCF section headings, including solicitation/contract subject matter where feasible.)*

See continuation page

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER *(Type or print)*		16A. NAME AND TITLE OF CONTRACTING OFFICER *(Type or print)*	
		Linda M. Hennequant	
15B. CONTRACTOR/OFFEROR	15C. DATE SIGNED	16B. CONTRACT AUTHORITY	16C. DATE SIGNED
(Signature of person authorized to sign)		*(Signature of Contracting Officer)*	

NAME OF OFFEROR OR CONTRACTOR

ITEM NO. (A)	SUPPLIES/SERVICES (B)	QUANTITY (C)	UNIT (D)	UNIT PRICE (E)	AMOUNT (F)
	Design Renovation, SSC, 3551 Combine St., Paso Robles, California 93446. Contracting Officer: Linda.hennequant@faa.gov ********** ***** PURPOSE: The purpose of this amendment is to Change the Offer Due Date, and answer Vendor Questions. CHANGE: Offer due date: 30-NOV-26 changed to 02-DEC-26 QUESTIONS & ANSWERS: 1 – Applicable Building Code The current code enforced by the City of Paso Robles is the 2025 California Building Code (CBC). Please confirm we are to design to the 2025 version. FAA ANSWER: Please design to the 2025 California Building Code (CBC). While the Statement of Work (SOW) references the 2022 edition, it explicitly states that “the design must adhere to all Building Codes and Design Standards adopted by the City of Paso Robles.” Because the City has since adopted the 2025 version, it supersedes the 2022 edition. 2 – Architectural, Civil, and Structural Design Services The Statement of Work indicates scope for MEP, Life Safety, and Fire Protection. Will architectural services be required? Can we provide, as an option, the cost for Architectural, Civil, and Structural design services? FAA ANSWER: Drawings and SOW are provided to show intent and scope. If additional architectural drawings are required for permit/construction you will need to provide. 3 – Existing Thermal Envelope Please confirm that this project will not require upgrading the existing thermal envelope (wall insulation, roof insulation, window glazing U-factors, etc.). FAA ANSWER: It is not expected to be needed as the FAA does not have a standard, any deficiencies will be identified on the on-site Continued...				

NAME OF OFFEROR OR CONTRACTOR

ITEM NO. (A)	SUPPLIES/SERVICES (B)	QUANTITY (C)	UNIT (D)	UNIT PRICE (E)	AMOUNT (F)
	pre-bid visit. 4 – Missing Sheets A001, A002, and A003 Sheet A201, General Notes, Note G, refers to Sheets A001, A002, and A003. These sheets were not provided in the DID set. Please provide them to assist in pricing. FAA ANSWER: These reference sheets are considered 'boilerplate' standard accessibility sheets you will need to provide any current sheets for this locality needed for permit/construction. 5 – Topographic and Boundary Survey The DIDs indicate a new fence and gates surrounding the majority of the existing parking. Should our proposal include a topographic and boundary survey? FAA ANSWER: That is not needed, the FAA will be doing it's own Metes and Bounds survey for the exact boundary locators. 6 – As-Built Documents and CAD/BIM Files Please provide available as-built documents and the CAD/BIM files of the provided DIDs. Please also provide fire sprinkler as-built drawings and calculations. FAA ANSWER: We will provide the CAD files for the DIDs. We do not have the original CAD files or as-builts for the building or the fire sprinkler. The building owner/leasing company would have those. 7 – Laminated Glass for Force Protection Please confirm whether existing doors and windows require laminated glass as a force protection measure. FAA ANSWER: This is not required. 8 – Window and Door Coverings Please confirm whether window or door coverings (privacy film, shades, blinds) are required on any or all glazing and fenestrations. FAA ANSWER: Shades or Blinds should be included on windows and doors. 9 – Door Security Hardware Please confirm which doors, if any, require Continued...				

ITEM NO. (A)	SUPPLIES/SERVICES (B)	QUANTITY (C)	UNIT (D)	UNIT PRICE (E)	AMOUNT (F)
	specific security hardware, such as card access, cipher hardware, a wireless access system, a biometric system, or alarmed systems. FAA ANSWER: None, only door hardware requirement as they must accept a Best Lock 7-pin core on all exterior and locked interior doors. 10 – Intrusion Detection System Please confirm whether an intrusion detection system (IDS) is required, including cameras or alarms for monitoring traffic and security breaches. FAA ANSWER: No, not part of this scope. 11 – Finish Specifications Please provide specifications for the new finishes: luxury vinyl tile, carpet, porcelain/ceramic tile, and acoustical ceiling system. FAA ANSWER: Specific finishes will be selected by FAA by 90% review. 12 – Locker Specification Please provide the specification for the eight (8) new lockers in Room 118, Back of House (BOH). FAA ANSWER: Vented metal lockers for PPE equipment, 18”W x 36”D x 72 “H. 13 – Electric Water Cooler Please confirm whether the indicated electric water cooler is a single unit or a high-low (bi-level) unit. Will a bottle filler be required in either case? FAA ANSWER: This should be a high-low unit with a bottle filler. 14 – Salvaged Plumbing Fixtures Sheet A200, Demo Note 4, indicates fixtures are to be salvaged. Please confirm that the existing fixtures meet current plumbing code water-saving standards. FAA ANSWER: This should be noted on your design that the contractor is to determine what is salvageable and meeting the permitting guidelines. There may not be any salvageable				

Continued...

NAME OF OFFEROR OR CONTRACTOR

ITEM NO. (A)	SUPPLIES/SERVICES (B)	QUANTITY (C)	UNIT (D)	UNIT PRICE (E)	AMOUNT (F)
	fixtures. 15 – Existing Flooring Please indicate the existing flooring type and extent. FAA ANSWER: Existing flooring includes ceramic/porcelain tile (general area) and polished concrete (back of house area). Will confirm on site visit. 16 – Existing Ceilings Please establish the existing ceiling type and extent. FAA ANSWER: Hard qypsum board ceiling (general areas) and exposed ceiling (back of house area). Will confirm on site visit. 17 – HVAC at ELEC/TELCO Room 105 Does ELEC/TELCO Room 105 require 24/7 HVAC? FAA ANSWER: Yes, this area requires a separate mini-split unit for conditioning. 18 – Air Conditioning at BOH Room 118 Please confirm whether BOH Room 118 requires air conditioning. FAA ANSWER: Yes, this is conditioned space. 19 – Partition Stud Type On Sheet A501, Partition Types General Notes, Keynote 3, and Partition Type Detail 1, please confirm whether all studs are to be wood or metal. FAA ANSWER: Specific partition types calls out 3 5/8″ metal studs. 20 – Door Inset Grilles Sheet A501, Notes by Number, Note 6, refers to inset grilles, but Note 6 is not listed on the Schedule. Please verify whether inset grilles are required on doors. FAA ANSWER: General notes are not all used on design, reference design schedule. 21 – Emergency Backup Power Please confirm whether emergency backup power and a generator are required. FAA ANSWER: No back-up power is required. Continued...				

ITEM NO. (A)	SUPPLIES/SERVICES (B)	QUANTITY (C)	UNIT (D)	UNIT PRICE (E)	AMOUNT (F)
	22 – Back-of-House Functions Please describe the functions and activities that will occur in the Back-of-House area. FAA ANSWER: This area is used for project material delivery and storage along with storage of parts for FAA navigational and communications equipment. There will also be a HAZMAT locker for pesticides and paint storage. Minimal shop tools and workbenches. It is not intended to house vehicles and we do not do any maintenance on FAA vehicles. 23 – Rooftop HVAC Unit Please confirm that the rooftop HVAC unit will be new and is part of the project scope. Is demolition of the existing HVAC system in the scope? FAA ANSWER: It is not part of the scope to replace the HVAC system that is on the roof. This system is provided by that lessor. The age of the system does not appear to need changing at this time. 24 – Roof-Mounted Antennas Will antennas be mounted on the roof? If so, please indicate weight, dimensions, and any special mounting requirements. FAA ANSWER: We will not be installing any roof top antennas. 25 – Does the ten-week completion period include both FAA review and final City of Paso Robles approval, or is it the deadline for submitting completed permit-ready drawings? FAA ANSWER: The ten-week completion period is from the NTP to the final permit drawing submittal to the City for approval. You cannot be responsible for City review timelines. 26 – The SOW requires the 90% design submission within three weeks of the "review submission." What event starts that three-week period? FAA ANSWER: FAA's return of approval/comments to the 90% design. 27 -Does the Texas architect have someone licensed in CA? If not, we would need to be the Architect of Record. Continued...				

NAME OF OFFEROR OR CONTRACTOR

ITEM NO. (A)	SUPPLIES/SERVICES (B)	QUANTITY (C)	UNIT (D)	UNIT PRICE (E)	AMOUNT (F)
	FAA ANSWER: Correct, you would need to be the Architect of Record 28 - Will we receive the CAD background drawings from the Texas architect or will we need to create our own drawings? This is important in terms of cost. FAA ANSWER: Yes, we will provide the CAD for the Design Intent Drawings 29 - What is the requirement for site survey? Do they need a boundary survey from a licensed surveyor? Or just a site visit to the existing building to verify the information in the design drawings from the Texas architect? FAA ANSWER: Just a site visit to the existing building not a land boundary survey. 30 - When is the project expected to be awarded? When are our services expected to start? FAA ANSWER: Award is expected within 60 days after the offer due date. A Post-award meeting will be held shortly after award to determine the start date. 31 - In addition to the required documents identified in Section L02, may offerors include supplemental qualifications such as key personnel resumes, relevant project sheets, or a brief overview of the team's experience working together? FAA ANSWER: There are no objections to this. However, the determination for award will be based on pricing. 32 - Does the Fire Protection Engineer need specific FAA experience? Will any specialty equipment require a specific Fire Protection system? FAA ANSWER: No, there are no FAA requirements for the fire suppression, only what is required by the city/state. 33 - What is the anticipated award date? FAA ANSWER: Within 60 days after Offer due date Continued...				

NAME OF OFFEROR OR CONTRACTOR

ITEM NO. (A)	SUPPLIES/SERVICES (B)	QUANTITY (C)	UNIT (D)	UNIT PRICE (E)	AMOUNT (F)
	34 - Leidos provided the architectural Design Intent Drawings; however, architectural construction documents will still be required for submission to the local jurisdiction for permitting. Should we assume the awarded team will be responsible for completing these drawings and serving as the Architect of Record? FAA ANSWER: Yes 35 - The SOW requires a site survey within seven days of Notice to Proceed. Can you confirm whether this refers to a formal land survey performed by a licensed land surveyor or on-site field verification of existing conditions by the A&E team? FAA ANSWER: Does not refer to a land survey, just an on-site field verification. 36 - Who will be responsible for preparing the architectural portion of the permit set and for addressing any architectural questions, revisions, or plan-check comments related to the Leidos Design Intent Drawings during development of the permit set and City review? Will Leidos remain available for architectural coordination and preparation of the architectural permit documents, or is the selected consultant expected to include architectural services as part of its team? FAA ANSWER: The intent is to include this with your offer and the selected consultant expected to include architectural services as part of its team. The Leidos Architect will be available for architectural coordination but not for the preparation of the architectural permit documents. That must be included in the offer. END OF AMENDMENT				