PROJECT SPECIFICATIONS

For

Project PBXP272019
B300 BDOC Renovation
At

179 CYBERSPACE WING
OHIO AIR NATIONAL GUARD
1947 HARRINGTON MEMORIAL ROAD
MANSFIELD LAHM AIRPORT, OHIO

TABLE OF CONTENTS

DIVISION 01
GENERAL REQUIREMENTS

SECTION 01 11 00 SUMMARY
PART 1 GENERAL
1.1 Work Covered by Contract Documents
1.2 Work Restrictions
1.3 Occupancy of Premises
1.4 Existing Work
1.5 Government Furnished Equipment and Materials
1.6 Submittals
PART 2 PRODUCTS (NOT USED)
PART 3 EXECUTION (NOT USED)

SECTION 01 20 00 PRICE AND PAYMENT PROCEDURES
PART 1 GENERAL
1.1 Product Substitution Procedures
1.2 Submittals
PART 2 PRODUCTS (NOT USED)
PART 3 EXECUTION (NOT USED)

SECTION 01 30 00 ADMINISTRATIVE REQUIREMENTS
PART 1 GENERAL
1.1 Project Management and Coordination
1.2 Submittals
1.3 Construction Progress Documentation
1.4 Survey and Layout Data
1.5 Construction Progress Reporting
1.6 Submittal Procedures
1.7 Special Procedures
PART 2 PRODUCTS (NOT USED)
PART 3 EXECUTION (NOT USED)

SECTION 01 33 00 SUPPLEMENTAL SUBMITTAL PROCEDURES
PART 1 GENERAL
1.1 Definitions
1.2 Submittals
1.3 Submittal Classification
1.4 Preparation
1.5 Quantity of Submittals
1.6 Information Only Submittals
1.7 Product Submittal Register
1.8 Variations
1.9 Scheduling
1.10 Government Approving Authority
1.11 Disapproved Submittals
1.12 Approved Submittals
1.13 Approved Samples
PART 2 PRODUCTS (NOT USED)
PART 3 EXECUTION (NOT USED)

SECTION 01 40 00 QUALITY REQUIREMENTS
PART 1 GENERAL
1.1 Abbreviations and Acronyms

1.2 Reference Standards
1.3 Submittals
1.4 Quality Assurance
1.5 Quality Control
1.6 Testing and Inspecting Services
1.7 Testing Laboratory Services
PART 2 PRODUCTS (NOT USED)
PART 3 EXECUTION (NOT USED)

SECTION 01 60 00 PRODUCT REQUIREMENTS
PART 1 GENERAL
1.1 Submittals
1.2 Common Product Requirements
1.3 Product Options
1.4 Product Delivery Requirements
1.5 Product Storage and Handling Requirements
PART 2 PRODUCTS (NOT USED)
PART 3 EXECUTION (NOT USED)

SECTION 01 70 00 EXECUTION AND CLOSEOUT REQUIREMENTS
PART 1 GENERAL
1.1 Submittals
1.2 Examination and Preparation
1.3 Field Engineering
1.4 Cleaning and Waste Management
1.5 Site Maintenance
1.6 Final Cleaning
1.7 Starting and Adjusting
1.8 Closeout Procedures
1.9 Closeout Submittals
1.10 Extra Stock Materials
PART 2 PRODUCTS (NOT USED)
PART 3 EXECUTION (NOT USED)

SECTION 1 74 19 CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL
PART 1 GENERAL
1.1 Related Documents
1.2 References
1.3 Definitions
1.4 Submittals
1.5 Construction Waste Management
1.6 Meetings
1.7 Oversight
1.8 Records
PART 2 PRODUCTS (NOT USED)
PART 3 EXECUTION
3.2 Construction Waste
3.3 Collection
3.4 Disposal
3.5 Hazardous Materials Waste

DIVISION
XXXXXXXXXX

END OF TABLE OF CONTENTS

SECTION 01 11 00
SUMMARY OF WORK

PART 1. GENERAL

1.1. WORK COVERED BY CONTRACT DOCUMENTS

1.1.1. The work included in this project consists of furnishing all plant, labor, materials, and equipment required to accomplish the project in strict accordance with these Specifications, the Statement of Work and the Drawings. The principal items of work include, but are not limited to:

1.1.1.1. Demolition and Removal; work locations shall be as shown on the Drawings. Perform such work required at each location with due care, including shoring, bracing, and so on.

1.1.1.2. Manufactured Articles, Materials, and Equipment; shall be applied, installed, connected, erected, used, cleaned, and conditioned as directed by the respective manufacturers, unless otherwise specified.

1.2. WORK RESTRICTIONS

1.2.1. Access to Site

1.2.1.1. Location of the work to be performed is at the 179 Cyberspace Wing, Ohio Air National Guard Base, 1947 Harrington Memorial Road, Mansfield, Ohio 44903-8049, Building #300. See attached Site Plan for the location of the existing site where the work locations are to take place at and for the other various areas on base pertinent to the job.

1.2.2. Coordination with Site Occupants

1.2.2.1. Work Schedule; shall be performed Monday through Friday, excluding Federal Holidays, unless otherwise directed or permitted by the Contracting Officer. Work shall be performed from 7:30 AM to 4:30 PM, unless otherwise directed or permitted by the Contracting Officer.

1.3. OCCUPANCY OF PREMISES

1.3.1. Building(s) will be occupied during performance of work under this Contract. Before work is started, arrange with the Contracting Officer a sequence of procedure, means of access, space for storage of materials and equipment, and use of approaches, corridors, and stairways.

1.3.2. Contractor Use of Site

1.3.2.1. During the construction period, Contractor shall have full use of the premises within the project limits as shown on the Drawings for execution of the work. Use of premises is limited only by Owner’s right to perform duties and functions as stated in the GENERAL CONDITIONS and in this section.

1.3.2.2. The Contractor, before starting any work relating to existing utilities (electrical, sewer, water, heat, gas, fire lines, etc.) that will temporarily discontinue or disrupt service to the existing facilities, will notify the Contracting Officer's Representative 72 hours in advance and obtain approval in writing before proceeding with this phase of the work.

1.4. EXISTING WORK

1.4.1. Remove or alter existing work in such a manner as to prevent injury or damage to any portions of the existing work which remain.

1.4.2. Repair or replace portions of existing work which have been altered during construction operations to match existing or adjoining work, as approved by the Contracting Officer. At the completion of operations, existing work must be in a condition equal to or better than that which existed before new work started.

1.5. GOVERNMENT FURNISHED MATERIAL AND EQUIPMENT:

1.5.1. The Government will furnish the following materials and equipment for installation by the Contractor:

1.5.1.1. NONE

1.6. SUBMITTALS: NONE

PART 2. PRODUCTS (NOT USED)

PART 3. EXECUTION (NOT USED)

END OF SECTION 01 11 00

SECTION 01 20 00
PRICE AND PAYMENT PROCEDURES

PART 1. GENERAL (SUBSTITUTION PROCEDURES)

1.1. PRODUCT SUBSTITUTION PROCEDURES

1.1.1. This Section includes administrative and procedural requirements for handling requests for substitutions made after award of the Contract. No substitutions will be evaluated during bidding.

1.1.2. Acceptable manufacturers listed in the Contract Documents are not intended to exclude manufacturers not listed. Products of equal performance will be considered.

1.1.3. Related work specified elsewhere in these Contract Documents:

1.1.3.1. Requirements for submitting Contractor’s Construction Progress schedule and the Submittal schedule: SECTION 01 33 00.

1.1.3.2. Requirements governing Contractor’s selection of products: SECTION 01 60 00.

1.1.4. Definitions: Substitutions are changes in products, materials, equipment, and methods of construction required by the Contract Documents proposed by the Contractor after award of the Contract are considered to be requests for substitutions.

1.1.4.1. The following are not considered to be requests for substitutions; revisions to the Contract Documents requested by Owner or Engineer, and specified options of products and construction methods included in the Contract Documents.

1.1.5. Substitution of products will be considered after award of contract only under one of the following conditions:

1.1.5.1. When the specified product is not available, a proposed substitution will not be considered unless proof is submitted that firm orders were placed within 30 days after

commencement of the work and reviewed by the Contracting Officer's Representative in which the items unavailability is due to a strike, lockout, bankruptcy, discontinuance of the manufacture of a product, or natural disasters.

1.1.5.2. When a guarantee of performance is required and, in the judgment of the Contractor, the specified product or process will not produce the desired results.

1.1.6. Submit in writing, 3 copies of each request for substitution, to the Contracting Officer's Representative within the 30 days after commencement of the work. After that date, if the Contractor ascertains he cannot obtain the material or equipment specified, or the performance cannot be guaranteed it may be considered or rejected at the discretion of the Engineer.

1.1.6.1. Requests for substitutions shall not be submitted in the form of a Request for Information (RFI).

1.1.6.2. Submit requests for substitutions in the form and according to procedures required for Change Order proposals.

1.1.6.3. The Contractor shall accompany any request for substitution with such drawings, specifications, samples, manufacturer's literature, performance data, and other information necessary to describe and evaluate the proposed substitution completely. The burden of proof shall be on the Contractor.

1.1.6.4. Permission to make any substitution after award of contract shall be affected by a Change Order. It shall not relieve the Contractor, any subcontractor, manufacturer, fabricator, or supplier from responsibility for any deficiency that may exist in the substituted product or for any departures or deviations from the requirements of the Contract Documents as modified by such Change Order. Except as otherwise expressly specified by the Contractor in his request for substitution and expressly approved in such Change Order, the Contractor shall be deemed to warrant by his request proposed substitute product will satisfy all standards and requirements satisfied by the originally specified product and the Change Order shall not be deemed to modify the Contract Documents with respect thereto.

1.1.6.5. If any substitution will affect a correlated function, adjacent construction, or the work of other trades or contractors, the necessary changes and modifications to the affected work shall be considered as an essential part of the proposed substitution, to be accomplished by the Contractor without additional expense to the Government if and when accepted.

1.2. SUBMITTALS: NONE

PART 2. PRODUCTS (NOT USED)

PART 3. EXECUTION (NOT USED)

END OF SECTION 01 20 00

SECTION 01 30 00
ADMINISTRATION REQUIREMENTS

PART 1. GENERAL

1.1. PROJECT MANAGEMENT AND COORDINATION

1.1.1. Project Coordination

1.1.1.1. Coordination between various trades and sections with reference to scheduling items of work shall be the responsibility of the Contractor. To this end the Contractor shall require that the subcontractors examine and familiarize themselves with the Specifications and Drawings and they frequently consult with each other and all other trades so that the work can be properly coordinated. The Contractor shall carefully check the work of his subcontractors in order to deliver to the Government the Contract work, complete and properly installed in conformance with the Contract requirements.

1.1.2. Project Meetings

1.1.2.1. The Contractor and any subcontractors, material men, or vendors whose presence is necessary or requested must attend meetings when called by the Contracting Officer or his Representative for the purpose of discussing the execution of the work. Each of such meetings will be held at the time and place designated by the Contracting Officer or his Representative. All decisions, instructions, and interpretations given by the Contracting Officer or his Representative at these meetings shall be binding and conclusive on the Contractor. The proceedings of these meetings will be recorded, and the Contractor will be furnished a reasonable number of copies for his use and for distribution to the various subcontractors, material men, and vendors involved.

1.1.2.2. Progress meetings may also be called by the General Construction Contractor for the purpose of coordinating, expediting, and scheduling the work of all contracts. Other contractors and their subcontractors, material men, or vendors whose presence is necessary or requested are required to attend.

1.1.3. Requests for Information (RFI)

1.1.3.1. Promptly on discovery of the need for interpretation of the Contract Documents, and if not possible to request interpretation at Project meeting, prepare and submit an RFI to the Contracting Officer with the content specified.

1.1.3.1.1. RFIs shall originate with the Contractor. RFIs submitted by entities other than Contractor will be returned with no response.

1.1.3.1.2. Coordinate and submit RFIs in a prompt manner so as to avoid delays in Contractor’s work or work of subcontractors.

1.1.3.2. Content of the RFI shall include a detailed, legible description of the item(s) needing interpretation, RFI numbered sequentially, reference to Drawing and detail, Specification section and paragraphs, field conditions, Contractor’s suggested solution and statement of impact to Contract times or price, and any attachments necessary to fully describe item needing interpretation.

1.1.3.3. The COR will review each RFI, determine action required, and return it to the Contractor. Allow seven working days for COR response for each RFI.

1.1.3.4. The following RFIs will be returned without action; request for approval of submittals, substitutions, coordination information already indicated in the Contract Documents, adjustments in the Contract times or price, interpretation of COR actions on Submittals, and incomplete RFIs or RFIs with numerous errors.

1.1.3.5. Multiple RFIs addressing similar or identical issues may be addressed by COR with single broad response.

1.1.3.6. COR action may include a request for additional information, in which case COR time for response will start again upon Contractor response and resubmittal.

1.1.3.7. If Contractor believes the RFI response warrants change in the Contract time or the price, notify Contracting Officer in writing within seven working days of receipt of the RFI response.

1.1.3.8. on receipt of COR action, update the RFI log and promptly distribute the RFI response to affected parties. Review response and notify COR within seven working days if Contractor disagrees with response.

1.1.3.9. Prepare, maintain, and submit a tabular log of RFIs organized by the RFI number. Submit log once every two weeks.

1.2. SUBMITTALS FOR THIS SECTION:

1.2.1. Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or “S” classification are for information only. Submit the following in accordance with Section 01 33 00 SUPPLEMENTAL SUBMITTAL PROCEDURES:

1.2.1.1. SD-01 Preconstruction Submittals

1.2.1.1.1. Construction Progress Schedule; G

1.2.1.1.2. Construction Progress Reports (Frequency determined by Contracting Officer)

1.2.1.1.3. Daily Construction Reports

1.2.1.2. SD-07 Certificates

1.2.1.2.1. Hazardous Materials Manifests; G

1.3. CONSTRUCTION PROGRESS DOCUMENTATION

1.3.1. Construction Progress Schedule: [**SD-01]** Before commencing any work the Contractor shall submit, for review and approval by the Contracting Officer's Representative, a schedule showing the commencement, the order, and the completion dates for the various parts of this work.

1.4. SURVEY AND LAYOUT DATA

1.4.1. The Contractor is responsible for properly laying out the work, and for lines and measurements for the work executed under the Contract Documents.

1.4.1.1. The Contractor, NOT the Government, is responsible to field verify all existing utilities within the limits and/or as shown on the Drawings, before laying out the work. The Contractor is to report errors or inaccuracies in writing to the Contracting Officer's Representative before commencing work.

1.4.1.2. The Contracting Officer or his Representative will in no case assume the responsibility for any layout of the work or damages to existing utilities while performance of work is underway.

1.5. CONSTRUCTION PROGRESS REPORTING

1.5.1. Reports

1.5.1.1. **[SD-01]** Construction Progress Reports consisting of the revised construction progress schedule and a narrative report consisting of comparison of actual progress with

planned progress, summaries of activities completed since previous report, planned activities for next report period, value analysis for month, identification of problem areas, description of current and anticipated delaying factors with impact, and proposed corrective actions

1.5.1.2. **[SD-01]** Daily Construction Reports prepared daily for recording information concerning events at the work site to include subcontractors at the site, count of working personnel at the site, equipment at the site, material deliveries, weather conditions, accidents at the site, stoppages, delays, shortages, losses, and emergency procedures.

1.5.1.3. Other reports may be used but not limited to Equipment and Material Location Reports, Field Condition Reports, and Special Reports for unusual events.

1.5.1.4. Inspection reports shall be recorded and submitted daily on approved forms certifying items correctly installed and items found to be defective with a statement on corrective measures taken.

1.6. SUBMITTAL PROCEDURES

1.6.1. Shop Drawings, Product Data, and Samples: Shop Drawings, Product Data, and Samples are technical submittals prepared by Contractor, subcontractor, manufacturer, or supplier and submitted by the Contractor to the COR as a basis for approval of the use of equipment and materials proposed for incorporation in the work or needed to describe installation, operation, maintenance, or technical properties, as specified in each Division of the Specifications.

1.6.1.1. Shop Drawings include custom-prepared data of all types including drawings, diagrams, performance curves, material schedules, templates, instructions, and similar information not in standard printed form applicable to other projects.

1.6.1.2. Product Data includes standard printed information on materials, products, and systems not custom-prepared for this project, other than the designation of selections from available choices.

1.6.1.3. Samples include both fabricated and unfabricated physical examples of materials, products, and work; both as complete units and as smaller portions of units of work; either for limited visual inspection or for more detailed testing and analysis. Mock-ups are a special form of Samples which are too large to be handled in the specified manner for transmittal of Sample submittals.

1.6.2. Informational Submittals are those technical reports, administrative submittals, certificates, and guarantees not defined as Shop Drawings, Product Data, or Samples.

1.6.3. Quality Requirements

1.6.3.1. Submittals such as Shop Drawings and Product Data shall be of suitable quality for legibility and reproduction purposes. Every line, character, and letter shall be clearly legible. Drawings such as reproducible shall be useable for further reproduction to yield legible hard copy.

1.6.3.2. Documents submitted to the COR that do not conform to specified requirements shall be subject to rejection by the COR, and upon request by the COR, Contractor shall resubmit conforming documents. If conforming submittals cannot be obtained, such documents shall be retraced, redrawn, or photographically restored as may be necessary to meet such requirements. Contractor’s failure to initially satisfy the legibility quality requirements will not relieve Contractor from meeting the required schedule for submittals.

1.6.4. Submittal Completeness

1.6.4.1. Submittals shall be complete with respect to dimensions, design criteria, materials of construction, and other information specified to enable COR to review the information effectively.

1.6.4.2. Where standard drawings are furnished which cover a number of variations of the general class of equipment, each drawing shall be annotated to indicate exactly which parts of the drawing apply to the equipment being furnished. Use hatch marks to indicate variations that do not apply to the submittal. The use of “highlighting markers” will not be an acceptable means of annotating submittals. Annotation shall also include proper identification of the submittal permanently attached to the drawing.

1.6.4.3. Reproductions or copies of Contract Drawings or portions thereof will not be accepted as complete fabrication or erection drawings. Contractor may use a reproduction of Contract Drawings for erection drawings to indicate information on erection or to identify detail drawing references. Whenever the drawings are revised to show this additional Contractor information, Engineer’s title block shall be replaced with Contractor’s title block, and Engineer’s professional seal shall be removed from the drawing. Contractor shall revise these erection drawings for subsequent Engineer revisions to the Contract Drawings.

1.6.5. Resubmission: Resubmittal procedure shall follow the same procedure as the initial submittal.

1.6.6. Contracting Officer's Action on Transmittal Form:

1.6.6.1. Incomplete or erroneous transmittals will be returned without action.

1.6.6.2. The remainder of the transmittal will be filled out by the Contracting Officer's Representative.

1.6.7. Submittal Procedures by Contractor:

1.6.7.1. Civil/Site items as follows:

1.6.7.1.1. (4) prints of shop drawings with transmittal forms.

1.6.7.1.2. (1) samples with transmittal forms.

1.6.7.1.3. (4) copies of brochures with transmittal forms.

1.6.8. Contracting Officer's Review:

1.6.8.1. Contracting Officer's Representative will process the submission and indicate the appropriate action on the submission and the transmittal.

1.7. SPECIAL PROCEDURES

1.7.1. Environmental Procedures:

1.7.1.1. Contractor shall dispose of all hazardous materials and hazardous wastes created by the project at an off installation location, certified for the disposal of the particular wastes, in accordance with all Federal, State, Local and Installation laws, rules, and regulations.

1.7.1.1.1. Accumulation, packaging, transportation, and disposal will be in accordance with 40 CFR, Parts 20-23, and Ohio EPA Regulations for hazardous waste. Coordinate with the Contracting Officer’s Representative (COR) for the installation’s EPA Identification Number.

1.7.1.1.2. Coordinate with the Installation Environmental Management Office when preparing hazardous materials manifests.

1.7.1.1.3. **[SD-07]** Provide a copy of all manifests to the COR on the day items are shipped, when comeback copy is received, and when disposal copy is received.

1.7.2. Security Procedures

1.7.2.1. Materials or items designated to become the property of the Government shall be as shown on the Drawings. Remove such items with care and store them in a location at the site to be designated by the Contracting Officer's Representative.

1.7.2.2. Materials or items designated to be reinstalled shall be as shown on the Drawings. Remove such items with care under the supervision of the trade responsible for reinstallation; protect and store until required. Replace material or items damaged in its removal with similar new material.

1.7.2.3. Materials or items demolished and not designated to become the property of the Government or to be reinstalled shall become the property of the Contractor and shall be removed from the Government's property.

1.7.2.4. The Contractor is responsible for any damage that may be caused by work to any part or parts of existing facilities or items designated for reuse.

PART 2. MATERIALS (NOT USED)

PART 3. EXECUTION (NOT USED)

END OF SECTION 01 30 00

SECTION 01 33 00
SUPPLEMENTAL SUBMITTAL PROCEDURES

PART 1. GENERAL

1.1. DEFINITIONS

1.1.1. Submittal Descriptions (SD): Submittal requirements are specified in the technical sections. Examples and descriptions of submittals identified by the Submittal Description (SD) numbers and titles follow:

1.1.1.1. SD-01 Preconstruction Submittals: For Government approved division 01 preconstruction submittals that are required prior to or commencing with the start of work must be submitted within 30 calendar days of contract award unless specified elsewhere in the specifications. Preconstruction Submittals include schedules and a tabular list of locations, features, and other pertinent information regarding products, materials, equipment, or components to be used in the work.

1.1.1.1.1. Certificates Of Insurance Surety Bonds

1.1.1.1.2. List Of Proposed Subcontractors List Of Proposed Products

1.1.1.1.3. Baseline Network Analysis Schedule (NAS) Submittal Register

1.1.1.1.4. Schedule Of Prices Or Earned Value Report

1.1.1.1.5. Work Plan

1.1.1.1.6. Quality Control (QC) plan

1.1.1.1.7. Environmental Protection Plan

1.1.1.2. SD-02 Shop Drawings: Drawings, diagrams and schedules specifically prepared to illustrate some portion of the work

1.1.1.3. SD-03 Product Data: Catalog cuts, illustrations, schedules, diagrams, performance charts, instructions and brochures illustrating size, physical appearance and other characteristics of materials, systems or equipment for some portion of the work.

1.1.1.4. SD-04 Samples

1.1.1.4.1. Fabricated or unfabricated physical examples of materials, equipment or workmanship that illustrate functional and aesthetic characteristics of a material or product and establish standards by which the work can be judged.

1.1.1.4.2. Color samples from the manufacturer's standard line (or custom color samples if specified) to be used in selecting or approving colors for the project.

1.1.1.4.3. Field samples and mock-ups constructed on the project site establish standards ensuring work can be judged. Includes assemblies or portions of assemblies that are to be incorporated into the project and those that will be removed at conclusion of the work.

1.1.1.5. SD-05 Design Data: Design calculations, mix designs, analyses or other data pertaining to a part of work.

1.1.1.6. SD-06 Test Reports

1.1.1.6.1. Report signed by authorized official of testing laboratory that a material, product or system identical to the material, product or system to be provided has been tested in accord with specified requirements. Unless specified in another section, testing must have been within three years of date of contract award for the project.

1.1.1.6.2. Report that includes findings of a test required to be performed on an actual portion of the work or prototype prepared for the project before shipment to job site.

1.1.1.6.3. Report that includes finding of a test made at the job site or on sample taken from the job site, on portion of work during or after installation.

1.1.1.6.4. nvestigation reports Daily logs and checklists

1.1.1.6.5. Final acceptance test and operational test procedure

1.1.1.7. SD-07 Certificates

1.1.1.7.1. Statements printed on the manufacturer's letterhead and signed by responsible officials of manufacturer of product, system or material attesting that the product, system, or material meets specification requirements. Must be dated after award of project contract and clearly name the project.

1.1.1.7.2. Document required of Contractor, or of a manufacturer, supplier, installer or Subcontractor through Contractor. The document purpose is to further promote the orderly progression of a portion of the work by documenting procedures, acceptability of methods, or personnel qualifications.

1.1.1.7.3. Confined space entry permits

1.1.1.7.4. Waste manifests documenting the orderly and safe transfer, shipping and disposal of regulated wastes in accordance with all Federal, State, Local, and Installation laws, rules, and regulations.

1.1.1.7.5. Text of posted operating instructions

1.1.1.8. SD-08 Manufacturer's Instructions: Preprinted material describing installation of a product, system or material, including special notices and (SDS) concerning impedances, hazards and safety precautions.

1.1.1.9. SD-09 Manufacturer's Field Reports

1.1.1.9.1. Documentation of the testing and verification actions taken by manufacturer's representative at the job site, in the vicinity of the job site, or on a sample taken from the job site, on a portion of the work, during or after installation, to confirm compliance with manufacturer's standards or instructions. The documentation must be signed by an authorized official of a testing laboratory or agency and state the test results; and indicate whether the material, product, or system has passed or failed the test.

1.1.1.9.2. Factory test reports.

1.1.1.10. SD-10 Operation and Maintenance Data

1.1.1.10.1. Data provided by the manufacturer, or the system provider, including manufacturer's help and product line documentation, necessary to maintain and install equipment, for operating and maintenance use by facility personnel.

1.1.1.10.2. Data required by operating and maintenance personnel for the safe and efficient operation, maintenance and repair of the item.

1.1.1.10.3. Data incorporated in an operations and maintenance manual or control system.

1.1.1.11. SD-11 Closeout Submittals

1.1.1.11.1. Documentation to record compliance with technical or administrative requirements or to establish an administrative mechanism.

1.1.1.11.2. Submittals required for Guiding Principle Validation (GPV) or Third Party Certification (TPC).

1.1.1.11.3. Special requirements necessary to properly close out a construction contract. For example, Record Drawings and as-built drawings. Also, submittal requirements necessary to properly close out a major phase of construction on a multi-phase contract.

1.1.2. Approving Authority: Office or designated person authorized to approve the submittal.

1.1.3. Work: As used in this section, on-site and off-site construction required by contract documents, including labor necessary to produce submittals, construction, materials, products, equipment, and systems incorporated or to be incorporated in such construction. In exception, excludes work to produce SD-01 submittals.

1.2. SUBMITTALS FOR THIS SECTION: NONE

1.3. SUBMITTAL CLASSIFICATION

1.3.1. Government Approved (G): Within the terms of the Contract Clause SPECIFICATIONS AND DRAWINGS FOR CONSTRUCTION, submittals are considered to be "shop drawings."

1.3.2. For Information Only: Submittals not requiring Government approval will be for information only. Within the terms of the Contract Clause SPECIFICATIONS AND DRAWINGS FOR CONSTRUCTION, they are not considered to be "shop drawings."

1.3.3. Sustainability Reporting Submittals (S): NOT USED

1.4. PREPARATION

1.4.1. Transmittal Form: Use Air Force Form 3000 for the transmittal of submittals. Ensure all information is included on the form. Attach the form to all submittals.

1.4.2. Submittal Format

1.4.2.1. Format of SD-01 Preconstruction Submittals: When the submittal includes a document that is to be used in the project, or is to become part of the project record, other than as a submittal, do not apply the Contractor's approval stamp to the document itself, but to a separate sheet accompanying the document. Provide data in the unit of measure used in the contract documents.

1.4.2.2. Format for SD-02 Shop Drawings

1.4.2.2.1. Provide shop drawings not less than 8 1/2 by 11 inches nor more than 30 by 42 inches, except for full-size patterns or templates. Prepare drawings to accurate size,

with scale indicated, unless another form is required. Ensure drawings are suitable for reproduction and of a quality to produce clear, distinct lines and letters, with dark lines on a white background.

1.4.2.2.2. Include the nameplate data, size, and capacity on drawings. Also include applicable federal, military, industry, and technical society publication references.

1.4.2.2.3. Dimension drawings, except diagrams and schematic drawings. Prepare drawings demonstrating interface with other trades to scale. Use the same unit of measure for shop drawings as indicated on the contract drawings. Identify materials and products for work shown.

1.4.2.2.4. Present shop drawings sized 8 1/2 by 11 inches as part of the bound volume for submittals. Present larger drawings in sets. Submit an electronic copy of drawings in PDF format.

1.4.2.2.5. Drawing Identification: Include on each drawing the drawing title, number, date, and revision numbers and dates, in addition to information required in paragraph IDENTIFYING SUBMITTALS.

1.4.2.2.6. Number drawings in a logical sequence. Each drawing is to bear the number of the submittal in a uniform location next to the title block. Place the Government contract number in the margin, immediately below the title block, for each drawing.

1.4.2.2.7. Reserve a blank space, no smaller than 2 inches on the right-hand side of each sheet for the Government disposition stamp.

1.4.2.3. Format of SD-03 Product Data

1.4.2.3.1. Present product data submittals for each section as specified in the technical sections. Include a cover sheet (or table of contents for bound volume submittals), listing the page and catalog item numbers for product data.

1.4.2.3.2. Indicate, by prominent notation, each product that is being submitted; indicate the specification section number and paragraph number to which it pertains.

1.4.2.3.3. Product Information:

1.4.2.3.3.1. Supplement product data with material prepared for the project to satisfy the submittal requirements where product data does not exist. Identify this material as developed specifically for the project, with information and format as required for submission of SD-07 Certificates.

1.4.2.3.3.2. Provide product data in units used in the Contract documents. Where product data are included in preprinted catalogs with another unit, submit the dimensions in contract document units, on a separate sheet.

1.4.2.3.4. Standards: Where equipment or materials are specified to conform to industry or technical-society reference standards of such organizations as the American National Standards Institute (ANSI), ASTM International (ASTM), National Electrical Manufacturer's Association (NEMA), Underwriters Laboratories (UL), or Association of Edison Illuminating Companies (AEIC), submit proof of such compliance. The label or listing by the specified organization will be acceptable evidence of compliance. In lieu of the label or listing, submit a certificate from an independent testing organization, competent to perform testing, and approved by the Contracting Officer. State on the certificate that the item has been tested in accordance with the specified organization's

test methods and that the item complies with the specified organization's reference standard.

1.4.2.3.5. Data Submission: Collect required data submittals for each specific material, product, unit of work, or system into a single submittal that is marked for choices, options, and portions applicable to the submittal. Mark each copy of the product data identically. Partial submittals will not be accepted, unless approved by the Contracting Officer on a case-by-case basis, for expedition of the construction effort.

1.4.2.3.6. Submit the manufacturer's instructions before installation.

1.4.2.4. Format of SD-04 Samples

1.4.2.4.1. Sample Characteristics

1.4.2.4.1.1. Furnish samples in the following sizes, unless otherwise specified or unless the manufacturer has prepackaged samples of approximately the same size as specified:

1.4.2.4.1.1.1. Sample of Equipment or Device: Full size.

1.4.2.4.1.1.2. Sample of Materials Less Than 2 by 3 inches: Built up to 8 1/2 by 11 inches.

1.4.2.4.1.1.3. Sample of Materials Exceeding 8 1/2 by 11 inches: Cut down to 8 1/2 by 11 inches and adequate to indicate color, texture, and material variations.

1.4.2.4.1.1.4. Sample of Linear Devices or Materials (such as conduit or handrails): 10 inch length or length of device to be supplied, if less than 10 inches.

1.4.2.4.1.1.5. Sample Volume of Nonsolid Materials (such as sand or paint): Pint

1.4.2.4.1.1.6. Color Selection Samples: 2 by 4 inches. However, where samples are specified for selection of color, finish, pattern, or texture, submit the full set of available choices for the material or product specified. Sizes and quantities of samples are to represent their respective standard unit.

1.4.2.4.1.1.7. Sample Panel: 4 by 4 feet.

1.4.2.4.1.1.8. Sample Installation: 100 square feet.

1.4.2.4.2. Sample Incorporation

1.4.2.4.2.1. Reusable Samples: Incorporate returned samples into work only if so specified or indicated. Incorporated samples are to be in undamaged condition at the time of use.

1.4.2.4.2.2. Recording of Sample Installation: Note and preserve the notation of any area constituting a sample installation, but remove the notation at the final clean-up of the project.

1.4.2.4.3. Comparison Sample

1.4.2.4.3.1. Samples Showing Range of Variation: Where variations in color, finish, pattern, or texture are unavoidable due to nature of the materials, submit sets of

samples of not less than three units showing extremes and middle of range. Mark each unit to describe its relation to the range of the variation.

1.4.2.4.3.2. When color, texture, or pattern is specified by naming a particular manufacturer and style, include one sample of that manufacturer and style, for comparison.

1.4.2.5. Format of SD-05 Design Data: Provide design data and certificates on 8 1/2 by 11 inch paper. Provide a bound volume for submittals containing numerous pages.

1.4.2.6. Format of SD-06 Test Reports: Provide reports on 8 1/2 by 11 inch paper in a complete bound volume. By prominent notation, indicate each report in the submittal. Indicate the specification number and paragraph number to which each report pertains.

1.4.2.7. Format of SD-07 Certificates: Provide design data and certificates on 8 1/2 by 11 inch paper. Provide a bound volume for submittals containing numerous pages.

1.4.2.8. Format of SD-08 Manufacturer's Instructions

1.4.2.8.1. Present manufacturer's instructions submittals for each section as a complete, bound volume. Include the manufacturer's name, trade name, place of manufacture, and catalog model or number on product data. Also include applicable federal, military, industry, and technical-society publication references. If supplemental information is needed to clarify the manufacturer's data, submit it as specified for SD-07 Certificates.

1.4.2.8.2. Submit the manufacturer's instructions before installation.

1.4.2.8.3. Standards: Where equipment or materials are specified to conform to industry or technical-society reference standards of such organizations as the American National Standards Institute (ANSI), ASTM International (ASTM), National Electrical Manufacturer's Association (NEMA), Underwriters Laboratories (UL), or Association of Edison Illuminating Companies (AEIC), submit proof of such compliance. The label or listing by the specified organization will be acceptable evidence of compliance. In lieu of the label or listing, submit a certificate from an independent testing organization, competent to perform testing, and approved by the Contracting Officer. State on the certificate that the item has been tested in accordance with the specified organization's test methods and that the item complies with the specified organization's reference standard.

1.4.2.9. Format of SD-09 Manufacturer's Field Reports: Provide reports on 8 1/2 by 11 inch paper in a complete bound volume. By prominent notation, indicate each report in the submittal. Indicate the specification number and paragraph number to which each report pertains.

1.4.2.10. Format of SD-10 Operation and Maintenance Data (O&M): Provide all manufacturers’ recommended operations and maintenance data. Ensure a complete package is delivered in bound volumes.

1.4.2.11. 11. Format of SD-11 Closeout Submittals

1.4.2.11.1. When the submittal includes a document that is to be used in the project or is to become part of the project record, other than as a submittal, do not apply the Contractor's approval stamp to the document itself, but to a separate sheet accompanying the document.

1.4.2.11.2. Provide data in the unit of measure used in the contract documents.

1.4.3. Source Drawings for Shop Drawings: The entire set of source drawing files (DWG) will not be provided to the Contractor. Request the specific Drawing Number for the preparation of shop drawings. Only those drawings requested to prepare shop drawings will be provided. These drawings are provided only after award.

1.4.3.1. Terms and Conditions

1.4.3.1.1. Data contained on these electronic files must not be used for any purpose other than as a convenience in the preparation of construction data for the referenced project. Any other use or reuse is at the sole risk of the Contractor and without liability or legal exposure to the Government. The Contractor must make no claim, and waives to the fullest extent permitted by law any claim or cause of action of any nature against the Government, its agents, or its subconsultants that may arise out of or in connection with the use of these electronic files. The Contractor must, to the fullest extent permitted by law, indemnify and hold the Government harmless against all damages, liabilities, or costs, including reasonable attorney's fees and defense costs, arising out of or resulting from the use of these electronic files.

1.4.3.1.2. These electronic source drawing files are not construction documents. Differences may exist between the source drawing files and the corresponding construction documents. The Government makes no representation regarding the accuracy or completeness of the electronic source drawing files, nor does it make representation to the compatibility of these files with the Contractor hardware or software. The Contractor is responsible for determining if any conflict exists. In the event that a conflict arises between the signed and sealed construction documents prepared by the Government and the furnished source drawing files, the signed and sealed construction documents govern. Use of these source drawing files does not relieve the Contractor of the duty to fully comply with the contract documents, including and without limitation the need to check, confirm and coordinate the work of all contractors for the project.If the Contractor uses, duplicates or modifies these electronic source drawing files for use in producing construction data related to this contract, remove all previous indication of ownership (seals, logos, signatures, initials and dates).

1.4.4. Electronic File Format

1.4.4.1. Provide submittals in electronic format, with the exception of material samples required for SD-04 Samples items. [In addition to the electronic submittal, provide three hard copies of the submittals.]

1.4.4.2. Compile the submittal file as a single, complete document, to include the Transmittal Form described within.

1.4.4.3. Name the electronic submittal file specifically according to its contents, and coordinate the file naming convention with the Contracting Officer.

1.4.4.4. Electronic files must be of sufficient quality that all information is legible.

1.4.4.5. Use PDF as the electronic format, unless otherwise specified or directed by the Contracting Officer.

1.4.4.6. Generate PDF files from original documents with bookmarks so that the text included in the PDF file is searchable and can be copied. If documents are scanned, optical character resolution (OCR) routines are required.

1.4.4.7. Index and bookmark files exceeding 30 pages to allow efficient navigation of the file.

1.4.4.8. When required, the electronic file must include a valid electronic signature or a scan of a signature.

1.5. QUANTITY OF SUBMITTALS

1.5.1. Number of SD-01 Preconstruction Submittal Copies: Unless otherwise specified, submit three sets of administrative submittals.

1.5.2. Number of SD-02 Shop Drawing Copies: Submit four copies of submittals of shop drawings requiring review and approval by a QC organization. Submit four copies of shop drawings requiring review and approval by the Contracting Officer.

1.5.3. Number of SD-03 Product Data Copies: Submit in compliance with quantity requirements specified for shop drawings.

1.5.4. Number of SD-04 Samples

1.5.4.1. Submit three samples, or three sets of samples showing the range of variation, of each required item. Two approved sample or set of samples will be retained by the approving authority and one will be returned to the Contractor.

1.5.4.2. Submit one sample panel or provide one sample installation where directed. Include components listed in the technical section or as directed.

1.5.4.3. Submit one sample installation, where directed.

1.5.4.4. Submit one sample of nonsolid materials.

1.5.5. Number of SD-05 Design Data Copies: Submit in compliance with quantity requirements specified for shop drawings.

1.5.6. Number of SD-06 Test Report Copies: Submit in compliance with quantity and quality requirements specified for shop drawings, other than field test results that will be submitted with QC reports.

1.5.7. Number of SD-07 Certificate Copies: Submit in compliance with quantity requirements specified for shop drawings.

1.5.8. Number of SD-08 Manufacturer's Instructions Copies: Submit in compliance with quantity requirements specified for shop drawings.

1.5.9. Number of SD-09 Manufacturer's Field Report Copies: Submit in compliance with quantity and quality requirements specified for shop drawings other than field test results that will be submitted with QC reports.

1.5.10. Number of SD-10 Operation and Maintenance Data Copies: Submit four copies of O&M data to the Contracting Officer for review and approval.

1.5.11. Number of SD-11 Closeout Submittals Copies: Unless otherwise specified, submit four sets of administrative submittals.

1.6. INFORMATION ONLY SUBMITTALS

1.6.1. Submittals without a "G" designation must be certified by the QC manager and submitted to the Contracting Officer for information-only. Provide information-only submittals to the

Contracting Officer a minimum of 14 calendar days prior to the Preparatory Meeting for the associated Definable Feature of Work (DFOW).

1.6.2. Approval of the Contracting Officer is not required on information only submittals.

1.6.3. The Contracting Officer will mark "receipt acknowledged" on submittals for information and will return only the transmittal cover sheet to the Contractor.

1.6.4. Normally, submittals for information only will not be returned. However, the Government reserves the right to return unsatisfactory submittals and require the Contractor to resubmit any item found not to comply with the contract.

1.6.5. This does not relieve the Contractor from the obligation to furnish material conforming to the plans and specifications; will not prevent the Contracting Officer from requiring removal and replacement of nonconforming material incorporated in the work; and does not relieve the Contractor of the requirement to furnish samples for testing by the Government laboratory or for check testing by the Government in those instances where the technical specifications so prescribe.

1.7. PROJECT SUBMITTAL REGISTER

1.7.1. A Project Submittal Register showing items of equipment and materials for when submittals are required by the specifications can be provided upon request.

1.7.2. Submittal Management: Prepare and maintain a submittal register, as the work progresses. Do not change data that is delivered by Government; retain data that is output as approved.

1.7.3. Delivery of Copies: Submit an updated electronic copy of the submittal register to the Contracting Officer with each invoice request. Provide an updated Submittal Register monthly regardless of whether an invoice is submitted.

1.8. VARIATIONS

1.8.1. Variations from contract requirements require Contracting Officer approval pursuant to contract Clause FAR 52.236-21 Specifications and Drawings for Construction, and will be considered where advantageous to the Government.

1.8.2. Considering Variations

1.8.2.1. Discussion of variations with the Contracting Officer before submission of a variation submittal will help ensure that functional and quality requirements are met and minimize rejections and resubmittals.

1.8.2.2. For variations that include design changes or some material or product substitutions, the Government may require an evaluation and analysis by a licensed professional engineer hired by the contractor.

1.8.2.3. Specifically point out variations from contract requirements in a variation submittal. Failure to point out variations may cause the Government to require rejection and removal of such work at no additional cost to the Government.

1.8.3. Proposing Variations

1.8.3.1. When proposing variation, deliver a submittal, clearly marked as a "VARIATION" to the Contracting Officer, with documentation illustrating the nature and features of the variation including any necessary technical submittals and why the variation is desirable and

beneficial to Government. If lower cost is a benefit, also include an estimate of the cost savings. In addition to documentation required for variation, include the submittals required for the item. Clearly mark the proposed variation in all documentation.

1.8.3.2. The Contracting Officer will indicate an approval or disapproval of the variation request; and if not approved as submitted, will indicate the Government's reasons therefore. Any work done before such approval is received is performed at the Contractor's risk."

1.8.3.3. Specifically point out variations from contract requirements in a variation submittal. Failure to point out variations may cause the Government to require rejection and removal of such work at no additional cost to the Government.

1.8.4. Warranting that Variations are Compatible: When delivering a variation for approval, the Contractor warrants that this contract has been reviewed to establish that the variation, if incorporated, will be compatible with other elements of work.

1.8.5. Review Schedule Extension: In addition to the normal submittal review period, a period of 14 days will be allowed for the Government to consider submittals with variations.

1.9. SCHEDULING

1.9.1. Schedule and submit concurrently product data and shop drawings covering component items forming a system or items that are interrelated. Submit pertinent certifications at the same time.

1.9.2. No delay damages or time extensions will be allowed for time lost in late submittals. Allow an additional ten days for review and approval of submittals for food service equipment and refrigeration and HVAC control systems.

1.9.3. Coordinate scheduling, sequencing, preparing, and processing of submittals with performance of work so that work will not be delayed by submittal processing. The Contractor is responsible for additional time required for Government reviews resulting from required resubmittals. The review period for each resubmittal is the same as for the initial submittal.

1.9.4. Submittals required by the contract documents are listed on the submittal register.

1.9.4.1. If a submittal is listed in the submittal register but does not pertain to the contract work, the Contractor is to include the submittal in the register and annotate it "N/A" with a brief explanation.

1.9.4.2. Approval by the Contracting Officer does not relieve the Contractor of supplying submittals required by the contract documents but that have been omitted from the register or marked "N/A."

1.9.5. Resubmit the submittal register and annotate it monthly with actual submission and approval dates. When all items on the register have been fully approved, no further resubmittal is required.

1.9.6. Contracting Officer review will be completed within 14 days after the date of submission.

1.10. GOVERNMENT APPROVING AUTHORITY

1.10.1. When the approving authority is the Contracting Officer, the Government will:

1.10.1.1. Note the date on which the submittal was received.

1.10.1.2. Review submittals for approval within the scheduling period specified and only for conformance with project design concepts and compliance with contract documents.

1.10.1.3. Identify returned submittals with one of the actions defined in paragraph REVIEW NOTATIONS and with comments and markings appropriate for the action indicated.

1.10.1.4. Upon completion of review of submittals requiring Government approval, stamp and date submittals.

1.10.2. Two copies of the submittal will be retained by the Contracting Officer and two copies of the submittal will be returned to the Contractor.

1.10.3. Review Notations: Submittals will be returned to the Contractor with the following notations:

1.10.3.1. Submittals marked "approved" or "accepted" authorize proceeding with the work covered.

1.10.3.2. Submittals marked "approved as noted" or "approved, except as noted, resubmittal not required," authorize proceeding with the work covered provided that the Contractor takes no exception to the corrections.

1.10.3.3. Submittals marked "not approved," "disapproved," or "revise and resubmit" indicate incomplete submittal or noncompliance with the contract requirements or design concept.

1.10.3.3.1. Resubmit with appropriate changes. Do not proceed with work for this item until the resubmittal is approved.

1.10.3.4. Submittals marked "not reviewed" indicate that the submittal has been previously reviewed and approved, is not required, does not have evidence of being reviewed and approved by Contractor, or is not complete.

1.10.3.4.1. A submittal marked "not reviewed" will be returned with an explanation of the reason it is not reviewed.

1.10.3.4.1.1. Resubmit submittals returned for lack of review by Contractor or for being incomplete, with appropriate action, coordination, or change.

1.10.3.5. Submittals marked "receipt acknowledged" indicate that submittals have been received by the Government. This applies only to "information-only submittals" as previously defined.

1.11. DISAPPROVED SUBMITTALS

1.11.1. Make corrections required by the Contracting Officer. If the Contractor considers any correction or notation on the returned submittals to constitute a change to the contract drawings or specifications, give notice to the Contracting Officer as required under the FAR clause titled CHANGES.

1.11.2. The Contractor is responsible for the dimensions and design of connection details and the construction of work. Failure to point out variations may cause the Government to require rejection and removal of such work at the Contractor's expense.

1.11.3. If changes are necessary to submittals, make such revisions and resubmit in accordance with the procedures above. No item of work requiring a submittal change is to be accomplished until the changed submittals are approved.

1.12. APPROVED SUBMITTALS

1.12.1. The Contracting Officer's approval of submittals is not to be construed as a complete check, and indicates only that Approval or acceptance by the Government for a submittal does not relieve the Contractor of the responsibility for meeting the contract requirements or for any error that may exist, because under the Quality Control (QC) requirements of this contract, the Contractor is responsible for ensuring information contained with in each submittal accurately conforms with the requirements of the contract documents.

1.12.2. After submittals have been approved or accepted by the Contracting Officer, no resubmittal for the purpose of substituting materials or equipment will be considered unless accompanied by an explanation of why a substitution is necessary.

1.13. APPROVED SAMPLES

1.13.1. Approval of a sample is only for the characteristics or use named in such approval and is not be construed to change or modify any contract requirements. Before submitting samples, provide assurance that the materials or equipment will be available in quantities required in the project. No change or substitution will be permitted after a sample has been approved.

1.13.2. Match the approved samples for materials and equipment incorporated in the work. If requested, approved samples, including those that may be damaged in testing, will be returned to the Contractor, at its expense, upon completion of the contract. Unapproved samples will also be returned to the Contractor at its expense, if so requested.

1.13.3. Failure of any materials to pass the specified tests will be sufficient cause for refusal to consider, under this contract, any further samples of the same brand or make as that material. The Government reserves the right to disapprove any material or equipment that has previously proved unsatisfactory in service.

1.13.4. Samples of various materials or equipment delivered on the site or in place may be taken by the Contracting Officer for testing. Samples failing to meet contract requirements will automatically void previous approvals. Replace such materials or equipment to meet contract requirements.

PART 2. PRODUCTS (NOT USED)

PART 3. EXECUTION (NOT USED)

END OF SECTION 01 33 00

SECTION 01 40 00
QUALITY REQUIREMENTS

PART 1. GENERAL

1.1. ABBREVIATIONS AND ACRONYMS: Lists and explains abbreviations and symbols used in the Contract Documents.

1.1.1. Reference to a technical society, institution, association, or governmental authority is made in the Specifications.

1.1.1.1.	ACI	American Concrete Institute
1.1.1.2.	ANSI	American National Standards Institute
1.1.1.3.	ASTM	American Society for Testing and Materials
1.1.1.4.	AWWA	American Water Works Association
1.1.1.5.	CSI	Construction Specification Institute
1.1.1.6.	FS	Federal Specification
1.1.1.7.	MS	Military Specification
1.1.1.8.	MSTD	Military Standard
1.1.1.9.	NEC	National Electric Code
1.1.1.10.	NFC	National Fire Code
1.1.1.11.	UL	Underwriters' Laboratories

1.2. REFERENCE STANDARDS

1.2.1. Except as modified by governing codes and by this Specification, comply with the applicable provisions and recommendations of ANSI A10.2, Safety Code for Building Construction.

1.2.2. For any requirements throughout the Specifications and Drawings that item(s) bear the label of the Underwriters Laboratories Inc. or similar organizations, the Contractor shall submit proof that such item(s) he proposes to furnish conforms to the standard of the testing organization. The label of the proposed organization shall be accepted as conforming to this requirement.

1.3. SUBMITTALS: NONE

1.4. QUALITY ASSURANCE

1.4.1. Testing and Inspecting Agency Qualifications

1.4.1.1. Testing and Inspection Requirements

1.4.1.1.1. Where technical sections of the Specifications require inspection and testing by a testing laboratory, engage a reputable, recognized testing laboratory, experienced in the type of work to be performed.

1.4.1.1.2. The representative of the testing laboratory shall be on the work site as necessary for sampling, inspection, and testing in accordance with the contract provisions.

1.4.1.1.3. Submit written reports of results within (14) days after completion of tests.

1.4.2. Testing and Inspection Devices

1.4.2.1. Either the Contractor or his testing laboratory shall provide and maintain all measuring and testing devices, laboratory equipment, instruments, and supplies necessary to accomplish the required testing and inspection.

1.4.2.2. All measuring and testing devices shall be calibrated periodically against certified standards.

1.5. QUALITY CONTROL

1.5.1. Field Quality Control Procedures

1.5.1.1. The Contractor’s QC staff shall function completely independently of the Contractor's job-supervisory staff.

1.5.2. Contractor Quality Control

1.5.2.1. Provide and maintain an effective Contractor Quality Control (CQC) program and perform sufficient inspections and tests of all items of work, including those of subcontractors, to ensure compliance with Contract Documents.

1.5.2.2. Include surveillance and tests specified in the technical sections of the Specifications.

1.5.2.3. Furnish appropriate facilities, instruments, and testing devices required for performance of the quality control function.

1.5.2.4. Controls must be adequate to cover construction operations and be keyed to the construction sequence.

1.5.3. The Contractor's Quality Control system shall provide for procedures to ensure that the latest Contract Documents, shop drawings, and instructions required by the Contract are used for fabrication, testing, and inspection.

1.6. TESTING AND INSPECTING SERVICES

1.6.1. All tests shall be documented and certified.

1.6.2. All compliance inspections shall record both conforming and defective items with an explanation for the cause of rejection, proposed remedial action, and corrective action taken.

1.6.3. Individual daily reports will be required of each inspector and technician covering the feature which is assigned and a consolidated daily report signed by the person in charge of the quality control staff.

1.7. TESTING LABORATORY SERVICES: The Contractor may arrange for a testing laboratory to provide on-site services required in lieu of direct employment of personnel.

PART 2. PRODUCTS (NOT USED)

PART 3. EXECUTION: (NOT USED)

END OF SECTION 01 40 00

SECTION 01 60 00
PRODUCT REQUIREMENTS

PART 1. GENERAL

1.1. SUBMITTALS FOR THIS SECTION: NONE

1.2. COMMON PRODUCT REQUIREMENTS

1.2.1. Owner-Furnished Products: The following items are furnished by the Government and installed by the Contractor:

1.2.1.1. None

1.2.2. The following items are furnished and installed by Government:

1.2.2.1. None.

1.3. PRODUCT OPTIONS

1.3.1. Product Approval Standards

1.3.1.1. Definitions:

1.3.1.1.1. The term "product" shall include material, equipment, assembly methods, manufacturer, brand, trade name, or other description.

1.3.1.2. Proof of Compliance:

1.3.1.2.1. Whenever the Contract Documents require a product be in accordance with federal specification, ASTM designation, ANSI specification, or other association standard, the Contractor shall present an affidavit from the manufacturer certifying the product complies therewith. Where requested or specified, submit supporting test data to substantiate compliance.

1.3.1.3. Inclusion in Specifications of Non-specified Products Prior to Bid Date:

1.3.1.3.1. For inclusion of products other than those specified, Bidders shall submit a request in writing at least (7) days prior to bid date. Requests received after this time will not be reviewed or considered regardless of cause. Requests shall clearly define and describe the product for which inclusion is requested. Inclusion by the Contracting Officer's Representative will be in the form of an addendum to the Specifications issued to all contract bidders on record.

1.4. PRODUCT DELIVERY REQUIREMENTS

1.4.1. Product Delivery Requirements

1.4.1.1. Materials, products, and equipment shall be properly containerized, packaged, boxed, and protected to prevent damage during transportation and delivery.

1.4.1.2. More detailed requirements for transportation and delivery are specified under the technical sections.

1.5. PRODUCT STORAGE AND HANDLING REQUIREMENTS

1.5.1. Provide suitable temporary weather tight storage facilities as may be required for materials that will be damaged by storage in the open.

1.5.2. Available storage space at the job site is limited to the site shown on the Drawings. Allocate such space for storage purposes. Any additional off-site space required is the responsibility of the Contractor.

1.5.3. Allocate the available storage areas and coordinate their use by the trades on the job. Maintain a current layout of all storage facilities.

1.5.4. Store and protect materials delivered at the site from damage. Do not use damaged material on the work.

1.5.5. Do not store or place materials in passageways, stairs, or other means of egress.

1.5.6. Where existing equipment and/or fixtures are indicated to be reused, repair such equipment and/or fixtures and refinish to put in perfect working order. Refinish as directed.

PART 2. PRODUCTS (NOT USED)

PART 3. EXECUTION (NOT USED)

END OF SECTION 01 60 00

SECTION 01 70 00
EXECUTION AND CLOSEOUT REQUIREMENTS

PART 1. GENERAL

1.1. SUBMITTALS REQUIRED FOR THIS SECTION

1.1.1. Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or “S” classification are for information only. Submit the following in accordance with Section 01 33 00 SUPPLEMENTAL SUBMITTAL PROCEDURES

1.1.1.1. SD-11 Closeout Submittals

1.1.1.1.1. Operations and Maintenance Data

1.1.1.1.2. Warranties

1.1.1.1.3. Project Record Documents

1.1.1.1.4. Real Property Cost Information

1.2. EXAMINATION AND PREPARATION

1.2.1. Acceptance of Conditions

1.2.1.1. The contractor shall not exceed the scope of work without prior approval from the Contracting Officer.

1.2.1.2. The Contracting Officer or his Representative will in no case assume the responsibility for any layout of the work or damages to existing underground utilities while performance of work is underway.

1.2.2. Protection of Adjacent Construction

1.2.2.1. The contractor shall protect all government property from damage. Any damages incurred in pursuance of this project shall be replaced and/or restored to original condition.

1.3. FIELD ENGINEERING

1.3.1. Construction Layout

1.3.1.1. The Contractor is responsible for properly laying out the work, and for lines and measurements for the work executed under the Contract Documents.

1.3.2. Construction Survey

1.3.2.1. The Contractor, NOT the Government, is responsible to field verify all existing underground utilities within the excavation limits and/or as shown on the Drawings and the conditions of the work site, before laying out the work. The Contractor is to report errors or inaccuracies in writing to the Contracting Officer's Representative before commencing work.

1.4. CLEANING AND WASTE MANAGEMENT

1.4.1. Progress Cleaning

1.4.1.1. The premises and job site shall be maintained in a reasonably neat and orderly condition, kept free from accumulations of waste materials and rubbish during entire construction period. Remove crates, cartons, other flammable waste materials, and trash from these areas as the work progresses, upon completion of each trades work, or at the end of each working day.

1.4.1.2. All trash, waste, and construction debris generated from this project shall become property of the contractor and shall be removed from the base. The disposal of these materials shall follow the appropriate Federal and State laws. This includes the disposal or recycling of hazardous materials

1.5. SITE MAINTENANCE

1.5.1. Care shall be taken by workmen not to mark, soil, or otherwise deface adjacent existing surfaces and/or new finished surfaces. In the event that existing surfaces and/or new finished surfaces become defaced, clean the surfaces from dirt, grease, loose paint, and so on, and restore surfaces to their original or finished condition.

1.6. FINAL CLEANING

1.6.1. Upon completion of the work, remove temporary buildings and structures, fences, scaffolding, surplus materials, and rubbish of every kind from the site of the work.

1.7. STARTING AND ADJUSTING

1.7.1. Checkout Procedures

1.7.1.1. Specific requirements and procedures for starting systems; testing, adjusting, and balancing; and demonstration of systems should be included in the division where the system is specified.

1.8. CLOSEOUT PROCEDURES

1.8.1. Final Closeout Review

1.8.1.1. Although any item found to be faulty may be rejected before it is used, final acceptance of an item by the Government is based on its satisfactory incorporation into the work and acceptance of the completed project.

1.9. CLOSEOUT SUBMITTALS

1.9.1. **[SD-11]** Operation and Maintenance Data: Prior to final payment in accordance with provisions of the General Conditions and before issuance of final certificate for payment, file the following papers with the Contracting Officer's Representative.

1.9.1.1. Operation and Maintenance Manuals:

1.9.1.1.1. Furnish (2) complete sets of manuals containing manufacturer's instructions for maintenance and operation of each item of equipment and apparatus furnished under the Contract and any additional data specifically required under various sections of the Specifications.

1.9.1.1.2. Arrange manuals in proper order, indexed and suitably bound.

1.9.1.1.3. Certify by endorsement thereon, each manual, as complete and accurate.

1.9.1.1.4. Assemble these manuals for all divisions of work, review for completeness, and submit them to the Contracting Officer's Representative.

1.9.1.1.5. Provide suitable transfer cases and deliver manuals therein, indexed and marked, for each division of work.

1.9.2. **[SD-11]** Warranties: Prior to final payment in accordance with provisions of the General Conditions and before issuance of final certificate for payment, file the following papers with the Contracting Officer's Representative.

1.9.2.1. Warranties: Required warranty and any other extended warranties stated in the technical sections of the Specifications.

1.9.2.2. Release or Waiver of Liens: As required.

1.9.3. **[SD-11]** Project Record Documents: Prior to final payment in accordance with provisions of the General Conditions and before issuance of final certificate for payment, file the following papers with the Contracting Officer’s Representative.

1.9.3.1. Project Record Documents:

1.9.3.1.1. As the work progresses keep a complete and accurate record of changes or deviations from the Contract Documents and shop drawings, indicating work as actually installed.

1.9.3.1.2. Changes shall be neatly and correctly shown on the respective portion of the affected document, using prints of the Drawings affected, or the Specifications, with appropriate supplementary notes.

1.9.3.1.2.1. This record set Drawings, shop drawings, and Specifications shall be kept at the job site for inspection by the Contracting Officer’s Representative.

1.9.3.1.2.2. These records shall be arranged in order, in accordance with the various sections of the Specifications, and properly indexed.

1.9.3.1.2.3. At the completion of work, certify by endorsement thereof, each revised print of the Drawings and Specifications as complete and accurate.

1.9.3.1.2.4. Prior to application for final payment, and as a condition to its approval by the Contracting Officer’s Representative, deliver record Drawings and Specifications, arranged in proper order, indexed, and endorsed as hereinbefore specified.

1.9.3.1.2.5. Provide suitable transfer cases and deliver the records therein, indexed and marked for each division of the work.

1.9.3.1.2.6. No review or receipt of such records by the Contracting Officer’s Representative shall be a waiver of any deviation from the Contract Documents or shop drawings or in any way relieve the Contractor from his responsibility to perform work in accordance with the Contract Documents and shop drawings to the extent they are in accordance with the Contract Documents.

1.9.4. **[SD-11]** Real Property Cost Information:

1.9.4.1. Submit information on costs of various components of the project to be used to complete ANG Real Property documents.

1.9.4.2. The format for the information will be provided by the Contracting Officer.

1.10. EXTRA STOCK MATERIALS

1.10.1. Any residual materials furnished by the Government or by the Contractor shall be returned into the Base Civil Engineer upon contract completion, except hazardous materials and hazardous waste. These items must be disposed of by the Contractor.

PART 2. PRODUCTS (NOT USED)

PART 3. EXECUTION (NOT USED)

END OF SECTION 01 70 00

SECTION 01 74 19
CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL

PART 1. GENERAL

1.1. RELATED DOCUMENTS

1.1.1. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.1.2. Section 01 57 19 of this Specification (if added): In case of conflicts between the requirements of Section 01 57 19 and this Section, the more restrictive requirements shall govern.

1.2. REFERENCES: The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

1.2.1. U.S. Environmental Protection Agency (EPA)

1.2.1.1. EPA SW-846 (Third Edition; Update IV) Test Methods for Evaluating Solid Waste: Physical/Chemical Methods

1.2.2. U.S. National Archives and Records Administration (NARA)

1.2.2.1. 40 CFR 241 Guidelines for Disposal of Solid Waste

1.2.2.2. 40 CFR 243 Guidelines for the Storage and Collection of Residential, Commercial, and Institutional Solid Waste

1.2.2.3. 40 CFR 258 Subtitle D Landfill Requirements

1.2.2.4. 40 CFR 273 Standards for Universal Waste Management

1.2.2.5. 40 CFR 273.2 Standards for Universal Waste Management – Batteries

1.2.2.6. 40 CFR 273.3 Standards for Universal Waste Management – Pesticides

1.2.2.7. 40 CFR 273.4 Standards for Universal Waste Management - Mercury Containing Equipment

1.2.2.8. 49 CFR 173 Shippers - General Requirements for Shipments and Packagings

1.2.2.9. 49 CFR 178 Specifications for Packagings

1.2.3. United States Air Force (USAF)

1.2.3.1. AFMAN 32-7002 Environmental Compliance and Pollution Prevention

1.3. DEFINITIONS:

1.3.1. Co-mingle -The practice of placing unrelated materials together in a single container, usually for benefits of convenience and speed.

1.3.2. Construction Waste - Waste generated by construction activities, such as scrap materials, damaged or spoiled materials, temporary and expendable construction materials, and other waste generated by the workforce during construction activities.

1.3.3. Demolition Debris/Waste - Waste generated from demolition activities, including minor incidental demolition waste materials generated as a result of Intentional dismantling of all or portions of a building, to include clearing of building contents that have been destroyed or damaged.

1.3.4. Diversion - The practice of diverting waste from disposal in a landfill, by means of eliminating or minimizing waste, or recycling/reuse of materials.

1.3.5. Final Construction Waste Diversion Report - A written assertion by a material recovery facility operator identifying constituent materials diverted from disposal, usually including summary tabulations of materials, weight in short-ton.

1.3.6. Landfill - Depositing waste in a solid waste disposal facility, usually a managed landfill, regulated in the US under the Resource Conservation and Recovery Act (RCRA).

1.3.7. Recycling - The series of activities, including collection, separation, and processing, by which products or other materials are diverted from the solid waste stream for use in the form of raw materials in the manufacture of new products sold or distributed in commerce, or the reuse of such materials as substitutes for goods made of virgin materials, other than fuel.

1.3.8. Reuse - The use of a product or materials again for the same purpose, in its original form or with little enhancement or change.

1.3.9. Salvage - Usable, salable items derived from buildings undergoing demolition or deconstruction, parts from vehicles, machinery, other equipment, or other components.

1.3.10. Source Separation - The practice of administering and implementing a management strategy to identify and segregate unrelated waste at the first opportunity.

1.4. SUBMITTALS FOR THIS SECTION: Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or “S” classification are for information only. Submit the following in accordance with Section 01 33 00 SUPPLEMENTAL SUBMITTAL PROCEDURES:

1.4.1. SD-01 Pre-Construction Submittals

1.4.1.1. Construction Waste Management Plan (In accordance with the Environmental Protection Plan)

1.4.2. SD-11 Closeout Submittals

1.4.2.1. Quarterly Construction and Demolition Debris Reporting Form

1.5. CONSTRUCTION WASTE MANAGEMENT:

1.5.1. Implement a construction waste management program for the project. Take a pro-active, responsible role in the management of construction waste, recycling process, disposal of demolition debris/waste, and require all subcontractors, vendors, and suppliers to participate in the construction waste management program. Establish a process for clear tracking, and documentation of construction waste and demolition debris/waste.

1.5.2. Construction waste and demolition debris/waste materials include un-used construction materials not incorporated in the final work, as well as demolition debris/waste materials from demolition activities or deconstruction activities. In the management of waste, consider the availability of viable markets, the condition of materials, the ability to provide material in suitable condition and in a quantity acceptable to available markets, and time constraints imposed by internal project completion mandates.

1.5.3. **[SD-01]** Develop and document how the construction waste management program will be implemented in a Construction Waste Management Plan. The Construction Waste Management Plan will be approved by the Contracting Officer. include the following in the plan:

1.5.3.1. Identify solid waste diversion goals for the project. At least 60% by weight of the project construction waste and demolition debris/waste shall be diverted from landfills.

1.5.3.2. Identify the names of individuals responsible for waste management and waste management tracking, along with roles and responsibilities on the project.

1.5.3.3. Delineate waste streams and characterization, including estimated material types and quantities of waste, in the plan. Manage all waste streams associated with the project. Typical waste streams are listed below. Include additional waste steams not listed:

1.5.3.3.1. Land Clearing Debris

1.5.3.3.2. Asphalt

1.5.3.3.3. Masonry and CMU Concrete

1.5.3.3.4. Metals (e.g., banding, stud trim, ductwork, piping, rebar, roofing, other trim, steel, iron, galvanized, stainless steel, aluminum, copper, zinc, bronze, etc.)

1.5.3.3.5. Wood (nails and staples allowed)

1.5.3.3.6. Glass

1.5.3.3.7. Paper

1.5.3.3.8. Plastics (PET, HDPE, PVC, LDPE, PP, PS, Other)

1.5.3.3.9. Gypsum

1.5.3.3.10. Non-hazardous paint and paint cans

1.5.3.3.11. Carpet

1.5.3.3.12. Ceiling Tiles

1.5.3.3.13. Insulation

1.5.3.3.14. Beverage Containers

1.5.3.4. List actions that will be taken to reduce solid waste generation, including coordination with subcontractors to ensure awareness and participation.

1.5.3.5. List each supplier who will deliver construction materials, in bulk, or package products in returnable containers or returnable packaging, or have take-back programs. List each program and the applicable material to actively monitor and track to assist in meeting waste diversion requirements on the project.

1.5.3.6. List of specific materials, by type and quantity that will be salvaged for resale, salvaged and reused on the current project, salvaged and stored for reuse on a future project, or recycled.

1.5.3.7. Identify the recycling facilities by name, address, and phone number and a description of the means of transportation of the recyclable materials. Ensure firms and

facilities used for recycling, reuse, and disposal are permitted for the intended use to the extent required by federal, state, and local regulations. Facilities or subcontractors offering construction waste transport on-site or off-site must ensure that proper shipping orders, bill of lading, manifests, or other shipping documents containing waste diversion information meet requirements of 40 CFR 273 Universal Waste Management, 49 CFR 173 Shippers - General Requirements for Shipments and Packaging's, and 49 CFR 178 Specifications for Packaging. Individuals signing manifests or other shipping documents should meet the minimum training requirements.

1.5.3.8. Identify local and regional re-use programs, including non-profit organizations such as schools, local housing agencies, and organizations that accept used materials such as material exchange networks and resale stores. Include the name, location, phone number for each re-use facility identified, and provide a copy of the permit or license for each facility.

1.5.3.9. Describe the specific approaches to be used in recycling/reuse of the various materials generated, including the areas on site and equipment to be used for processing, sorting, and temporary storage of materials. Provide information on how any solid waste materials, whether for disposal or recycling will be protected from contamination and whether materials will be site-separated and self- hauled to designated centers, or whether mixed materials will be collected by a waste hauler and removed from the site

1.5.3.10. Identify materials that cannot be recycled or reused with an explanation or justification, to be approved by the Contracting Officer.

1.5.3.11. Provide the name of the landfill to be used and identify any local jurisdiction requirements for waste management. Include those requirements, points of contact, etc.

1.5.3.12. Provide a copy of the training plan for subcontractors and other services to prevent contamination by co-mingling materials identified for diversion and waste materials.

1.5.3.13. Provide a description of the regular meetings to be held to address waste management.

1.5.3.14. An approved construction waste management plan will not relieve the Contractor of responsibility for compliance with applicable environmental regulations or meeting project cumulative waste diversion requirement.

1.5.4. Ensure all subcontractors, and the Quality Control Manager, Environmental POC, and the Contracting Officer receive a copy of the approved Construction Waste Management Plan. The plan demonstrates how to meet the project waste diversion requirement.

1.6. MEETINGS:

1.6.1. Conduct Construction Waste Management meetings. After award of the Contract and prior to commencement of work, schedule and conduct a meeting with the Contracting Officer or Contracting Officer Representative to discuss the proposed Construction Waste Management Plan (in conjunction with the Environmental Protection Plan – if required) and to develop a mutual understanding relative to the management of the construction waste management program and how waste diversion requirements will be met. At a minimum, discuss and document waste management goals at the Preconstruction Meeting, Regular Quality Control meetings. And the Work Safety Meeting (if applicable).

1.7. OVERSIGHT:

1.7.1. The Project Manager, is responsible for overseeing and documenting results from executing the Construction Waste Management Plan for the project.

1.8. RECORDS (DOCUMENTATION):

1.8.1. Maintain records to document the types and quantities of waste generated and diverted though re-use, recycling and/or sale to third parties; or through disposal to a landfill or incinerator facility.

1.8.2. **[SD-11]** Report quarterly utilizing the Construction Demolition and Debris Reporting Form provided by the Government.

1.8.3. Provide explanations for any materials not recycled, reused or sold.

1.8.4. Collect and retain manifests, weight tickets, sales receipts, and invoices specifically identifying diverted project waste materials or disposed materials.

PART 2. PRODUCTS (NOT USED)

PART 3. PART 3 - EXECUTION

3.1. Execute demolition or deconstruction activities in accordance with Section 02 41 00 DEMOLITION. Manage demolition debris/waste or deconstruction materials in accordance with the approved construction waste management plan.

3.2. CONSTRUCTION WASTE (INCLUDES DEMOLITION DEBRIS/WASTE)

3.2.1. Divert a minimum of 60 percent by weight of the project construction waste and demolition debris/waste from landfills. Follow applicable industry standards in the management of waste. Apply sound environmental principles in the management of waste. (1) Practice efficient waste management when sizing, cutting, and installing products and materials and (2) use all reasonable means to divert construction waste and demolition debris/waste from landfills and incinerators and to facilitate the recycling or reuse of excess construction materials.

3.2.2. Provide on-site instruction of appropriate separation, handling, recycling, salvage, reuse, and return methods to be used by all parties at the appropriate stages of the projects. Train subcontractors and other service providers to either separate waste streams or use the co-mingling method as described in the Construction Waste Management Plan.

3.3. COLLECTION:

3.3.1. Collect, store, protect, and handle reusable and recyclable materials at the site in a manner which prevents contamination, and provides protection from the elements to preserve their usefulness and monetary value.

3.3.2. Provide receptacles and storage areas designated specifically for recyclable and reusable materials and label them clearly and appropriately to prevent contamination from other waste materials. Keep receptacles or storage areas neat and clean.

3.3.3. Separate materials by one of the following methods described herein:

3.3.3.1. SOURCE SEPARATION METHOD: Separate waste products and materials that are recyclable from trash and sort as described below into appropriately marked separate containers and then transport to the respective recycling facility for further processing. Deliver materials in accordance with recycling or reuse facility requirements (e.g., free of dirt, adhesives, solvents, petroleum contamination, and other substances deleterious to the recycling process). Separate materials into the category types as defined in the Construction Waste Management Plan.

3.3.3.2. CO-MINGLED METHOD: Place waste products and recyclable materials into a single container and then transport to an authorized recycling facility, which meets all applicable requirements to accept and dispose of recyclable materials in accordance with all applicable local, state and federal regulations. The Co-mingled materials must be sorted and processed in accordance with the approved Construction Waste management Plan.

3.4. DISPOSAL:

3.4.1. Control accumulation of waste materials and trash. Recycle or dispose of collected materials off-site at intervals approved by the Contracting Officer and in compliance with waste management procedures as described in the waste management plan. Except as otherwise specified in other sections of the specifications, dispose of in accordance with the following:

3.4.1.1. REUSE: Give first consideration to reusing construction and demolition materials as a disposition strategy. Recover for reuse materials, products, and components as described in the approved Construction Waste Management Plan. Coordinate with the Contracting Officer or Contracting Officer Representative to identify onsite reuse opportunities or material sales or donation available through Government resale or donation programs. Sale of recovered materials is not allowed on the Installation.

3.4.1.2. RECYCLE: Recycle non-hazardous construction and demolition/debris materials that are not suitable for reuse. Track rejection of contaminated recyclable materials by the recycling facility. Rejected recyclables materials will not be counted as a percentage of diversion calculation. Recycle all fluorescent lamps, HID lamps, mercury (Hg) -containing thermostats and ampoules, and PCBs-containing ballasts and electrical components as directed by the Contracting Officer. Do not crush lamps on site as this creates a hazardous waste stream with additional handling requirements.

3.4.1.2.1. Qualified Recycling Program (QRP): In accordance with Air Force Manual 32-7002: “Environmental Compliance and Pollution Prevention”, Paragraph 6.6.3.5, the Contractor shall participate in the installation’s Qualified Recycling Program.

3.4.1.2.1.1. Segregate the following materials generated during construction or demolition: ferrous and non-ferrous scrap metal, and scrap copper including cable and wire. Place items in separate containers apart from normal construction and demolition debris. Label containers to prevent non-QRP materials from being disposed of in the containers. Ensure security of the containers to prevent theft. Arrange for transport, or deliver QRP materials to a licensed recycler.

3.4.1.2.1.2. Obtain weight tickets, sales price, and sale amount for Environmental Management Office records.

3.4.1.2.1.3. The following forms of payment from the recycler are acceptable: Bank Drafts, Cashier’s Checks and Certified Checks. Payment should be to the order of:

U.S. Treasury
Attn: 179th Environmental
1947 Harrington Memorial Rd.
Mansfield, Ohio 44903

3.4.1.3. COMPOST: Richland County, Ohio manages a composting facility South of the installation. Composting on the installation is not allowed. Compostable materials include plant materials and sawdust. Composting as a strategy must be explicitly addressed in the Construction Waste Management Plan to ensure it is feasible.

3.4.1.4. LANDFILL: Dispose by landfill only those waste materials with no practical use, economic benefit, or recycling opportunity.

3.5. HAZARDOUS MATERIALS/HAZARDOUS WASTE: Handle hazardous materials and hazardous waste in accordance with applicable regulations and coordinate with the Base Environmental Management Office.

END OF SECTION 01 74 19

SECTION XX XX XX
XXXXXXXXXX

---------- END OF SPECIFICATION ----------