DEPARTMENT OF THE ARMY
U.S. ARMY CORPS OF ENGINEERS, MOBILE DISTRICT
100 CANAL STREET
MOBILE, AL 36602-1901

CESAM-CT November 13, 2026

U.S. Army Corps Of Engineers
Mobile District, Directorate of Contracting
100 Canal Street
Mobile, AL 36602

REPLY TO THE ATTENTION OF:
CESAM-CT

SUBJECT: Amended Request for Proposal (RFP) Solicitation No. W9127827RA002 Amendment 0002 – FY27 Florida Panhandle Optimized Remediation Contract (ORC) for Eglin Air Force Base, Hurlburt Field, and Tyndall Air Force Base, Florida

TO: ALL INTERESTED PARTIES

Requirement Overview: The U.S. Army Corps of Engineers (USACE), Mobile District, is pleased to issue this Request for Proposal for the FY27 Florida Panhandle Optimized Remediation Contract (ORC) for Eglin Air Force Base, Hurlburt Field, and Tyndall Air Force Base, Florida. This requirement is for a stand-alone, definitive (C-type) contract for performance-based remediation services at the three Air Force installations. This contract includes all work, equipment, and services required to achieve Performance Objectives within the Performance Periods specified in the Performance Work Statement, including administrative, management, and general support required to execute this ORC. This contract will have a ten (10) year period of performance and will be awarded based on the availability of funds.

Note: Additional GFI files not already in the Air Force Administrative Record (AR) will be sent to the Offerors via DOD Safe.

Revisions Made: Performance Work Statement (PWS), Section L, Section L Attachment L001 Past Performance Questionnaire (PPQ), CLIN Structure, IMS Structure Template, Key Personnel and Bid Sheet have all been updated.

Request for Information (RFI) submission window has been extended. All inquiries regarding this solicitation must be submitted in writing via ProjNet as indicated in Section L of this solicitation (Instructions for ProjNet included). **Inquiries will be accepted until November 20, 2026, at 1400 CST**. The Government is not obligated to respond to inquiries received after this deadline.

Proposals must be received **no earlier than [0700 CST] on December 07, 2026 and no later than [1400 CST] on December 18, 2026**. Submissions shall be delivered electronically via the [PIEE/Procurement Integrated Enterprise Environment] as specified in Section L. Please also include

Please be sure to submit a completed FY27 Florida Panhandle ORC Bid Sheet (Attachment 18), with your offer. Be sure to round all final CLIN costs to the nearest whole dollar.

Please be sure to also include a signed copy of each SF30 RFP Amendment (0001 and 0002) along with a signed copy of the original SF30 Solicitation with your proposal.

Respectfully:

Paul M. Adamo

Paul M. Adamo

SSG, USA

Contracting Officer

Attachments:

1. RFP Amendment 0002
2. Original Solicitation (without original additional attachments included)
3. RFP Amendment 0001
4. FY27 Florida Panhandle ORC PWS and Enclosures (Revised)
5. Section L Proposal Submission Requirements and Instructions (Revised)
6. Section L Attachment L001 PPQ (Revised)
7. FY27 Florida Panhandle ORC CLIN Structure (Revised)
8. FY27 Florida Panhandle ORC IMS Structure Template (Revised)
9. FY27 Florida Panhandle ORC Key Personnel (Revised)
10. FY27 Florida Panhandle ORC Bid Sheet (Revised)

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT

1. CONTRACT ID CODE	PAGE	OF	PAGES
J	1		24

2. AMENDMENT/MODIFICATION NUMBER	3. EFFECTIVE DATE	4. REQUISITION/PURCHASE REQUISITION NUMBER	5. PROJECT NUMBER *(If applicable)*
0002	13 NOV 2026		

6. ISSUED BY	CODE	7. ADMINISTERED BY *(If other than Item 6)*	CODE
W074 ENDIST MOBILE KO CONTRACTING DIVISION, 100 CANAL STREET MOBILE, AL 36602-3630 UNITED STATES DANIELLE KACHELE, EMAIL: DANIELLE.L.KACHELE@USACE.ARMY.MIL TELEPHONE: (251) 694-3812	W91278	SCD: PAS:	

8. NAME AND ADDRESS OF CONTRACTOR *(Number, street, county, State and ZIP Code)*	(X)	9A. AMENDMENT OF SOLICITATION NUMBER
	☒	W9127827RA002
		9B. DATED *(SEE ITEM 11)*
		11 SEP 2026
	☐	10A. MODIFICATION OF CONTRACT/ORDER NUMBER
		10B. DATED *(SEE ITEM 13)*
CODE / FACILITY CODE		

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

☒ The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers ☐ is extended. ☒ is not extended.

Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing items 8 and 15, and returning 1 copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or electronic communication which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by letter or electronic communication, provided each letter or electronic communication makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA *(If required)*

SEE SECTION G - CONTRACT ADMINISTRATION DATA

13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NUMBER AS DESCRIBED IN ITEM 14.

CHECK ONE	
☐	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: *(Specify authority)* THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NUMBER IN ITEM 10A.
☐	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES *(such as changes in paying office, appropriation data, etc.)* SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).
☐	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:
☐	D. OTHER *(Specify type of modification and authority)*

E. IMPORTANT: Contractor ☐ is not ☒ is required to sign this document and return 1 copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (*Organized by UCF section headings, including solicitation/contract subject matter where feasible.)*

The subject Request for Proposal for: FY27 Florida Panhandle ORC for the Air Force; is modified in the following: Performance Work Statement (PWS), Section L, Section L Attachment L001 Past Performance Questionnaire (PPQ), CLIN Structure, IMS Structure Template, Key Personnel and Bid Sheet have all been updated.

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER *(Type or print)*		16A. NAME AND TITLE OF CONTRACTING OFFICER *(Type or print)*	
15B. CONTRACTOR/OFFEROR	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA	16C. DATE SIGNED
(Signature of person authorized to sign)		*(Signature of Contracting Officer)*	

Previous edition unusable

STANDARD FORM 30 (REV. 11/2016)
Prescribed by GSA FAR (48 CFR) 53.243

SOLICITATION, OFFER, AND AWARD

1. This Contract is a Rated Order under the Defense Priorities and Allocations System (DPAS) - Code of Federal Regulations - at 15 CFR 700.

RATING

PAGE OF PAGES 1 627

2. CONTRACT NUMBER	3. SOLICITATION NUMBER	4. TYPE OF SOLICITATION	5. DATE ISSUED	6. REQUISITION/PURCHASE NUMBER
	W9127827RA002	☐ SEALED BID (IFB) INVITATION FOR BID ☒ NEGOTIATED (RFP) REQUEST FOR PROPOSAL		

7. ISSUED BY	CODE	8. ADDRESS OFFER TO *(If other than item 7)*
W074 ENDIST MOBILE KO CONTRACTING DIVISION, 100 CANAL STREET MOBILE, AL 36602-3630 UNITED STATES DANIELLE KACHELE, EMAIL: DANIELLE.L.KACHELE@USACE.ARMY.MIL TELEPHONE: (251) 694-3812	W91278	

NOTE: In sealed bid solicitations "offer" and "offeror" mean "bid" and "bidder".

SOLICITATION

9. Sealed offers in original and 1 copies for furnishings the supplies or services in the Schedule will be received at the place specified in item 8, or if hand carried, in the depository located in _____ until 02:00 PM *(Hour)* local time 18 DEC 2026 *(Date)*

CAUTION - LATE Submissions, Modifications, and Withdrawals: See Section L, Provision Number 52.214-7 or 52.215-1. All offers are subject to all terms and conditions contained in this solicitation.

10. FOR INFORMATION CALL:	A. NAME	B. TELEPHONE *(NO COLLECT CALLS)*			C. EMAIL ADDRESS
		AREA CODE	NUMBER	EXTENSION	
	DANIELLE KACHELE	251	694-3812		DANIELLE.L.KACHELE@USACE.ARMY.M

11. TABLE OF CONTENTS

(X)	SECTION	DESCRIPTION	PAGE(S)	(X)	SECTION	DESCRIPTION	PAGE(S)
		PART I - THE SCHEDULE				*PART II - CONTRACT CLAUSES*	
☒	A	SOLICITATION/CONTRACT FORM	1-2	☒	I	CONTRACT CLAUSES	551-593
☒	B	SUPPLIES OR SERVICES AND PRICES/COSTS	3-302			*PART III - LIST OF DOCUMENTS, EXHIBITS AND OTHER ATTACHMENTS*	
☒	C	DESCRIPTION/SPECIFICATIONS/WORK STATEMENT	303		J	LIST OF ATTACHMENTS	
	D	PACKAGING AND MARKING				*PART IV - REPRESENTATIONS AND INSTRUCTIONS*	
☒	E	INSPECTION AND ACCEPTANCE	304-544	☒	K	REPRESENTATIONS, CERTIFICATIONS AND OTHER STATEMENTS OF OFFERORS	594-613
☒	F	DELIVERIES OR PERFORMANCE	545				
☒	G	CONTRACT ADMINISTRATION DATA	546-550	☒	L	INSTRUCTIONS, CONDITIONS, AND NOTICES TO OFFERORS	614-626
	H	SPECIAL CONTRACT REQUIREMENTS		☒	M	EVALUATION FACTORS FOR AWARD	627

OFFER *(Must be fully completed by offeror)*

NOTE: Item 12 does not apply if the solicitation includes the provisions at 52.214-16, Minimum Bid Acceptance Period.

12. In compliance with the above, the undersigned agrees, if this offer is accepted within _____ calendar days *(60 calendar days unless a different period is inserted by the offeror)* from the date for receipt of offers specified above, to furnish any or all items upon which prices are offered at the set opposite each item, delivered at the designated point(s), within the time specified in the schedule.

13. DISCOUNT FOR PROMPT PAYMENT *(See Section I, Clause Number 52.232-8)*	10 CALENDAR DAYS (%)	20 CALENDAR DAYS (%)	30 CALENDAR DAYS (%)	CALENDAR DAYS (%)

14. ACKNOWLEDGMENT OF AMENDMENTS *(The offeror acknowledges receipt of amendments to the SOLICITATION for offerors and related documents numbered and dated):*	AMENDMENT NUMBER	DATE	AMENDMENT NUMBER	DATE

15A. NAME AND ADDRESS OF OFFEROR	CODE	FACILITY	16. NAME AND THE TITLE OF PERSON AUTHORIZED TO SIGN OFFER *(Type or print)*

15B. TELEPHONE NUMBER			☐ 15C. CHECK IF REMITTANCE ADDRESS IS DIFFERENT FROM ABOVE - ENTER SUCH ADDRESS IN SCHEDULE.	17. SIGNATURE	18. OFFER DATE
AREA CODE	NUMBER	EXTENSION			

AWARD *(To be completed by Government)*

19. ACCEPTED AS TO ITEMS NUMBERED	20. AMOUNT	21. ACCOUNTING AND APPROPRIATION

22. AUTHORITY FOR USING OTHER THAN FULL OPEN COMPETITION UNDER THE UNITED STATES CODE AT: ☐ 10 U.S.C. 3204(a) ☐ 41 U.S.C. 3304(a) ( )	23. SUBMIT INVOICES TO ADDRESS SHOWN IN *(4 copies unless otherwise specified)*	ITEM
24. ADMINISTERED BY *(If other than Item 7)*	25. PAYMENT WILL BE MADE BY	CODE

26. NAME OF CONTRACTING OFFICER *(Type or print)*	27. UNITED STATES OF AMERICA *(Signature of Contracting Officer)*	28. AWARD DATE

IMPORTANT - Award will be made on this Form, or on Standard Form 26, or by other authorized official written notice.

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT

1. CONTRACT ID CODE	PAGE	OF	PAGES
J	1		2

2. AMENDMENT/MODIFICATION NUMBER	3. EFFECTIVE DATE	4. REQUISITION/PURCHASE REQUISITION NUMBER	5. PROJECT NUMBER *(If applicable)*
0001	16 SEP 2026		

6. ISSUED BY	CODE	7. ADMINISTERED BY *(If other than Item 6)*	CODE
W074 ENDIST MOBILE KO CONTRACTING DIVISION, 100 CANAL STREET MOBILE, AL 36602-3630 UNITED STATES DANIELLE KACHELE, EMAIL: DANIELLE.L.KACHELE@USACE.ARMY.MIL TELEPHONE: (251) 694-3812	W91278	SCD: PAS:	

8. NAME AND ADDRESS OF CONTRACTOR *(Number, street, county, State and ZIP Code)*	(X)	9A. AMENDMENT OF SOLICITATION NUMBER W9127827RA002 9B. DATED *(SEE ITEM 11)* 11 SEP 2026
	☐	10A. MODIFICATION OF CONTRACT/ORDER NUMBER 10B. DATED *(SEE ITEM 13)*

CODE	FACILITY CODE

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

☒ The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers ☐ is extended. ☒ is not extended.

Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods:
(a) By completing items 8 and 15, and returning 1 copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted;
or (c) By separate letter or electronic communication which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER.
If by virtue of this amendment you desire to change an offer already submitted, such change may be made by letter or electronic communication, provided each letter or electronic communication makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA *(If required)*

SEE SECTION G - CONTRACT ADMINISTRATION DATA

13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NUMBER AS DESCRIBED IN ITEM 14.

CHECK ONE	
☐	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: *(Specify authority)* THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NUMBER IN ITEM 10A.
☐	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES *(such as changes in paying office, appropriation data, etc.)* SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).
☐	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:
☐	D. OTHER *(Specify type of modification and authority)*

E. IMPORTANT: Contractor ☐ is not ☒ is required to sign this document and return 1 copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (*Organized by UCF section headings, including solicitation/contract subject matter where feasible.)*

The subject Request for Proposal for: FY26 Florida Panhandle ORC for the Air Force; is modified in the following: Attachment 5 Entry Authorization List (EAL) Excel Attachment has been revised to make it accessible and useable.

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER *(Type or print)*		16A. NAME AND TITLE OF CONTRACTING OFFICER *(Type or print)*	
15B. CONTRACTOR/OFFEROR *(Signature of person authorized to sign)*	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA *(Signature of Contracting Officer)*	16C. DATE SIGNED

PERFORMANCE WORK STATEMENT

For

FY27 Florida Panhandle Group
Optimized Remediation Contract

At

Eglin Air Force Base, Florida
Hurlburt Field, Florida
Tyndall Air Force Base, Florida

US Army Corps of Engineers (USACE) - Mobile District

Contract: W91278XXXXXXX
Solicitation: W9127827RA002

09 November 2026

TABLE OF CONTENTS

1.0 SCOPE 5

1.1 INTRODUCTION 5
1.2 OVERVIEW OF ORC SCOPE AND REQUIREMENTS 6
1.2.1 Specific Scope Discussion and Limits 8
1.2.2 Preliminary Assessment/Site Inspection, Remedial Investigation or Remedial Investigation/Feasibility Study (including Supplemental Investigations), and Decision Document 8
1.2.3 Response Complete or Site Closeout 8
1.2.4 Remedial Action-Operation with Optimization 8
1.2.5 Remedial Action-Operation and Reduce Life Cycle Cost; Long Term Management and Reduce Life Cycle Cost 9
1.2.6 Remedial Action-Operation or Long-Term Management (as appropriate) 9
1.2.7 Alternate Objectives 9
1.2.8 PO ACTIVITIES 9
1.3 PERFORMANCE REQUIREMENTS 10
1.3.1 Table 1: Performance Table 10
1.3.2 Additional Scope Discussion and Limits 19

2.0 APPLICABLE DOCUMENTS 20

3.0 GOVERNMENT FURNISHED INFORMATION AND PROPERTY 21

4.0 MANAGEMENT, PLANNING, AND REPORTING REQUIREMENTS 21

4.1 PROJECT MANAGEMENT PLAN 22
4.2 SCHEDULE AND PLANNING REQUIREMENTS – INTEGRATED MASTER SCHEDULE 23
4.3 MILESTONE PAYMENT SCHEDULE 26
4.4 COST AND STATUS REPORTING 29

4.4.1 INVOICES 29

4.5 ORC DOCUMENT REPOSITORY 30
4.6 MEETING AND CONFERENCE REQUIREMENTS 30
4.6.1 Meeting/Teleconference Support 30
4.6.2 Public Meetings and Hearings 31
4.6.2.1 Community Involvement Plan (CIP) Update 32
4.7. SPATIAL DATA (MAP) REQUIREMENTS 32
4.8 INFORMATION SECURITY 34
4.8.1 Cybersecurity Standard Operating Procedure 34
4.9 NOTIFICATION REQUIREMENTS 34
4.10 PERMITS 34
4.10.1 Environmental Permits 35
4.10.2 Rights of Access to Non-AF Real Property 35
4.11 PHOTO DOCUMENTATION 35
4.12 REMOTE AND/OR AUSTERE SITES 36
4.13 INSTALLATION/SITE ACCESS AND SECURITY 36
4.14 WORKSITE ACTIVITIES AND COORDINATION 38
4.14.1 Coordination of Activities 38
4.14.2 GENERAL REQUIREMENTS DURING FIELD ACTIVITIES 38
4.14.3 Radiological Waste, Hazardous Material, and Hazardous Waste Permitting and Reporting 39
4.14.3.1 Regulatory Requirements 41
4.15 ORC TRANSITION PLAN 41

5.0 CHEMISTRY REQUIREMENTS 42

5.1 QUALITY ASSURANCE 42
5.2 LABORATORY SELECTION 43
5.3 ANALYTICAL DATA MANAGEMENT 43
5.4 RECORD KEEPING 43
5.5 PFAS SAMPLING AND ANALYSIS 44

6.0 MUNITIONS RESPONSE AND EXPLOSIVES SAFETY REQUIREMENTS 44

6.1 3RS (RECOGNIZE, RETREAT, REPORT) EXPLOSIVES SAFETY EDUCATION PROGRAM TRAINING 44
6.2 EXPLOSIVE SAFETY SUBMITTALS 45
6.3 ENVIRONMENTAL REQUIREMENTS 45
6.4 MEC RELATED GUIDANCE 45
6.5 REVISION 02 UNIFORM FEDERAL POLICY QUALITY ASSURANCE PROJECT PLAN (UFP-QAPP) 46
6.6 QUALITY CONTROL 46
6.7 QUALITY MANAGEMENT 46
6.8 GEOPHYSICAL DELIVERABLE REQUIREMENTS 47
6.9 GEOGRAPHIC INFORMATION SYSTEM 47

7.0 PLANS AND REPORTS 47

7.1 QUALITY PROGRAM PLANS 47
7.1.1 Work Plans 47
7.1.2 Health and Safety Plan 48
7.1.3 Construction Quality Plan 48
7.2 TECHNICAL PLANS AND REPORTS 48
7.3 DELIVERABLE SUBMISSION CYCLE 50
7.4 RESPONSE TO COMMENTS 51
7.5 PROJECT DELIVERY TEAM 51

8.0 SITE WORK 51

8.1 CONSERVATION 51
8.2 SITE CHARACTERIZATION AND FIELD INVESTIGATION 52
8.3 SITE PREPARATION 52
8.4 DEMOLITION 52
8.5 SITE RESTORATION 53

9.0 ENVIRONMENTAL REQUIREMENTS 53

9.1 ENVIRONMENTAL RESTORATION PROCESS APPLICATION 54
9.1.1 Conceptual Site Model Guidance 54
9.1.2 Exit Strategy 55
9.5 INNOVATIVE AND PROVEN TECHNOLOGIES 64
9.6 OPERATIONS AND MAINTENANCE 64
9.7 MPPEH REMOVAL AND SUPPORT 64
9.8 HAZARDOUS/NON-HAZARDOUS WASTE REMOVAL AND SUPPORT 64
9.9 STUDY EFFORT INCIDENTAL TO REMEDY OR CORRECTIVE ACTION 65
9.10 FIVE-YEAR REVIEW SUPPORT 65
9.11 IDENTIFICATION OF NEW SITE 65
9.12 CHANGE AND DIFFERING CONDITIONS 65
9.13 OTHER PROVISIONS 65
9.14 KEY PERSONNEL 66

10.0 PERFORMANCE STANDARDS AND SURVEILLANCE ACTIVITIES 66

11.0 POINTS OF CONTACT 66

12.0 CONTRACTOR MANPOWER REPORTING REQUIREMENTS 67

12.1 CONTRACTOR MANPOWER REPORTING REQUIREMENTS 67
12.2 VETERANS EMPLOYMENT 67
12.3 SUSTAINABILITY REQUIREMENTS 68

13.0 PERIOD OF PERFORMANCE 69

1.0 SCOPE

This requirement is for environmental remediation activities at Eglin Air Force Base (AFB), Hurlburt Field, and Tyndall AFB. This Performance Work Statement (PWS) defines the scope of environmental services necessary to conduct site restoration under the Optimized Remediation Contract (ORC). The range of activities includes investigation, design, construction of remedial systems, operation and maintenance of established remedies, optimization at applicable sites, and achievement of site-specific objectives. The Contractor shall undertake Environmental Remediation activities to achieve Performance Objectives (POs) at 56 Installation Restoration Program (IRP) sites and five Military Munitions Response Program (MMRP) sites. The Period of Performance (PoP) for this "C" Type Contract will be ten (10) years from the date of award.

NOTE: For purposes of this ORC, the term "Government" includes the Air Force (AF) and United States Army Corps of Engineers (USACE). While regulators are a governmental entity, they are also a third party over whom the AF has no control and, as such, will be referred to as "regulators."

1.1 Introduction

EGLIN AFB

Eglin AFB is located east of Pensacola, Florida, occupying 724 square miles of land in the northwest Florida panhandle. Its 101,000 square miles of air space extends over the eastern third of the Gulf of Mexico, an area extending from the Florida Panhandle to the Florida Keys. Seventeen miles of shoreline allows test and evaluation of a littoral environment. The surrounding properties include wetlands, unimproved, rural, highly developed residential areas, commercial areas, and light industrial areas.

Eglin AFB is the former home of the 39th Bomb Wing and the 4135th Strategic Wing. The Eglin Range is managed by the 96th Wing. It is primarily a weapons development, testing and training base, with tenant units from the Navy, Army, and National Guard, that is currently undergoing massive growth (>$1 billion) due to Base Realignment and Closure (BRAC) activities such as bed-down facilities for the F-35 Joint Strike Fighter training mission and relocation of the US Army 7th Special Forces Group from Fort Bragg, North Carolina.

Remediation activities at Eglin AFB are being conducted pursuant to the Resource Conservation and Recovery Act (RCRA) and Chapter 62-780 Florida Administrative Code (FAC) requirements. Regulatory oversight is provided by the Florida Department of Environmental Protection (FDEP).

Eglin AFB is being administered under a RCRA Corrective Action / Hazardous and Solid Waste Amendments (HSWA) Permit. The RCRA Permit is renewed on a five (5) year cycle and the next renewal is scheduled to occur in FY29. The Contractor is responsible for all costs associated with the RCRA Permit renewal.

HURLBURT FIELD

Hurlburt Field is a United States AF installation in the Florida panhandle between Pensacola and Panama City and covers approximately 6,600 acres in Okaloosa County. Hurlburt Field was originally designated as Eglin Auxiliary Field No. 9, one of the original pilot and gunnery training fields built in the 1940s. Hurlburt Field is home of the 1st Special Operations Wing, a

part of Air Force Special Operations Command (AFSOC). The mission of the wing is to organize, train, and equip USAF special operations forces for global deployment, and to assist foreign countries in the establishment of internal air defense abilities. The wing focuses on unconventional warfare including counterinsurgency and psychological operations during low intensity conflicts.

Remediation activities at Hurlburt Field are being conducted pursuant to the Comprehensive Environmental Rehabilitation, Compensation, and Liability Act (CERCLA) for MMRP sites only, RCRA, and Chapter 62-780 FAC. Regulatory oversight is provided by the FDEP.

Hurlburt Field is being administered under a RCRA Corrective Action / HSWA Permit. The RCRA Permit is renewed on a ten (10) year cycle and the next renewal is scheduled to occur in FY31; the HSWA portion of the permit is updated approximately every 2.5 years. The Contractor is responsible for all costs associated with the RCRA Permit renewal.

TYNDALL AFB

Tyndall AFB occupies approximately 29,000 acres on a narrow 18-mile-long northwest-southeast trending peninsula. Tyndall AFB was activated in 1941, initially as an Army Air Corps facility. It was re-designated as an AFB in 1947. Currently, Tyndall AFB is part of the Air Combat Command and is used for the training of air defense crews and provides combat power for AF missions.

Tyndall AFB was finalized for listing on the National Priorities List (NPL) on 1 April 1997. A Federal Facility Agreement (FFA) between the United States Environmental Protection Agency (USEPA) Region 4, FDEP, and the AF was signed 20 September 2013 and the FFA became final and effective on 3 January 2014. The Contractor shall adhere to CERCLA requirements and terms in the Final FFA dated 3 January 2014.

Remediation activities at Tyndall AFB are being conducted pursuant to the FFA under the CERCLA with the exception of OT018, TA523, TU204, and TU233. These Petroleum, Oil, and Lubricant (POL) sites are addressed under the FDEP Contaminated Site Cleanup Criteria (Chapter 62-780, F.A.C.). Sites deferred from CERCLA by FFA paragraph 9.2.1.2 to another program will achieve the site PO with approval from the applicable regulatory agency. Regulatory oversight is provided by USEPA Region 4 and FDEP.

1.2 Overview of ORC Scope and Requirements

The Contractor shall perform all the necessary environmental remediation activities needed to achieve the performance requirement described in Table 1: Performance Table, and additional scope in 1.3.2. This PWS and enclosures listed below detail the project requirements needed to meet the AF objectives:

- Enclosure 1 – Acronyms and Definitions
- Enclosure 2A – Eglin AFB Well Abandonment List
- Enclosure 2B – Hurlburt Field Well Abandonment List
- Enclosure 2C – Tyndall AFB Well Abandonment List
- Enclosure 2D – Eglin AFB Administrative Record List

- Enclosure 2E – Hurlburt Field Administrative Record List
- Enclosure 2F – Tyndall AFB Administrative Record List
- Enclosure 3 – FL Panhandle ORC Government Furnished Property (GFP)
- Enclosure 4 – Community Involvement Plan (CIP) Guidance version 4
- Enclosure 5 – Eglin Standard Operating Procedures (ESOP) 1-20

The intent of the ORC initiative is to advance site cleanup during the Period of Performance (PoP) in the most efficient and cost-effective manner, as supported by a cost-benefit analysis and exit strategy that achieves the greatest reduction in life-cycle cost (LCC). The AF is interested in substantial reduction of long-term environmental liabilities and total LCC. Technical approaches reduced to a minimal level of effort, with no well-planned contingencies, or that provide no assurance to the Government that the POs will be achieved without work stoppages or change orders, are not in keeping with the intent of this performance-based contracting effort. The AF is required to implement remedies, as necessary, to enable the mission, protect human health and the environment, and comply with laws and regulations. The goal of the ORC initiative is to ensure the AF continues to fulfill all facets of its Environmental Restoration Program (ERP) Mission by effectively and efficiently managing the program in a performance-based, results-oriented, and cost-conscious framework.

The AF requires all sites to be remediated to meet standards that allow for the current or reasonably anticipated future land use of the property. Accurate documentation and reporting of contaminant removal and cost savings are essential components to optimization success. In accordance with Defense Environmental Restoration Program (DERP) and Air Force Instruction (AFI) 32-7020, the AF defines optimization under the ORC as reducing contaminant mass and concentrations, reducing LCC, or any combination of activities that accelerates Response Complete (RC)/Site Closeout (SC) resulting from the remedial implementation undertaken by the Contractor, exceeding what is required to maintain compliance with an approved Decision Document (DD).

The Contractor shall maintain compliance with all DDs/Records of Decision (RODs)/Proposed Plans/RCRA Permits currently in place until they are no longer required, or an alternate approach is approved. The Contractor shall conduct DD/ROD amendments or Explanations of Significant Differences (ESDs) as required to implement new approaches.

The Contractor shall function as an integral team member in support of the Air Force Civil Engineer Center (AFCEC) mission, to include the sharing of information with USACE, other AFCEC contractors, and AF personnel, in cooperation with community stakeholders, regulators, and other government entities.

Requirements for efficient management of this contract include achieving the POs within the Performance Period (PP) as outlined in Table 1 and the work detailed in Section 1.3.2 of this PWS. Requirements include timely identification and resolution of impediments to successful project execution. The Contractor shall provide all personnel, equipment, supplies, tools, materials, and other items necessary to perform the tasks defined in this PWS. The Contractor is solely responsible for reviewing all available information and forming independent, professional conclusions and interpretations of site conditions and requirements to achieve the POs of this contract within the PoP specified in accordance with Section 3.0. AFCEC will rely on the Contractor's expertise in recognizing and addressing problematic issues during the execution of

this contract. The Contractor shall perform all work in accordance with federal, state, and local statutes and regulations. The Contractor shall also comply with Installation regulations. Remedies shall conform to environmental permits, DD requirements, or other legal requirements. The Contractor shall continue work throughout the entire duration of the PoP. The Contractor's local office presence will be relied upon to provide rapid-response actions for field activities and on-site meetings.

1.2.1 Specific Scope Discussion and Limits

The scope of this contract is to perform environmental remediation services for the sites listed in Table 1 of the PWS. The ORC Contractor shall assume contractual liability and responsibility for achieving the POs. If the selected technical approach is not effective, as demonstrated by the trends in the performance model, the Contractor shall develop and implement a revised technical approach to achieve the POs, including DD amendments, if required, to implement the remedial approach. This scope includes all known contaminants linked to the specific sites per Table 1 of the PWS (including contaminants on, under, or sourced at/migrating from the specific sites) without regard to quantity (e.g., plume size, concentrations). See reference to Section 1.3.2 of this PWS for exclusions. The AF remains statutorily responsible for all sites listed in Table 1 and the work described in Section 1.3.2.

All cost associated with this Contract shall be rounded to whole dollars, including CLIN Price, MPS, invoices, etc.

1.2.2 Preliminary Assessment/Site Inspection, Remedial Investigation or Remedial Investigation/Feasibility Study (including Supplemental Investigations), and Decision Document

Table 1 of the PWS identifies Preliminary Assessment/Site Inspection (PA/SI), Remedial Investigation (RI), or RI/Feasibility Study (FS), including Supplemental Investigations, and DDs as the PO for selected sites. The Contractor is responsible for achieving these POs as identified in Table 1 and the work described in Section 1.3.2. See PO definitions in Enclosure 1, Acronyms and Definitions.

1.2.3 Response Complete or Site Closeout

Table 1 of the PWS identifies Response Complete (RC) or Site Closeout (SC) as the PO for selected sites. The Contractor is responsible for achieving these objectives as identified in Table 1 and the work described in Section 1.3.2. See PO definitions in Enclosure 1, Acronyms and Definitions. The performance components, including the need for a performance model, are described in Section 8.1.3.

1.2.4 Remedial Action-Operation with Optimization

Table 1 of the PWS identifies the following POs, which include optimization as follows: 1. Remedy in Place (RIP) and Remedial Action-Operation (RA-O) with Optimization, 2. DD Amendment (or ESD) with Remedy Implementation and RA-O with Optimization, or 3. RA-O with Optimization. The Contractor is responsible for achieving these POs as identified in Table 1and additional scope described in Section 1.3.2. See PO definitions in Enclosure 1, Acronyms and Definitions.

The optimization and performance components, including the need for a performance model showing interim and final performance payment milestones, are described in Section 8.1.3. Optimization goals may include one or more of the following:

1. Shorten time to RC, SC, or other Department of Defense (DoD) goals.
2. Improve remedy performance and/or accelerate the progress of the remediation.
3. Enhance source or plume control for engineering systems.

1.2.5 Remedial Action-Operation and Reduce Life Cycle Cost; Long Term Management and Reduce Life Cycle Cost

NOT APPLICABLE

1.2.6 Remedial Action-Operation or Long-Term Management (as appropriate)

Table 1 of the PWS identifies RA-O, Long-Term Management (LTM), or Land Use Controls (LUCs) in accordance with the approved DD/ROD as the PO for selected sites. See PO definitions in Enclosure 1, Acronyms and Definitions.

The Contractor shall achieve the following objectives for each RA-O, LTM, or LUC site:

- Maintain compliance with all DDs and permits (currently in place or to be approved) throughout the PP. Update or revise site-specific work plans, monitoring plans, and/or DDs, as appropriate.
- For RA-O sites, develop performance models addressing all COCs and breakdown products. Refer to Section 8.1.3.1, Performance Models.
- Provide a realistic projection to achieve SC or RC after the PoP (the Contractor shall identify which PO is the optimal endpoint).

1.2.7 Alternate Objectives

NOT APPLICABLE

1.2.8 PO Activities

The Contractor is responsible for all activities leading to the completion of the POs described in Section 1.2 and listed in Table 1 or Section 1.3.2 of the PWS, inclusive of the following:

- Maintaining and performing all required O&M on remediation systems and equipment for the full duration of the contract, ensuring continuous, reliable, and compliant system performance.
- Keeping systems operating as intended throughout the contract PoP, or until the system is no longer needed (e.g., Achievement of RC), whichever is longer. If a system becomes non-operational, the Contractor is responsible for all costs associated with repairs and upgrades. If the repair or replacements will take longer than 10 days from the time of initial non-operation, the timeline for repair should be coordinated with the COR and the Contractor shall submit, in writing, the plan to get the system operating again to the COR and Installation RPM within 10 days. The plan shall include the planned repairs and timeline.

- O&M of all wells, including the following examples: semi-annual inspections, well repairs, replacement of missing or broken parts/tags/locks, well pad repair or replacement, removal of obstructions, and well redevelopment.
- Replacing wells if necessary; and/or abandoning wells with AF, USACE, and regulatory approval (if required) when the well is no longer necessary.

Site maintenance including vegetation control (if required) to maintain fencelines, structures, and access routes.

1.3 Performance Requirements

1.3.1 Table 1: Performance Table

Table 1 presents the POs, PPs, and Performance Standards associated with all Installations/sites under this ORC. The PP specified in Table 1 is from the date of award of the first performance AFCEC Contract Line-Item Number (CLIN) or AFCEC Sub-Contract Line-Item Number (Sub-CLIN) for the site unless otherwise specified. All approvals (both Government and regulator) per the Performance Standard are required in writing. Additional scope discussion and limits can be found in Section 1.3.2.

Table 1: Performance Table

Site	Performance Objective	Performance Period*	Performance Standard
N/A	Project Management Plan (PMP): 1) Revision 00 PMP 2) Revision 01 PMP 3) Updates as necessary	Revision 00 PMP within 60 calendar days from contract award, Revision 01 PMP within 14 calendar days of receipt of AF and USACE comments on Revision 00 and update as necessary throughout the PoP. The AF and USACE will determine when whole document PMP updates are warranted	AF and USACE approval of PMP. The PMP should be maintained with accuracy and completeness based on the current technical approach for each site, management structure, etc.
N/A	Integrated Master Schedule (IMS)/Milestone Payment Schedule (MPS)	Revision 00 IMS/MPS within 60 calendar days from contract award, Revision 01 IMS/MPS within 14 calendar days of receipt of AF and USACE comments on Revision 00, and updates by the 10th of each month throughout the PoP	AF and USACE approval of IMS/MPS.
N/A	Base-wide Quality Program Plans (QPPs) for each Installation	Revision 00 Base-wide QPP within 60 calendar days from contract award and update as necessary throughout the PoP	AF, USACE, and regulatory approval of Base-wide QPP.

Site	Performance Objective	Performance Period*	Performance Standard
Eglin AFB			
All Open Sites (IRP, MMRP, Per- and polyfluoroalkyl substances (PFAS), etc.)	Community Involvement Plan (CIP) and updates are required prior to the RI phase, after the DD/ROD is signed, and every three (3) years thereafter for each Installation and associated Geographically Separated Units, per Enclosure 4.	Revision 00 CIP or Update within 180 calendar days from AFCEC Sub-CLIN award; Revision 01 CIP or Update within 14 calendar days of receipt of AF comments on Revision 00; Revision 02 CIP or Update within 14 calendar days of approval by the AF	AF and USACE approval of CIP.
CF288	Achieve Remedial Action Plan (RAP)	Five (5) years	AF, USACE, and regulatory approval of RAP
DP009	LTM in accordance with the approved ROD/DD	Through the duration of the PoP	AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).
DP084	LTM in accordance with the approved ROD/DD	Through the duration of the PoP	AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).
DP261	LTM in accordance with the approved ROD/DD	Through the duration of the PoP	AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).
FT028	LTM in accordance with the approved ROD/DD	Through the duration of the PoP	AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).
LF003	RAO in accordance with the approved ROD/DD	Through the duration of the PoP	AF, USACE, and regulatory approval of RA-O documentation (e.g., Quinquennially Groundwater Monitoring Reports, Land Use Control Inspection Reports).
LF005	LTM in accordance with the approved ROD/DD	Through the duration of the PoP	AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).
LF008	LTM in accordance with the approved ROD/DD	Through the duration of the PoP	AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).

Site	Performance Objective	Performance Period*	Performance Standard
LF010	LTM in accordance with the approved ROD/DD	Through the duration of the PoP	AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).
LF051	LTM in accordance with the approved ROD/DD	Through the duration of the PoP	AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).
LF322	Site Assessment	Four (4) years	AF, USACE, and regulatory approval of PA/SI.
OT083	LTM in accordance with the approved ROD/DD	Through the duration of the PoP	AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).
OT100	LTM in accordance with the approved ROD/DD	Through the duration of the PoP	AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).
OT262	LTM in accordance with the approved ROD/DD	Through the duration of the PoP	AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).
OT263	LTM in accordance with the approved ROD/DD	Through the duration of the PoP	AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).
OT264	LTM in accordance with the approved ROD/DD	Through the duration of the PoP	AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).
OT265	LTM in accordance with the approved ROD/DD	Through the duration of the PoP	AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).
OT269	LTM in accordance with the approved ROD/DD	Through the duration of the PoP	AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).
OT270	LTM in accordance with the approved ROD/DD	Through the duration of the PoP	AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).

Site	Performance Objective	Performance Period*	Performance Standard
OT271	LTM in accordance with the approved ROD/DD	Through the duration of the PoP	AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).
POI523	LTM in accordance with the approved ROD/DD	Through the duration of the PoP	AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).
SS025	LTM in accordance with the approved ROD/DD	Through the duration of the PoP	AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).
SS026	LTM in accordance with the approved ROD/DD	Through the duration of the PoP	AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).
SS086	LTM in accordance with the approved ROD/DD	Through the duration of the PoP	AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).
SS278	LTM in accordance with the approved ROD/DD	Through the duration of the PoP	AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).
SS281	LTM in accordance with the approved ROD/DD	Through the duration of the PoP	AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).
SS283	LTM in accordance with the approved ROD/DD	Through the duration of the PoP	AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).
SS313	SC	Six (6) years	AF, USACE, and regulatory approval of SC documentation (e.g., Site Closeout Report and Well Abandonment Confirmation Report).
ST069	RC	Six (6) years	AF, USACE, and regulatory approval of RC documentation (e.g., Revision 02 Remedial Action Completion Report and System Decommissioning and Well Abandonment Report

Site	Performance Objective	Performance Period*	Performance Standard
Hurlburt Field			
All Open Sites (IRP, MMRP, Per- and polyfluoroalkyl substances (PFAS), etc.)	CIP and updates are required prior to the RI phase, after the DD/ROD is signed, and every three (3) years thereafter for each Installation and associated Geographically Separated Units, per Enclosure 4.	Revision 00 CIP or Update within 180 calendar days from AFCEC Sub-CLIN award; Revision 01 CIP or Update within 14 calendar days of receipt of AF comments on Revision 00; Revision 02 CIP or Update within 14 calendar days of approval by the AF	AF and USACE approval of CIP.
CG219	Achieve Remedial Action Plan (RAP)	Five (5) years	AF, USACE, and regulatory approval of RAP
LF013	LTM in accordance with the approved ROD/DD	Through the duration of the PoP	AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).
LF014	LTM in accordance with the approved ROD/DD	Through the duration of the PoP	AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).
LF015	LTM in accordance with the approved ROD/DD	Through the duration of the PoP	AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).
LF016	LTM in accordance with the approved ROD/DD	Through the duration of the PoP	AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).
LF017	LTM in accordance with the approved ROD/DD	Through the duration of the PoP	AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).
LF018	LTM in accordance with the approved ROD/DD	Through the duration of the PoP	AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).
LF019	LTM in accordance with the approved ROD/DD	Through the duration of the PoP	AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).

Site	Performance Objective	Performance Period*	Performance Standard
LF020	LTM in accordance with the approved ROD/DD	Through the duration of the PoP	AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).
SS125	SC	Seven (7) years	AF, USACE, and regulatory approval of SC documentation (e.g., Site Closeout Report and Well Abandonment Confirmation Report).
ST123	LTM in accordance with the approved ROD/DD	Through the duration of the PoP	AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).
XU002	ROD/DD	Ten (10) years	AF, USACE, and regulatory approval of ROD/DD (i.e., Air Force and regulatory signatures on Revision 02 ROD/DD).
Tyndall AFB			
All Open Sites (IRP, MMRP, Per- and polyfluoroalkyl substances (PFAS), etc.)	CIP and updates are required prior to the RI phase, after the DD/ROD is signed, and every three (3) years thereafter for each Installation and associated Geographically Separated Units, per Enclosure 4.	Revision 00 CIP or Update within 180 calendar days from AFCEC Sub-CLIN award; Revision 01 CIP or Update within 14 calendar days of receipt of AF comments on Revision 00; Revision 02 CIP or Update within 14 calendar days of approval by the AF	AF and USACE approval of CIP.
DA046	SC	Ten (10) years	AF, USACE, and regulatory approval of SC documentation (e.g., Site Closeout Report and Well Abandonment Confirmation Report).
FR038	LTM in accordance with the approved ROD/DD	Through the duration of the PoP	AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).
FT016	FS Upon achievement of LUCIP, conduct RA-O in accordance with the Interim Action ROD/DD throughout the duration of the PoP	Ten (10) years	AF, USACE, and regulatory approval of FS and LUCIP. AF, USACE, and regulatory approval of RA-O documentation (e.g., Land Use Control Inspection Reports, etc.).

Site	Performance Objective	Performance Period*	Performance Standard
FT016	1,4-Dioxane Step 2	Five (5) years	AF, USACE, and regulatory approval of Technical Memorandum/Report
FT017	FS Upon achievement of LUCIP, conduct RA-O in accordance with the Interim Action ROD/DD throughout the duration of the PoP	Ten (10) years	AF, USACE, and regulatory approval of FS and LUCIP AF, USACE, and regulatory approval of RA-O documentation (e.g., Land Use Control Inspection Reports, etc.).
LF006	RC Upon achievement of RC, continue LTM in accordance with the ROD/DD throughout the PoP	Seven (7) years	AF, USACE, and regulatory approval of RC documentation (e.g., Revision 02 Remedial Action Completion Report and Revision 02 Land Use Control Implementation Plan). AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).
LF007	RC Upon achievement of RC, continue LTM in accordance with the ROD/DD throughout the PoP	Seven (7) years	AF, USACE, and regulatory approval of RC documentation (e.g., Revision 02 Remedial Action Completion Report). AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).
OT018	Confirmatory Sampling	Four (4) years	AF, USACE, and regulatory approval of Confirmatory Sampling Report

Site	Performance Objective	Performance Period*	Performance Standard
OT029	RC Upon achievement of RC, continue LTM in accordance with the ROD/DD throughout the PoP	Seven (7) years	AF, USACE, and regulatory approval of RC (e.g., Proposed Plan, Regulator approval of, and Air Force signature on Record of Decision, Final Remedial Action Report). AF and USACE approval of Performance Model Evaluation Report during RA-O. AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).
OW217	Final ROD Upon achievement of LUCIP, conduct RA-O in accordance with the Interim Action ROD/DD throughout the duration of the PoP	Six (6) years	AF, USACE, and regulatory approval of ROD/DD (i.e., Air Force and regulatory signatures on Revision 02 ROD/DD). AF, USACE, and regulatory approval of RA-O documentation (e.g., Land Use Control Inspection Reports, etc.).
OW582	RIP Upon achievement of RIP, continue RA-O in accordance with the ROD/DD throughout the duration of the PoP	Four (4) years	AF, USACE, and regulatory approval of RIP (e.g., Construction Completion Report and first RA-O Report demonstrating remedy is operating properly and successfully). AF and USACE approval of Performance Model Evaluation Report during RA-O. AF, USACE, and regulatory approval of RA-O documentation (e.g., Annual Groundwater Monitoring Reports, Monthly O&M Reports, Land Use Control Inspection Reports, etc.).

Site	Performance Objective	Performance Period*	Performance Standard
SR169	SC (Well Abandonment)	Four (4) years	AF, USACE, and regulatory approval of SC documentation (e.g., Site Closeout Report, No Further Action Explosive Safety Submission, and Well Abandonment Report).
SR170	Record of Decision/Decision Document (ROD/DD)	Four (4) Years	AF, USACE, and regulatory approval of/signatures on ROD/DD.
SR170A	LTM in accordance with the approved ROD/DD	Through the duration of the PoP	AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).
SS015	Final ROD Upon achievement of LUCIP, conduct RA-O in accordance with the Interim Action ROD/DD throughout the duration of the PoP	Six (6) years	AF, USACE, and regulatory approval of ROD/DD (i.e., Air Force and regulatory signatures on Revision 02 ROD/DD). AF, USACE, and regulatory approval of RA-O documentation (e.g., Land Use Control Inspection Reports, etc.).
SS026	Final ROD Upon achievement of LUCIP, conduct RA-O in accordance with the Interim Action ROD/DD throughout the duration of the PoP	Six (6) years	AF, USACE, and regulatory approval of ROD/DD (i.e., Air Force and regulatory signatures on Revision 02 ROD/DD). AF, USACE, and regulatory approval of RA-O documentation (e.g., Land Use Control Inspection Reports, etc.).
TA523	LTM in accordance with the approved ROD/DD	Through the duration of the PoP	AF, USACE, and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).
TS183	RA-O with optimization in accordance with the approved ROD/DD	Through the duration of the PoP	AF, USACE, and regulatory approval of RA-O documentation (e.g., Annual Groundwater Monitoring Reports, Monthly O&M Reports, Land Use Control Inspection Reports, etc.). AF and USACE approval of Performance Model Evaluation Report.

Site	Performance Objective	Performance Period*	Performance Standard
TU204	SC	Five (5) years	AF, USACE, and regulatory approval of SC documentation (e.g., Site Closeout Report and Well Abandonment Confirmation Report).
TU205	Final ROD Upon achievement of LUCIP, conduct RA-O in accordance with the Interim Action ROD/DD throughout the duration of the PoP	Six (6) years	AF, USACE, and regulatory approval of ROD/DD (i.e., Air Force and regulatory signatures on Revision 02 ROD/DD). AF, USACE, and regulatory approval of RA-O documentation (e.g., Land Use Control Inspection Reports, etc.).
TU233	SC	Seven (7) years	AF, USACE, and regulatory approval of SC documentation (e.g., Site Closeout Report and Well Abandonment Confirmation Report).

* The Performance Period is from the date of award of the first performance AFCEC Sub-CLIN.

1.3.2 Additional Scope Discussion and Limits

In addition to the requirements identified in Table 1, the Contractor shall be responsible for:

a. Establishing a quality assurance/quality control (QA/QC) process to ensure documents are of an acceptable quality and do not contain typos, formatting issues, contradictory information in tables, texts, and figures, etc.
b. Contaminants for which there are promulgated federal, state, or local standards.
c. Additional sites or work which may be added to the contract via modification if AFCEC determines during the PoP, that clean-up needs to be accomplished at a site where Per- and polyfluoroalkyl substances (PFAS) are present, and there is a promulgated State Maximum Contaminant Level (MCL) that is approved for use by the DoD as an Applicable or Relevant and Appropriate Requirement standard.
d. Conducting 1,4-Dioxane investigations as described in "Interim Air Force Guidance on Sampling and Response Actions for 1,4-Dioxane at Operational and Base Realignment and Closure Installations," dated 24 May 2013.
e. Management and disposal of investigation-derived waste (IDW) media associated with PFAS in accordance with AF Guidance Memorandum "Updated Interim Guidance on Destruction or Disposal of Materials Containing Per- and Polyfluoroalkyl Substances in the United States" dated 20 February 2026 (or the most recent and applicable ASD or SAF/IEE guidance on PFAS destruction or disposal of Materials containing PFAS), and Section 4.14.2 of this document.
f. The Contractor shall analyze IDW for PFAS using EPA Standard Method 1633 as required for waste acceptance. This includes, but is not limited to, sites:

    - Eglin AFB: CF288, FT028, LF003, LF005, SS086, SS281, SS283, and ST069.
    - Hurlburt Field: CG219, ST123, and SS125.

- Tyndall AFB: DA046, FT016, FT017, LF006, OT029, OW217, SR169, SS015, SS026, TA523, TS183 and TU205.

g. Ensuring that remedial actions do not negatively impact the distribution of any other contaminants and/or emerging contaminants (e.g., PFAS, 1,4-dioxane).
h. Eglin AFB: Providing one (1) 4'x6' full color printed dry-erase laminated wall maps (one for Eglin Main Base and one for Eglin Reservation) and one (1) 3'x5' full color printed dry erase laminated wall map for Duke Field twice during the contract Period of Performance (PoP) (approximately FY29 and FY33). The costs for the maps shall be proposed as part of the project management plan AFCEC Sub-CLIN. The Installation will provide GIS files for printing.
i. Hurlburt Field and Tyndall AFB: Providing two (2) 4'x6' full color printed dry-erase laminated wall maps twice during the contract PoP (approximately FY29 and FY33). The costs for the maps shall be proposed as part of the project management plan AFCEC Sub-CLINs. The Installation will provide GIS files for printing.

The Contractor shall NOT be responsible for:

j. Reasonably unanticipated contaminants at sites identified in Table 1 (e.g., previously undetected mercury within a TCE plume); however, Contractors shall be responsible for reasonably anticipated contaminants (e.g., vinyl chloride in a TCE plume).
k. Remediation or treatment of contaminants for which there are no promulgated federal, state, or local standards or AF agreements at the time of contract award, unless included via modification.
l. Official regulatory changes occurring after contract award, as documented in Administrative Code, laws, and regulations, e.g., decrease in residential Soil Cleanup Target Levels, Groundwater Cleanup Target Levels, etc.
m. Sites not identified in Table 1.
n. Sites containing radiological waste.
o. Remediation of sites with Munitions and Explosives of Concern. MEC includes but may not be limited to: Unexploded Ordnance (UXO), as defined in 10 United States Code (U.S.C.) 101(e)(5); Discarded Military Munitions (DMM), as defined in 10 U.S.C. 2710(e)(2); or Munitions Constituents (MC), as defined in 10 U.S.C. 2710(e)(3), present in high enough concentrations to pose an explosive hazard.

2.0 APPLICABLE DOCUMENTS

The Contractor shall identify and comply with all applicable federal, state, and local statutes; DoD and AF instructions, manuals, handbooks, regulations, guidance, and policy letters (including AF policy and guidance for IRP and MMRP); Executive Orders (EOs), American Society for Testing and Materials (ASTM) Standards, American Petroleum Institute Codes, National Fire Protection Association (NFPA) Standards, Association for Materials Protection and Performance, National Electric Codes (NEC), Uniform Fire Codes, and International Building Codes, including all changes and amendments in effect on the date of issuance of this contract. It is the Contractor's responsibility to identify and comply with all applicable requirements. In addition, the Contractor shall refer to the current versions of the DoD Policy and Guidelines for Acquisitions Involving Environmental Sampling or Testing and the United States AF Construction Management Implementation Guide.

The Contractor shall identify and comply with all applicable documents for the Installations including RODs, ROD Amendments, ESDs, RCRA Permits and subsequent modifications, documents, the Endangered Species Act, other DDs, Deeds, waste management guidance, and conveyance notices.

3.0 GOVERNMENT FURNISHED INFORMATION AND PROPERTY

Government Furnished Information (GFI) is contained in the Administrative Record (https://ar.cce.af.mil/) or listed in Enclosure 2. The documentation provided represents the most recent and appropriate documentation available for the Installation(s) and sites identified in this PWS. Electronic format is not guaranteed.

The Contractor shall properly account for and manage all new and existing Government Furnished Property (GFP) procured and utilized at the Installations as-is where-is, in accordance with the Federal Acquisition Regulation (FAR). All Real Property installed during the contract shall be turned over to the Government consistent with procedures identified in Section 9.3.2.

The Contractor shall be responsible for providing all other supplies and equipment, not already installed and not listed in Enclosure 3, that are required to achieve the POs of this contract. All AF-owned property, including real property used for remediation purposes, must be maintained by the Contractor in accordance with applicable maintenance requirements and usability for the intended purpose. The Contractor is responsible for disposal of unneeded, unusable, or obsolete GFP as required, and transfer of remaining GFP to the Government at the end of the contract PoP. Prior to the disposal of excess or unserviceable equipment listed in Enclosure 3, the Contractor shall coordinate activities with the Contracting Officer (CO/KO) for disposition instructions.

4.0 MANAGEMENT, PLANNING, AND REPORTING REQUIREMENTS

The Contractor shall implement a full range of environmental remediation activities as required to meet POs of this contract and in accordance with all applicable or relevant and appropriate federal, state, and local laws and regulations; DoD policies; and Installation-specific orders, agreements, or rules. The Contractor shall supply all labor, equipment, and materials necessary to accomplish the work through the entire PoP of the contract. The Contractor shall perform management and planning functions, including performance measurement and fund status reporting.

The PMP, IMS, and MPS documents shall be fully integrated and consistent. Consistency shall be maintained throughout the PoP by fully implementing programmatic change control processes compliant with EC 5.2.1 (Execution of Change Control Boards) and PMP guidance. It is the Contractor's responsibility to clearly demonstrate an applied understanding and compliance with ORC requirements, application of guidance/requirements, and consistency between the PMP, IMS, and MPS. The Contractor shall create the IMS and MPS files and deliver them as separate files as required.

The Contractor shall work closely with the Project Manager (PM)/COR to ensure effective communication is maintained to execute the Contract in accordance with this PWS and other contract requirements. Project management coordination shall include, but not limited to, contract option AFCEC Sub-CLIN reviews to confirm the contract option modification is in alignment with the IMS/MPS, reviews of performance progress, and other issues identified by the PM/COR.

4.1 Project Management Plan

The Contractor shall develop and maintain a detailed PMP. The PMP shall specify the project's resources and tasks corresponding to the AFCEC CLINs/Sub-CLINs for this contract as required for the planning, execution, control, and completion of the stated POs. At a minimum, the PMP shall include the following sections:

- Florida Panhandle ORC Group management structure, points of contact, etc.
- Technical approach, risk register, and risk management plan for achieving the POs in accordance with the PWS,
- Exit strategies and cost benefit analysis
- Cost/schedule baseline for the Contract,
- Organization and integration of the project team,
- Project controls, and change management,
- Transitional activities,
- Risk management,
- Schedule management
- Communication management,
- Quality management,
- Health and safety management
- Security management
- Resource management
- Subcontractor management
- Procurement management

The aforementioned PMP sections are not intended to be generic narratives; each section shall include the specific details for how each topic will be fully implemented for this contract including references to thresholds, mitigations, procedures, graphs, charts, etc. Procedures for execution of all tasks included in this PWS shall be included in the project Quality Management Plan, attached to the PMP. The Contractor is responsible for complying with the AFCEC/USACE PMP Guidance and standard industry practice. Clarification on PMP content and the level of detail required to address the program shall be provided by the PM/COR. The Contractor shall implement an effective Configuration Management/Change Control process for gathering and analyzing project data to keep costs and schedules on track. The functions of project controls include initiating, planning, monitoring, and controlling, communicating, and closing out project costs and schedule. Ultimately, project controls are repeatable processes for measuring project status, forecasting likely outcomes based on those measurements and then improving project performance if those projected outcomes are unacceptable.

In addition to narratives in the PMP for the previously listed sections, at a minimum, the following detailed plans shall be included in the PMP as attachments:

- Configuration management, Change management, and change control plan
- Risk management plan
- Basis of Schedule
- Schedule management plan
- Communication management plan

- Quality management plan
- Health and safety management plan
- Subcontractor management plan
- Resource management plan
- Security management plan
- Training management plan
- Investigation-derived waste management plan
- Quarterly Project Status Summary

The Contractor is responsible for complying with the ORC PMP Guidance in effect at the time of ORC issuance, as well as standard industry practices. Clarification on PMP content and the level of detail required to address the ORC program shall be provided by the COR.

The PMP shall demonstrate a comprehensive decomposition of each work package/PO deliverable and exhibit a clear and concise correlation between the PWS, IMS, and MPS. The Contractor is responsible for complying with the guidance for the development of CLIN Structures, IMS, and MPS per the ORC PMP Guidance at the time of ORC issuance.

Revision 00 of the PMP shall be submitted in accordance with Table 1. Revision 00 of the PMP and subsequent revisions shall be subject to AF and USACE review and approval. Revision 01 of the PMP shall be due within fourteen (14) calendar days of receipt of AF and USACE comments on Revision 00. The Contractor shall maintain the PMP throughout the duration of the contract, utilizing dated page changes and track change deletions and insertions (electronic copies) as practicable. Whole document PMP updates during the life of the ORC may be necessary based on the accumulation of small incremental changes or significant changes (e.g., contract requirements, technical approaches, risk and issue management, or key personnel). The Contractor shall prepare two whole document updates during the PoP of the ORC. The AF and USACE will determine when PMP updates are warranted.

4.2 Schedule and Planning Requirements – Integrated Master Schedule

The Contractor shall prepare and submit an IMS in both hardcopy and electronic format (Microsoft Project and Adobe Acrobat portable document file). The IMS will be finalized during the development of the PMP, and the Contractor shall update it monthly.

The following are minimum AF requirements for the IMS:

- Present a realistic sequence and timing of all activities and documents necessary to demonstrate achievement of the PO within the PP. The IMS shall demonstrate full compliance with the PWS, including achieving POs within the required PP.
- Utilize a realistic calendar (i.e., work week of five, eight-hour days, no submittals on Federal holidays, etc.), appropriate logic ties, clearly defined constraints, and identify key points where risk mitigation/contingency actions may need to be taken.
    - The IMS shall be organized and aligned with the USACE CLINs and AFCEC CLIN/Sub-CLIN structure and include but is not limited to: Installation Name: Identify EESOH-MIS Installation Name per Table 1. The Installation name must be included in every line of every AFCEC Sub-CLIN.

- Site Number: Identify EESOH-MIS Site ID per Table 1 and Site Alias, if applicable. The EESOH-MIS Site ID must be included on every line of the IMS where applicable.
- USACE CLIN: Identify USACE CLIN per Section B of the contract. The USACE CLIN must be included on every line of the IMS, as appropriate.
- AFCEC CLIN: Identify AFCEC CLIN per Section B of the contract. The AFCEC CLIN must be included on every line of the IMS, as appropriate.
- AFCEC Sub-CLIN: Identify AFCEC Sub-CLIN per Section B of the contract. The AFCEC Sub-CLIN must be included on every line of the IMS, as appropriate.

  Note: AFCEC Sub-CLINs for compliance activities (routine regulatory requirements to comply with binding agreements) are denoted as ####CX, and AFCEC Sub-CLINs for performance activities (remedial advancement or progress towards the PO) are denoted as ####AX. For example, for POs of RA-O with Optimization, the Performance Goal "A" AFCEC Sub-CLINs are specifically for reporting progress in achieving the performance goal identified in the performance model (separate reports for each year). This requires a separate report identifying the most recent result for the performance indicator(s), usually a COC concentration, and how that compares with the projected value of the performance indicator in the performance model. The "C" AFCEC Sub-CLINs are specifically for operating the remedy and reporting all required results, such as COC concentrations, geochemical, groundwater elevations, etc.
- Milestone Payment Identification Number (MPS #)
- AFCEC CLIN/Sub-CLIN Task Description: Include a detailed description of all activities (e.g., meetings, permitting, site access, work plans, mobilization, field work, documents, reviews, coordination with stakeholders, etc.) associated with achievement of the PO, and a clear indication of regulatory, i.e., CERCLA/RCRA/State Program phase completions (e.g., RIP Achieved, RC Achieved, etc.) and PO achievement.
  - Activities should not be grouped together; every activity must have a separate entry. For example, the IMS must show separate activities for sample collection, sample analysis, data validation, Environmental Resources Program Information Management System (ERPIMS) upload, injections (mobilization, substrate injection, demobilization), and well installation (mobilization, drilling/well completion, demobilization).
- Start and Finish Dates: Planned and Actual document Start dates and Finish dates for each required activity and document, including appropriate durations and Government and regulatory review periods, in accordance with Section 7.2 of the PWS.
  - Include an obligation date, notice to proceed date, or projected award date as the first activity for each AFCEC CLIN/Sub-CLIN. Ensure that the obligation/notice to proceed date is in the same fiscal year (FY) as the first line item of work.

        - Include a clearly identified final field work (e.g., FINAL FIELD ACTIVITY) Start date and Finish Date for each site (i.e., indicate when the final set of field activities, such as injections, groundwater sampling, or others, will be complete).
    - Milestone Payment Amount: Include negotiated amount consistent with the approved MPS, ensuring the sum of all milestone payments equals the value of the AFCEC CLIN/Sub-CLIN per Section B of the contract. Include both summary and non-summary payments.
    - Percent Complete: Record completion status of all activities and documents as approved by the COR.
    - Predecessor and Successor: Define relationships and constraints associated with activities and documents.

The Contractor shall prepare and maintain the IMS in accordance with the ORC PMP Guidance and USACE ER 1-1-11 (Project Schedules). . The Contractor shall maintain and submit an IMS monthly in electronic format (i.e., Excel, PDF, and native file formats) in accordance with the requirements above and include updates to progress and approved changes (e.g., Government or regulatory review periods, technical approaches, milestone payment updates, or contract requirements). The IMS shall be submitted electronically to the Contractor's ORC document repository and in accordance with instructions from the COR.

USACE requires the use of Oracle Primavera P6 software for schedule development, and project management and reporting. The AF requires schedules to be submitted in MS Project format. The Contractor shall prepare and manage the IMS using Primavera P6 and convert the IMS to MS Project format using the export functionality in Primavera P6 or other method. The Contractor shall review the exported MS Project file and ensure all required detail is present in the MS Project file.

The following are minimum USACE/AF requirements for the IMS:

- Presents a realistic sequence and timing of all activities and documents necessary to demonstrate achievement of the PO within the PP. The IMS shall demonstrate full compliance with the PWS, including achieving all POs within the required PP.
- The IMS shall include the entire ORC scope consisting of all work steps, elements, activities compliant with PWS requirements, execute technical approaches, mitigate risks, etc. required to achieve all objectives in this ORC. The IMS shall include all planning and lead tasks, e.g., procurement, reviews, setup, etc.
- The schedule shall utilize realistic and appropriate calendars (e.g., work week of five eight-hour days), appropriate logic ties, constraints shall be clearly defined, and the schedule shall identify key points where risk mitigation/contingency actions may be taken.
- The IMS shall be updated monthly and provided to the PM/COR and AF RPM with each CPSMR. Each status shall clearly indicate which activities have been updated using unique highlighting of activities (e.g., completed tasks-green, delayed/behind schedule-

yellow, critical-red). Updates shall be described in a monthly IMS update narrative report in the CPSMR.

- The IMS monthly update Narrative Report shall include at a minimum: reporting period, summary of progress, planned vs actual progress, milestones achieved upcoming activities, variances, challenges/risks/issues, proposed schedule modifications, etc.

4.3 Milestone Payment Schedule

The Contractor shall prepare and submit an IMS, from which they will extract the information required to generate an MPS and submit them as two separate files. NOTE: The MPS is not part of the proposal. Award of the contract does not equate to final acceptance of the IMS. The IMS and MPS, including payment milestones and percentages, will be discussed and agreed upon among the Government and Contractor during the review of the initial PMP/IMS/MPS and approved by the COR.

The following are minimum AF requirements for the MPS:

- Present appropriate milestone payments considered integral and necessary to the achievement of the POs.
- The interim and final milestone payments to performance models as described in Section 9.1.3.1 (also see Sections 1.2.4 through 1.2.5).
- Include a reasonable number of milestone payments per AFCEC CLIN/Sub-CLIN based on the scope and anticipated duration to achieve AFCEC CLIN/Sub-CLIN objective and/or PO.
- Align with the AFCEC CLINs/Sub-CLINs in Section B of the award document and includes the following columns:
    - Installation Name: Identify EESOH-MIS Installation Name per Table 1.
    - EESOH-MIS Site ID: Identify EESOH-MIS Site ID per Table 1 and Site Alias, if applicable.
    - USACE CLIN: Identify USACE CLIN per Section B of the contract.
    - AFCEC CLIN: Identify AFCEC CLIN per Section B of the contract.
    - AFCEC Sub-CLIN: Identify AFCEC Sub-CLIN per Section B of the contract.

      Note: AFCEC Sub-CLINs for compliance activities (routine regulatory requirements to comply with binding agreements) are denoted as ####CX, and AFCEC Sub-CLINs for performance activities (remedial advancement or progress towards the PO) are denoted as ####AX. For example, for POs of RA-O with Optimization, the Performance Goal "A" AFCEC Sub-CLINs are specifically for reporting progress in achieving the performance goal identified in the performance model (separate reports for each year). This requires a separate report identifying the most recent result for the performance indicator(s), usually a COC concentration, and how that compares with the projected value of the performance indicator in the performance model. The "C" AFCEC Sub-CLINs are specifically for operating the remedy and reporting all required results, such as COC concentrations, geochemical, groundwater elevations, etc.

- Milestone Payment Identification Number: Include a unique number assigned to each milestone payment for tracking purposes.
- Milestone Payment Description: Include a detailed description of a definable and measurable step considered integral and necessary to the achievement of the AFCEC CLIN/Sub-CLIN objective and/or PO.
- Milestone Payment Amount: Include negotiated amount, ensuring the sum of all milestone payments equals the value of the AFCEC CLIN/Sub-CLIN per Section B of the contract.
- Milestone Payment Percentage: Include percentage of the milestone payment in relation to the total AFCEC CLIN/Sub-CLIN value. The final payment milestone(s) within an AFCEC CLIN/Sub-CLIN demonstrating achievement of the AFCEC CLIN/Sub-CLIN objective must be a minimum of 20% of the total AFCEC CLIN/Sub-CLIN value. This may include both the AF and USACE-approved and the regulator-approved versions. Milestones should not be front-loaded but instead be commensurate with the work completed.
- Completion Date: Document completion date for each milestone payment consistent with the Finish date presented in the IMS.
- Percent Complete: Identify completion status (0% or 100%) of all milestone payments as approved by the COR.
- Invoice Number: Clearly indicate the invoice number associated with the milestone payment as approved by the COR for the purposes of tracking payment. This information can be completed as invoices are prepared.

- Exclude unacceptable milestone payments representing a “progress” payment or a monthly payment for level of effort expended, including:
  - Preparation and/or submittal of documents
  - Site mobilization/demobilization (unless exempted by CO/KO)
  - Accomplishment of field activities, including the following:
    - Substrate/chemical injection
    - Injection letter work plans
    - Injection summary memoranda
      - Field documentation tech memos
      - Semi-annual cap inspection tech memos
      - Quarterly and monthly Land Use Controls (LUC)/LTM inspection reports
      - Quarterly discharge reports
      - Construction bond
      - Revision 00 reports
      - Well construction logs

        - Payments of less than 2% of AFCEC Sub-CLIN cost
    - Submittal of a monthly status
    - Management and overhead costs (e.g., program/project management, monthly reporting, etc.)
    - Allocation of PMP, Base-wide Quality Program Plan (QPP), or other Base-wide costs to specific sites
    - Multiple revisions of a document before USACE/AF/regulatory approval

Refer to the ORC PMP Guidance, Section 4.2, for more detailed information on common errors in the preparation of the MPS.

The Contractor shall maintain and submit an MPS monthly, in electronic format in accordance with the requirements above and include updates to progress (e.g., Percent Complete, Invoice Number; see Section 4.4 Cost and Status Reporting). The MPS shall be submitted electronically to the Contractor's ORC document repository and in accordance with instructions from the COR. The Contractor shall prepare and maintain the MPS in accordance with the CLIN, IMS, and MPS Guidance.

Milestone payments within an AFCEC CLIN/Sub-CLIN may be revised in response to changes in the approach for achievement of the AFCEC CLIN/Sub-CLIN objective without a contract modification so long as the changes do not impact the total value or objective of the AFCEC CLIN/Sub-CLIN. All changes to the MPS, with the exception of tracking invoicing of completed milestone payments, must be approved by the COR.

Completion of milestones shall demonstrate that payment is appropriate and warranted. COR approval of the documentation supporting the completion of the milestone is required for payment. In general, milestones are considered complete upon approval by AF/USACE (and regulators, where required). Where regulatory approval or acceptance is required for this documentation, AF and USACE approval will occur following regulatory approval of the documentation. Approval occurs upon final signature of documents requiring signature by the AF and/or regulators. The COR will take into consideration the appropriate approval of necessary documentation by regulators consistent with the applicable regulatory drivers of this PWS. The Contractor may propose a revision of the milestones to reflect the PMP and provide for interim milestones. Interim milestones will only be accepted if they represent significant progress toward milestone completion, and completion of these interim steps can be measured and demonstrated. Payments will be tied to the successful completion of major milestones or an interim milestone plan approved by the Government through the COR. To that end, all proposed interim milestones should be associated with easily demonstrated metrics tied to performance measurements (e.g., Government approval of a Revision 01 report, regulatory approval of a Revision 02 such as semi-annual and annual groundwater monitoring reports, RI Reports, or RODs). All milestones must have a defined means for demonstrating completion to facilitate certification.

Milestones must represent tangible progress toward achieving the PO. In general, progress payments are disallowed. Progress payments include payment for interim steps needed to achieve the PO. For example, milestones for conducting monthly landfill inspections would represent progress payments. Acceptable milestones would be a semi-annual or annual LTM Report of the results of the landfill inspections.

For milestones where regulatory approval is required and cannot be obtained, the AF and USACE will evaluate the Contractor's supporting documents to determine if they are legally and technically acceptable to warrant payment for achieving that milestone.

The Contractor is limited to one invoice submitted to the AF/USACE per month. The invoice must itemize the milestone payments for each AFCEC CLIN/Sub-CLIN associated with the invoice. The Contractor will not receive payment until milestones are achieved in accordance with the MPS. The AF and USACE will not approve partial payments.

Note that AF/USACE approval of the first version of a document that will be submitted for regulatory review is a valid milestone. AF/USACE and regulatory approval of the final version of that document is also an acceptable milestone.

4.4 Cost and Status Reporting

The Contractor shall prepare and submit a monthly Contractor's Progress, Status, and Management Report (CPSMR). The CPSMR shall be used to review and evaluate the overall progress of the project, along with any existing or potential problem areas. The report shall be prepared and submitted in an electronic format to the Contractor's ORC document repository and/or in accordance with the CPSMR Template. The CPSMR shall also be used to indicate whether efforts for each site are on target to meet the PO. The Contractor shall submit an updated IMS and MPS with the CPSMR each month.

4.4.1 Invoices

Contractor shall submit identified progress payment requests upon accomplishing the Project Milestones presented in the MPS. The MPS, outlined by the Government, shall form the basis for payment for each AFCEC Sub-CLIN. The Contractor is limited to one invoice per month. Months when no payment milestones are achieved will have no invoice.

The Contractor invoices shall include payments for all milestones that were satisfactorily completed during the billing period. It is understood that some of the Project Milestones presented in the Task & Milestone Schedule may be eliminated or modified based on how the Contractor proposes to proceed to achieve Project Completion efficiently. Acceptance and approval by the PM/COR shall constitute acceptance of the work associated with each item of the MPS. A copy of the invoice will be provided to the PM/COR, TM, and AFCEC PM.

The Contractor shall submit a draft invoice package to the PM/COR and AFCEC RPM for concurrence that all performance standards and quality elements have been met. Each invoice package shall include a draft ENG-93, copies of Government and regulatory approval documentation, i.e., letter or email, updated MPS with payment milestones on the invoice highlighted, and AFCEC Sub-CLIN-specific spreadsheet that summarizes pricing, invoiced amounts, USACE CLIN, AFCEC CLIN, and other detail required by the PM/COR. Upon Government approval, the Contractor shall submit via email the ENG-93 to the PM/COR and AFCEC RPM.

A copy of the electronic ENG Form 93 may be found at the following website http://www.publications.usace.army.mil/USACEPublications/EngineerForms.aspx.

The PM/COR shall identify the date requirement for submitting the final invoice for the contract, if not completed in advance of funds expiration/PoP. Typically, the final invoice shall be submitted to USACE no later than 31 July of the canceling funds year. Non-canceling funded

AFCEC CLINs/Sub-CLINs may have additional time for final invoicing, based on PM/COR approval. Any AFCEC CLIN/Sub-CLIN with canceling year funds where the PO will not be achieved must be modified to de-obligate unachieved payment milestones in time for the Contractor to submit the final invoice by 31 July. The Contractor is responsible for identifying payment milestones that will not be achieved and initiating the modification process at least 60 days before the final invoice for canceling year funds is due.

4.5 ORC Document Repository

The Contractor shall maintain a document repository for all ORC documents. The repository is intended to be a single access point for all ORC documentation. It shall be accessible to stakeholders during the life of the ORC. The Contractor shall notify AFCEC, COR, and Installation RPM(s) when data is included in the repository. At contract close-out, all repository documents will be transferred to digital video disc media and delivered to AFCEC and USACE.

The Contractor shall create and maintain a Master Document List (MDL) that includes all documents prepared during this contract, whether the document is a deliverable or not. The Contractor shall maintain the project documents for the duration of this contract and deliver to the AF no later than 90 calendar days prior to PoP expiration.

4.6 Meeting and Conference Requirements

4.6.1 Meeting/Teleconference Support

The Contractor shall participate in post-award meetings, Project Management Review (PMR) meetings, and teleconferences with the AF and USACE as necessary to achieve the POs in this PWS. The Contractor shall coordinate meetings, provide logistical support (e.g., facilities, audio/visual), create and present materials, and lead technical discussions. At a minimum, the Contractor shall participate in bi-weekly teleconference status meetings; in person or more frequent meetings may be required for critical work activities or data discussions. Also, other periodic (e.g. quarterly) in-person meetings shall be required, as necessary.

The Contractor shall also attend and/or support meetings and teleconferences to discuss technical or regulatory issues, project progress, and status with the AF and regulatory agency representatives. Specifically, the Contractor shall host an internal kick-off meeting with the AF and USACE within fifteen (15) calendar days from contract award. In keeping with the AF's commitment to the regulators, the Contractor shall host a kick-off meeting with the AF and regulators within thirty (30) calendar days from contract award. At a minimum, the following topics will be discussed at the regulatory kick-off meeting: project schedules for field work and deliverables; achieve a mutual understanding of expected review times; identify standards, criteria, and guidance to be used during site characterization and remediation; identify potential points of compliance; identify regulatory processes and other applicable state agency programs (i.e., Water Protection, Department of Health, Air Pollution, etc.); identify site constraints and dependencies (i.e., site access, right of entry, security, ongoing site activities, topography, slope stability, etc.); and determine potential community interests.

The Contractor shall attend and provide both technical and logistical support for quarterly Tier I/Tier II partnering meetings, and teleconferences. Teleconferences shall also be required to discuss progress and any technical or management issues. Also, other periodic meetings/teleconferences shall be required, as necessary. Currently, regulatory meetings occur on a monthly basis for Eglin AFB and Hurlburt Field and quarterly for Tyndall AFB. However,

the frequency of meetings may change based on the status of the environmental restoration program. The AF will be present for all technical and public meetings with the regulatory agencies; however, the Contractor shall coordinate the meetings, provide logistical support (e.g., facilities, audio/visual), create and present materials, and lead technical discussions. The Contractor must have the ability to present data concerning the nature and extent of contamination, including source types and affected media, site geology, site hydrogeology, and biological, geochemical conditions, and monitoring points, in a three-dimensional representation. The Contractor shall clearly identify themselves as "Contractors" in all situations involving stakeholders. The Contractor shall prepare and submit for AF and USACE review and concurrence any presentation materials and agendas for meetings no less than one week (5 working days) prior to the event. The Contractor shall prepare minutes for all meetings attended within 14 calendar days following the event. Travel to/from the Installation and to other continental U.S.) locations for meeting attendance, briefings, and/or presentations may be required to support this remedial action. These activities are considered incidental to the effort required and shall not be included for separate milestone payments.

The AF has authority for all regulatory interactions pursued on behalf of the AF, Tyndall AFB, Eglin AFB, and Hurlburt Field. The Contractor shall not contact any regulatory agency without prior notification and approval by the Installation RPM(s).

4.6.2 Public Meetings and Hearings

The Contractor shall support all community involvement requirements to meet CERCLA, RCRA, and other regulatory requirements, including public meetings, public notices, RAB meetings, Technical Working Groups, Community Advisory Group meetings, public comment periods, and responsiveness summary preparation.

Community relations activities will be the responsibility of Tyndall AFB, Eglin AFB, and Hurlburt Field. The Contractor shall support those activities, such as public meetings, in coordination with the AFB, by providing necessary existing technical information to the Installations. The Contractor shall not discuss the program with anyone that does not have an official "need to know" for the purpose of task completion. The Contractor shall not provide any press releases relating to this work without express written authorization from the Installations and AFCEC.

Eglin AFB, Hurlburt Field, and Tyndall AFB previously have had RAB meetings that are currently adjourned. Since these installations have no active RAB, the Contractor shall provide the support required to reassess community interest every 24 months and reactivate or establish the RAB(s), as necessary per AFI 32-7020 requirements. In coordination with AFCEC and the Installation RPM(s), the Contractor shall attend teleconferences as necessary with the assigned Public Affairs Officer (PAO) to ensure the PAO is fully aware of all ongoing activities, public outreach status, compliance with applicable regulations, and possible issues that might impact the AF and its public image. The Contractor shall coordinate with the Installation RPM(s) before any contact with the PAO.

Examples of Public Affairs requirements include the presentation of technical information and logistical support, such as advertising, audio-visual materials, handouts, reports, recordings, verbatim transcripts, poster boards, slides, synopses, etc., for events and/or meetings in support of the Government's position. All reports and other information generated under this contract

shall become the property of the Government, and distribution to any other source by the Contractor is prohibited unless authorized by the COR.

The Contractor shall use staff trained in public affairs to complement the technical staff on the project. These trained staff members must attend all meetings with the public, along with the appropriate technical staff. The credentials of the trained staff must be submitted to and approved by the COR in advance of any meeting with the public. The trained staff shall demonstrate effective public communications skills and experience in building relationships with stakeholders involved in cleanup activities or similar efforts.

The Contractor shall research, coordinate, and provide responses to short-notice internal and external requests for information, such as congressional inquiries and media requests, as needed by the PAO or other applicable action officers. These inquiries require the Contractor to provide the AF factual and responsive information within the time period designated by the RPM at the time of request.

4.6.2.1 Community Involvement Plan (CIP) Update

The Contractor shall prepare a CIP or Update the existing CIP, in accordance with Table 1, to support the Installation's community involvement program (see Enclosure 4). The CIP or Update shall address how the AF will conduct public outreach about cleanup activities and how community members can engage and participate in decision-making throughout the cleanup process. One CIP or Update is prepared for each Installation. A consolidated CIP or Update is prepared for the parent Installation and any applicable Geographically Separate Units.

The Contractor is required to prepare a CIP or update the existing CIP at each Installation. CIPs shall be prepared as early as possible in the CERCLA process, specifically prior to the RI phase. CIP updates are completed after the DD/ROD is signed and every three (3) years thereafter. CIP updates are also required for Removal Actions with planning periods greater than six (6) months and removal activities lasting more than four (4) months.

4.7. Spatial Data (Map) Requirements

The Contractor shall NOT establish new Geographic Information Systems (GIS).

In furtherance of the environmental construction or restoration effort, the Contractor shall provide geospatial data and maps of Installation features (historical, existing, or planned) that are altered or constructed as required to achieve the POs of this contract.

The Contractor shall provide data to update the GIS and/or computer-aided design and drafting (CADD) files as required to achieve the POs of this contract. Source data and product data remain the property of the U.S. Government.

The Contractor shall also ensure GIS data is submitted in a file geodatabase that meets the current AF adaptation of Spatial Data Standards for Facilities, Infrastructure, and Environment (SDSFIE) within the AF GeoBase program. The Contractor shall consult with each Installation RPM and/or Installation Geospatial Integration Office (GIO) office to ensure CADD and GIS data are compatible with each Installation's requirements.

All products associated with this contract which provide a map representation of the location of Installation features (historical, existing, or planned) including Installation maps, site plans, area development plans, walls-out as-built depictions, or other related overhead (plan) views of an

Installation (partial or entire) must adhere to the requirements detailed below. (NOTE: This requirement does not currently involve walls-in facility floor plans or interior renderings.)

All maps and associated data must comply with the latest version of SDSFIE available from the SDSFIE website: https://www.sdsfie.mil/ and SAF/IEE Guidance Memorandum for Data Visualization Standards for Environmental Documents. Questions can be sent to the AFCEC Geospatial Engineering Office (GEO) at AFCEC.GEO.Workflow@us.af.mil or (210) 925-4620. This data will be organized using the current version of the standard approved by the Headquarters AF GeoBase Office as the functional lead for Installation mapping and visualization. The SDSFIE will determine file and feature class identification and definition, attribution, and valid domain values. When any geospatial information collected as a result of the contract includes information identified in the Common Installation Picture or recognized Mission Data Set (MDS), the Contractor will deliver data consistent with the established requirements for the data and ensure functionality with the receiving system. Information must be collected at no less than 1:1200 scale. Spatial data will meet or exceed National Map Accuracy Standards at those scales. Metadata will be provided and use Federal Geographic Data Committee Content Standards for Digital Geospatial Metadata for organization.

As a requirement of this contract, the Contractor shall provide to the Government all shape files, file geodatabases, map exchange files, and Geospatial data accumulated as a result of the investigation recorded on compact discs (CDs; FedEx for delivery on the next business day) and also electronically. Geospatial data must be delivered in a geo-referenced GIS format (feature-based file structures with one-to-one cardinality between spatial records and attribute records), including Environmental Systems Research Institute's shapefile and geodatabase formats. All attribute data as specifically outlined in the contract must be included either in the GIS data file or as a separate table with a SDSFIE key variable that may be used to relationally join the separate table with the GIS data file. All geospatial data must be delivered in the North American Datum 1983 (NAD83) projection, State Plane Coordinate System, using feet or metric coordinate units. For all locations within the Restricted Area, Universal Transverse Mercator coordinates must also be provided. Further guidance on mapping units, coordinate systems, and projections is available from the Installation GIO.

Survey-Grade Global Positioning Systems (GPS) or comparable traditional survey methods will be used to collect geospatial data. The use of survey-grade GPS will depend on the precision requirements of the product data. These requirements will be specified later in this PWS for all contract activities involving geospatial data. In the case of contracts involving utility construction, location and attribute data will be obtained at the time of excavation. Further information about precision requirements should be obtained from the Installation Execution Support (GeoBase) Office.

Source data and product data remain the property of the U.S. Government. The Contractor shall be required to explain and demonstrate the company's process for protecting all geospatial data, including but not limited to geometry, attributes, metadata, topologies, and relational database schemas and operations used in association with this PWS. Further information about security and non-disclosure requirements should be obtained from the Installation GIO. Some Installation map data/source and/or product may be considered by the Government to be Controlled Unclassified Information (CUI). The intent of this clause is to prevent the intentional or unintentional dissemination of CUI, including unauthorized access to the source and product data by any entity wishing to do harm to the AF or U.S. Government while the data resides on

the Contractor's computer network. The Contractor is not authorized to release this information to any third party without the explicit consent of the AFCEC GIO or its involved Installation. All source information must be returned to the Government POC or destroyed upon completion of this project. Documentation of information destruction shall be provided to the Installation RPM(s). Special requirements for handling classified map data, if applicable, will be addressed elsewhere in this PWS.

4.8 Information Security

4.8.1 Cybersecurity Standard Operating Procedure

All information created, stored, or transmitted under this contract is the property of the Government. The Contractor will remove all Government information from the Contractor's computers in accordance with AF and DoD policy and provide certification of removal to the CO/KO at the end of the contract.

All subcontractors will adhere to the same cybersecurity standards listed above.

4.9 Notification Requirements

The Contractor shall notify the COR, with courtesy copies to AFCEC and Installation RPM(s), of critical issues that may affect the contract performance and/or human health, safety, and the environment. Verbal notification shall be made immediately, followed by written notification to the CO/KO with courtesy copies to AFCEC and Installation RPM(s) within five (5) working days.

The types of issues that require notification include, but are not limited to, health risks, spills, Notices of Violation (NOVs) (received or anticipated), changes in critical personnel, and Munitions and Explosives of Concern (MEC).

If potential MEC items are discovered during field activities, the Contractor shall stop work and follow the 3Rs or explosive safety (Recognize, Retreat, Report). The Contractor shall report the discovery to base security, the COR, AFCEC, and Installation RPM(s), and implement the appropriate safety precautions. If an item is suspected to be a chemical munition (liquid-filled), the Contractor shall call base security, who will contact Base Explosive Ordnance Disposal (EOD) to assess the item. Field activities shall not continue until clearance is received from the CO/KO. If the Contractor anticipates working beyond the PP to achieve a final milestone due to unanticipated MEC, the Contractor shall submit a PP extension request to the CO/KO and copy the PM/COR at least 60 calendar days prior to the expiration date of the USACE CLIN.

4.10 Permits

The Contractor shall develop, coordinate, apply, comply with, and/or modify all federal, state, local, and other applicable environmental permits, access agreements, easements, licenses, and certificates required to achieve the POs of this contract as detailed in Sections 4.10.1 and 4.10.2. The AF has signature authority for all easement agreements and modifications and/or renewals of new or existing permits, licenses, and certificates required under this contract. The Contractor shall maintain a library of these documents at the Contractor's site office and the corporate facility handling this contract. The Contractor shall comply with all applicable permit conditions.

4.10.1 Environmental Permits

Pursuant to CERCLA (42 U.S.C. 9621(e)), no federal, state, or local permits shall be required for onsite removal or remedial actions. The Contractor must consult with the AF prior to obtaining environmental permits for all on-site and off-site CERCLA activities. For non-CERCLA restoration sites, the Contractor shall assist the AF to comply with all applicable permit conditions, including permit modification requirements and payment of permit fees. If the Contractor has any questions about whether a particular permit may or may not be required, the Contractor shall consult with the AF prior to obtaining the permit. The Contractor shall be responsible for reviewing and responding to site-specific underground utility locating systems request tickets or other dig permit requests that require the identification of subsurface appurtenances and utilities associated with the remediation systems included in this contract. If the Contractor obtains environmental permits, it is responsible for implementing and paying for them. Utility location ticket requests will be sent to the Contractor, and the Contractor will be required to review, respond to, and address all location requirements in accordance with state law and regulations. The Contractor shall maintain all records pertaining to location requests.

4.10.2 Rights of Access to Non-AF Real Property

The Contractor shall prepare documents using AF-provided templates, pay the rent or purchase price and associated expenses for the AF to maintain or modify existing rights of access, or to acquire new rights of access, to non-AF land that the Contractor needs to satisfy the POs of this contract. On the AF's behalf, the designated Installation official will negotiate and sign the documents to obtain or modify the necessary rights of access with technical assistance from the Contractor. Based on the stated right of access needs of the Contractor, the AF will determine which type of right of access (e.g., right of entry, license, easement, lease, or fee acquisition) will be obtained. Technical assistance expected or that may be requested by the AF from the Contractor for rights of access include a description of the amount of real property on which access is being sought, the provision of property surveys, title searches, and title insurance (necessary only for easements, leases for greater than 30 years, or fee acquisitions), environmental site due diligence, appraisals of fair market value, the amount of expected intrusion on the property or property disturbance, cost estimates for restoring the property to its original condition after access is no longer needed, and potential technical witness testimony if the AF must pursue involuntary condemnation through the U.S. Department of Justice in state or federal court. Payment of associated expenses includes costs associated with providing the aforementioned technical assistance, fees for recordation of real property documents associated with acquiring the right(s) of access, costs for payment of or restoring property damage resulting from Contractor's activities on the property on which the right(s) of access were acquired, costs for obtaining "dig safe" or "utility clearance" approvals from appropriate utility and governmental entities, and costs for notifying or communicating with affected property owners regarding rights of access.

4.11 Photo Documentation

The Contractor shall prepare digital photographic documentation, as required to achieve the POs of this contract. The Contractor shall limit photographic documentation of site(s) to building(s) under investigation, field activities, and sample locations. Photographs that include AF personnel, mission-critical assets, or that could reveal troop movements are not permitted. Photography of any kind shall be coordinated through the COR and Installation RPM.

4.12 Remote and/or Austere Sites

The Contractor may be requested to perform work as specified at remote and/or austere locations. The Contractor shall be responsible for all personnel, security, supplies, equipment, and infrastructure (including, but not limited to, potable water, utility systems, housing, dining, transportation, and medical care) when no facilities and services are available. This shall include providing these facilities and services to a limited number of Government personnel or other Contractor personnel (such as Title II personnel) present or visiting to oversee or assess the work.

4.13 Installation/Site Access and Security

The Contractor shall assign one individual as the ORC security POC. The Contractor security POC shall be responsible for managing site/Installation access and security issues for the Contractor and subcontractor personnel. The Contractor security POC shall communicate and coordinate all Installation access needs with the Installation RPM. Access for field activities shall not be presumed by the Contractor and must be coordinated with and verified by the Installation RPM.

The Contractor shall obtain and monitor assigned security badges, and passes used by all applicable personnel for the duration of this contract. It is the responsibility of the Contractor to track and maintain all Installation badging and ensure base and IRP security protocols are maintained. Lost or misplaced badges are to be reported to the AF RPM immediately (see notification requirements in this PWS). All security badges and passes shall be returned to the Installation POC upon expiration of the badge//pass, upon completion of the project, or when possession of the badge//pass is no longer necessary (e.g., upon removal of Contractor personnel from specific projects). The Contractor is fully responsible for ensuring personnel, including subcontractors, are trained and qualified to enter and do work on a Government military Installation. Contractors are to have a favorable adjudication background prior to requesting access to Government sites, Installations, and buildings.

The Contractor shall be fully responsible for providing fully trained and qualified personnel who meet all qualifications and requirements to gain unimpeded base access without escort. Contractor personnel shall be United States Citizens or shall have all required documentation to obtain site access badging without escort by Government personnel. It is the responsibility of the Contractor to ensure personnel are qualified and meet all Installation access requirements and have a favorable National Agency Check with Inquiries (NACI) background evaluation. Contractor personnel in violation of Installation security and access requirements may no longer have access to the Installation(s). It is understood that some areas may have special access requirements and escort by Eglin Restoration Management Section personnel may be required, e.g., flightline.

Additional access or security requirements/limitations that may impact scheduling are provided below. Advance coordination for site access is required as follows:

Eglin AFB: CF288 is located on land leased to the Military Family Housing Contractor so access to the site needs to be coordinated with the Housing Contractor.

Eglin AFB: DP009, LF322, OT264, POI500, POI521, POI523, SS025, and SS313 require range clearance through Joint Test and Training Operation Control Center Z clearance or its successor for access.

Eglin AFB: DP084, LF005, LF010, LF051, LF322, OT083, OT100, OT262 OT263, OT264, OT265, OT269, OT270, OT271, SS025, SS278, SS313, and ST069 can only be accessed with four-wheel drive vehicles.

Eglin AFB: LF003 – Abandonment of wells at the site will require check in at the DRMO facility at Bldg. 525.

Eglin AFB: LF010 requires check in at Building 2063 before accessing site.

Eglin AFB: SS281 requires escorts at all times work is performed.

Eglin AFB: FT028 and SS026 require escorts with a non-Controlled Movement Area flightline driver's license.

Hurlburt Field: CG219 requires coordination with Housing Office for access.

Hurlburt Field: LF013 and XU002 are within the fenced Explosive Ordnance Disposal (EOD) area and require advanced coordination with EOD for access. A 4-wheel drive vehicle is recommended but not required. Anomaly avoidance techniques as defined in Department of the Army Engineer Manual 385-1-97 should be utilized when leaving the established roads for any activities including visual surveys. When needed, the Contractor shall provide UXO escort/avoidance for the inspection of LUCs and any subsurface disturbance (e.g., replacement of signs, installation of new signs) at LF013 and for sampling activities related to the supplemental RI for XU002. All UXO Technicians shall be Tech II or above (Reference Department of Defense Explosives Safety Board. (2016). TP-18 Minimum Qualifications for Personnel Conducting Munitions and Explosives of Concern-Related Activities) for escort/avoidance. If, while on site, a suspected MEC item is found, the 3Rs of explosive safety (Recognize, Retreat, Report) shall be followed.
Hurlburt Field: The majority of ST123 is within the fenced petroleum, oil, and lubricant area and requires signing in at the entry control point.

Tyndall AFB: DA046, FT016, FT017, OT029, OW217, OW582, SS015, SS026, TU204, TU205, and TU233: Portions of these sites may require access to the flightline. Flightline access is restricted. Work performed on/near flightline requires prior coordination with Base Operations, and deconflicting work with flying hours may be necessary. Depending on the area accessed, personal vehicles may not be allowed and only Government or commercial vehicles allowed. Vehicle flightline passes and/or flightline drivers licenses/training may be required. Restrictions may be placed upon height of equipment (drilling rigs, etc.) and/or frequency interference from remotely operated equipment. Photography is limited along the flightline north of Florida Ave. A photography permit is required from Airfield Operations in this area.

Tyndall AFB: TU233: Building 9725 is a controlled access area. A courtesy notification typically determines whether gate access assistance will be required or not.

Tyndall AFB: OT018: Contractor must coordinate with and obtain permission from Marina Island, LLC and the City of Lynn Haven to access the site and conduct any sampling.

4.14 Worksite Activities and Coordination

4.14.1 Coordination of Activities

The Contractor shall coordinate worksite activities with all applicable personnel to ensure the protection of human health and the environment; prevent damage to property, utilities, materials, supplies, and equipment; and avoid work interruptions. The Contractor shall provide security to work areas, if needed. The Contractor shall perform emergency response to situations arising from project activities. The Contractor shall perform emergency repairs to facilities, systems, improvements, or utilities damaged while executing the contract requirements. The Contractor shall comply with all local, state, federal, and military laws and guidance covering security activities. The Contractor shall comply with Occupational Safety and Health Administration (OSHA) safety and health regulations and local safety office requirements. The Contractor is required to provide the CO/KO and PM/COR copies of any OSHA report(s), findings, and issues submitted during the duration of the contract. The Contractor shall ensure all on-Installation activities are coordinated with the AF RPM and that notification is provided in sufficient time for the AF RPM to notify regulators, AF organizations or tenants, or other parties. Coordination details shall be included in the Contractor's communication management plan, included in the PMP.

4.14.2 General Requirements during Field Activities

The Contractor shall comply with all applicable federal, state, and any other applicable regulations concerning safety during site characterization and remedial activities, including, but not limited to, drilling, sampling, and remediation and operations activities. All AFB, USACE, and Contractor employees shall be authorized to stop fieldwork that is being conducted in an unsafe manner until the deficiency is properly addressed to ensure worker safety.

All activities requiring Contractor access to the Installation (e.g., drilling operations, sample collections, well development and testing, surveying, demolition, operations and maintenance, etc.) or affecting other Installation activities shall be coordinated with appropriate Installation personnel before implementation. Work will be implemented in a manner that minimizes disruption of Installation mission and operations. Due to range training and mission activities, site access may be impacted and require advanced coordination and/or non-core workday hours scheduling. The Contractor shall identify Installation access coordination and deconfliction as a schedule risk that may require extensive coordination and may result in substantial delays.

The Contractor shall coordinate worksite activities with all applicable AF and USACE personnel to ensure the protection of human health and the environment; the prevention of damage to property, utilities, materials, supplies, and equipment; and the avoidance of work interruptions. The Contractor shall provide physical security to work areas by furnishing security equipment and personnel. The Contractor shall perform emergency response to situations arising from project activities. The Contractor shall perform emergency repairs to facilities, systems, improvements, or utilities damaged in the course of executing the Contract requirements. The Contractor shall comply with all local, state, federal and military law and guidance covering security activities. The Contractor must comply with Occupational Safety and Health Administration (OSHA) safety and health regulations, USACE EM-385-1-1, and all local safety office requirements. The Contractor shall be required to provide the CO/KO, PM/COR, and

AFCEC RPM copies of any OSHA report(s), notices, findings, issues submitted during the duration of the Contract.

For environmental services, all on-site workers (Contractor and subcontractor) performing hazardous operations, including working with contaminated media, e.g., environmental sampling, monitoring, remediation, etc., and hazardous materials, must have completed the OSHA 1910.120 Hazardous Waste Operations and Emergency Response (HAZWOPER) training and/or other applicable training, plus annual refresher courses. The Contractor shall maintain documentation supporting training records and have the Accident Prevention Plan (APP) and Site Safety and Health Plan (SSHP) on site, available for workers, USACE, AF, and/or regulatory review.

The Contractor shall be responsible for any damage caused to property of the United States (Federal property) by the activities of the Contractor under this contract and shall exercise due diligence in the protection of all property located on the premises against fire or damage from any and all other causes. Any property of the United States damaged or destroyed by the Contractor incident to the exercise of the privileges herein granted shall be promptly repaired or replaced by the Contractor to a condition satisfactory to the PM/COR or reimbursement is made by the Contractor sufficient to restore or replace the property to a condition satisfactory to the PM/COR in accordance with FAR Clause 52.245-2.

4.14.3 Radiological Waste, Hazardous Material, and Hazardous Waste Permitting and Reporting

The Contractor shall handle all hazardous materials, and hazardous waste in accordance with applicable federal, state, local, Installation, and USACE requirements. The Contractor shall provide all documentation related to hazardous materials use, and hazardous waste disposal to AFCEC, COR, and Installation RPM(s). Additionally, the Contractor shall register with the Hazardous Materials Pharmacy program (if available) at the Installation to ensure appropriate and efficient tracking of the Contractor's hazardous material purchases, inventories, use, and releases as required by the Emergency Planning and Community Right-to-Know Act, EOs, or any Installation reporting requirements.

The Contractor shall also comply with federal, state, local, Installation, and USACE requirements for any task involving the transportation of hazardous waste, and contaminated material to off-site treatment, storage, and/or disposal facilities. This includes 40 Code of Federal Regulations (CFR) Parts 260 and 263, 49 CFR Parts 172, 173, 178, and 179, and all other applicable federal, state, and local transportation regulations. The Contractor is responsible for all disposal costs of hazardous waste.

Hurlburt Field: The Contractor shall submit the types and quantities of hazardous materials being brought onto Hurlburt Field per the Hurlburt Field 90-day Haz Waste Program.

Tyndall AFB: The Contractor shall submit Tyndall AFB Forms 81 (Contractors Hazardous Material Questionnaire), 82 (Hazardous Material Inventory), and 83 (Environmental Reporting) if any reportable hazardous materials are used during the duration of the contract. Tyndall AFB Forms 81 and 82 should be submitted to the Hazardous Materials Office (HAZMO) at 325CES.hazmat@us.af.mil seven to 10 days prior to the start of work. A current Safety Data Sheet for each item listed by the Contractor on Form 82 should be provided along with the submittal. The Tyndall AFB Form 83 (Environmental Reporting) should be submitted on a

monthly basis to document hazardous material usage until the project is completed. Some examples of reportable chemicals and trackable usage include, but are not limited to, paints, solvents, adhesives, gasoline being stored on-site and used in equipment, degreasers, compressed gasses, any aerosol cans, sealants, lubricants, cleaners, and pesticides. Hazardous Waste Determination form must be signed by the CZOE PM and submitted to udg_325ces_hazwasteoffice@us.af.mil for any material transported off base.

Eglin AFB, Hurlburt Field and Tyndall AFB: In strict accordance with Installation Policy, unless otherwise authorized, the Contractor shall be responsible for the management and disposal of IDW within 90 days of collection.

The Contractor shall perform all work in a manner that minimizes the pollution of air, water, or land and develop contingency measures for the cleanup of any spills that may occur during the performance of this Contract. The Contractor is responsible for performing IDW characterization, management, and disposal in support of the environmental restoration project in this contract. Waste management activities, including identification, hazardous waste determination, characterization, segregation and storage, labeling and marking, preparation of transportation documents, and record keeping, shall be in accordance with USEPA and Department of Transportation (DOT) regulations, state hazardous waste regulations, where applicable, and the Installation RCRA permit, when applicable. All IDW generated by the DERP is subject to the Off-Site Rule (40 CFR 300.440). Wastes may be placed in facilities compliant with RCRA or other applicable federal or state requirements. The Contractor is responsible for disposal costs of all IDW.

All waste media from areas with identified PFAS contamination shall be segregated, stored, and disposed of in accordance with the guidance provided in Section 1.3.

The Contractor shall write and implement waste management plans for Government review and approval before initiating on-site restoration work. These plans shall document the process for making a hazardous waste determination for IDW in accordance with 40 CFR 262.11 and detail the procedures for managing the waste and documenting its disposal. For work involving the generation and disposal of hazardous waste, the Contractor shall coordinate activities with the Installation hazardous waste manager and perform waste management that complies with all generator requirements in 40 CFR Part 262. These requirements include, but are not limited to, making hazardous waste determinations, determining generator category, obtaining USEPA ID numbers, notification of hazardous waste activity, use of the manifest system, complying with pre-transportation requirements, and maintaining records in accordance with 40 CFR 262.40 and 40 CFR 262.44. For Installations with existing hazardous waste ID numbers, coordinate waste with the Installation environmental staff. Note that the Installation is the waste generator and oversees and approves waste management activities. The Installation has signature authority as the generator on hazardous waste manifests prepared by the Contractor; however, Contractors may be required to sign waste characterization profiles, bills of lading for non-hazardous waste, and other DOT shipping papers.

The Contractor must obtain a Certificate of Disposal/Destruction/or Placement for all hazardous waste, CERCLA remediation waste, Formerly Utilized Sites Remedial Action Program waste, asbestos containing material, polychlorinated biphenyls (PCBs), etc., from the ultimate disposal facility. The certificate must correlate to each shipment of waste to the facility. The Contractor shall submit the certificates to the CO/KO for placement in the project/site file.

After IDW disposal is complete at the site, an IDW report addendum shall be prepared to describe the IDW activities at each site and included as an addendum to one of the final reports.

4.14.3.1 Regulatory Requirements

All activities and IDW documents required by this scope of work shall comply with and reflect the following regulations and appropriate guidance publications, at a minimum:

1. DOT, Hazardous Material Regulations, 49 CFR Subtitle B, Chapter I, Subchapters A, B, and C.
2. USEPA, Regulations, 40 CFR Chapter I, Subchapter I – Solid Waste.
3. USEPA Regulations, 40 CFR Chapter I, Subchapter J – Superfund, Emergency Planning, and Community Right-To-Know Programs.
4. CERCLA, 42 USC 9601-9675
5. RCRA 42 USC 6901 et seq.
6. USACE EP 415-1-266, "Construction – Resident Engineer Management Guide (REMG) for Hazardous, Toxic, and Radioactive Waste (HTRW) Projects" (most current version).
7. USACE EP 200-1-2, "Environmental Quality-Process and Procedures for Shipping Hazardous Wastes and Other Hazardous Materials" (most current version)
8. USACE, EM 385-1-1, Safety and Health Requirements
9. USACE, ER 385-1-92, Safety and Occupational Health Requirements for Environmental Cleanup Projects
10. USACE, EM 200-1-2, Environmental Quality Technical Project Planning Process
11. OSHA, 29 CFR 1910.120, Hazardous Waste Operations and Emergency Response Standard (HAZWOPER)
12. Other applicable federal, state, and local solid waste requirements.

4.15 ORC Transition Plan

The ORC Transition Plan is a strategic document that is initiated by the ORC Contractor two years prior to the PoP end date and is delivered at least 90 days prior to the PoP end date. The ORC Transition Plan should include, but not be limited to, information regarding site statuses, the status of all operating treatment systems, contractor-owned materials that will be removed and may be needed by the incoming contractor, and documents that may be in review with the regulators at the end of the PoP. To streamline the Transition Plan, the Contractor is encouraged to reference other documents containing site status information. The purpose of this plan is to support a seamless transition for the incoming ORC Contractor upon the award of a follow-on ORC. This plan serves as a critical reference for the incoming Contractor when detailing transitional activities within their PMP.

5.0 CHEMISTRY REQUIREMENTS

The Contractor shall be responsible for the quality of all required chemistry services performed. The Contractor shall ensure that all chemistry-related tasks are conducted in accordance with the project-specific Work Plan (WP). Any samples that are delayed or lost by the overnight carrier or destroyed in shipping must be resampled within 30 days at the expense of the Contractor. The Contractor shall identify a Program Chemist as key personnel in the project WP. The Program Chemist will act as a POC on all chemistry-related issues and shall be responsible for ensuring that all Data Quality Objectives (DQOs) are met.

Data quality includes analytical and non-analytical data, measurements, and all other types of data/information collected to support achievement of each PO. The Contractor shall develop and implement a Quality Management Plan (QMP) that addresses all aspects of the contract, including but not limited to, document quality, schedule updates, fieldwork, field documentation, etc. The Contractor shall conduct audits of all field efforts and shall provide the PM/COR with a report summarizing each field effort, areas of assessment, issues identified, and corrective actions taken. The outline and content details shall be submitted to the PM/COR for review and approval prior to preparation of the Revision 00 document. The PM/COR may require additional detail and/or procedures to ensure all topics related to project execution are thoroughly addressed in the QMP.

All laboratory services shall be conducted in accordance with the approved project UFP-QAPP work plan. The UFP-QAPP shall include SOPs for field activities, sampling, and laboratory analytical procedures. Samples shall not be submitted for analysis until Revision 02 UFP-QAPP work plan is approved, i.e., approval by both the Government and regulatory agencies.

5.1 Quality Assurance

The Contractor shall develop project-specific DQOs to ensure data of adequate quality are collected to support project decisions. DQOs shall be developed in consensus with the restoration project team and in accordance with the Uniform Federal Policy for Quality Assurance Project Plans (UFP-QAPP) and USEPA QA/G4, “Guidance on Systematic Planning Using the Data Quality Objective Process” (most recent version) and documented in the project WP. The Contractor shall ensure that all requirements specified in the project WP are met. If not met, the Contractor may be required to re-accomplish sampling at the Contractor’s expense.

All laboratory services shall be conducted in accordance with the approved project WP. Samples shall not be submitted for analysis until the WP is approved.

The Contractor shall administer an AFCEC-approved performance evaluation sample program, verify and validate data, and perform corrective actions in accordance with the project WP. See attached AFCEC guidance document, Ensuring Chemistry Data Quality – AFCEC Performance Evaluation Program. Data validation shall be conducted on requirements presented in the WP and performed by an independent, qualified, and experienced data validator in accordance with DoD General Data Validation Guidelines and any applicable Modules. One hundred percent of the data shall be validated. The level of data validation shall be project-specific, a minimum of Stage 2B, documented in the project-specific WP, and approved by the COR. The data validation standard operating procedure shall be included in the WP. Significant deviations from project requirements discovered during data validation shall be communicated with the project chemist and COR as part of the data validation process.

A data validation report shall be prepared, sufficiently document the data validation procedure, and provide a clear understanding of the data's representativeness. The results of the data validation shall be summarized in the associated technical report, with supporting data validation reports included in an appendix. A data usability assessment of the validated data shall be performed. The results of the data usability assessment shall be included in the technical report and shall identify the limitations of the data and the effect qualified results have on the decisions being made for the project.

5.2 Laboratory Selection

The Contractor shall select a laboratory with analytical capabilities sufficient for the methods specified in the WP and adequate throughput capacity to handle the project's analytical workload during all field activities. During analysis and reporting, the Contractor shall ensure that the selected laboratory is accredited under the DoD Environmental Laboratory Accreditation Program (ELAP), state, and federal requirements, including state certification where appropriate. The Contractor shall include backup laboratories in the UFP-QAPP for contingency if quality, capacity, or other issues arise.

The Contractor may establish an on-site laboratory at the project site if it is determined necessary by the Contractor. However, on-site test laboratories shall also be accredited under the DoD ELAP and meet all state and federal requirements, including state certification where appropriate. Laboratories providing sample analysis for this project must be certified by the State of Florida. Florida laboratory certification requirements can be found at: http://www.floridahealth.gov/licensing-and-regulation/environmental-laboratories/environmental-laboratory-certification/index.html

5.3 Analytical Data Management

The Contractor shall ensure that all hard copy and electronic data deliverables supplied by the laboratory are complete and adequate to support the quality and usability of the data. Raw data packages shall be submitted to the Installation RPM within 90 days of the completion of the sampling event. Data packages shall meet federal and state standards and include all information required to re-create the analysis, including correspondence with the laboratory regarding QA/QC exceedances and documentation of corrective actions.

Analytical data and data management must be consistent and compliant with requirements stated in the UFP-QAPP and shall include all information required to re-create the analysis, including correspondence with the laboratory regarding exceeding quality assurance/quality control (QA/QC) measurements and documentation of corrective actions. The Contractor shall meet ERPIMS data deliverable requirements as currently required by AFCEC. Digital analytical data reports shall be Level IV including QA/QC results, chromatographs, and manual integrations completed during analysis.

5.4 Record Keeping

The Contractor shall create and maintain in one location written (in bound, numbered logbooks) and electronic records, e.g., laboratory data, survey data, photo-documentation, sufficient to recreate each sampling, analytical, testing, and monitoring event, and shall make these records available to the Government upon request at any point during this Contract.

The Contractor shall maintain records of, and derived from, all activities outlined in the appropriate portion of the Quality Program Plan (QPP) supporting the generation of these sampling and analysis records, i.e., procedures. The Contractor shall also retain written calculations using information obtained from sampling, analysis monitoring, and testing activities, to include all raw data. All information shall be provided to the Government upon request. All field documentation shall be recorded in bound, numbered logbooks. Field logbooks shall have numbered pages and shall include a complete record of all field activities sufficient to fully recreate the data-collection activity. If multiple field logbooks are required, each shall be numbered and specifically identified to indicate dates and sites where used. The QMP shall include a specific procedure addressing the collection of field notes, and management and chain of custody of all field logbooks.

Use of electronic field documentation may be used if specifically approved by the PM/COR. If approved, electronic field documentation software shall be digitally signed to document the date, time, and person entering the information. Any digital notes edited in the software after collection must be annotated by the software with the identification/time/reason for making the change.

Field documentation shall be recorded at the time of data collection/fieldwork, i.e., in real time, details may not be added after the fact. All information required to fully recreate sampling, investigation, and remediation events shall be documented in the field logbook. Use of field forms may augment but not replace the detail required in the field logbook, i.e., all data and information must be in the field logbook. The field logbooks are a critical part of the official project record; the Contractor shall include procedures for maintenance, review, tracking, etc. of the field logbook in the programmatic UFP-QAPP. The Contractor shall make these records available to the Government upon request. The Contractor shall retain records for a minimum of five years.

5.5 PFAS Sampling and Analysis

If PFAS sampling is required, samples shall be analyzed in accordance with DoD and AF policy using an appropriate US EPA test method for the media being tested. In addition, the Contractor shall follow any applicable current installation, State, or Federal requirements or guidance for PFAS sampling.

Although not currently planned, remediation systems may be retrofitted for PFAS removal during the ORC PoP by a non-ORC contractor. Collection of influent, mid, and effluent samples for PFAS analysis along with O&M activities associated with PFAS treatment (e.g., treatment media changeouts, component repairs or replacement), may be added to the ORC contract via modification. Any such retrofitting will be coordinated in advance with the ORC Contractor to identify and abate conflicts.

6.0 Munitions Response and Explosives Safety Requirements

6.1 3Rs (Recognize, Retreat, Report) Explosives Safety Education Program Training

All Contractor employees, to include subcontractor employees, performing on-site work shall take the 3Rs Safety Training. Training must be completed by on-site personnel prior to the commencement of on-site work. The 3Rs Safety Training is available at the following website: https://www.denix.osd.mil/uxo/3rs-training/index.html. Certificates of completion are valid for

1 year and training must be updated annually during the on-site performance of work. Completed certificates shall be maintained by the Contractor and made available to the COR if requested.

6.2 Explosive Safety Submittals

All Explosive Safety Submittals, if required, will be provided by the Government. The Contractor shall be responsible for notifying the Government when an intrusive activity involving the potential or intentional interaction with military munitions six months in advance of the action. The Government does not anticipate any work involving intrusive investigation of MEC as part of this work.

6.3 Environmental Requirements

The Contractor shall perform contract tasks in areas which potentially contain MEC hazards and shall comply with all applicable federal, state and local laws and regulations; and applicable site-specific orders, agreements, or rules; as well as Army and DOD requirements, such as those established by the DOD Explosive Safety Board; while performing these contract tasks. The Contractor shall ensure that all activities performed by its personnel, subcontractors and suppliers are executed in accordance with these requirements. Any incident of non-compliance noted by the Contractor shall immediately be brought to the attention of the COR telephonically and then by written notice. Nothing in this contract shall relieve the Contractor of its responsibility to comply with applicable laws and regulations.

The Contractor shall comply with all site-specific time and procedural requirements (federal, state, and local) described in the permits obtained. The Army technical experts will also independently review Contractor work to ensure compliance with all applicable requirements.

6.4 MEC Related Guidance

MEC includes, but may not be limited to: Unexploded Ordnance (UXO), as defined in 10 United States Code (U.S.C.) 101(e)(5); Discarded Military Munitions (DMM), as defined in 10 U.S.C. 2710(e)(2); or Munitions Constituents (MC), as defined in 10 U.S.C. 2710(e)(3), present in high enough concentrations to pose an explosive hazard.

MEC distinguishes specific categories of military munitions that may pose unique explosives safety risks. Because MEC that is being actively managed may be determined to be hazardous waste, 29 Code of Federal Regulations (CFR), Hazardous Waste Operations and Emergency Response, Section 1910.120 may apply.

The Contractor shall comply with all property-owner or other site-specific time and procedural requirements (federal, state, and local) described in the approvals obtained.

The contractor will comply with all applicable guidance for conducting munitions response including the MR QAPP Tool Kit #1, MR QAPP Tool Kit #2, IGD EM 200-1-15, DESR 6055.09 Edition 1 Change 2, EM 385-1-97, DoDM 4140.72, and DoDI 4140.62.

6.5 Revision 02 Uniform Federal Policy Quality Assurance Project Plan (UFP-QAPP)

Revision 02 versions of UFP-QAPP Worksheets (WS) #9, Project Planning Session Summaries #10, Conceptual Site Model (CSM), and WS #11, Data Quality Objectives (steps 1 through 4) will be updated throughout the project as new information becomes available; however, initial worksheets will identify:

- Problem statement as it is currently understood.
- The goals of data collection as it is currently understood.
- The information inputs that have tentatively been identified to fill data gaps in the preliminary CSM and answer study questions.
- The boundaries of the project as they are currently understood.

The Contractor's proposed approach shall be consistent with these Revision 02 MR-QAPP Worksheets and shall implement the remedy in its entirety as described and defined in the Decision Document (DD).

6.6 Quality Control

The Contractor shall be held responsible for quality control to the quality standards set forth in MR-QAPP and IGD EM 200-1-15. The Government shall be held responsible for quality assurance. Following task order award and during project implementation, the Contractor shall develop and submit documentation of project-specific quality assurance (QA) and QC activities prepared in accordance with the MR QAPP. The Government will review and return the quality systems documentation, with comments, indicating acceptance or rejection. If necessary, the Contractor shall revise the documentation to address all comments and shall submit the revised documentation to the Government for acceptance. In addition, the Contractor shall develop and submit Quality Control Summary Reports to summarize the quality control details of the task order project. The problems and successes of the work done to control the quality of the activities shall be included in the summary reports.

6.7 Quality Management

The Contractor must ensure that the quality of all work performed or produced under this contract meets Army approval, through the COR. Quality control plans must be prepared and approved by the COR prior to performance of physical work.

The Final QASP has been prepared by the Army. The QASP highlights key quality control activities or events that the COR will use to determine when Army (COR or CO/KO) inspections can be conducted to assess progress toward and/or completion of milestones. Activities identified in the QASP should be appropriately coded in the project schedule to allow for planning of QA inspections.

6.8 Geophysical Deliverable Requirements

Geophysical Data Deliverables, if required, shall be in accordance with IGD EM 200-1-15 and site-specific Standard Operating Procedures (SOPs), with the following exceptions and additions: final, processed data shall be delivered in Geosoft databases that can be opened and viewed without the need of external or additional formatting and all data packages will be made available at the electronic data delivery system developed for the project.

6.9 Geographic Information System

The Contractor shall utilize a geographic information system (GIS) to maintain and manage all project and geospatial data in accordance with Section 4.7 of this PWS and EM 200-1-2, ER 1110-1-8156, EM 1110-1-2909, EM 1110-1-1200, and IGD EM 200-1-15 and applicable Interim Guidance Documents. The Contractor shall adhere to all applicable federal, DOD, and Army geospatial data standards for tasks and deliverables in this PWS.

7.0 PLANS AND REPORTS

7.1 Quality Program Plans

The QPP shall include the WP, the Health and Safety Plan (HSP; as required by 29 CFR 1910.120), and the Construction Quality Plan (CQP) if required. For the Eglin AFB Base-wide QPP, the contractor shall include the Eglin Standard Operating Procedures (ESOPs) provided in Enclosure 5. Hurlburt Field and Tyndall AFB do not have Installation-specific SOPs.

7.1.1 Work Plans

Prepare WPs to comply with DoD, AF, USACE, USEPA (epa.gov/quality), state, and local regulations and guidance. Base-wide and site-specific WPs that require sampling and analysis shall be prepared in accordance with the UFP-QAPP, using the optimized UFP-QAPP worksheets. The optimized UFP-QAPP worksheets shall constitute the entire WP when sampling and analysis are required. WPs shall be specified as separate payment milestones under the site-specific AFCEC Sub-CLIN(s) as appropriate.

The Contractor shall prepare, for USACE and AF review and approval, site-specific UFP-QAPP WP(s) for this Contract. The Contractor must implement, maintain, and comply with the approved programmatic UFP-QAPP WP. Unapproved deviations may require corrective actions at the Contractor's expense.

Project-specific UFP-QAPP WPs shall be written in the format specified in the Inter-Governmental Data Quality Task Force Optimized UFP-QAPP Worksheets (March 2012), or most recent version, and in accordance with other USEPA and DoD guidance documents. The Investigation-Derived Waste (IDW) Management Plan shall be prepared in accordance with AF guidance AFGM 2019-32-01 and requirements included in this PWS, in addition to all federal and state regulations as appendices and shall be included as an attachment to the UFP-QAPP WP.

Base-wide UFP-QAPP WPs shall be prepared for each Installation and shall contain "generic" worksheets and documents that would apply to all sites at each Installation. In addition, the Base-wide UFP-QAPP contains support documents that may be used/referenced for site-specific data

collection activities, FDEP and laboratory standard operating procedures, etc. Site-specific UFP-QAPP work plans may reference specific "generic" worksheets or information contained in the Base-wide UFP-QAPP.

At a minimum, the Contractor shall prepare work plans that include the UFP-QAPP, HSP, IDW Management Plan, and CQP, as required. Additional components may be required by the PM/COR.

7.1.2 Health and Safety Plan

The Contractor shall prepare a HSP to comply with AF, USACE, OSHA, USEPA, federal/state/local health and safety regulations and guidance, including USACE Engineering Manual (EM) 385-1-1 and ER 385-1-92. In accordance with EM 385-1-1, the HSP will consist of a Site Safety and Health Plan (SSHP) and Accident Prevention Plan (APP). Utilize to the fullest extent possible any existing related HSP, tailored specifically to the current effort. The Contractor shall maintain written certification that the approved HSP has been reviewed with all personnel who work at the project site prior to their mobilization. The Contractor and all subcontractors are required to comply with the approved HSP (including SSHP and APP). The Government can shut down operations due to non-compliance without cost to the Government until safety issues are resolved.

Prior to the start of any fieldwork, the PM/COR and Mobile District Safety Office must approve the Contractor's APP/SSHP. In addition, the PM/COR must approve any changes to the APP/SSHP prior to commencing work covered by the changes. The APP/SSHP may be included as an appendix or attachment to the site-specific UFP-QAPP, or a separate submittal. The Contractor shall provide comprehensive Health and Safety oversight of all field activities. The SSHP shall be fully compliant with site-specific plans detailed in 29 CFR 1910.120.

7.1.3 Construction Quality Plan

The Contractor shall provide a CQP to comply with AF, USACE, OSHA, USEPA, federal, state, and local quality regulations, if needed.

7.2 Technical Plans and Reports

The Contractor shall provide reports and various other deliverables in accordance with the most appropriate industry standard, or where applicable, any federal or state guidelines.

Technical plans and reports are required to demonstrate that POs and milestones are being met and that payment is appropriate.

Most documents must be submitted for initial AF and USACE review, followed by submittal to one or more regulatory agencies. The Contractor shall ascertain the number of copies required for delivery to all relevant parties. Regulatory agency review times will be based on the agency reviewing the document, the complexity of the deliverable, and the workload of the technical review team, including regulatory partners. The AF is unable to commit to review times for another agency. The Contractor shall be responsible for coordinating the document review schedule with all stakeholders. However, historical regulatory review times have averaged 60 calendar days for higher complexity documents and 30 calendar days for low complexity documents and review of responses to comments for all documents. High complexity documents include Uniform Federal Policy- Quality Assurance Project Plan (UFP-QAPP) Work Plans both Base-wide and site-specific, Remedial Investigation or Site Assessment Reports, Feasibility

Studies, Proposed Plans, Records of Decision, Remedial Design/Remedial Action Work Plans or Remedial Action Plans (RAP), Remedial Action Completion or Status Reports, Site Rehabilitation Completion Reports (SRCR) both conditional and unconditional, and Land Use Control or Institutional Control Implementation Plans (LUCIP or ICIP). Low complexity documents include Groundwater Monitoring Reports, Well Abandonment Work Plans and Reports, System Decommissioning Work Plans and Reports, and Land Use Control Inspection Reports. Historical regulatory legal reviews of documents such as Conditional SRCRs and LUCIP/ICIPs have taken several months. Please be advised that the workload for those averages may not mirror the workload under an ORC-accelerated environment. Therefore, Contractors should review available information and form independent conclusions as to the time necessary, as well as risks and appropriate mitigation and contingency measures, to achieve the PO and PP with their approach. Legally binding documents such as reports, correspondence, No Further Action (NFA) documents, regulatory closure documents, RODs, or other DDs shall be signed by the AF and not the Contractor.

The Contractor shall submit all plans, reports, and other documents in Revision 00, Revision 01, Revision 02 versioning nomenclature. Not all documents will require submittal of all versions. The Contractor shall provide multiple versions of the following documents:

- Installation POCs: Electronic copies of all documents.
- AFCEC Program Management Office: Electronic copies of all documents.
- PM/COR: Electronic copies of all documents.
- Regulators: Electronic copies of all documents.

The following are the AF and USACE estimated review times. These are estimated based on historical document review timeframes but may vary considerably depending on workload and availability of Government and regulatory personnel. Complex documents, permit modifications, and Decision Documents may require additional time. It is imperative that the Contractor be proactive and anticipate delays which may impact the IMS. The Contractor shall implement contingencies to mitigate delays that may adversely impact schedule. Document/plan review durations is a significant schedule risk for the ORC. The Contractor shall use appropriate duration estimating techniques identified in the basis of schedule document and shall perform risk analysis simulations to ensure schedule risk is understood, documented, and mitigated for efficient execution. In order to mitigate and avoid schedule delays, it is imperative that the Contractor develop and execute an effective document quality management program, documented in the QMP, and provide work products compliant with requirements and free of error.

Reviewer	**Document Review (for each version)**	**Response To Comments Review**
AF (AFCEC/CZR) and USACE Review	30 calendar days	21 calendar days
AF (AFCEC/CZR & CZPR), USACE, and Legal* Review	60 calendar days	
Coordination/Signature – Installation	90 calendar days	
Coordination/Signature – CZ	90 calendar days	

Reviewer	Document Review (for each version)	Response To Comments Review
* Legal review required per AFI 32-7020 for: PA/SIs that result in Site Closeout, Engineering Evaluations/Cost Analysis, Removal Action Memoranda, FS, Proposed Plan, ROD, and ROD modifications, Five-Year Reviews, Remedial Action Completion Reports (RACRs), Site Closeout Reports, NPL deletion requests. See AFI 32-7020 for additional information. * Document review times are estimates and actual review times may vary greatly due to complexity of documents, the number of other ORC documents in the review queue, and overall workload of the reviewer. It is the Contractor's responsibility to fully evaluate the range of potential review times and select durations using the risk-based approach described for the IMS. * Inadequate document quality may impede the review process and further extend the review/approval cycle for documents.		

The Contractor shall upload all documents to its ORC document repository. The documents required for this contract shall be proposed by the Contractor and will be included in the Contractor's IMS. The Contractor shall be responsible for providing electronic deliverables to the Government in a format appropriate for upload to the Air Force Administrative Record.

7.3 Deliverable Submission Cycle

Major deliverables are defined as any document that must be submitted to the Government/regulatory agency. All major deliverables specified in this PWS shall be submitted in three phases unless otherwise stated. Submission requirements–including number of copies, distribution, and submission schedule–will be included with the Contractor's proposal and prior to award.

The first submission shall be considered Revision 00 and shall be submitted for Government-only review. The Contractor shall respond to each comment in writing and shall make the appropriate revisions to Revision 00. Revision 00 UFP-QAPP work plans, Revision 00 Site Assessment Reports, and Revision 00 RAPs may require a full 90-day review by the Government. This includes review by the project delivery team (PDT), and revisions by the Contractor.

The revised Revision 00 shall be submitted as Revision 01 for regulatory review. The Contractor shall again respond to each comment in writing and shall make the appropriate revisions to Revision 01. Should a review meeting be scheduled, the minutes of the meeting shall contain the written record of the comments and responses provided by the Contractor. The revised Revision 01 shall be submitted as Revision 02. However, these submittal requirements should in no way be construed to limit the number of regulatory submittals required in order for the Contractor to obtain regulatory approval, i.e., multiple versions of documents may be required to adequately address comments and receive approval.

Document review timeframes are estimated ranges for similar projects; however, the Contractor shall make an independent assessment of review/approval timeframes and risk to each document, and incorporate this into the IMS:

The Contractor shall submit all plans, reports, and other deliverable documents in Revision 00, Revision 01, and Revision 02 versions as appropriate for that specific document. All documents may not require submittal of all versions. Document submittals shall include both native file formats (e.g., MS Word, MS Project, etc.) and pdf. Multiple versions of documents may be

required to be generated by the Contractor. Revision 00, Revision 01, and Revision 02 versions of documents are defined in Enclosure 1, Acronyms and Definitions.

The deliverables shall be proposed by the Contractor and will be included in the ORC PMP, IMS, and MPS. Deliverables shall be submitted digitally.

7.4 Response to Comments

The Contractor shall submit written responses for all written comments generated during the review of project deliverables. Copies of the comment responses shall be provided for all participants in the review process for each particular deliverable. Wherever practical, the minutes of review meetings may be used as the vehicle to provide the written response. Deliverable review comments are expected to be resolved in one iteration of response to comments (RTCs); however, multiple iterations may be required to resolve issues and ensure the Contractor has adequately addressed all comments and issues.

The requirement for superior document quality is a critical requirement for this ORC. Documents/work products containing errors and documents where response to comments are inadequately addressed may require multiple iterations of review and response to comment. Documents requiring multiple iterations of Government/regulatory review and Contractor response to comment is the responsibility of the Contractor, is a risk to be mitigated in the IMS, and is included in the scope of this PWS.

7.5 Project Delivery Team

The Project Delivery Team (PDT) for the FY27 Florida Panhandle ORC Group may change as personnel assignments evolve and changes will be incorporated during future PWS modifications. Personnel changes will not require a stand-alone modification to the PWS.

The ORC PDT includes the following personnel and roles:
USACE Project Manager: Henry Brookins
USACE Contracting Officer Representative: Vic Cunningham
USACE Technical Manager: TBD
USACE Contracting Officer: Kenneth P. Harlan
USACE Chemist: Michael Bullard
AFCEC Program Manager: Kayla Trevino
AFCEC RPM Tyndall: John Winters
AFCEC RPM Eglin: Janice Mann
AFCEC RPM Hurlburt Field: Janice Mann

8.0 SITE WORK

The Contractor shall perform site preparation, site characterization, field investigation, conservation, demolition, and site restoration as required to achieve the POs of this contract.

8.1 Conservation

Activities shall be planned and implemented in a manner that protects existing site utilities, structures, surface features, service operations, monitoring and other types of wells, and the general site environment. This includes the protection of prehistoric and/or historic sites

identified in the Installation Integrated Cultural Resources Management Plan; endangered/threatened wildlife species and their potential habitats; exemplary natural areas as defined in the base Integrated Natural Resources Management Plan; and trees, shrubs, and other vegetation not in the affected zone from dust damage, soil compaction, and physical contact with machines and equipment. Work activities shall be coordinated with AFCEC, COR, Installation RPM(s), Cultural Resources POCs, the Natural Resources POCs, and Installation Operating Support POCs to ensure compliance with these requirements.

If appropriate, the Contractor shall conserve uncontaminated topsoil by removal, storage, or redistribution. All reasonable measures shall be taken to minimize and suppress fugitive emissions of dust, vapors, and other site materials during site work. All fill materials shall be non-contaminated with the proper documentation to demonstrate as such. The Contractor shall conduct all operations and activities with the intent of reducing the amount of pollution generated. Specific areas to be focused on are the generation of solid waste, the use of hazardous materials, the use of ozone-depleting chemicals, the generation of hazardous waste, and the use of energy and water. During site work, the Contractor shall plan, construct, operate, maintain, optimize, and decommission systems necessary to control stormwater run-on and run-off and transport surface water drainage to a treatment plant, discharge location, or any other appropriate destination.

Additional requirements/coordination are required as follows:

Tyndall AFB: FT016, LF006, LF007, or OT029. If intrusive work is conducted at these sites, the Contractor shall provide archaeological oversight if required by Tyndall AFB.

8.2 Site Characterization and Field Investigation

The Contractor shall perform field investigation and sampling/analysis to characterize environmental conditions, in accordance with approved DQOs, as required to achieve the POs of the site. The Contractor shall identify specific site characterization activities proposed to achieve the POs.

8.3 Site Preparation

The Contractor shall perform site work as necessary to prepare sites for field activities. Security and access controls shall be implemented to prevent unauthorized site entry and protect wildlife from site exposure. The Contractor shall survey existing utilities to determine adequacy and need for modifications to support site activities. The Contractor shall obtain appropriate approvals and shall construct connections or new systems for electrical power, water, sewer, gas distribution, telephone, and other utilities, as required, to achieve the POs of this contract. Additionally, the provision and cost of utility metering devices associated with the implementation of existing and proposed remedies, including the installation of individual meters for necessary utilities, is the responsibility of the Contractor. The Contractor shall meter all utilities consumption every month. The Contractor shall/shall not be responsible for the associated cost of utilities.

8.4 Demolition

Any demolition activities shall be ancillary to other requirements. The Contractor shall demolish facilities, systems, and other improvements as required in this contract in accordance with

applicable federal, state, and local laws and regulations. The Contractor shall conduct demolition efforts in conjunction with such activities as new environmental remedial system construction and site clearing, if required to achieve the POs of this contract. The Contractor shall perform surveys as part of demolition efforts and is responsible for providing GIS information to USACE and Installation Civil Engineering.

8.5 Site Restoration

The Contractor shall decontaminate equipment and facilities, decommission facilities as necessary, and fully restore the site(s) as close as possible to pre-construction conditions prior to demobilizing from the site(s). The Contractor shall remove any temporary facilities and implement erosion control measures such as seeding, mulching, sodding, and placing erosion control fabrics; restore roads, structures, and utilities; and plant trees, shrubbery, grasses, and other vegetation. The Contractor shall document and report on activities and train Government personnel to perform required maintenance, as requested.

9.0 ENVIRONMENTAL REQUIREMENTS

The Contractor shall perform a full range of activities to achieve the POs of this contract. Requirements may include, but are not limited to, completion of conceptual design(s), construction, implementation, demolition, and emergency response as related to environmental engineering and construction tasks.

The Contractor shall execute environmental restoration projects in accordance with approved DQOs and applicable federal, state, and local laws and regulations. The Contractor shall evaluate, complete, and modify designs as necessary, and plan, optimize, install, construct, test, and decommission any site as required to achieve the POs of this contract. The Contractor shall document all activities as stated herein.

The Contractor may change the site-specific approach for attaining POs as needed, based on approval of the RPM/COR, due to site conditions, regulatory changes, etc. All changes to the site-specific PO attainment approach shall be maintained current in the PMP, IMS, and MPS.

The Contractor shall perform support such as designing, planning, programming, scoping, studying, investigating, evaluating, optimizing, and consulting on environmental engineering and construction efforts. The Contractor shall also provide training to Government and other Contractor personnel regarding the O&M of equipment, systems, and facilities during equipment shakedown periods. The Contractor shall perform O&M of equipment, systems, and facilities prior to approval by the Government.

The Contractor shall implement Environmental Management System (EMS) principles in accordance with Contractor requirements of DAFI 32-7001 (*Environmental Management*), to include Green and Sustainable Remediation (GSR) techniques, to the extent practicable while ensuring protection of human health and the environment. EMS and GSR are defined in Enclosure 1, Acronyms and Definitions. An EMS follows the “Plan-Do-Check-Act” cycle and considers the environmental impact of investigative and remedial activities during the remedy selection process, as well as O&M of the remediation activity. The Contractor shall incorporate an EMS approach into all environmental restoration projects, evaluating activities and selecting a remedy, product, and/or service that minimizes the environmental impact from the remedy, yet provides the maximum environmental benefit to the cleanup over the entire life of the remedial project. The Contractor shall mitigate, minimize, or otherwise manage the potential

environmental impacts from all remediation activities. Contractors working on AF Installations must complete an initial EMS awareness-level training and integrate EMS training with other required Contractor orientation and training.

9.1 Environmental Restoration Process Application

The Contractor shall perform all activities necessary to meet all ORC requirements. Environmental restoration requirements include the full range of investigation, cleanup, optimization, and LTM activities. The Contractor shall develop and update a CSM and an exit strategy as described in this PWS. The Contractor shall also provide logical approaches to improve remedy protectiveness, effectiveness, and cost efficiency, and to facilitate progress toward the completion of the POs. The goals are to assess and optimize remedy performance and monitoring, demonstrate remedy progress in accordance with approved performance models, and take the site to its best long-term use or its closure.

This contract involves a performance-based approach, where the contracted work is performed with a focus on results. Results are achieved by 1) the achievement of the PO in the PP in accordance with the Performance standard per Table 1, or 2) the achievement of interim milestones that demonstrate value-added progress towards the achievement of the PO. This ORC enables the Contractor to select actions best suited to the site requirements, ensures that best management practices and best available technologies are employed, and focuses on continual improvement by applying an EMS approach. The Contractor's proposed approach shall be commensurate with site conditions, site status, and requirements to achieve the PO within the PP.

9.1.1 Conceptual Site Model Guidance

For all sites, the Contractor shall prepare or update site CSMs following DQOs. The CSM is a comprehensive written and graphical description of all available information about site conditions that could influence remedy design, selection, or performance. Thus, the CSM forms the basis for defining Remedial Action Objectives (RAOs) and developing and implementing an exit strategy. A CSM incorporates several elements, including the following:

- Three-dimensional representation of:
  - Nature and extent of contaminant (including source types and affected media)
  - Site geology
  - Site hydrogeology
  - Biological and geochemical conditions
  - Monitoring points
- Contaminant fate and transport in the environment;
- Risks, receptors, and potential receptors (under current and reasonably expected future exposure scenarios);
- Past remedial actions and locations of remedial components and monitoring points
- Historical, current, and expected future land uses; and
- Other factors relevant to the understanding of contamination at the site.[1]

[1] ITRC. (2004). *Remediation Process Optimization: Identifying Opportunities for Enhanced and More Efficient Site Remediation.*

The Contractor shall develop initial or updated CSMs for all sites listed in Table 1 of this PWS and work described in Section 1.3.2. An appropriately detailed CSM is required beginning with the remedial investigation phase for all restoration program sites and must be maintained until the end of the project life.

The Contractor shall update the CSM as new data and site knowledge are acquired. This is crucial for assessing and optimizing remedy performance and performance monitoring programs.[2] New data may be obtained upon completion of remedial investigation, supplemental investigation, pilot studies, bioremediation investigations, and routine monitoring of remedy performance. Revisions to the CSM will be included in investigation and monitoring reports, as necessary. For more information, see USEPA Groundwater Road Map (Office of Solid Waste and Emergency Response [OSWER] Directive No. 9283.1-34, 2011) and Environmental Cleanup Best Management Practices: Effective Use of the Project Life Cycle Conceptual Site Model (EPA 542-F-11-011, 2011), Interstate Technology and Regulatory Council (ITRC guidance (ITRC, 2004 and 2006), and ASTM International (formerly known as ASTM) standard designations E1689 (2014) and D5979 (2014).

9.1.2 Exit Strategy

The Contractor shall develop a stand-alone exit strategy for all Table 1 sites and work described in Section 1.3.2 where a remedy is planned or in place. Exit strategies and cost-benefit analysis shall be included in the PMP. Initial exit strategy development is required at the point of remedy selection for all Table 1 sites and work described in Section 1.3.2 and must be maintained until the end of the project life. For sites where a remedy is already in place, include a new or updated exit strategy along with work planning documents. If the exit strategy changes, the revised document must be resubmitted. An exit strategy for a site is the detailed plan for achieving the RAOs that have been selected as the end points. Stated another way, the RAOs are the overall goals that must be met for the site to achieve RC or be approved for SC or planned land use. An exit strategy represents a formalized process for taking the site from its current state to its best long-term use or to closure (independent of duration). The strategy represents a plan to actively manage the site and make decisions at various points that will best tailor remedial and monitoring efforts to achieve the RAOs in the most efficient and effective manner. The strategy is best developed with consideration of stakeholder and regulatory agency concerns, resource constraints, and technical realities; it also includes well-defined means to measure and track progress. An exit strategy is dynamic and must be updated as new data and site knowledge are acquired. The exit strategy would need to be modified or revised if the plan for achieving the RAOs is failing. Such failure may be identified when interim milestones are not achieved, even after corrective action. Contingent actions identified in the exit strategy decision logic would then be implemented.

A well-developed exit strategy contains six elements:

1. DD for the remedial activity goals,
2. Summary of the CSM, including a description of the future site land use,
3. Decision logic, flow chart, or defined sequence of remedial activities and contingency triggers,

[2] ITRC. (2006). *Exit Strategy–Seeing the Forest Beyond the Trees.*

4. Clearly established process to evaluate performance relative to the decision parameter,
5. Provisions for periodic re-evaluation of the project goals and remedial activity decisions (e.g., contingency planning), and
6. Means to verify cleanup following cessation of active remediation.

Because it is difficult to optimize any element of a remedial decision if the overall objectives (remediation end points) and site-specific technical constraints are not well understood, any optimization effort should begin with an evaluation of the exit strategy, which incorporates the previously listed six elements.[3] For more information, see ITRC guidance (ITRC, 2004 and 2006).

9.1.3 Performance and Optimization

9.1.3.1 Performance Models

The Contractor shall develop performance models for all sites listed in Table 1 of this PWS and the work described in Section 1.3.2 that are not currently in LTM status. The PMP and work planning documents shall contain the performance models. Final performance models shall be submitted as part of the WP required under PWS Section 7.1.1. Performance models shall describe how site conditions are expected to change over time, using appropriate performance indicators, from the current state through PO achievement. The Contractor shall add all new data to the performance model and provide annual Performance Model Evaluation Reports, which demonstrate whether the remedial response is progressing and performing consistently with the performance model.

Performance model and site management approach shall incorporate the following:

- Development and documentation of the approach to determine remedial progress relative to the defined performance indicators, associated decision criteria, and objectives consistent with the performance model. The documented approach is expected to facilitate decisions about optimization as well as provide a quantifiable understanding of how the response is progressing, list contingency options, and demonstrate when the objective has been reached. An individual site may have more than one performance model (e.g., different parts of the site that are addressed by separate remedies and represented by different sets of monitoring wells). Contingencies must be developed for performance that does not achieve interim milestones. These contingencies must be identified in the exit strategy. The Contractor must inform AF of any contingency being implemented and receive AF approval before implementation.
- Demonstrate an understanding of the site-specific CSM as it relates to the operation of existing systems, distribution of contaminants, and remedy effectiveness and degradation rates (see details on the definition of CSM in Section 9.1.1). Update the CSM using DQOs as needed based on performance and monitoring data throughout the PP and implement remedy contingencies as warranted by the evolving CSM. Submit updated CSMs after receipt of new information.

[3] ITRC. (2004). *Remediation Process Optimization: Identifying Opportunities for Enhanced and More Efficient Site Remediation.*

- Develop an exit strategy that identifies and implements opportunities to improve remedy protectiveness, effectiveness, and cost efficiency, and to facilitate progress toward the end goal of the exit strategy, including innovative technologies. The goal is to accelerate contaminant reduction, thereby minimizing future AF liability and cost to the greatest degree feasible. Update the exit strategy as dictated by site progress throughout the PP. Submit updated remediation strategies after receipt of new information.
- Develop baselines and performance models for all contaminants, including degradation products (e.g., vinyl chloride), that are regulated. These models should describe the historic and expected course of the remedial progress (i.e., how conditions are expected to change over time as demonstrated by appropriate performance indicators) from the current baseline state through PO achievement.
- Define the baseline state for each COC. The baseline state is determined using select monitoring wells representative of the site with sufficient data to develop statistics-based historic concentration trends for site COCs. A scientific approach that uses a line of best-fit (e.g., first-order decay rate) is appropriate for estimating the baseline attenuation rate. The baseline attenuation rate, in turn, can be used to extrapolate a baseline concentration to the end of the PP. Supporting information for the baseline concentrations shall include the rationale for the well selection and the time period used to develop the trends, justification for the selected line of best-fit, actual values used to define the trend, and extension of the line of best-fit to predict values for future years independent of future remedy implementation plans. For additional details on the development of baselines, refer to the ORC PMP Guidance.
- Using the baseline as a starting point (above), develop a scientifically based remedial performance model for each COC. The performance model shall be representative of the contaminant extent being addressed and include performance indicators, decision criteria, and annual and final goals achievable within the PP. The AF will scrutinize selected performance indicators to ensure they demonstrate achievement of response objectives and not merely progress. The Performance Model shall also be used to maintain or return the performance of a remedy as described by the model. The Performance Model shall indicate performance milestones that will be used to determine if the remedy is achieving the projected change in the performance indicator. Goals should be consistent with the performance model used to optimize remedial efficiency, quantify how the response is progressing, and demonstrate when the annual and final goals have been achieved. The performance model shall show projected changes to the site performance indicator(s) based on an assumed rate of change (e.g., an estimated biodegradation rate constant). Subsequent changes to the performance model will only be permitted at the discretion of the AF.

  Performance Models will identify at least three (3) ranges, subject to AF approval:

  1. Ideal-to-acceptable performance
  2. Process-improvement-and-corrective-action range requiring modifications to the remedy to return to acceptable performance, and
  3. Process-failure-and-contingency action range requiring implementation of an acceptable option to the current remedy.

The Contractor shall specify the number of consecutive data points that would trigger corrective action.

- Sites with a PO of RA-O with Optimization will have payment tied to achieving performance at the interim milestone and final milestones. This requirement applies only to sites in the categories defined in Sections 1.2.4 and 1.2.5. Milestone payments are contingent upon meeting or exceeding annual performance goals in accordance with the approved performance model.
- The Performance Model Evaluation Report should include the analytical data for performance indicators, the method for determining the value of the performance indicator, the performance model graph with results plotted and showing the ranges discussed above, a thorough discussion of supporting data, and a discussion of any modifications to the remedy that will be required in the immediate or near-term.
- Refer to the ORC PMP Guidance for additional information on the creation and use of performance models.

9.1.3.2 Optimization Benefits Reporting

The Contractor shall achieve the following objectives for sites described in Section 1.2.4 and Section 1.2.5. The Contractor shall document and submit all optimization actions implemented on an annual basis as required in the Optimization Benefits Template. The AF defines optimization, under the ORC, as the reduction of contaminant mass and concentrations, reduction in LCC, or any combination of activities prompting acceleration to RC, as a result of remedial implementation the Contractor undertakes, above and beyond what is required to maintain compliance in accordance with an approved DD. The Contractor is encouraged and required to implement potential optimization opportunities at all sites where the Contractor can successfully accelerate the achievement of the PO. This requirement will allow the AF to fulfill the DoD requirement to accurately account for accelerated contaminant removal and cost savings (i.e., reduction in liability) because of optimization activities.

9.1.3.3 Optimization Summary and Forecasting

The Contractor shall achieve the following objectives for sites described in Section 1.2.4 and Section 1.2.5. The Contractor shall deliver one Optimization Summary and Forecasting Report two years prior to the PoP end date. The Optimization Summary and Forecasting Report shall:

- Document what remedial strategies were implemented, what remains to be implemented to achieve RC and/or SC after the ORC PP ends, and any modifications arising from performance to date.
- Identify post-PoP out-year requirements associated with the probable site progression pathway, including transition of remedies, abandonment of infrastructure (e.g., piping, wells), monitoring, and maintenance through achievement of RC.
- Document a remedy-focused CSM updated with recent monitoring data reflecting the progress of the implemented remedy and supporting the expected future progress of the remedy.
- Provide a realistic schedule to achieve SC or RC after the PoP (the Contractor shall identify which PO is the optimal endpoint).

9.2 Transition of Work

Activities will transition to this contract upon completion of the current Contractor's field support and/or final deliverable on sites noted in the tables below. The Contractor shall ramp up management of this contract to ensure seamless operations of existing systems and no lapses in service.

The Contractor shall cease all sampling activities at least six (6) months before the end of the PoP to allow for sample validation and final invoicing activities.

9.2.1 Table 2: Transition of Work

Contract Number	Agency / Contractor / PoP End	Final Expected Endpoint
Eglin AFB		
W912EP-16-D-0008 / W91278-21-F-0021	USACE Mobile / BHATE ZAPATA / 07/12/2027	CF288: RI DP009: LTM DP084: LTM DP261: LTM FT028: RA-O LF003: RA-O LF005: RA-O LF008: LTM LF010: LTM LF051: RA-O OT083: LTM OT100: LTM OT262: LTM OT263: LTM OT264: LTM OT265: LTM OT269: LTM OT270: LTM OT271: LTM POI523: LTM SS025: LTM SS026: LTM SS086: LTM SS278: LTM SS281: RA-O SS283: RC ST069: RA-O
W91278-20-D-0019/ W91278-21-F-0481	USACE Mobile / Petroleum Resources & Development, Inc.	SS313: RAP
Hurlburt Field		

Contract Number	Agency / Contractor / PoP End	Final Expected Endpoint
W912EP-16-D-0008 / W91278-21-F-0021	USACE Mobile / BHATE ZAPATA / 07/12/2027	CG219: RI LF013: LTM LF014: LTM LF015: LTM LF016: LTM LF017: LTM LF018: LTM LF019: LTM LF020: LTM SS125: RA-O ST123: RA-O
Tyndall AFB		
W912EP-16-D-0008 / W91278-21-F-0021	USACE Mobile / BHATE ZAPATA / 07/12/2027	DA046: RIP FR038: LTM FT016: iROD FT017: iROD LF006: ROD LF007: ROD OT029: ROD OW217: iROD OW582: ROD SS015: iROD SS026: iROD TA523: RIP TU205: iROD TU233: RA-O
W9128F-19-D-0014 / W91278F-21-F-0140	USACE Omaha/ EA Engineering, Science, and Technology / 06/23/2028	SR169: No Action ROD SR170: FS SR170A: RC TS183: RIP

9.2.2 Table 3: Sampling Transition

Site ID	Contract (PoP End)	Final RA-O/ LTM Event under Existing Contract	Expected Date of Last Sampling Event under Existing Contract	Existing Contract Final Reports/ Outcome	Next Expected Sampling Event under ORC
Eglin AFB					

Site ID	Contract (PoP End)	Final RA-O/ LTM Event under Existing Contract	Expected Date of Last Sampling Event under Existing Contract	Existing Contract Final Reports/ Outcome	Next Expected Sampling Event under ORC
DP009 DP084 DP261 FT028 LF003 LF005 LF008 LF010 LF051 OT083 OT100 OT262 OT263 OT264 OT265 OT269 OT270 OT271 POI523 SS025 SS026 SS086 SS278 SS281 SS283 ST069	July 2027	Annual LUC Inspections	Nov/Dec 2026	Annual LUC Inspection Report	Nov/Dec 2027
ST069	Jul 2027	Semi-Annual Groundwater Sampling	Aug 2026	Annual Performance Monitoring Report	Aug 2027

Hurlburt Field					
LF013 LF014 LF015 LF016 LF017 LF018 LF019 LF020 ST123	Jul 2027	Semi-Annual LUC Inspections	Nov/Dec 2026	Annual LUC Inspection Report	Nov/Dec 2027
SS125	Jul 2027	Performance Monitoring Event	Jul 2025	Remedial Action Interim Report	Mar 2028
Tyndall AFB					
FR038	Jul 2027	Annual Land Use Control (LUC) Inspection	Mar/Apr 2026	Annual LUC Report	Apr/May 2027
SR170A	Jun 2028	Annual LUC Inspection	Apr 2028	Annual LUC Report	Apr 2029
TS183	Jun 2028	Annual Groundwater Sampling/LUC Inspection	Aug 2027	Annual Groundwater Sampling/LUC Inspection Report	Aug 2028

9.3 Environmental Construction

The Contractor shall perform construction, restoration, and demolition of utilities, real property systems, and infrastructure in support of environmental restoration requirements as required to achieve the POs of this contract. Construction and demolition activities shall conform to applicable AF, USACE, and other federal, state, and local standards and regulations, including Installation-specific regulations. The Contractor shall erect or install support buildings, equipment enclosures, and storage facilities for construction materials and contaminated material awaiting disposal as permitted by the Installation.

9.3.1 Design

A conceptual design (typically 10 - 30% design) for environmental projects may be provided to the Contractor for completion of the design and then construction. This work may be provided in phases. The Contractor is accountable for all aspects of the final design under federal, state, and applicable local laws. All completed designs shall be signed and sealed in accordance with all applicable requirements. The Contractor shall complete project working drawings and the various plans and schedules, including a construction schedule, and obtain submittal approvals and permits. Working drawings and specifications shall comply with codes, laws, and the request for proposal requirements. The working drawings shall be submitted for AF review.

The Contractor shall assist with coordinating regulatory reviews and responding to regulatory comments, shall ensure technical adequacy of the final design, and shall provide QC of all phases of the contract.

9.3.2 Inspection

Upon completion of the final construction, the Contractor shall conduct a pre-final walk-through inspection and publish the pre-final inspection findings in a pre-final inspection report.

The Contractor shall conduct a final inspection and publish the findings in a final inspection report. The inspection shall concentrate on the items identified at the pre-final inspection and recorded in the pre-final report. The final inspection report shall (1) certify that all items of the design have been implemented and that the construction is complete and (2) include a record of "signed and sealed" as-built drawings and specifications verifying that all development standards have been met. At the final inspection, the Contractor shall present a completed DD Form 1354, Transfer and Acceptance of Real Property to the Base Civil Engineer or other appropriate organization for signature and approval.

9.3.3 Delivery and Warranty

The Contractor shall complete all inspection and commissioning requirements prior to the final inspection. The warranty shall be issued in accordance with FAR 52.246-21. Extended warranties offered by the Contractor and its subcontractors or suppliers may be accepted at the Government's discretion. The Contractor shall review installed equipment and prepare a repository of equipment/systems with information such as scheduled maintenance, compatibility with existing systems, vendor sources, and warranty expiration dates for all systems installed at sites that will not achieve site closure by the end of the PoP. The Contractor shall also provide system O&M manuals and parts lists to the Government.

9.4 Environmental Resources Program Information Management System

The Contractor shall comply with the ERPIMS data requirements for all field-derived data/information supported by the ERPIMS data structure. This includes, but is not limited to, sampling data, remediation system identification data, remediation technology performance data, relevant QA/QC data, lithology, groundwater, monitoring well location, well construction, well maintenance, and/or abandonment information. After receipt of the contract, the Contractor shall submit an ERPIMS Data Submission Schedule within 30 calendar days of award to establish the projected framework for ERPIMS data submissions. The Contractor shall record and enter field and laboratory data and submit this data as specified in the latest ERPIMS Data Loading Handbook (DLH) using the latest version of the ERPIMS software utility (ERPTools). ERPIMS data submissions are required within 90 calendar days of the conclusion of each sampling event unless a written waiver or extension is obtained from the CO/KO in coordination with the AFCEC Environmental Restoration Branch Chief. The AFCEC website (address provided under separate cover) offers the latest DLH, ERPTools client software, ERPIMS policy, ERPIMS Help Desk contact info, data submission requirements, ERPTools training schedules, and more. Data submissions shall be error-free, pass all validation checks, and fully comply with the ERPIMS DLH. The Contractor shall ensure that any required corrections are accomplished within the contract PoP and before funds expiration. The preferred procedure is for laboratories to use ERPTools to input/submit chemistry data for initial validation, import, and submission by the Prime Contractor. ERPTools training is available to prime and laboratory Contractors. All ORC

milestones that include analytical sampling shall include successful ERPIMS loading of all relevant ERPIMS data elements into the production database as a minimum acceptance criterion.

9.5 Innovative and Proven Technologies

The Contractor shall, to the extent reasonably practical, plan, design, construct, operate, monitor, and decommission innovative environmental remediation, monitoring, and other technologies as required to achieve the POs of this contract. The AF seeks technologies and methodologies that are innovative, sustainable, cost-effective, and will lead to accelerated closure of environmental sites.

9.6 Operations and Maintenance

The Contractor shall perform RA-O/O&M requirements following DQOs in accordance with Section 5.1. The Contractor shall be responsible for the operation, maintenance, repair, replacement, and installation of new wells, as well as for the monitoring, optimization, and evaluation of both in-place and proposed environmental systems and well networks throughout their active life. This shall include all materials required to replace any exhaustible process materials required to operate and maintain the individual processes specified in the system O&M manuals and equipment manufacturer specifications. The Contractor shall provide system O&M manuals and parts lists to the Government within 90 calendar days of system installation or modification. The Contractor shall provide an O&M manual within 180 calendar days for systems that do not have an O&M manual or for which the existing manual is deficient. The Contractor shall be responsible for training maintenance personnel in system operations. The Contractor shall ensure that the operation of the environmental system is optimal and effective at achieving system goals.

The Contractor shall review installed equipment and prepare databases of equipment/systems with information such as scheduled maintenance, compatibility with existing systems, vendor sources, and warranty expiration dates for all systems installed at sites that will not achieve SC by the end of the PoP. The Contractor shall maintain a complete inventory of system as-built drawings (in hardcopy and electronic) and shall update the drawings in red-line based on revisions to the systems.

9.7 MPPEH Removal and Support

Small Arms Ammunition Range Removal and Support

The Contractor shall conduct annual LUC inspections at MMRP sites identified in Table 1 of the PWS to achieve the POs of this contract. If, during the LUC inspections, MPPEH is encountered, the Contractor shall immediately follow the instructions in Section 4.9 of this PWS and inform the RPM.

9.8 Hazardous/Non-Hazardous Waste Removal and Support

The Contractor shall destroy, recycle, and dispose of hazardous/non-hazardous waste and material and provide all hazardous materials use and hazardous waste disposal documentation to AFCEC, COR, and Installation RPM(s). An AF representative will sign all hazardous material/waste manifests. The Contractor shall perform associated investigative work and support activities required for waste management.

9.9 Study Effort Incidental to Remedy or Corrective Action

The Contractor may engage in supplemental study work in pursuit of a remedy or corrective action. This may include, but is not limited to, (1) performing bench-scale and pilot-scale studies of remediation technology, and (2) drafting new DDs (e.g., ROD Amendment, ESD, RCRA Permit modification).

9.10 Five-Year Review Support

In accordance with AF policy, the Contractor shall support Five-Year Reviews (e.g., supplying documents to independent reviewers, attending site inspections, and participating in meetings/interviews) of all RAs, including non-CERCLA cleanup actions using the USEPA guidance document "Comprehensive Five-Year Review Guidance," OSWER No 9355.7-03B-P, June 2001. The Contractor shall also be responsible for implementing findings, recommendations, and/or deficiencies documented in a Five-Year Review, which have been identified in the GFI, for any site identified in Table 1 and work described in Section 1.3.2. The Five-Year Review will be prepared by an independent contractor outside of this ORC.

9.11 Identification of New Site

If, during the course of site activities, the Contractor discovers contamination that appears to not be related to the existing sites, the Contractor shall first notify the CO/KO in writing and copy the PM/COR, AFCEC RPM, and AFCEC PM. The Contractor shall collect additional data, as required by the PM/COR and AFCEC RPM, and provide conclusive documentation that supports contamination is not associated with an existing site.

9.12 Change and Differing Conditions

The Contractor shall identify changes in condition (FAR 52.243-5) and/or differing site conditions (FAR 52.236-2) stated in this PWS and other requirements for this ORC and promptly notify the CO/KO and PM/COR verbally and in writing before conditions are disturbed and before any cost or schedule impact is incurred by the Contractor. If notification and reporting requirements stated in the FAR are not completed in the stated timeframe and manner, the Government will not be obligated to acknowledge/approve the change in condition, and the Contractor may not receive compensation.

9.13 Other Provisions

The Contractor shall notify the PM/COR, AFCEC RPM, AFCEC Program Manager, and the AF Authorized Representatives within three business days of becoming aware of the occurrence of an event described below:

1) Contractor or any agent or subcontractor receives notice of violation of any Governmental enactment, requirement, or authorization, which relates to the performance of the PWS;
2) Permits, licenses, or other Governmental authorizations relating to implementation of the PWS are revoked or denied;
3) Litigation is commenced or threatened concerning or impacting the PWS or any sites;
4) Any other condition occurs or is threatened to occur which may have a materially adverse effect on the timely performance of the PWS, or the timely performance of any duties the

Contractor or the AFB may have under any applicable law, regulation, ordinance, order, decree or plan;

5) The AFB personnel are interfering or wrongfully preventing Contractor from performing its material duties and obligations under this PWS or to such an extent that the Contractor's costs are being adversely impacted.

9.14 Key Personnel

The Contractor shall propose and provide qualified key personnel for the critical project functions identified for the work in this PWS for the duration of the contract. No changes to individuals serving as key personnel may be made post award without concurrence by the PM/COR and approval of the CO/KO. All changes to personnel serving in critical project functions must maintain the standards and requirements stated in this PWS. Critical project functions are functional roles that may be held by any labor category in the Contract and are defined by education, training, experience, and professional certification. Key Personnel critical project functions for this ORC work include the following positions:

a. Program Manager
b. Senior Project Manager(s)
c. Senior Site Manager(s)
d. Contracts Manager
e. Program QA/QC Manager
f. Program Risk Assessor
g. Program Health and Safety Manager
h. Program Chemist
i. Public Affairs Officer
j. Project Controls Manager
k. Project Scheduler
l. Security Manager

10.0 Performance Standards and Surveillance Activities

The AF and USACE will utilize the QA activities to define the procedures and guidelines to evaluate the technical and quality performance of the Contractor in accordance with this PWS. The QA activities ensure that the work, including that of subcontractors and suppliers, complies with the regulatory and contractual requirements, and documents all the various activities required to achieve completion of AFCEC CLINs/Sub-CLINs and contract requirements not associated directly with an AFCEC CLIN/Sub-CLIN are being accomplished, tracked, and surveilled.

The Contractor is fully responsible for executing the work under this contract and supervising/directing the work of subcontractors. Surveillance of Contractor performance and compliance shall be completed in accordance with the PWS. The Government's contractual relationship and oversight responsibilities are only with the Contractor.

11.0 POINTS OF CONTACT

ORC POCs will be specified upon contract award, presented at the ORC kickoff, and documented in the programmatic Base-wide UFP-QAPPs.

12.0 CONTRACTOR MANPOWER REPORTING REQUIREMENTS

12.1 Contractor Manpower Reporting Requirements

The Contractor shall report ALL Contractor labor hours (including subcontractor labor hours) required for performance of services provided under this contract for the AF via a secure data collection site. The Contractor is required to completely fill in all required data fields at https://sam.gov/content/entity-reporting.

Reporting inputs will be for labor executed during the PoP for each Government FY. The Government FY is from 1 October through 30 September. While inputs may be reported any time during the FY, all data shall be reported no later than 31 October of each calendar year. Contractors may direct questions to the SAM.gov Help Desk.

The required information includes: (1) Contracting Office, CO/KO, COR; (2) Contract number, including task and delivery order number; (3) Beginning and end dates covered by reporting period; (4) Contractor name, address, phone number, e-mail address, identity of Contractor employee entering data; (5) Estimated direct labor hours (including subcontractor); (6) Estimated direct labor dollars paid this reporting period (including subcontractor); (7) Total payments (including subcontractor); (8) Predominant Federal Service Code (FSC) reflecting services provided by Contractor (and separate predominant FSC for each subcontractor if different); (9) Estimated data collection cost; (10) Organizational title associated with the Unit Identification Code (UIC) for the Army Requiring Activity (the Army Requiring Activity is responsible for providing the Contractor with its UIC for the purposes of reporting this information; (11) Locations where Contractor and subcontractors perform the work (specified by zip code in the United States and nearest City, Country, when in an overseas location, using standardized nomenclature provided on website); (12) Presence of deployment or contingency contract language; and, (13) Number of Contractor and subcontractor employees deployed in theater this reporting period (by country).

As part of its submission, the Contractor shall also provide the estimated total cost (if any) incurred to comply with this reporting requirement. Reporting period will be the PoP not to exceed 12 months ending 30 September of each Government fiscal year and must be reported by 31 October of each calendar year.

Uses and Safeguarding of Information: Information from the secure website is considered to be proprietary in nature when the contract number and Contractor identity are associated with the direct labor hours and direct labor dollars. At no time will any data be released to the public with the Contractor name and contract number associated with the data.

User Manuals: Data for AF service requirements must be input at the SAM.gov link https://sam.gov/content/entity-reporting.

12.2 Veterans Employment

Emphasis for USACE Contracts: In addition to complying with the requirements outlined in FAR Part 22.13, FAR Provision 52.222-38, FAR Clause 52.222-35, FAR Clause 52.222-37, DFARS 222.13 and Department of Labor regulations, USACE Contractors and subcontractors at all tiers are encouraged to promote the training and employment of U.S. veterans while

performing under a USACE contract. While no set-aside, evaluation preference, or incentive applies to the solicitation or performance under the resultant Contract, USACE Contractors are encouraged to seek out highly qualified veterans to perform services under this Contract. The following resources are available to assist USACE Contractors in their outreach efforts:

- Federal Veteran employment information at https://www.fedshirevets.gov
- Department of Labor Veterans Employment Assistance http://www.dol.gov/vets
- Department of Veterans Affairs–VOW to Hire Heroes Act http://benefits.va.gov/vow
- Army Wounded Warrior Program – http://wtc.army.mil/modules/employers/index.html
- U.S. Chamber of Commerce Foundation–Hiring Our Heroes https://www.uschamberfoundation.org/hiring-our-heroes
- Guide to Hiring Veterans – Reference Material https://obamawhitehouse.archives.gov/blog/2012/04/10/white-house-business-councils-guidehiringveterans

12.3 Sustainability Requirements

Green Procurement is the purchase of environmentally preferable products and services and is known as sustainable acquisitions and Green Procurement. Practicing Green Procurement takes into consideration economic facets, environmental considerations, and resource efficiency.

Here are some of the benefits of Green Procurement:

- Prevents pollution and reduces environmental impact,
- Increases Eglin AFB, Hurlburt Field, and Tyndall AFB energy independence,
- Protects and conserves natural resources,
- Minimizes waste,
- Supports new markets and job creation,
- Supports the USACE Campaign Plan and Sustainability Plan Goals,
- Saves money by reducing waste,
- It is a federal mandate

Some Mandatory Environmental Initiatives are as follows:

- Energy Star,
- Federal Energy Management Program (FEMP)-Designated Products,
- WaterSense,
- BioPreferred/Biobased,
- Environmentally Preferable Purchasing (EPP),
- Electronic Product Environmental Assessment Tool (EPEAT),
- Significant New Alternatives Policy (SNAP),
- Recovered Materials,

FAR Part 23 requires Federal agencies to ensure that 95% of new contract actions require products that are:

- Energy-efficient,

- Biobased,
- Non-ozone depleting,
- Water-efficient,
- Environmentally preferable,
- Made with recovered materials,

The Contractor shall review and follow scope, purpose, applicability, and policy of FAR Part 23 and FAR 52.223-4 requirements, as they pertain to their specific Contract requirements to meet sustainability acquisitions or Green procurement initiatives. Some examples of sustainability achievements are:

- Car-pooling to meeting from local offices,
- Doubled-sided documents using recycled paper,
- Submittal of documents through electronic methods,
- Use of energy-efficient products,
- Use of non-toxic or low-toxic products,
- Reconditioned or remanufactured supplies or materials,

POs have been identified for each of the sites (refer to PWS Site Summary Table below) and other support tasks. These are intended to inform the Contractor of work that is to be accomplished at the sites.

13.0 Period of Performance

The Florida Panhandle ORC Group has a total PoP of ten (10) years, with no individually funded AFCEC CLINs/Sub-CLINs extending beyond the five (5) year life of funds. Individually funded AFCEC CLINs and AFCEC Sub-CLINs will have Performance Periods assigned based on the timeframes stated in this PWS.

PAST PERFORMANCE EVALUATION QUESTIONNAIRE (L001)

INSTRUCTIONS TO OFFERORS SENDING REFERENCE QUESTIONNAIRE FORMS:

Section A (Part I and Part II) shall be completed by the Offeror (the firm requesting the reference) prior to issuing the questionnaires. The Offeror shall send the questionnaires for projects that are in progress or completed in the past four (4) years to the individuals who will provide the reference. For Government contracts, send to the Contracting Officer (KO) or KO's Contracting Specialist. For commercial references, send to personnel with duties similar to those for Government contracts. It is the responsibility of the Offeror to follow-up and encourage references to submit the questionnaire. The completed questionnaire shall be submitted via e-mail directly from the person providing the reference.

INSTRUCTIONS TO PERSON PROVIDING REFERENCE:

In order to assess potential vendors, the USACE contracting office is obtaining past performance information with respect to each Offeror. As a reference for work performed by the firm identified in Section A of this questionnaire, your candid response will assist in the evaluation process. Please complete Section B (Part I and Part II) of the questionnaire as thoroughly as possible. The subject line in the submission e-mail shall clearly indicate: FY27 Florida Panhandle Group Optimized Remediation Contract Past Performance Questionnaire Submission for <Company Name> and the message shall originate from the reference's government or commercial e-mail system.

In addition to this questionnaire, you may receive a follow-up phone call to confirm or clarify information. Your input into this evaluation is greatly appreciated. If you have questions regarding this questionnaire or require assistance, please submit inquiries to the KO or KO's Contracting Specialist.

SECTION A TO BE COMPLETED BY OFFEROR (THE FIRM REQUESTING THE REFERENCE)
PART I: PROGRAM OFFEROR INFORMATION
COMPANY NAME OF OFFEROR:
OFFEROR ADDRESS:
COMPANY NAME OF SERVICES PERFORMING TEAM MEMBER FOR THIS REFERENCE (IF APPLICABLE):
TEAM MEMBER ADDRESS:

PART II: PAST PERFORMANCE INFORMATION
TITLE OF PROJECT/CONTRACT NUMBER FOR WHICH REFERENCE IS REQUESTED:
AGENCY/CUSTOMER
CONTRACT/ORDER/SUBCONTRACT/ OTHER:
CONTRACT TYPE: (Check all that apply) ☐ **FP** ☐ **CPFF-Completion** ☐ **CPFF-Term** ☐ **CPIF** ☐ **CPAF** ☐ **IDIQ/Task Order** ☐ **Requirements** ☐ **Labor-Hour** ☐ **T&M** ☐ **CR** ☐ **Other (Specify)** _____
DATE OF AWARD:
PERIOD OF PERFORMANCE (INCLUDING OPTIONS):
CONTRACT AMOUNT: • **INITIAL CONTRACT DOLLAR VALUE (W/OPTIONS)**: _____ • **FINAL CONTRACT DOLLAR VALUE (W/OPTIONS):** _____
ROLE ON PROJECT: ☐ **PRIME** ☐ **SUBCONTRACTOR (EXPLAIN TYPE AND EXTENT OF SUBCONTRACTING, IF APPLICABLE):** ☐ **OTHER (EXPLAIN)**

GENERAL DESCRIPTION OF TYPE OF SERVICES/PRODUCTS REQUIRED UNDER THE CONTRACT:

NOTE: These two sections are limited to two (2) pages.

DESCRIBE COMPLEXITY OF WORK:

Tasks of moderate complexity included:

Tasks of high complexity included:

SECTION B TO BE COMPLETED BY EVALUATOR (PERSON PROVIDING REFERENCE)
PART I: REFERENCE INFORMATION
NAME & TITLE:
ORGANIZATION (INCLUDING AGENCY AND/OR COMPANY):
CONTRACT ROLE (e.g. CO, COTR):
ADDRESS:
PHONE NUMBER:
FAX NUMBER:
E-MAIL:

PART II: INFORMATION ABOUT PROJECT/CONTRACT FOR WHICH REFERENCE IS REQUESTED
Please identify and correct any information that is not accurate in Section A.
Please objectively assess the requesting firm in each performance element below by assigning an "X" to the most appropriate rating as described below:

Performance Element	Exceptional	Very Good	Satisfactory	Marginal	Unsatisfactory
1. Technical Performance / Quality of Service	· Met all performance requirements / Exceeded 20 % or more · Minor problems / Highly effective corrective actions / Improved performance/quality results	· Met all performance requirements / Exceeded 5% or more · Minor problems / Effective corrective actions	· Met all performance requirements · Minor problems / Satisfactory corrective actions	· Some performance requirements not met · Performance reflects serious problem / Ineffective corrective actions	· Most performance requirements are not met · Recovery not likely
Assessment (Check Box)	☐	☐	☐	☐	☐
2. Cost Control	· Significant reductions while having met all contract requirements · Use of value engineering or other innovative management techniques · Quickly resolved cost issues /	· Reduction in overall cost/price while having met all contract requirements · Use of value engineering or other innovative management techniques · Quickly resolved cost/price issues /	· Met overall cost/price estimates while having met all contract requirements	· Do not meet cost/price estimates · Inadequate corrective action plans / No innovative techniques to bring overall expenditures within limits	· Significant cost overruns · Not likely to recovery cost control

	Effective corrective actions facilitated cost reductions	Effective corrective actions to facilitate overall cost/price reductions			
Assessment (Check Box)	☐	☐	☐	☐	☐
3. Schedule (Timeliness)	· Significantly exceeded delivery requirements (All on-time with many early deliveries to the Government's benefit) · Quickly resolved delivery issues / Highly effective corrective actions	· On-Time deliveries / Some early deliveries to the Government's benefit · Quickly resolved delivery issues / Effective corrective actions	· On-time deliveries · Minor problems / Did not effect delivery schedule	· Some late deliveries · No corrective actions	· Many late deliveries · Negative cost impact / Loss of capability for Government · Ineffective corrective actions / Not likely to recover
Assessment (Check Box)	☐	☐	☐	☐	☐
4. Business Relations	· Highly professional / Responsive / Proactive · Significantly exceeded expectations · High user satisfaction · Significantly exceeded SB/SDB subcontractor goals · Minor changes implemented without cost impact / Limited change proposals / Timely definitization of change proposals	· Professional / Responsive · Exceeded expectations · User satisfaction · Exceeded subcontractor goals · Limited change proposals / Timely definitization of change proposals	· Professional / Reasonably responsive · Met expectations · Adequate user satisfaction · Met subcontractor goals · Reasonable change proposals / Reasonable definitization cycle	· Less Professionalism and Responsiveness · Low user satisfaction / No attempts to improve relations · Unsuccessful in meeting subcontractor goals · Unnecessary change proposals / Untimely definitization of change proposals	· Delinquent responses / Lack of cooperative spirit · Unsatisfied user / Unable to improve relations · Significantly under subcontractor goals · Excessive unnecessary change proposals to correct poor management · Significantly untimely definitization of change proposals

Assessment (Check Box)	☐	☐	☐	☐	☐

FOR #5, PLEASE ANSWER "Yes" or "No", as appropriate **5.** Given the choice, would you do business with this contractor again?	YES	NO
6. Additional comments you would like to share		

SIGNATURE _____ **DATE:** _____

SECTION L

PROPOSAL SUBMISSION REQUIREMENTS AND INSTRUCTIONS

1. GENERAL REQUIREMENTS

This is a Revolutionary Federal Acquisition Regulation (FAR) Overhaul (RFO) Part 15, competitive, best value, source selection. Competing contractors, hereinafter referred to as "Offeror", shall submit a proposal that includes the required submission information indicated below to demonstrate the Offeror's technical capabilities to perform the work described in this solicitation. In addition, each Offeror shall also include its price and other administrative information described below. By submission of a proposal, the Offeror accedes to all the terms of this request for proposal (RFP). It is imperative that Offerors review the RFP and all related information thoroughly before preparing their proposal.

The Government reserves the right to reject any and/all offers.

2. WHO MAY SUBMIT

Any firm that participated in preparation of this solicitation, whether as a Government contractor or as a subcontractor to a Government contractor, is not eligible to participate in this solicitation as a prime contractor or a subcontractor due to a conflict of interest. The Government considers such firms to have an unfair competitive advantage and therefore will not consider such firms.

3. REQUEST FOR INFORMATION (RFI)

Any questions about this solicitation, including technical questions about the Technical Provisions (TP's), shall be submitted via the Bidder Inquiry Portal in ProjNet at https://www.projnet.org/projnet. Questions shall be submitted no later 30 October 2026, at 2:00pm CST to allow time for a response, and an amendment to the solicitation, if necessary. On this date and time, the portal will be closed. For technical questions, no other means of communication (e-mail, fax or telephone) will be accepted. Oral exchanges between Offerors and the Government prior to award of the contract will not be binding. In addition to the information available to the Offerors on the Bidder Inquiry Portal, any information concerning this solicitation will be furnished to all Offerors as an amendment to the solicitation if the information is necessary to the submittal of offers.

To submit and review inquiries, an Offeror needs to be a current registered user of the ProjNet system. To register, go to https://www.projnet.org/projnet, click the "BID" tab, select "Bidder Inquiry", select agency "USACE", enter the "Bidder Inquiry Key" for the solicitation listed below, and your e-mail address, and then click login. Complete all required information and then click "Create User". Verify that information on the next screen is correct and click "Continue".

From this page you can view all bidder inquiries for this solicitation or submit an inquiry. Offerors will receive an acknowledgement of their question via e-mail, and the Mobile District's technical team will post a response to the ProjNet system after it has been processed.

Solicitation Number is: W9127827RA002

Bidder Inquiry Key is: **9QF4AD-YBP4Y9**

Note: Any inquiry submitted and answered within this system, will be accessible to view by all interested Offerors on this solicitation.

If there are any conflicts between the solicitation and the responses provided in the ProjNet system, the solicitation governs. Changes to the solicitation will be made by amendment.

4. PROPOSAL SUBMISSION REQUIREMENTS

Submit the proposal package to the U.S. Army Corps of Engineers (USACE) following instructions in the RFP Letter. The Government must receive your proposal no later than the time and date specified in the RFP Letter. Proposals received after the required time and date deadline will be handled in accordance with (IAW) RFO 15.107. Offerors should not assume that they will have an opportunity to clarify or correct anything in their proposals after submitting it in response to the original Solicitation, so any submissions should be submitted on the best terms possible and free of errors. Any and all amendments to the solicitation shall be acknowledged by completion of SF 30 provided with the amendment.

4.1 Submittal Volumes

Submit the proposals in two separate volumes, labeled with quantities as follows:

Vol 1 – Technical Approach, Management Approach, and Performance
- Tab A – Technical Approach and Risk Management Approach
- Tab B – Project Management Approach, and Organization
- Tab C – Integrated Master Schedule
- Tab D – Past Performance of Prime Contractor

Vol 2 – Administrative Requirements/Price

4.2 Submittal Details

- Submit electronic copies in both pdf and native formats, i.e., MS Word, Excel, Primavera P6 via Procurement Integrated Enterprise Environment (PIEE).

- Each paragraph shall be single spaced and separated by at least one blank line. A standard, 12-point minimum font size applies. Times New Roman fonts are required. Font limitations do not apply to charts, tables, exhibits, and figures, but font must be legible. A page is considered one single sided 8.5” by 11” unless otherwise noted. 11” by 17” pages may be used to depict figures, tables, and exhibits.

- Page size shall be 8.5” x 11” for all pages except for the IMS, figures, tables, and exhibits which shall be 11” x 17”. In addition to pdf format, submit the AFCEC Contract Line-Item Number (CLIN)/Sub-CLIN pricing sheet in Microsoft Excel format, and submit the Integrated Master Schedule in Primavera P6 format. The pdf format version of the IMS

will be considered the master file should any of the native Primavera P6 files be altered after submittal to the government.

- The submission shall be clearly indexed and logically assembled. Each volume shall be clearly identified and shall begin at the top of a page. All pages of each volume shall be appropriately numbered (i.e., page x of x) and identified by the complete company name, date and Request for Proposal (RFP) number in the header and/or footer. A Table of Contents should be created using the Table of Contents feature in MS Word. Files shall use the following page setup parameters:

  Margins – Top, Bottom, Left, Right – 1”
  Gutter – 0”
  From Edge – Header, Footer 0.5”

To effectively and equitably evaluate proposals, the Source Selection Evaluation Board (SSEB) must receive information, in the order described below, that clearly describes an Offeror's approach and capabilities to successfully execute the Florida Panhandle Optimized Remediation Contract (ORC) program as required by this RFP. It is therefore an Offeror’s responsibility to submit proposal information that is fully responsive to the submission requirements of this section. Offerors are responsible for organizing material sequentially under tabs and numbered pages as set out below to facilitate evaluation. Materials that are not properly organized may easily be overlooked during evaluations, possibly affecting an Offeror’s rating. Offers should be concise, addressing only the information outlined in this section.

The Government intends to award without negotiations. Therefore, the offeror’s initial proposal should contain its best terms from a price and technical standpoint. However, the Government reserves the right to conduct negotiations if it is later determined by the Contracting Officer to be necessary. The Government may also issue clarification requests to offerors to resolve minor or clerical errors.

5. SPECIFIC PROPOSAL SUBMISSION INSTRUCTIONS

There are two separate volumes required in response to this solicitation. Volume I includes four (4) non-price evaluation factors. Volume II includes administrative requirements and proposed pricing.

TABLE 1 - EVALUATION FACTORS AND ORDER OF RELATIVE IMPORTANCE

Volume	Factor - Description	Relative Importance	Page Limitation
Vol I - Tab A	Factor 1 (2 total pages per each site (21 sites) as shown on Section 5.1, includes both site technical approach and risk management); 42 total pages for these sites (1a) Site Technical Approach and and (1b) Site Risk Management Approach	1st in relative importance; more important than Factor 2	Introduction – 1 page Sections (1a) and (1b) Tyndall AFB - 2 pages x 14 sites = 28 pages Eglin AFB – 2 pages x 4 sites = 8 pages Hurlburt Field – 2 pages x 3 sites = 6 pages
Vol I - Tab B	Factor 2 (2a) ORC Management Approach, (2b) ORC Organization, and (2c) Key Personnel (2d) Subcontractor Plan	2nd in relative importance; less important than Factor 1 and more important than Factor 3	(2a) – 5 pages (2b) - 1 page text and 1 page for chart (2c) – 1 page per position 2d – 1 page

Vol I - Tab C	Factor 3 – Integrated Master Schedule	3rd in relative importance; less important than Factor 2 and more important than Factor 4	IMS – No page limit
Vol I - Tab D	Factor 4 – Past Performance Information of the Prime Contractor or JV	4th in relative importance; less important than Factor 3	5 pages, excluding "quality of past performance"
Vol II	Administrative Requirements (Including Price)	Not Rated. Price evaluated by Price Analysis	No page limit

In general, the non-price factors (Volume 1) combined are significantly more important than price in relative importance and consideration.

5.1 Volume I – Tab A. Factor 1.– (1a) Project Technical Approach, and (1b) Risk Management Approach,

All narratives must contain sufficient detail to demonstrate an understanding of the condition of each site, the steps required to achieve the Performance Objectives (PO), and to demonstrate a reasonable approach that is capable of achieving the PO within the PP and remain compliant with site-specific, Government, Installation-specific and regulatory requirements. The narratives must address RFP submission requirements as detailed herein. Offerors are cautioned that "parroting" of the technical requirements of the Performance Work Statement (PWS) with a statement of intent to perform does not reflect an understanding of the requirement or capability to perform. Offerors are responsible for including sufficient details to permit a complete and accurate evaluation of each proposal by subject matter experts. Proprietary information shall be clearly marked.

The offeror may include a one (1) page introduction of the experience and capabilities of their company/JV. The introduction should focus on the following:

- Experience with executing/completing similar tasks to those identified in Table 1 of the PWS.
- Experience performing investigation and remediation work, including HTRW and MMRP projects, on a government contract, preferably at an Air Force installation in the state of Florida.
- Experience that demonstrates progression through the phases of work required by the PWS.
- Experience executing environmental restoration projects in accordance with Florida Administrative Code and US Air Force requirements.
- Experience that demonstrates progression through multiple phases of State cleanup programs for regulatory frameworks applicable to this ORC.

- Experience in design, implementation, and operation & maintenance (O&M) of treatment systems (e.g., pump and treat, air sparge/biosparge, soil vapor extraction, in-situ or ex-situ chemical oxidation, indoor air mitigation, etc.), capping, and soil excavations within the state of Florida in similar geological settings as those found at Eglin Air Force Base, Hurlburt Field, and Tyndall Air Force Base, Florida.
- Experience managing multiple, comingled areas of concern in different phases of investigation and cleanup that require more than one (1) remedial action or technology to be implemented, differing regulatory frameworks, and emerging contaminants.

Factor 1a – Technical Approach

The Offeror shall submit an AFCEC CLIN/Sub-CLIN -specific technical approach narrative to explain their approach to execute the unique complexities, challenges, opportunities, and constraints inherent to this ORC as required by the solicitation. Reference the PWS, attachments, and appendices for project information required by this solicitation. Address the following items at a minimum, in a narrative format:

The narrative for each AFCEC CLIN/Sub-CLIN must identify technical and regulatory sound approaches, the key decision points for strategy transitions, and the proposed metrics for measuring progress towards achieving site-specific PO's. Technical approaches must be described in sufficient detail to support Government evaluation of how all objectives and requirements in the PWS and other applicable agreements will be met or exceeded while ensuring protection of human and ecological health, maintaining regulatory compliance, and minimizing Air Force life-cycle costs. The technical approach must present a detailed methodology specific to each site AFCEC CLIN/Sub-CLIN that an individual knowledgeable of the site requirements, status, technologies, and regulatory framework would find acceptable. The Offeror's proposed approach must present a technically sound methodology that specifically addresses the site-specific issues tied to achieving the performance objective documented in the RFP and Air Force Administrative Record.

The technical approach will be reviewed to ensure it is consistent with the offeror's price proposal, including the level of effort and staffing.

Factor 1b Risk Management Approach

Offerors must present a site-specific risk management approach that includes a detailed assessment of each risk identified in the risk register, the likelihood of occurrence, severity of occurrence, Plan B mitigations, and threshold conditions/decision logic for initiating the implementation of the risk mitigation. Risk identification and mitigation must be comprehensive, detailed, technically reasonable, and demonstrate reduction of risk to the Government. Project risks include, but are not limited to, failure of the technical approach to effectively promote the site toward the PO within a reasonable timeframe, site access issues, regulatory review and approval, etc.

Factors 1a and 1b - Technical and risk management approaches shall be submitted for the sites listed below with a 2-page limit for each site. If the offeror elects to include more than one site in

a technical and risk management approach, the page limit is cumulative (e.g., two sites included in one technical/risk management approach will have a 4-page limit).; FY start dates are to be used in IMS preparation.:

- Eglin AFB – CF288, LF322, SS313, ST069
- Hurlburt Field – CG219, SS125, XU002 (MMRP)
- Tyndall AFB – DA046, LF006, LF007, OT018, OT029, OW217, SR169 (MMRP), SR170 (MMRP), SS015, SS026, TS183 (MMRP), TU204, TU205, TU233

Technical and risk management approaches are not required for Land Use Control (LUC)-only sites. All LUC-only sites can be combined and shown on 1 page, per installation
(1 page x 3 installations = 3 total pages)

Site-Specific technical approach narratives for the Florida Panhandle ORC shall be clear, concise, thorough, logically organized, and convincing.

5.2 Volume I – Tab B Factor 2 – Project Management Approach

The Project Management Approach Tab B shall include details for the overall organization, structural framework, and management of the ORC. Page limitation is presented in Table 1. Address the following items, in a narrative format:

(a) ORC Management Approach – Describe how project resources will be managed to achieve project performance objectives and to ensure consistency for the entire Florida Panhandle ORC.

Reference the PWS, attachments, and appendices for project information required by this solicitation. The ORC Management Approach narrative must address the following topics, at a minimum:

1) Management of multiple and concurrent events within the PWS scope,

2) Remediation technologies proposed and team experience with those technologies,

3) Procedures and processes ensuring submission of high-quality technical accurate documents and deliverables for change management, prime and subcontractor staffing management, sampling and analysis, and health and safety

4) Effective communication strategy between stakeholders (USACE, Air Force, regulators, Community, and others)

5) Procedures and processes to monitor, mitigate, and/or address management risks.

6) Key office and personnel locations supporting this ORC

7) ORC Information Portal approach and implementation

8) Methods for documenting field activities, data collection, etc.

In addition, the ORC Management Approach narrative must include the following components:

- Describe how the IMS will be prepared, managed, maintained, updated, and controlled through the period of performance (POP), and how schedule risk will be assessed and mitigated
- Describe the Project Control and Change Control processes to be used to manage the ORC, define configuration items and how changes to these will be managed.
- Describe the ORC Information Portal format platform and access methodology

(b) ORC Organization – Describe how the Florida Panhandle ORC will be organized, coordinated, and integrated to ensure effective execution. Describe, the ORC management organizational structure, lines of communication, and lines of authority. Include an organizational chart and ensure the information fully supports the narrative. The narrative should clearly describe the offerors' organizational approach to execute the work required by the solicitation.

(c) Key Personnel - Provide resumes for the positions identified in the Key Personnel criteria provided in the RFP. The Offeror shall only include resumes for the Key Personnel listed and individual resumes shall not exceed one (1) page in length. Key Personnel shall provide a resume to demonstrate project experience for their assigned role for the ORC, clearly demonstrating duties performed supporting their assignment. Resumes must address all requirements stated in the Key Personnel attachment and emphasize "relevant" experience pertaining to the PWS and ORC requirements. Resumes must provide experience with regard to minimum education, qualifications, and certifications as required by the PWS.

(d) Subcontracts - Define planned key subcontractors and how subcontractors will be supervised and managed throughout the POP.

5.3 Volume I – Tab C Factor 3 - Integrated Master Schedule (IMS)

Include an IMS compliant AFCEC CLIN structure provided in the RFP, consistent with the Offeror's proposed approach, and in accordance with the requirements in the PWS and guidance. The IMS shall present a realistic and complete sequence and timing of activities and documents necessary to execute the ORC and achieve performance objectives within the performance periods; demonstrate logical incorporation of realistic Government and regulatory review periods as defined in the PWS; identify timing of decision points addressing risk mitigation and/or contingency strategies; demonstrate a thorough and realistic plan for ORC execution. The IMS version submitted for this proposal shall be prepared for all AFCEC CLINs/Sub-CLINs in Attachment 3 FY27 FLPHORC_CLIN structure provided in the RFP.

The IMS shall clearly demonstrate the offerors' plan for achieving performance objectives within the performance periods defined in the PWS. For IMS development, assume a notice to proceed

(NTP) date within one week of contract award. Assume a contract award date of 01 July 2027 for proposal purposes only.

5.4 Volume I - Tab D Factor 4 – Past Performance Information of the Prime Contractor

The Past Performance of the Offeror consists of (a) Relevant Company Effort and (b) Quality of Past Performance. The Government will review recent, relevant company efforts and quality information provided by the owners of those efforts to assess the Offeror's past experience and probability of successfully performing the work described in this solicitation. To be considered for evaluation, a project must meet both the recency and relevancy criteria defined below

(a) Performed under a contract or task order, as those terms are defined in RFO 2.101, for Federal projects, or similar contractual agreements for state or local governments, or the commercial or private sector. (Multiple projects under a single contract or task order are considered one project. However, do not combine multiple projects under separate contracts or task orders to create a single project.);

(b) RECENCY: The Government will first determine whether the submitted project is recent. Recent means a project completed, or substantially completed (50% or more), within the last ten (10) years from the solicitation issuance date. Percentage complete is defined as the total amount of work completed on the project. Submitted projects that are not recent will not be evaluated. Projects that demonstrate 100% complete may be evaluated more favorably.

(c) RELEVANCY: A relevant project is one that is similar in scope (type, size, complexity and dollar value) to the individual AFCEC CLIN project described in this solicitation. For a project to be assessed any degree of "relevancy" it must reflect successful performance of environmental remediation activities similar to the Contract requirements included in this solicitation.

(d) It is the responsibility of the Offeror to identify, detail, and demonstrate the relevancy of the submitted projects to the solicitation criteria elements. Including the relevancy of any projects submitted for an affiliate, team member, etc of the offeror. In the event the offeror intends to team with an affiliate or other entity, a teaming agreement is required, and shall be submitted along with your proposal. It is the responsibility of the offeror to outline the level of effort and substantial involvement that affiliate will perform on this project, for their past experience to be evaluated. The evaluation board will not make assumptions.

Project portfolios demonstrating the following characteristics will be given greater consideration. A Detailed narrative of actions Offerors have taken to ensure past successes in the listed criteria will be considered in the evaluation.

- Experience performing IRP related assessment and corrective actions at government installations, AF installations in Florida are preferred.

- Experience with Florida Department of Environmental Protection
- Experience in support of AF DERP

Relevant Company Effort:

The Offeror shall provide no more than three (3) examples of recent, relevant projects performed as the prime contractor that demonstrate the ability of the company to perform work similar to that required by this solicitation. If a teaming agreement, or commitment is not provided, the projects and experience of any team members outside of the Offeror will not be evaluated.

For each project, the Offeror shall furnish the information specified below. Attachment 2, at the end of this section, may be used to present the information. The work effort shown does not have to be a task order under an IDIQ contract, but where it is, clearly indicate so. If more than three (3) projects are submitted for evaluation, only the first three (3) projects will be evaluated.

(1) Company Name
(2) Name of Project
(3) Location of Project
(4) Project Owner
(5) General Scope of Project (Include type DB, DBB, Other)
(6) Your Role and Type Work Your Company Self-Performed onsite other than Management Services.
(7) Total Cost of the single project
(8) Extent and Type of Work Subcontracted Out
(9) Project Work Period - Start and Completion/Scheduled Completion Dates (Provide Month/Year)
(10) Termination or Liquidated Damages Information; Comments Regarding any known performance deemed unacceptable to the customer, or not in accordance with the contract terms and conditions.
(11) Most recent CPARS, if available

5.4.1 Quality of Past Performance (Does not count against Factor 1 page limitation)

(1) The Offeror shall submit evidence of the quality of their past performance for each project. For Federal Government projects, the Offeror shall provide a recent contractor performance evaluation, whether interim or final, found in the Contractor Performance Assessment Reporting System (CPARS). If a proper evaluation does not exist in CPARS, because it has not been completed or the project is a non-Federal Government project, the Offeror shall provide a completed Past Performance Questionnaire (PPQ) (See Attachment L001). If, at the time of evaluation, a final contractor performance evaluation exists in CPARS, and yet the Offeror submits a PPQ, only the evaluation in CPARS will be considered.

(2) Past performance surveys/assessment/evaluation forms other than CPARS or PPQs are unacceptable and will not be considered or evaluated.

(3) Completed PPQs that were submitted in response to previous solicitations may be used in this source selection. However, Offerors shall not incorporate such PPQs by reference and thus must resubmit the PPQ with their proposal. This does not, however, preclude the Government from utilizing previously submitted PPQ information in the Past Performance evaluation.

While the Government may elect to consider data from other sources outside the proposal including, but not limited to evaluating additional CPARS evaluations, the burden of providing current, detailed and complete past performance information rests with the Offeror.

(4) If an Offeror has been required to take corrective action for any substandard performance or experienced other performance or quality problems, e.g., cost overruns, extended performance periods, regulatory compliance, numerous warranty calls, etc., the Offeror must explain the circumstances and the corrective actions taken.

(5) If an Offeror's client/customer will only provide completed PPQs directly to the U.S. Army Corps of Engineers, Mobile District, Offerors must ensure the client/customer submits the PPQ by the proposal due date using the following electronic mailing address: cesam.plansroom@sam.usace.army.mil. The solicitation number shall be included on the PPQ form. PPQs received after the proposal due date will be considered untimely and will not be considered during the evaluation.

(6) Quality of past performance documentation shall be submitted for all contractor entities identified as the Prime or Joint Venture who will be in a binding contractual relationship with the Government.

5.4.2 All Business Entities:

Only information pertaining to the corporate entity listed on the proposal cover letter will be considered the most relevant in the evaluation. Information related to a parent company, affiliates, or first tier subcontractors will only be considered if the offeror provides a detailing of the relevancy of said partner/affiliate, and outlines the substantial level of involvement said partner/affiliate will have in the execution of the project.

5.4.3 Verification:

The Government reserves the right to verify the information on projects submitted for evaluation, and to review CPARS, or other Government project appraisal systems, for information on other projects performed by the Offeror whether submitted as part of a proposal or not. The Government also reserves the right to contact project clients/customer, or other references. For any adverse performance information found for which the Offeror has not had an opportunity to address, the Offeror will be afforded an opportunity to explain.

5.5 Volume II

Administrative Requirements (Including Price). Prior to making an award, the following submitted information will be checked for compliance:

5.5.1 General Requirements

(1) A cover letter on Company letterhead documenting the submission of the proposal at the end of this section with the signature of the official of the company so duly authorized to bind the company contractually. Include the proposal data sheet (Attachment 1).

(2) Acknowledgement of all amendments by completion of the SF30 Amendment form.

(3) Organizational Conflicts of Interest (OCI) Disclosure: The Offeror shall provide a disclosure statement with its proposal that concisely describes all the relevant facts concerning any past or present OCIs relating to this solicitation. If applicable, in the same statement, the Offeror shall provide information to assure the Government that the conflicts of interest have been mitigated and/or neutralized to the maximum extent possible. If a conflict of interest is discovered after award of this contract, the Contracting Officer will make a decision on whether or not to terminate the contract. If no conflicts of interest exist, the Offeror shall provide a statement stating no Conflicts of Interest exist.

(2) Pricing (proposal bid schedule). The Offeror shall submit pricing in pdf and excel format using the AFCEC CLIN structure bid sheet included with the RFP.

5.5.2 Price

Provide AFCEC CLIN /Sub-CLIN-specific pricing using Attachment 3 FY27 FLPHORC CLIN Structure provided in the RFP. All ORC Pricing shall follow the format and guidance requirements provided in the RFP. **All cost associated with this Contract shall be rounded to whole dollars, including CLIN Price, MPS, invoices, etc.** The Offeror shall not propose zero-dollar AFCEC CLIN pricing.

5.5.3 Price Breakdown Requirements.

At the request of the Government, the offeror may be required to submit a “price breakdown” of the bid items. The format of the breakdown will be directed by the Government, and at a minimum, shall include pricing details for the major categories of work, e.g., document preparation, investigation/remediation fieldwork, site inspections, etc. This information will not be needed sooner than three working days after the proposal submission due date. The price breakdown information may be required for the initial proposals and, if requested, for any revised proposals.

USACE CLIN	AFCEC CLIN/Sub-CLIN Number	Optional Task Item Number	Installation	Site	AFCEC CLIN/Sub-CLIN Description	Projected/Estimated Award Date (Pending availability of funding and bona fide need as determined by the Government. ALL OPTIONS EXPIRE 114 MONTHS AFTER CONTRACT AWARD)*1	Period of Performance (yrs)
	0001		N/A	N/A	Complete Project Management Plan (PMP)		
0001	0001CA		N/A	N/A	Complete PMP	Base Year (2027)	1
0002	0001CB	001	N/A	N/A	Update PMP	Optional Task based on need	1
0003	0001CC	002	N/A	N/A	Update PMP	Optional Task based on need	1
0004	0001CD	003	N/A	N/A	Complete ORC Transition Plan	FY35	1
	0002		N/A	N/A	Develop Integrated Master Schedule (IMS)/Milestone Payment Schedule (MPS) and Update Monthly		
0005	0002CA		N/A	N/A	Develop IMS/MPS and Update Monthly	Base Year (2027)	1
0006	0002CB	004	N/A	N/A	Update IMS/MPS Monthly	FY28	1
0007	0002CC	005	N/A	N/A	Update IMS/MPS Monthly	FY29	1
0008	0002CD	006	N/A	N/A	Update IMS/MPS Monthly	FY30	1
0009	0002CE	007	N/A	N/A	Update IMS/MPS Monthly	FY31	1
0010	0002CF	008	N/A	N/A	Update IMS/MPS Monthly	FY32	1
0011	0002CG	009	N/A	N/A	Update IMS/MPS Monthly	FY33	1
0012	0002CH	010	N/A	N/A	Update IMS/MPS Monthly	FY34	1
0013	0002CJ	011	N/A	N/A	Update IMS/MPS Monthly	FY35	1
0014	0002CK	012	N/A	N/A	Update IMS/MPS Monthly	FY36	1
	0003		Eglin AFB	N/A	Update Community Involvement Plan		
0015	0003CA		Eglin AFB	All Open Sites (IRP, MMRP, PFAS, etc)	Update Community Involvement Plan	Base Year (2027)	1
0016	0003CB	013	Eglin AFB	All Open Sites (IRP, MMRP, PFAS, etc)	Update Community Involvement Plan	FY30	1
0017	0003CC	014	Eglin AFB	All Open Sites (IRP, MMRP, PFAS, etc)	Update Community Involvement Plan	FY33	1
0018	0003CD	015	Eglin AFB	All Open Sites (IRP, MMRP, PFAS, etc)	Update Community Involvement Plan	FY36	1
	0004		Eglin AFB	N/A	Complete IRP Basewide Quality Program Plans (QPP)		
0019	0004CA		Eglin AFB	N/A	Complete IRP Basewide QPP	Base Year (2027)	2
0020	0004CB	016	Eglin AFB	N/A	Update IRP Basewide QPP	Optional Task based on need	1
0021	0004CC	017	Eglin AFB	N/A	Update IRP Basewide QPP	Optional Task based on need	1
	0005		Eglin AFB	N/A	Perform RCRA Corrective Action/Hazardous and Solid Waste Amendments (CA/HSWA) Permit Renewal and Modification		
0022	0005CA	018	Eglin AFB	N/A	Perform RCRA CA/HSWA Permit Renewal	FY29	1
0023	0005CB	019	Eglin AFB	N/A	Perform RCRA CA/HSWA Permit Modification	Optional Task	1
	0006		Eglin AFB	N/A	Perform Well Abandonment		
0024	0006CA	020	Eglin AFB	N/A	Abandon up to one hundred fifty-five (155) Basewide Wells	FY29	3
	0007		Eglin AFB	CF288	Achieve Remedial Action Plan (RAP)		
0025	0007AA	021	Eglin AFB	CF288	Achieve Supplemental Site Assessment	FY28	3
0026	0007AB	022	Eglin AFB	CF288	Achieve RAP	Optional Task	2
	0008		Eglin AFB	DP009	Conduct LTM		
0027	0008CA		Eglin AFB	DP009	Conduct LTM in accordance with the approved DD/ROD	Base Year (2027)	1
0028	0008CB	023	Eglin AFB	DP009	Conduct LTM in accordance with the approved DD/ROD	FY28	1
0029	0008CC	024	Eglin AFB	DP009	Conduct LTM in accordance with the approved DD/ROD	FY29	1
0030	0008CD	025	Eglin AFB	DP009	Conduct LTM in accordance with the approved DD/ROD	FY30	1
0031	0008CE	026	Eglin AFB	DP009	Conduct LTM in accordance with the approved DD/ROD	FY31	1
0032	0008CF	027	Eglin AFB	DP009	Conduct LTM in accordance with the approved DD/ROD	FY32	1
0033	0008CG	028	Eglin AFB	DP009	Conduct LTM in accordance with the approved DD/ROD	FY33	1
0034	0008CH	029	Eglin AFB	DP009	Conduct LTM in accordance with the approved DD/ROD	FY34	1
0035	0008CJ	030	Eglin AFB	DP009	Conduct LTM in accordance with the approved DD/ROD	FY35	1
0036	0008CK	031	Eglin AFB	DP009	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0009		Eglin AFB	DP084	Conduct LTM		
0037	0009CA		Eglin AFB	DP084	Conduct LTM in accordance with the approved DD/ROD	Base Year (2027)	1
0038	0009CB	032	Eglin AFB	DP084	Conduct LTM in accordance with the approved DD/ROD	FY28	1
0039	0009CC	033	Eglin AFB	DP084	Conduct LTM in accordance with the approved DD/ROD	FY29	1
0040	0009CD	034	Eglin AFB	DP084	Conduct LTM in accordance with the approved DD/ROD	FY30	1
0041	0009CE	035	Eglin AFB	DP084	Conduct LTM in accordance with the approved DD/ROD	FY31	1
0042	0009CF	036	Eglin AFB	DP084	Conduct LTM in accordance with the approved DD/ROD	FY32	1
0043	0009CG	037	Eglin AFB	DP084	Conduct LTM in accordance with the approved DD/ROD	FY33	1
0044	0009CH	038	Eglin AFB	DP084	Conduct LTM in accordance with the approved DD/ROD	FY34	1
0045	0009CJ	039	Eglin AFB	DP084	Conduct LTM in accordance with the approved DD/ROD	FY35	1
0046	0009CK	040	Eglin AFB	DP084	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0010		Eglin AFB	DP261	Conduct LTM		
0047	0010CA		Eglin AFB	DP261	Conduct LTM in accordance with the approved DD/ROD	Base Year (2027)	1
0048	0010CB	041	Eglin AFB	DP261	Conduct LTM in accordance with the approved DD/ROD	FY28	1
0049	0010CC	042	Eglin AFB	DP261	Conduct LTM in accordance with the approved DD/ROD	FY29	1
0050	0010CD	043	Eglin AFB	DP261	Conduct LTM in accordance with the approved DD/ROD	FY30	1
0051	0010CE	044	Eglin AFB	DP261	Conduct LTM in accordance with the approved DD/ROD	FY31	1
0052	0010CF	045	Eglin AFB	DP261	Conduct LTM in accordance with the approved DD/ROD	FY32	1
0053	0010CG	046	Eglin AFB	DP261	Conduct LTM in accordance with the approved DD/ROD	FY33	1
0054	0010CH	047	Eglin AFB	DP261	Conduct LTM in accordance with the approved DD/ROD	FY34	1
0055	0010CJ	048	Eglin AFB	DP261	Conduct LTM in accordance with the approved DD/ROD	FY35	1
0056	0010CK	049	Eglin AFB	DP261	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0011		Eglin AFB	FT028	Conduct LTM		
0057	0011CA		Eglin AFB	FT028	Conduct LTM in accordance with the approved DD/ROD	Base Year (2027)	1
0058	0011CB	050	Eglin AFB	FT028	Conduct LTM in accordance with the approved DD/ROD	FY28	1
0059	0011CC	051	Eglin AFB	FT028	Conduct LTM in accordance with the approved DD/ROD	FY29	1
0060	0011CD	052	Eglin AFB	FT028	Conduct LTM in accordance with the approved DD/ROD	FY30	1
0061	0011CE	053	Eglin AFB	FT028	Conduct LTM in accordance with the approved DD/ROD	FY31	1
0062	0011CF	054	Eglin AFB	FT028	Conduct LTM in accordance with the approved DD/ROD	FY32	1
0063	0011CG	055	Eglin AFB	FT028	Conduct LTM in accordance with the approved DD/ROD	FY33	1
0064	0011CH	056	Eglin AFB	FT028	Conduct LTM in accordance with the approved DD/ROD	FY34	1
0065	0011CJ	057	Eglin AFB	FT028	Conduct LTM in accordance with the approved DD/ROD	FY35	1
0066	0011CK	058	Eglin AFB	FT028	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0012		Eglin AFB	LF003	Conduct RA-O		
0067	0012CA		Eglin AFB	LF003	Conduct LTM in accordance with the approved DD/ROD	Base Year (2027)	1
0068	0012CB	059	Eglin AFB	LF003	Conduct LTM in accordance with the approved DD/ROD	FY28	1
0069	0012CC	060	Eglin AFB	LF003	Conduct LTM in accordance with the approved DD/ROD	FY29	1
0070	0012CD	061	Eglin AFB	LF003	Conduct LTM in accordance with the approved DD/ROD	FY30	1
0071	0012CE	062	Eglin AFB	LF003	Conduct LTM in accordance with the approved DD/ROD	FY31	1
0072	0012CF	063	Eglin AFB	LF003	Conduct LTM in accordance with the approved DD/ROD	FY32	1
0073	0012CG	064	Eglin AFB	LF003	Conduct LTM in accordance with the approved DD/ROD	FY33	1
0074	0012CH	065	Eglin AFB	LF003	Conduct LTM in accordance with the approved DD/ROD	FY34	1
0075	0012CJ	066	Eglin AFB	LF003	Conduct LTM in accordance with the approved DD/ROD	FY35	1
0076	0012CK	067	Eglin AFB	LF003	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0013		Eglin AFB	LF005	Conduct LTM		
0077	0013CA		Eglin AFB	LF005	Conduct LTM in accordance with the approved DD/ROD	Base Year (2027)	1
0078	0013CB	068	Eglin AFB	LF005	Conduct LTM in accordance with the approved DD/ROD	FY28	1
0079	0013CC	069	Eglin AFB	LF005	Conduct LTM in accordance with the approved DD/ROD	FY29	1
0080	0013CD	070	Eglin AFB	LF005	Conduct LTM in accordance with the approved DD/ROD	FY30	1
0081	0013CE	071	Eglin AFB	LF005	Conduct LTM in accordance with the approved DD/ROD	FY31	1
0082	0013CF	072	Eglin AFB	LF005	Conduct LTM in accordance with the approved DD/ROD	FY32	1
0083	0013CG	073	Eglin AFB	LF005	Conduct LTM in accordance with the approved DD/ROD	FY33	1
0084	0013CH	074	Eglin AFB	LF005	Conduct LTM in accordance with the approved DD/ROD	FY34	1
0085	0013CJ	075	Eglin AFB	LF005	Conduct LTM in accordance with the approved DD/ROD	FY35	1
0086	0013CK	076	Eglin AFB	LF005	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0014		Eglin AFB	LF008	Conduct LTM		
0087	0014CA		Eglin AFB	LF008	Conduct LTM in accordance with the approved DD/ROD	Base Year (2027)	1
0088	0014CB	077	Eglin AFB	LF008	Conduct LTM in accordance with the approved DD/ROD	FY28	1
0089	0014CC	078	Eglin AFB	LF008	Conduct LTM in accordance with the approved DD/ROD	FY29	1

USACE CLIN	AFCEC CLIN/Sub-CLIN Number	Optional Task Item Number	Installation	Site	AFCEC CLIN/Sub-CLIN Description	Projected/Estimated Award Date (Pending availability of funding and bona fide need as determined by the Government. ALL OPTIONS EXPIRE 114 MONTHS AFTER CONTRACT AWARD)*1	Period of Performance (yrs)
0090	0014CD	079	Eglin AFB	LF008	Conduct LTM in accordance with the approved DD/ROD	FY30	1
0091	0014CE	080	Eglin AFB	LF008	Conduct LTM in accordance with the approved DD/ROD	FY31	1
0092	0014CF	081	Eglin AFB	LF008	Conduct LTM in accordance with the approved DD/ROD	FY32	1
0093	0014CG	082	Eglin AFB	LF008	Conduct LTM in accordance with the approved DD/ROD	FY33	1
0094	0014CH	083	Eglin AFB	LF008	Conduct LTM in accordance with the approved DD/ROD	FY34	1
0095	0014CJ	084	Eglin AFB	LF008	Conduct LTM in accordance with the approved DD/ROD	FY35	1
0096	0014CK	085	Eglin AFB	LF008	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0015		Eglin AFB	LF010	Conduct LTM		
0097	0015CA		Eglin AFB	LF010	Conduct LTM in accordance with the approved DD/ROD	Base Year (2027)	1
0098	0015CB	086	Eglin AFB	LF010	Conduct LTM in accordance with the approved DD/ROD	FY28	1
0099	0015CC	087	Eglin AFB	LF010	Conduct LTM in accordance with the approved DD/ROD	FY29	1
0100	0015CD	088	Eglin AFB	LF010	Conduct LTM in accordance with the approved DD/ROD	FY30	1
0101	0015CE	089	Eglin AFB	LF010	Conduct LTM in accordance with the approved DD/ROD	FY31	1
0102	0015CF	090	Eglin AFB	LF010	Conduct LTM in accordance with the approved DD/ROD	FY32	1
0103	0015CG	091	Eglin AFB	LF010	Conduct LTM in accordance with the approved DD/ROD	FY33	1
0104	0015CH	092	Eglin AFB	LF010	Conduct LTM in accordance with the approved DD/ROD	FY34	1
0105	0015CJ	093	Eglin AFB	LF010	Conduct LTM in accordance with the approved DD/ROD	FY35	1
0106	0015CK	094	Eglin AFB	LF010	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0016		Eglin AFB	LF051	Conduct LTM		
0107	0016CA		Eglin AFB	LF051	Conduct LTM in accordance with the approved DD/ROD	Base Year (2027)	1
0108	0016CB	095	Eglin AFB	LF051	Conduct LTM in accordance with the approved DD/ROD	FY28	1
0109	0016CC	096	Eglin AFB	LF051	Conduct LTM in accordance with the approved DD/ROD	FY29	1
0110	0016CD	097	Eglin AFB	LF051	Conduct LTM in accordance with the approved DD/ROD	FY30	1
0111	0016CE	098	Eglin AFB	LF051	Conduct LTM in accordance with the approved DD/ROD	FY31	1
0112	0016CF	099	Eglin AFB	LF051	Conduct LTM in accordance with the approved DD/ROD	FY32	1
0113	0016CG	100	Eglin AFB	LF051	Conduct LTM in accordance with the approved DD/ROD	FY33	1
0114	0016CH	101	Eglin AFB	LF051	Conduct LTM in accordance with the approved DD/ROD	FY34	1
0115	0016CJ	102	Eglin AFB	LF051	Conduct LTM in accordance with the approved DD/ROD	FY35	1
0116	0016CK	103	Eglin AFB	LF051	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0017		Eglin AFB	LF322	Achieve Site Assessment		
0117	0017AA	104	Eglin AFB	LF322	Achieve Site Assessment	FY29	4
	0018		Eglin AFB	OT083	Conduct LTM		
0118	0018CA		Eglin AFB	OT083	Conduct LTM in accordance with the approved DD/ROD	Base Year (2027)	1
0119	0018CB	105	Eglin AFB	OT083	Conduct LTM in accordance with the approved DD/ROD	FY28	1
0120	0018CC	106	Eglin AFB	OT083	Conduct LTM in accordance with the approved DD/ROD	FY29	1
0121	0018CD	107	Eglin AFB	OT083	Conduct LTM in accordance with the approved DD/ROD	FY30	1
0122	0018CE	108	Eglin AFB	OT083	Conduct LTM in accordance with the approved DD/ROD	FY31	1
0123	0018CF	109	Eglin AFB	OT083	Conduct LTM in accordance with the approved DD/ROD	FY32	1
0124	0018CG	110	Eglin AFB	OT083	Conduct LTM in accordance with the approved DD/ROD	FY33	1
0125	0018CH	111	Eglin AFB	OT083	Conduct LTM in accordance with the approved DD/ROD	FY34	1
0126	0018CJ	112	Eglin AFB	OT083	Conduct LTM in accordance with the approved DD/ROD	FY35	1
0127	0018CK	113	Eglin AFB	OT083	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0019		Eglin AFB	OT100	Conduct LTM		
0128	0019CA		Eglin AFB	OT100	Conduct LTM in accordance with the approved DD/ROD	Base Year (2027)	1
0129	0019CB	114	Eglin AFB	OT100	Conduct LTM in accordance with the approved DD/ROD	FY28	1
0130	0019CC	115	Eglin AFB	OT100	Conduct LTM in accordance with the approved DD/ROD	FY29	1
0131	0019CD	116	Eglin AFB	OT100	Conduct LTM in accordance with the approved DD/ROD	FY30	1
0132	0019CE	117	Eglin AFB	OT100	Conduct LTM in accordance with the approved DD/ROD	FY31	1
0133	0019CF	118	Eglin AFB	OT100	Conduct LTM in accordance with the approved DD/ROD	FY32	1
0134	0019CG	119	Eglin AFB	OT100	Conduct LTM in accordance with the approved DD/ROD	FY33	1
0135	0019CH	120	Eglin AFB	OT100	Conduct LTM in accordance with the approved DD/ROD	FY34	1
0136	0019CJ	121	Eglin AFB	OT100	Conduct LTM in accordance with the approved DD/ROD	FY35	1
0137	0019CK	122	Eglin AFB	OT100	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0020		Eglin AFB	OT262	Conduct LTM		
0138	0020CA		Eglin AFB	OT262	Conduct LTM in accordance with the approved DD/ROD	Base Year (2027)	1
0139	0020CB	123	Eglin AFB	OT262	Conduct LTM in accordance with the approved DD/ROD	FY28	1
0140	0020CC	124	Eglin AFB	OT262	Conduct LTM in accordance with the approved DD/ROD	FY29	1
0141	0020CD	125	Eglin AFB	OT262	Conduct LTM in accordance with the approved DD/ROD	FY30	1
0142	0020CE	126	Eglin AFB	OT262	Conduct LTM in accordance with the approved DD/ROD	FY31	1
0143	0020CF	127	Eglin AFB	OT262	Conduct LTM in accordance with the approved DD/ROD	FY32	1
0144	0020CG	128	Eglin AFB	OT262	Conduct LTM in accordance with the approved DD/ROD	FY33	1
0145	0020CH	129	Eglin AFB	OT262	Conduct LTM in accordance with the approved DD/ROD	FY34	1
0146	0020CJ	130	Eglin AFB	OT262	Conduct LTM in accordance with the approved DD/ROD	FY35	1
0147	0020CK	131	Eglin AFB	OT262	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0021		Eglin AFB	OT263	Conduct LTM		
0148	0021CA		Eglin AFB	OT263	Conduct LTM in accordance with the approved DD/ROD	Base Year (2027)	1
0149	0021CB	132	Eglin AFB	OT263	Conduct LTM in accordance with the approved DD/ROD	FY28	1
0150	0021CC	133	Eglin AFB	OT263	Conduct LTM in accordance with the approved DD/ROD	FY29	1
0151	0021CD	134	Eglin AFB	OT263	Conduct LTM in accordance with the approved DD/ROD	FY30	1
0152	0021CE	135	Eglin AFB	OT263	Conduct LTM in accordance with the approved DD/ROD	FY31	1
0153	0021CF	136	Eglin AFB	OT263	Conduct LTM in accordance with the approved DD/ROD	FY32	1
0154	0021CG	137	Eglin AFB	OT263	Conduct LTM in accordance with the approved DD/ROD	FY33	1
0155	0021CH	138	Eglin AFB	OT263	Conduct LTM in accordance with the approved DD/ROD	FY34	1
0156	0021CJ	139	Eglin AFB	OT263	Conduct LTM in accordance with the approved DD/ROD	FY35	1
0157	0021CK	140	Eglin AFB	OT263	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0022		Eglin AFB	OT264	Conduct LTM		
0158	0022CA		Eglin AFB	OT264	Conduct LTM in accordance with the approved DD/ROD	Base Year (2027)	1
0159	0022CB	141	Eglin AFB	OT264	Conduct LTM in accordance with the approved DD/ROD	FY28	1
0160	0022CC	142	Eglin AFB	OT264	Conduct LTM in accordance with the approved DD/ROD	FY29	1
0161	0022CD	143	Eglin AFB	OT264	Conduct LTM in accordance with the approved DD/ROD	FY30	1
0162	0022CE	144	Eglin AFB	OT264	Conduct LTM in accordance with the approved DD/ROD	FY31	1
0163	0022CF	145	Eglin AFB	OT264	Conduct LTM in accordance with the approved DD/ROD	FY32	1
0164	0022CG	146	Eglin AFB	OT264	Conduct LTM in accordance with the approved DD/ROD	FY33	1
0165	0022CH	147	Eglin AFB	OT264	Conduct LTM in accordance with the approved DD/ROD	FY34	1
0166	0022CJ	148	Eglin AFB	OT264	Conduct LTM in accordance with the approved DD/ROD	FY35	1
0167	0022CK	149	Eglin AFB	OT264	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0023		Eglin AFB	OT265	Conduct LTM		
0168	0023CA		Eglin AFB	OT265	Conduct LTM in accordance with the approved DD/ROD	Base Year (2027)	1
0169	0023CB	150	Eglin AFB	OT265	Conduct LTM in accordance with the approved DD/ROD	FY28	1
0170	0023CC	151	Eglin AFB	OT265	Conduct LTM in accordance with the approved DD/ROD	FY29	1
0171	0023CD	152	Eglin AFB	OT265	Conduct LTM in accordance with the approved DD/ROD	FY30	1
0172	0023CE	153	Eglin AFB	OT265	Conduct LTM in accordance with the approved DD/ROD	FY31	1
0173	0023CF	154	Eglin AFB	OT265	Conduct LTM in accordance with the approved DD/ROD	FY32	1
0174	0023CG	155	Eglin AFB	OT265	Conduct LTM in accordance with the approved DD/ROD	FY33	1
0175	0023CH	156	Eglin AFB	OT265	Conduct LTM in accordance with the approved DD/ROD	FY34	1
0176	0023CJ	157	Eglin AFB	OT265	Conduct LTM in accordance with the approved DD/ROD	FY35	1
0177	0023CK	158	Eglin AFB	OT265	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0024		Eglin AFB	OT269	Conduct LTM		
0178	0024CA		Eglin AFB	OT269	Conduct LTM in accordance with the approved DD/ROD	Base Year (2027)	1
0179	0024CB	159	Eglin AFB	OT269	Conduct LTM in accordance with the approved DD/ROD	FY28	1
0180	0024CC	160	Eglin AFB	OT269	Conduct LTM in accordance with the approved DD/ROD	FY29	1
0181	0024CD	161	Eglin AFB	OT269	Conduct LTM in accordance with the approved DD/ROD	FY30	1
0182	0024CE	162	Eglin AFB	OT269	Conduct LTM in accordance with the approved DD/ROD	FY31	1
0183	0024CF	163	Eglin AFB	OT269	Conduct LTM in accordance with the approved DD/ROD	FY32	1
0184	0024CG	164	Eglin AFB	OT269	Conduct LTM in accordance with the approved DD/ROD	FY33	1
0185	0024CH	165	Eglin AFB	OT269	Conduct LTM in accordance with the approved DD/ROD	FY34	1
0186	0024CJ	166	Eglin AFB	OT269	Conduct LTM in accordance with the approved DD/ROD	FY35	1
0187	0024CK	167	Eglin AFB	OT269	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0025		Eglin AFB	OT270	Conduct LTM		
0188	0025CA		Eglin AFB	OT270	Conduct LTM in accordance with the approved DD/ROD	Base Year (2027)	1
0189	0025CB	168	Eglin AFB	OT270	Conduct LTM in accordance with the approved DD/ROD	FY28	1
0190	0025CC	169	Eglin AFB	OT270	Conduct LTM in accordance with the approved DD/ROD	FY29	1
0191	0025CD	170	Eglin AFB	OT270	Conduct LTM in accordance with the approved DD/ROD	FY30	1

USACE CLIN	AFCEC CLIN/Sub-CLIN Number	Optional Task Item Number	Installation	Site	AFCEC CLIN/Sub-CLIN Description	Projected/Estimated Award Date (Pending availability of funding and bona fide need as determined by the Government. ALL OPTIONS EXPIRE 114 MONTHS AFTER CONTRACT AWARD)*1	Period of Performance (yrs)
0192	0025CE	171	Eglin AFB	OT270	Conduct LTM in accordance with the approved DD/ROD	FY31	1
0193	0025CF	172	Eglin AFB	OT270	Conduct LTM in accordance with the approved DD/ROD	FY32	1
0194	0025CG	173	Eglin AFB	OT270	Conduct LTM in accordance with the approved DD/ROD	FY33	1
0195	0025CH	174	Eglin AFB	OT270	Conduct LTM in accordance with the approved DD/ROD	FY34	1
0196	0025CJ	175	Eglin AFB	OT270	Conduct LTM in accordance with the approved DD/ROD	FY35	1
0197	0025CK	176	Eglin AFB	OT270	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0026		Eglin AFB	OT271	Conduct LTM		
0198	0026CA		Eglin AFB	OT271	Conduct LTM in accordance with the approved DD/ROD	Base Year (2027)	1
0199	0026CB	177	Eglin AFB	OT271	Conduct LTM in accordance with the approved DD/ROD	FY28	1
0200	0026CC	178	Eglin AFB	OT271	Conduct LTM in accordance with the approved DD/ROD	FY29	1
0201	0026CD	179	Eglin AFB	OT271	Conduct LTM in accordance with the approved DD/ROD	FY30	1
0202	0026CE	180	Eglin AFB	OT271	Conduct LTM in accordance with the approved DD/ROD	FY31	1
0203	0026CF	181	Eglin AFB	OT271	Conduct LTM in accordance with the approved DD/ROD	FY32	1
0204	0026CG	182	Eglin AFB	OT271	Conduct LTM in accordance with the approved DD/ROD	FY33	1
0205	0026CH	183	Eglin AFB	OT271	Conduct LTM in accordance with the approved DD/ROD	FY34	1
0206	0026CJ	184	Eglin AFB	OT271	Conduct LTM in accordance with the approved DD/ROD	FY35	1
0207	0026CK	185	Eglin AFB	OT271	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0027		Eglin AFB	POI523	Conduct LTM		
0208	0027CA		Eglin AFB	POI523	Conduct LTM in accordance with the approved DD/ROD	Base Year (2027)	1
0209	0027CB	186	Eglin AFB	POI523	Conduct LTM in accordance with the approved DD/ROD	FY28	1
0210	0027CC	187	Eglin AFB	POI523	Conduct LTM in accordance with the approved DD/ROD	FY29	1
0211	0027CD	188	Eglin AFB	POI523	Conduct LTM in accordance with the approved DD/ROD	FY30	1
0212	0027CE	189	Eglin AFB	POI523	Conduct LTM in accordance with the approved DD/ROD	FY31	1
0213	0027CF	190	Eglin AFB	POI523	Conduct LTM in accordance with the approved DD/ROD	FY32	1
0214	0027CG	191	Eglin AFB	POI523	Conduct LTM in accordance with the approved DD/ROD	FY33	1
0215	0027CH	192	Eglin AFB	POI523	Conduct LTM in accordance with the approved DD/ROD	FY34	1
0216	0027CJ	193	Eglin AFB	POI523	Conduct LTM in accordance with the approved DD/ROD	FY35	1
0217	0027CK	194	Eglin AFB	POI523	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0028		Eglin AFB	SS025	Conduct LTM		
0218	0028CA		Eglin AFB	SS025	Conduct LTM in accordance with the approved DD/ROD	Base Year (2027)	1
0219	0028CB	195	Eglin AFB	SS025	Conduct LTM in accordance with the approved DD/ROD	FY28	1
0220	0028CC	196	Eglin AFB	SS025	Conduct LTM in accordance with the approved DD/ROD	FY29	1
0221	0028CD	197	Eglin AFB	SS025	Conduct LTM in accordance with the approved DD/ROD	FY30	1
0222	0028CE	198	Eglin AFB	SS025	Conduct LTM in accordance with the approved DD/ROD	FY31	1
0223	0028CF	199	Eglin AFB	SS025	Conduct LTM in accordance with the approved DD/ROD	FY32	1
0224	0028CG	200	Eglin AFB	SS025	Conduct LTM in accordance with the approved DD/ROD	FY33	1
0225	0028CH	201	Eglin AFB	SS025	Conduct LTM in accordance with the approved DD/ROD	FY34	1
0226	0028CJ	202	Eglin AFB	SS025	Conduct LTM in accordance with the approved DD/ROD	FY35	1
0227	0028CK	203	Eglin AFB	SS025	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0029		Eglin AFB	SS026	Conduct LTM		
0228	0029CA		Eglin AFB	SS026	Conduct LTM in accordance with the approved DD/ROD	Base Year (2027)	1
0229	0029CB	204	Eglin AFB	SS026	Conduct LTM in accordance with the approved DD/ROD	FY28	1
0230	0029CC	205	Eglin AFB	SS026	Conduct LTM in accordance with the approved DD/ROD	FY29	1
0231	0029CD	206	Eglin AFB	SS026	Conduct LTM in accordance with the approved DD/ROD	FY30	1
0232	0029CE	207	Eglin AFB	SS026	Conduct LTM in accordance with the approved DD/ROD	FY31	1
0233	0029CF	208	Eglin AFB	SS026	Conduct LTM in accordance with the approved DD/ROD	FY32	1
0234	0029CG	209	Eglin AFB	SS026	Conduct LTM in accordance with the approved DD/ROD	FY33	1
0235	0029CH	210	Eglin AFB	SS026	Conduct LTM in accordance with the approved DD/ROD	FY34	1
0236	0029CJ	211	Eglin AFB	SS026	Conduct LTM in accordance with the approved DD/ROD	FY25	1
0237	0029CK	212	Eglin AFB	SS026	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0030		Eglin AFB	SS086	Conduct LTM		
0238	0030CA		Eglin AFB	SS086	Conduct LTM in accordance with the approved DD/ROD	Base Year (2027)	1
0239	0030CB	213	Eglin AFB	SS086	Conduct LTM in accordance with the approved DD/ROD	FY28	1
0240	0030CC	214	Eglin AFB	SS086	Conduct LTM in accordance with the approved DD/ROD	FY29	1
0241	0030CD	215	Eglin AFB	SS086	Conduct LTM in accordance with the approved DD/ROD	FY30	1
0242	0030CE	216	Eglin AFB	SS086	Conduct LTM in accordance with the approved DD/ROD	FY31	1
0243	0030CF	217	Eglin AFB	SS086	Conduct LTM in accordance with the approved DD/ROD	FY32	1
0244	0030CG	218	Eglin AFB	SS086	Conduct LTM in accordance with the approved DD/ROD	FY33	1
0245	0030CH	219	Eglin AFB	SS086	Conduct LTM in accordance with the approved DD/ROD	FY34	1
0246	0030CJ	220	Eglin AFB	SS086	Conduct LTM in accordance with the approved DD/ROD	FY35	1
0247	0030CK	221	Eglin AFB	SS086	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0031		Eglin AFB	SS278	Conduct LTM		
0248	0031CA		Eglin AFB	SS278	Conduct LTM in accordance with the approved DD/ROD	Base Year (2027)	1
0249	0031CB	222	Eglin AFB	SS278	Conduct LTM in accordance with the approved DD/ROD	FY28	1
0250	0031CC	223	Eglin AFB	SS278	Conduct LTM in accordance with the approved DD/ROD	FY29	1
0251	0031CD	224	Eglin AFB	SS278	Conduct LTM in accordance with the approved DD/ROD	FY30	1
0252	0031CE	225	Eglin AFB	SS278	Conduct LTM in accordance with the approved DD/ROD	FY31	1
0253	0031CF	226	Eglin AFB	SS278	Conduct LTM in accordance with the approved DD/ROD	FY32	1
0254	0031CG	227	Eglin AFB	SS278	Conduct LTM in accordance with the approved DD/ROD	FY33	1
0255	0031CH	228	Eglin AFB	SS278	Conduct LTM in accordance with the approved DD/ROD	FY34	1
0256	0031CJ	229	Eglin AFB	SS278	Conduct LTM in accordance with the approved DD/ROD	FY35	1
0257	0031CK	230	Eglin AFB	SS278	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0032		Eglin AFB	SS281	Conduct LTM		
0258	0032CA		Eglin AFB	SS281	Conduct LTM in accordance with the approved DD/ROD	Base Year (2027)	1
0259	0032CB	231	Eglin AFB	SS281	Conduct LTM in accordance with the approved DD/ROD	FY28	1
0260	0032CC	232	Eglin AFB	SS281	Conduct LTM in accordance with the approved DD/ROD	FY29	1
0261	0032CD	233	Eglin AFB	SS281	Conduct LTM in accordance with the approved DD/ROD	FY30	1
0262	0032CE	234	Eglin AFB	SS281	Conduct LTM in accordance with the approved DD/ROD	FY31	1
0263	0032CF	235	Eglin AFB	SS281	Conduct LTM in accordance with the approved DD/ROD	FY32	1
0264	0032CG	236	Eglin AFB	SS281	Conduct LTM in accordance with the approved DD/ROD	FY33	1
0265	0032CH	237	Eglin AFB	SS281	Conduct LTM in accordance with the approved DD/ROD	FY34	1
0266	0032CJ	238	Eglin AFB	SS281	Conduct LTM in accordance with the approved DD/ROD	FY35	1
0267	0032CK	239	Eglin AFB	SS281	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0033		Eglin AFB	SS283	Conduct LTM		
0268	0033CA		Eglin AFB	SS283	Conduct LTM in accordance with the approved DD/ROD	Base Year (2027)	1
0269	0033CB	240	Eglin AFB	SS283	Conduct LTM in accordance with the approved DD/ROD	FY28	1
0270	0033CC	241	Eglin AFB	SS283	Conduct LTM in accordance with the approved DD/ROD	FY29	1
0271	0033CD	242	Eglin AFB	SS283	Conduct LTM in accordance with the approved DD/ROD	FY30	1
0272	0033CE	243	Eglin AFB	SS283	Conduct LTM in accordance with the approved DD/ROD	FY31	1
0273	0033CF	244	Eglin AFB	SS283	Conduct LTM in accordance with the approved DD/ROD	FY32	1
0274	0033CG	245	Eglin AFB	SS283	Conduct LTM in accordance with the approved DD/ROD	FY33	1
0275	0033CH	246	Eglin AFB	SS283	Conduct LTM in accordance with the approved DD/ROD	FY34	1
0276	0033CJ	247	Eglin AFB	SS283	Conduct LTM in accordance with the approved DD/ROD	FY35	1
0277	0033CK	248	Eglin AFB	SS283	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0034		Eglin AFB	SS313	Achieve Site Closeout		
0278	0034AA	249	Eglin AFB	SS313	Achieve Remedial Action	FY28	3
0279	0034AB	250	Eglin AFB	SS313	Achieve Site Closeout	Optional Task based on need	3
	0035		Eglin AFB	ST069	Achieve Response Complete		
0280	0035AA	251	Eglin AFB	ST069	Achieve Response Complete	FY28	3
0281	0035AB	252	Eglin AFB	ST069	Achieve Conditional Site Closeout	Optional Task based on need	3
0282	0035CA		Eglin AFB	ST069	Conduct RA-O in accordance with the approved DD / ROD	Base Year (2027)	1
0283	0035CB	253	Eglin AFB	ST069	Conduct RA-O in accordance with the approved DD / ROD	FY28	1
0284	0035CC	254	Eglin AFB	ST069	Conduct RA-O in accordance with the approved DD / ROD	FY29	1
0285	0035CD	255	Eglin AFB	ST069	Conduct RA-O in accordance with the approved DD / ROD	FY30	1
0286	0035CE	256	Eglin AFB	ST069	Conduct RA-O in accordance with the approved DD / ROD	FY31	1
0287	0035CF	257	Eglin AFB	ST069	Conduct RA-O in accordance with the approved DD / ROD	FY32	1
0288	0035CG	258	Eglin AFB	ST069	Conduct RA-O in accordance with the approved DD / ROD	FY33	1
0289	0035CH	259	Eglin AFB	ST069	Conduct RA-O in accordance with the approved DD / ROD	FY34	1
0290	0035CJ	260	Eglin AFB	ST069	Conduct LTM in accordance with the approved DD/ROD	FY35	1
0291	0035CK	261	Eglin AFB	ST069	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0036		Hurlburt Field	N/A	Update Community Involvement Plan		

USACE CLIN	AFCEC CLIN/Sub-CLIN Number	Optional Task Item Number	Installation	Site	AFCEC CLIN/Sub-CLIN Description	Projected/Estimated Award Date (Pending availability of funding and bona fide need as determined by the Government. ALL OPTIONS EXPIRE 114 MONTHS AFTER CONTRACT AWARD)*1	Period of Performance (yrs)
0292	0036CA		Hurlburt Field	All Open Sites (IRP, MMRP, PFAS, etc)	Update Community Involvement Plan	Base Year (2027)	1
0293	0036CB	262	Hurlburt Field	All Open Sites (IRP, MMRP, PFAS, etc)	Update Community Involvement Plan	FY31	1
0294	0036CC	263	Hurlburt Field	All Open Sites (IRP, MMRP, PFAS, etc)	Update Community Involvement Plan	FY34	1
0295	0036CD	264	Hurlburt Field	All Open Sites (IRP, MMRP, PFAS, etc)	Update Community Involvement Plan	FY36	1
	0037		Hurlburt Field	N/A	Complete IRP Basewide Quality Program Plans (QPP)		
0296	0037CA		Hurlburt Field	N/A	Complete IRP Basewide QPP	Base Year (2027)	2
0297	0037CB	265	Hurlburt Field	N/A	Update IRP Basewide QPP	Optional Task based on need	1
0298	0037CC	266	Hurlburt Field	N/A	Update IRP Basewide QPP	Optional Task based on need	1
	0038		Hurlburt Field	N/A	Complete MMRP Quality Program Plan (QPP)		
0299	0038CA		Hurlburt Field	N/A	Complete MMRP QPP	Base Year (2027)	2
0300	0038CB	267	Hurlburt Field	N/A	Update MMRP QPP	Optional Task based on need	1
0301	0038CC	268	Hurlburt Field	N/A	Update MMRP QPP	Optional Task based on need	1
	0039		Hurlburt Field	N/A	Perform Well Survey, Inventory, and Condition Assessment		
0302	0039CA	269	Hurlburt Field	N/A	Complete Well Survey, Inventory, and Condition Assessment	FY29	2
0303	0039CB	270	Hurlburt Field	N/A	Update Well Survey, Inventory, and Condition Assessment	FY33	2
	0040		Hurlburt Field	N/A	Perform RCRA Corrective Action/Hazardous and Solid Waste Amendments (CA/HWSA) Permit Renewal and Modification		
0304	0040CA	271	Hurlburt Field	N/A	Perform RCRA CA/HSWA Permit Renewal	FY30	1
0305	0040CB	272	Hurlburt Field	N/A	Perform RCRA CA/HSWA Permit Modification	Optional Task based on need	1
	0041		Hurlburt Field	N/A	Perform Well Abandonment		
0306	0041CA	273	Hurlburt Field	N/A	Abandon up to eighty-six (86) Basewide Wells	FY29	3
	0042		Hurlburt Field	CG219	Achieve Remedial Action Plan (RAP)		
0307	0042AA		Hurlburt Field	CG219	Achieve Supplemental Site Assessment	Base Year (2027)	3
0308	0042AB	274	Hurlburt Field	CG219	Achieve RAP	Optional Task	2
	0043		Hurlburt Field	LF013	Conduct LTM		
0309	0043CA		Hurlburt Field	LF013	Conduct LTM in accordance with the approved DD/ROD	Base Year (2027)	1
0310	0043CB	275	Hurlburt Field	LF013	Conduct LTM in accordance with the approved DD/ROD	FY28	1
0311	0043CC	276	Hurlburt Field	LF013	Conduct LTM in accordance with the approved DD/ROD	FY29	1
0312	0043CD	277	Hurlburt Field	LF013	Conduct LTM in accordance with the approved DD/ROD	FY30	1
0313	0043CE	278	Hurlburt Field	LF013	Conduct LTM in accordance with the approved DD/ROD	FY31	1
0314	0043CF	279	Hurlburt Field	LF013	Conduct LTM in accordance with the approved DD/ROD	FY32	1
0315	0043CG	280	Hurlburt Field	LF013	Conduct LTM in accordance with the approved DD/ROD	FY33	1
0316	0043CH	281	Hurlburt Field	LF013	Conduct LTM in accordance with the approved DD/ROD	FY34	1
0317	0043CJ	282	Hurlburt Field	LF013	Conduct LTM in accordance with the approved DD/ROD	FY35	1
0318	0043CK	283	Hurlburt Field	LF013	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0044		Hurlburt Field	LF014	Conduct LTM		
0319	0044CA		Hurlburt Field	LF014	Conduct LTM in accordance with the approved DD/ROD	Base Year (2027)	1
0320	0044CB	284	Hurlburt Field	LF014	Conduct LTM in accordance with the approved DD/ROD	FY28	1
0321	0044CC	285	Hurlburt Field	LF014	Conduct LTM in accordance with the approved DD/ROD	FY29	1
0322	0044CD	286	Hurlburt Field	LF014	Conduct LTM in accordance with the approved DD/ROD	FY30	1
0323	0044CE	287	Hurlburt Field	LF014	Conduct LTM in accordance with the approved DD/ROD	FY31	1
0324	0044CF	288	Hurlburt Field	LF014	Conduct LTM in accordance with the approved DD/ROD	FY32	1
0325	0044CG	289	Hurlburt Field	LF014	Conduct LTM in accordance with the approved DD/ROD	FY33	1
0326	0044CH	290	Hurlburt Field	LF014	Conduct LTM in accordance with the approved DD/ROD	FY34	1
0327	0044CJ	291	Hurlburt Field	LF014	Conduct LTM in accordance with the approved DD/ROD	FY35	1
0328	0044CK	292	Hurlburt Field	LF014	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0045		Hurlburt Field	LF015	Conduct LTM		
0329	0045CA		Hurlburt Field	LF015	Conduct LTM in accordance with the approved DD/ROD	Base Year (2027)	1
0330	0045CB	293	Hurlburt Field	LF015	Conduct LTM in accordance with the approved DD/ROD	FY28	1
0331	0045CC	294	Hurlburt Field	LF015	Conduct LTM in accordance with the approved DD/ROD	FY29	1
0332	0045CD	295	Hurlburt Field	LF015	Conduct LTM in accordance with the approved DD/ROD	FY30	1
0333	0045CE	296	Hurlburt Field	LF015	Conduct LTM in accordance with the approved DD/ROD	FY31	1
0334	0045CF	297	Hurlburt Field	LF015	Conduct LTM in accordance with the approved DD/ROD	FY32	1
0335	0045CG	298	Hurlburt Field	LF015	Conduct LTM in accordance with the approved DD/ROD	FY33	1
0336	0045CH	299	Hurlburt Field	LF015	Conduct LTM in accordance with the approved DD/ROD	FY34	1
0337	0045CJ	300	Hurlburt Field	LF015	Conduct LTM in accordance with the approved DD/ROD	FY35	1
0338	0045CK	301	Hurlburt Field	LF015	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0046		Hurlburt Field	LF016	Conduct LTM		
0339	0046CA		Hurlburt Field	LF016	Conduct LTM in accordance with the approved DD/ROD	Base Year (2027)	1
0340	0046CB	302	Hurlburt Field	LF016	Conduct LTM in accordance with the approved DD/ROD	FY28	1
0341	0046CC	303	Hurlburt Field	LF016	Conduct LTM in accordance with the approved DD/ROD	FY29	1
0342	0046CD	304	Hurlburt Field	LF016	Conduct LTM in accordance with the approved DD/ROD	FY30	1
0343	0046CE	305	Hurlburt Field	LF016	Conduct LTM in accordance with the approved DD/ROD	FY31	1
0344	0046CF	306	Hurlburt Field	LF016	Conduct LTM in accordance with the approved DD/ROD	FY32	1
0345	0046CG	307	Hurlburt Field	LF016	Conduct LTM in accordance with the approved DD/ROD	FY33	1
0346	0046CH	308	Hurlburt Field	LF016	Conduct LTM in accordance with the approved DD/ROD	FY34	1
0347	0046CJ	309	Hurlburt Field	LF016	Conduct LTM in accordance with the approved DD/ROD	FY35	1
0348	0046CK	310	Hurlburt Field	LF016	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0047		Hurlburt Field	LF017	Conduct LTM		
0349	0047CA		Hurlburt Field	LF017	Conduct LTM in accordance with the approved DD/ROD	Base Year (2027)	1
0350	0047CB	311	Hurlburt Field	LF017	Conduct LTM in accordance with the approved DD/ROD	FY28	1
0351	0047CC	312	Hurlburt Field	LF017	Conduct LTM in accordance with the approved DD/ROD	FY29	1
0352	0047CD	313	Hurlburt Field	LF017	Conduct LTM in accordance with the approved DD/ROD	FY30	1
0353	0047CE	314	Hurlburt Field	LF017	Conduct LTM in accordance with the approved DD/ROD	FY31	1
0354	0047CF	315	Hurlburt Field	LF017	Conduct LTM in accordance with the approved DD/ROD	FY32	1
0355	0047CG	316	Hurlburt Field	LF017	Conduct LTM in accordance with the approved DD/ROD	FY33	1
0356	0047CH	317	Hurlburt Field	LF017	Conduct LTM in accordance with the approved DD/ROD	FY34	1
0357	0047CJ	318	Hurlburt Field	LF017	Conduct LTM in accordance with the approved DD/ROD	FY35	1
0358	0047CK	319	Hurlburt Field	LF017	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0048		Hurlburt Field	LF018	Conduct LTM		
0359	0048CA		Hurlburt Field	LF018	Conduct LTM in accordance with the approved DD/ROD	Base Year (2027)	1
0360	0048CB	320	Hurlburt Field	LF018	Conduct LTM in accordance with the approved DD/ROD	FY28	1
0361	0048CC	321	Hurlburt Field	LF018	Conduct LTM in accordance with the approved DD/ROD	FY29	1
0362	0048CD	322	Hurlburt Field	LF018	Conduct LTM in accordance with the approved DD/ROD	FY30	1
0363	0048CE	323	Hurlburt Field	LF018	Conduct LTM in accordance with the approved DD/ROD	FY31	1
0364	0048CF	324	Hurlburt Field	LF018	Conduct LTM in accordance with the approved DD/ROD	FY32	1
0365	0048CG	325	Hurlburt Field	LF018	Conduct LTM in accordance with the approved DD/ROD	FY33	1
0366	0048CH	326	Hurlburt Field	LF018	Conduct LTM in accordance with the approved DD/ROD	FY34	1
0367	0048CJ	327	Hurlburt Field	LF018	Conduct LTM in accordance with the approved DD/ROD	FY35	1
0368	0048CK	328	Hurlburt Field	LF018	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0049		Hurlburt Field	LF019	Conduct LTM		
0369	0049CA		Hurlburt Field	LF019	Conduct LTM in accordance with the approved DD/ROD	Base Year (2027)	1
0370	0049CB	329	Hurlburt Field	LF019	Conduct LTM in accordance with the approved DD/ROD	FY28	1
0371	0049CC	330	Hurlburt Field	LF019	Conduct LTM in accordance with the approved DD/ROD	FY29	1
0372	0049CD	331	Hurlburt Field	LF019	Conduct LTM in accordance with the approved DD/ROD	FY30	1
0373	0049CE	332	Hurlburt Field	LF019	Conduct LTM in accordance with the approved DD/ROD	FY31	1
0374	0049CF	333	Hurlburt Field	LF019	Conduct LTM in accordance with the approved DD/ROD	FY32	1
0375	0049CG	334	Hurlburt Field	LF019	Conduct LTM in accordance with the approved DD/ROD	FY33	1
0376	0049CH	335	Hurlburt Field	LF019	Conduct LTM in accordance with the approved DD/ROD	FY34	1
0377	0049CJ	336	Hurlburt Field	LF019	Conduct LTM in accordance with the approved DD/ROD	FY35	1
0378	0049CK	337	Hurlburt Field	LF019	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0050		Hurlburt Field	LF020	Conduct LTM		
0379	0050CA		Hurlburt Field	LF020	Conduct LTM in accordance with the approved DD/ROD	Base Year (2027)	1
0380	0050CB	338	Hurlburt Field	LF020	Conduct LTM in accordance with the approved DD/ROD	FY28	1
0381	0050CC	339	Hurlburt Field	LF020	Conduct LTM in accordance with the approved DD/ROD	FY29	1

USACE CLIN	AFCEC CLIN/Sub-CLIN Number	Optional Task Item Number	Installation	Site	AFCEC CLIN/Sub-CLIN Description	Projected/Estimated Award Date (Pending availability of funding and bona fide need as determined by the Government. ALL OPTIONS EXPIRE 114 MONTHS AFTER CONTRACT AWARD)*1	Period of Performance (yrs)
0382	0050CD	340	Hurlburt Field	LF020	Conduct LTM in accordance with the approved DD/ROD	FY30	1
0383	0050CE	341	Hurlburt Field	LF020	Conduct LTM in accordance with the approved DD/ROD	FY31	1
0384	0050CF	342	Hurlburt Field	LF020	Conduct LTM in accordance with the approved DD/ROD	FY32	1
0385	0050CG	343	Hurlburt Field	LF020	Conduct LTM in accordance with the approved DD/ROD	FY33	1
0386	0050CH	344	Hurlburt Field	LF020	Conduct LTM in accordance with the approved DD/ROD	FY34	1
0387	0050CJ	345	Hurlburt Field	LF020	Conduct LTM in accordance with the approved DD/ROD	FY35	1
0388	0050CK	346	Hurlburt Field	LF020	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0051		Hurlburt Field	SS125	Achieve Site Closeout		
0389	0051AA	347	Hurlburt Field	SS125	Achieve Remedial Action Plan	FY28	1
0390	0051AB	348	Hurlburt Field	SS125	Achieve Response Complete	Optional Task	4
0391	0051AC	349	Hurlburt Field	SS125	Achieve Site Closeout	Optional Task	2
	0052		Hurlburt Field	ST123	Conduct LTM		
0392	0052CA		Hurlburt Field	ST123	Conduct LTM in accordance with the approved DD/ROD	Base Year (2027)	1
0393	0052CB	350	Hurlburt Field	ST123	Conduct LTM in accordance with the approved DD/ROD	FY28	1
0394	0052CC	351	Hurlburt Field	ST123	Conduct LTM in accordance with the approved DD/ROD	FY29	1
0395	0052CD	352	Hurlburt Field	ST123	Conduct LTM in accordance with the approved DD/ROD	FY30	1
0396	0052CE	353	Hurlburt Field	ST123	Conduct LTM in accordance with the approved DD/ROD	FY31	1
0397	0052CF	354	Hurlburt Field	ST123	Conduct LTM in accordance with the approved DD/ROD	FY32	1
0398	0052CG	355	Hurlburt Field	ST123	Conduct LTM in accordance with the approved DD/ROD	FY33	1
0399	0052CH	356	Hurlburt Field	ST123	Conduct LTM in accordance with the approved DD/ROD	FY34	1
0400	0052CJ	357	Hurlburt Field	ST123	Conduct LTM in accordance with the approved DD/ROD	FY35	1
0401	0052CK	358	Hurlburt Field	ST123	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0053		Hurlburt Field	XU002	Achieve DD/ROD		
0402	0053AA		Hurlburt Field	XU002	Achieve Remedial Investigation	Base Year (2027)	3
0403	0053AB	359	Hurlburt Field	XU002	Achieve Feasibility Study	Optional Task	2
0404	0053AC	360	Hurlburt Field	XU002	Achieve Proposed Plan	Optional Task	2
0405	0053AD	361	Hurlburt Field	XU002	Achieve Record of Decision (ROD)	Optional Task	3
	0054		Tyndall AFB	N/A	Update Community Involvement Plan		
0406	0054CA		Tyndall AFB	All Open Sites (IRP, MMRP, PFAS, etc)	Update Community Involvement Plan	Base Year (2027)	1
0407	0054CB	362	Tyndall AFB	All Open Sites (IRP, MMRP, PFAS, etc)	Update Community Involvement Plan	FY30	1
0408	0054CC	363	Tyndall AFB	All Open Sites (IRP, MMRP, PFAS, etc)	Update Community Involvement Plan	FY33	1
0409	0054CD	364	Tyndall AFB	All Open Sites (IRP, MMRP, PFAS, etc)	Update Community Involvement Plan	FY36	1
	0055		Tyndall AFB	N/A	Complete IRP Basewide Quality Program Plans (QPP)		
0410	0055CA		Tyndall AFB	N/A	Complete IRP Basewide QPP	Base Year (2027)	2
0411	0055CB	365	Tyndall AFB	N/A	Update IRP Basewide QPP	Optional Task based on need	1
0412	0055CC	366	Tyndall AFB	N/A	Update IRP Basewide QPP	Optional Task based on need	1
	0056		Tyndall AFB	N/A	Complete MMRP Quality Program Plan (QPP)		
0413	0056CA		Tyndall AFB	N/A	Complete MMRP QPP	Base Year (2027)	2
0414	0056CB	367	Tyndall AFB	N/A	Update MMRP QPP	Optional Task based on need	1
0415	0056CC	368	Tyndall AFB	N/A	Update MMRP QPP	Optional Task based on need	1
	0057		Tyndall AFB	N/A	Perform Well Survey, Inventory, and Condition Assessment		
0416	0057CA	369	Tyndall AFB	N/A	Complete Well Survey, Inventory, and Condition Assessment	FY29	2
0417	0057CB	370	Tyndall AFB	N/A	Update Well Survey, Inventory, and Condition Assessment	FY33	2
	0058		Tyndall AFB	DA046	Achieve Site Closeout		
0418	0058AA	371	Tyndall AFB	DA046	Achieve Confirmatory Sampling	FY28	3
0419	0058AB	372	Tyndall AFB	DA046	Achieve Feasiblity Study	Optional Task	2
0420	0058AC	373	Tyndall AFB	DA046	Achieve Site Closeout (No Action Proposed Plan/Record of Decision (PP/ROD))	Optional Task	5
	0059		Tyndall AFB	FR038	Conduct LTM		
0421	0059CA		Tyndall AFB	FR038	Conduct LTM in accordance with the approved DD/ROD	Base Year (2027)	1
0422	0059CB	374	Tyndall AFB	FR038	Conduct LTM in accordance with the approved DD/ROD	FY28	1
0423	0059CC	375	Tyndall AFB	FR038	Conduct LTM in accordance with the approved DD/ROD	FY29	1
0424	0059CD	376	Tyndall AFB	FR038	Conduct LTM in accordance with the approved DD/ROD	FY30	1
0425	0059CE	377	Tyndall AFB	FR038	Conduct LTM in accordance with the approved DD/ROD	FY31	1
0426	0059CF	378	Tyndall AFB	FR038	Conduct LTM in accordance with the approved DD/ROD	FY32	1
0427	0059CG	379	Tyndall AFB	FR038	Conduct LTM in accordance with the approved DD/ROD	FY33	1
0428	0059CH	380	Tyndall AFB	FR038	Conduct LTM in accordance with the approved DD/ROD	FY34	1
0429	0059CJ	381	Tyndall AFB	FR038	Conduct LTM in accordance with the approved DD/ROD	FY35	1
0430	0059CK	382	Tyndall AFB	FR038	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0060		Tyndall AFB	FT016	Achieve Feasibility Study		
0431	0060AA		Tyndall AFB	FT016	Achieve Land Use Control Implementation Plan	Base Year (2027)	1
0432	0060AB	383	Tyndall AFB	FT016	Achieve Post MILCON Confirmatory Sampling	Optional Task	3
0433	0060AC	384	Tyndall AFB	FT016	Achieve Feasibility Study	Optional Task	6
0434	0060CA	385	Tyndall AFB	FT016	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY28	1
0435	0060CB	386	Tyndall AFB	FT016	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY29	1
0436	0060CC	387	Tyndall AFB	FT016	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY30	1
0437	0060CD	388	Tyndall AFB	FT016	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY31	1
0438	0060CE	389	Tyndall AFB	FT016	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY32	1
0439	0060CF	390	Tyndall AFB	FT016	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY33	1
0440	0060CG	391	Tyndall AFB	FT016	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY34	1
0441	0060CH	392	Tyndall AFB	FT016	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY35	1
0442	0060CJ	393	Tyndall AFB	FT016	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY36	1
	0061		Tyndall AFB	FT016	Complete 1,4 Dioxane Step 2		
0443	0061AA		Tyndall AFB	FT016	Complete 1,4-Dioxane Step 2 Nature and Extent Determination	Base Year (2027)	5
	0062		Tyndall AFB	FT017	Achieve Feasibility Study		
0444	0062AA		Tyndall AFB	FT017	Achieve Land Use Control Implementation Plan	Base Year (2027)	1
0445	0062AB	394	Tyndall AFB	FT017	Achieve Post MILCON Confirmatory Sampling	Optional Task	3
0446	0062AC	395	Tyndall AFB	FT017	Achieve Feasibility Study	Optional Task	6
0447	0062CA	396	Tyndall AFB	FT017	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY28	1
0448	0062CB	397	Tyndall AFB	FT017	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY29	1
0449	0062CC	398	Tyndall AFB	FT017	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY30	1
0450	0062CD	399	Tyndall AFB	FT017	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY31	1
0451	0062CE	400	Tyndall AFB	FT017	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY32	1
0452	0062CF	401	Tyndall AFB	FT017	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY33	1
0453	0062CG	402	Tyndall AFB	FT017	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY34	1
0454	0062CH	403	Tyndall AFB	FT017	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY35	1
0455	0062CJ	404	Tyndall AFB	FT017	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY36	1
	0063		Tyndall AFB	LF006	Achieve Response Complete		
0456	0063AA		Tyndall AFB	LF006	Achieve Record of Decision	Base Year (2027)	3
0457	0063AB		Tyndall AFB	LF006	Achieve Remedial Design and Remedial Action Work Plan	Optional Task	1
0458	0063AC	405	Tyndall AFB	LF006	Achieve Remedy in Place	FY28	3
0459	0063AD	406	Tyndall AFB	LF006	Optimize the site in support of Response Complete	Optional Task	1
0460	0063AE	407	Tyndall AFB	LF006	Achieve Response Complete	Optional Task	1
0461	0063CA	408	Tyndall AFB	LF006	Conduct LTM in accordance with the approved DD/ROD	FY34 - Upon Completion of 0063AE (CLIN 0460)	1
0462	0063CB	409	Tyndall AFB	LF006	Conduct LTM in accordance with the approved DD/ROD	FY35	1
0463	0063CC	410	Tyndall AFB	LF006	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0064		Tyndall AFB	LF007	Achieve Response Complete		
0464	0064AA		Tyndall AFB	LF007	Achieve Record of Decision	Base Year (2027)	3
0465	0064AB	411	Tyndall AFB	LF007	Achieve Remedial Design and Remedial Action Work Plan	Optional Task	1
0466	0064AC	412	Tyndall AFB	LF007	Achieve Remedy in Place	Optional Task	1
0467	0064AD	413	Tyndall AFB	LF007	Optimize the site in support of Response Complete	Optional Task	1
0468	0064AE	414	Tyndall AFB	LF007	Achieve Response Complete	Optional Task	1
0469	0064CA	415	Tyndall AFB	LF007	Conduct LTM in accordance with the approved DD/ROD	FY34 - Upon Completion of 0064AE (CLIN 0468)	1
0470	0064CB	416	Tyndall AFB	LF007	Conduct LTM in accordance with the approved DD/ROD	FY35	1

USACE CLIN	AFCEC CLIN/Sub-CLIN Number	Optional Task Item Number	Installation	Site	AFCEC CLIN/Sub-CLIN Description	Projected/Estimated Award Date (Pending availability of funding and bona fide need as determined by the Government. ALL OPTIONS EXPIRE 114 MONTHS AFTER CONTRACT AWARD)*1	Period of Performance (yrs)
0471	0064CC	417	Tyndall AFB	LF007	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0065		Tyndall AFB	OT018	Achieve Confirmatory Sampling		
0472	0065AA	418	Tyndall AFB	OT018	Achieve Confirmatory Sampling	FY30	4
	0066		Tyndall AFB	OT029	Achieve Response Complete		
0473	0066AA		Tyndall AFB	OT029	Achieve Record of Decision	Base Year (2027)	2
0474	0066AB	419	Tyndall AFB	OT029	Achieve Remedial Design and Remedial Action Work Plan	Optional Task	1
0475	0066AC	420	Tyndall AFB	OT029	Achieve Remedy in Place	Optional Task	2
0476	0066AD	421	Tyndall AFB	OT029	Achieve Response Complete	Optional Task	2
0477	0066CA	422	Tyndall AFB	OT029	Conduct LTM in accordance with the approved DD/ROD	FY34 - Upon Completion of 0066AD (CLIN 0493)	1
0478	0066CB	423	Tyndall AFB	OT029	Conduct LTM in accordance with the approved DD/ROD	FY35	1
0479	0066CC	424	Tyndall AFB	OT029	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0067		Tyndall AFB	OW217	Achieve Final ROD and RA-O		
0480	0067AA		Tyndall AFB	OW217	Achieve Land Use Control Implementation Plan	Base Year (2027)	1
0481	0067AB	425	Tyndall AFB	OW217	Achieve Post MILCON Confirmatory Sampling	Optional Task	2
0482	0067AC	426	Tyndall AFB	OW217	Achieve Feasibility Study	Optional Task	1
0483	0067AD	427	Tyndall AFB	OW217	Achieve Proposed Plan/Record of Decision	Optional Task	2
0484	0067CA	428	Tyndall AFB	OW217	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY28	1
0485	0067CB	429	Tyndall AFB	OW217	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY29	1
0486	0067CC	430	Tyndall AFB	OW217	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY30	1
0487	0067CD	431	Tyndall AFB	OW217	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY31	1
0488	0067CE	432	Tyndall AFB	OW217	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY32	1
0489	0067CF	433	Tyndall AFB	OW217	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY33	1
0490	0067CG	434	Tyndall AFB	OW217	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY34	1
0491	0067CH	435	Tyndall AFB	OW217	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY35	1
0492	0067CJ	436	Tyndall AFB	OW217	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY36	1
	0068		Tyndall AFB	OW582	Achieve Remedy in Place and RA-O		
0493	0068AA	437	Tyndall AFB	OW582	Achieve Remedial Design and Remedial Action Work Plan	FY29	1
0494	0068AB	438	Tyndall AFB	OW582	Achieve Remedy in Place	Optional Task	3
0495	0068CA	439	Tyndall AFB	OW582	Conduct RAO in accordance with the approved DD / ROD and evaluate performance model	FY33 - Upon Completion of 0068AB (CLIN 0513)	1
0496	0068CB	440	Tyndall AFB	OW582	Conduct RAO in accordance with the approved DD / ROD and evaluate performance model	FY34	1
0497	0068CC	441	Tyndall AFB	OW582	Conduct RAO in accordance with the approved DD / ROD and evaluate performance model	FY35	1
0498	0068CD	442	Tyndall AFB	OW582	Conduct RAO in accordance with the approved DD / ROD and evaluate performance model	FY36	1
	0069		Tyndall AFB	SR169	Achieve Site Closeout		
0499	0069AA	443	Tyndall AFB	SR169	Achieve Site Closeout	FY29	4
	0070		Tyndall AFB	SR170	Achieve DD/ROD		
0500	0070AA		Tyndall AFB	SR170	Achieve Record of Decision	Base Year (2027)	4
	0071		Tyndall AFB	SR170A	Conduct LTM		
0501	0071CA	444	Tyndall AFB	SR170A	Conduct LTM in accordance with the approved DD / ROD	FY29	1
0502	0071CB	445	Tyndall AFB	SR170A	Conduct LTM in accordance with the approved DD / ROD	FY30	1
0503	0071CC	446	Tyndall AFB	SR170A	Conduct LTM in accordance with the approved DD / ROD	FY31	1
0504	0071CD	447	Tyndall AFB	SR170A	Conduct LTM in accordance with the approved DD / ROD	FY32	1
0505	0071CE	448	Tyndall AFB	SR170A	Conduct LTM in accordance with the approved DD / ROD	FY33	1
0506	0071CF	449	Tyndall AFB	SR170A	Conduct LTM in accordance with the approved DD / ROD	FY34	1
0507	0071CG	450	Tyndall AFB	SR170A	Conduct LTM in accordance with the approved DD / ROD	FY35	1
0508	0071CH	451	Tyndall AFB	SR170A	Conduct LTM in accordance with the approved DD / ROD	FY36	1
	0072		Tyndall AFB	SS015	Achieve Final ROD and RA-O		
0509	0072AA		Tyndall AFB	SS015	Achieve Land Use Control Implementation Plan	Base Year (2027)	1
0510	0072AB	452	Tyndall AFB	SS015	Achieve Post MILCON Confirmatory Sampling	Optional Task based on need	2
0511	0072AC	453	Tyndall AFB	SS015	Achieve Feasibility Study	Optional Task based on need	1
0512	0072AD	454	Tyndall AFB	SS015	Achieve-Proposed Plan/Record of Decision (PP/ROD)	Optional Task based on need	2
0513	0072CA	455	Tyndall AFB	SS015	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY28	1
0514	0072CB	456	Tyndall AFB	SS015	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY29	1
0515	0072CC	457	Tyndall AFB	SS015	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY30	1
0516	0072CD	458	Tyndall AFB	SS015	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY31	1
0517	0072CE	459	Tyndall AFB	SS015	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY32	1
0518	0072CF	460	Tyndall AFB	SS015	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY33	1
0519	0072CG	461	Tyndall AFB	SS015	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY34	1
0520	0072CH	462	Tyndall AFB	SS015	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY35	1
0521	0072CJ	463	Tyndall AFB	SS015	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY36	1
	0073		Tyndall AFB	SS026	Achieve Final ROD and RA-O		
0522	0073AA		Tyndall AFB	SS026	Achieve Land Use Control Implementation Plan	Base Year (2027)	1
0523	0073AB	464	Tyndall AFB	SS026	Achieve Post MILCON Confirmatory Sampling	Optional Task based on need	2
0524	0073AC	465	Tyndall AFB	SS026	Achieve Feasibility Study	Optional Task based on need	1
0525	0073AD	466	Tyndall AFB	SS026	AchieveProposed Plan/Record of Decision (PP/ROD)	Optional Task based on need	2
0526	0073CA	467	Tyndall AFB	SS026	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY28	1
0527	0073CB	468	Tyndall AFB	SS026	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY29	1
0528	0073CC	469	Tyndall AFB	SS026	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY30	1
0529	0073CD	470	Tyndall AFB	SS026	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY31	1
0530	0073CE	471	Tyndall AFB	SS026	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY32	1
0531	0073CF	472	Tyndall AFB	SS026	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY33	1
0532	0073CG	473	Tyndall AFB	SS026	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY34	1
0533	0073CH	474	Tyndall AFB	SS026	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY35	1
0534	0073CJ	475	Tyndall AFB	SS026	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY36	1
	0074		Tyndall AFB	TA523	Conduct LTM		
0535	0074CA		Tyndall AFB	TA523	Conduct LTM in accordance with the approved DD/ROD	Base Year (2027)	1
0536	0074CB	476	Tyndall AFB	TA523	Conduct LTM in accordance with the approved DD/ROD	FY28	1
0537	0074CC	477	Tyndall AFB	TA523	Conduct LTM in accordance with the approved DD/ROD	FY29	1
0538	0074CD	478	Tyndall AFB	TA523	Conduct LTM in accordance with the approved DD/ROD	FY30	1
0539	0074CE	479	Tyndall AFB	TA523	Conduct LTM in accordance with the approved DD/ROD	FY31	1
0540	0074CF	480	Tyndall AFB	TA523	Conduct LTM in accordance with the approved DD/ROD	FY32	1
0541	0074CG	481	Tyndall AFB	TA523	Conduct LTM in accordance with the approved DD/ROD	FY33	1
0542	0074CH	482	Tyndall AFB	TA523	Conduct LTM in accordance with the approved DD/ROD	FY34	1
0543	0074CJ	483	Tyndall AFB	TA523	Conduct LTM in accordance with the approved DD/ROD	FY35	1
0544	0074CK	484	Tyndall AFB	TA523	Conduct LTM in accordance with the approved DD/ROD	FY36	1
	0075		Tyndall AFB	TS183	RA-O with Optimization		
0545	0075AA	485	Tyndall AFB	TS183	Prepare Performance Model in year 2 and achieve the performance goals per the Performance Model and provide Performance Evaluation Report years 3 and 4	FY28	2
0546	0075AB	486	Tyndall AFB	TS183	Achieve the performance goals per the performance model and provide Performance Evaluation Report years 5, 6, and 7	Optional Task	3
0547	0075AC	487	Tyndall AFB	TS183	Achieve the performance goals per the performance model and provide Performance Evaluation Report years 8, and 9, develop an Optimization Summary and Forecasting Report in year 8 and provide final performance goal in year 10	Optional Task	3
0548	0075CA	488	Tyndall AFB	TS183	Conduct RA-O in accordance with the approved DD / ROD	FY28	1
0549	0075CB	489	Tyndall AFB	TS183	Conduct RA-O in accordance with the approved DD / ROD	FY29	1
0550	0075CC	490	Tyndall AFB	TS183	Conduct RA-O in accordance with the approved DD / ROD	FY30	1
0551	0075CD	491	Tyndall AFB	TS183	Conduct RA-O in accordance with the approved DD / ROD	FY31	1
0552	0075CE	492	Tyndall AFB	TS183	Conduct RA-O in accordance with the approved DD / ROD	FY32	1
0553	0075CF	493	Tyndall AFB	TS183	Conduct RA-O in accordance with the approved DD / ROD	FY33	1
0554	0075CG	494	Tyndall AFB	TS183	Conduct RA-O in accordance with the approved DD / ROD	FY34	1
0555	0075CH	495	Tyndall AFB	TS183	Conduct RA-O in accordance with the approved DD / ROD	FY35	1
0556	0075CJ	496	Tyndall AFB	TS183	Conduct RA-O in accordance with the approved DD / ROD	FY36	1
	0076		Tyndall AFB	TU204	Achieve Site Closeout		
0557	0076AA	497	Tyndall AFB	TU204	Optimize the site in support of Site Closeout	FY29	1
0558	0076AB	498	Tyndall AFB	TU204	Achieve Response Complete	Optional Task based on need	3
0559	0076AC	499	Tyndall AFB	TU204	Achieve Site Closeout	Optional Task based on need	1
	0077		Tyndall AFB	TU205	Achieve Final ROD and RA-O		

USACE CLIN	AFCEC CLIN/Sub-CLIN Number	Optional Task Item Number	Installation	Site	AFCEC CLIN/Sub-CLIN Description	Projected/Estimated Award Date (Pending availability of funding and bona fide need as determined by the Government. ALL OPTIONS EXPIRE 114 MONTHS AFTER CONTRACT AWARD)*1	Period of Performance (yrs)
0560	0077AA		Tyndall AFB	TU205	Achieve Land Use Control Implementation Plan	Base Year (2027)	1
0561	0077AB	500	Tyndall AFB	TU205	Achieve Post MILCON Confirmatory Sampling	Optional Task based on need	2
0562	0077AC	501	Tyndall AFB	TU205	Achieve Feasibility Study	Optional Task based on need	1
0563	0077AD	502	Tyndall AFB	TU205	Achieve Proposed Plan/Record of Decision (PP/ROD)	Optional Task based on need	2
0564	0077CA	503	Tyndall AFB	TU205	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY28	1
0565	0077CB	504	Tyndall AFB	TU205	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY29	1
0566	0077CC	505	Tyndall AFB	TU205	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY30	1
0567	0077CD	506	Tyndall AFB	TU205	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY31	1
0568	0077CE	507	Tyndall AFB	TU205	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY32	1
0569	0077CF	508	Tyndall AFB	TU205	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY33	1
0570	0077CG	509	Tyndall AFB	TU205	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY34	1
0571	0077CH	510	Tyndall AFB	TU205	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY35	1
0572	0077CJ	511	Tyndall AFB	TU205	Conduct RA-O in accordance with the approved Interim Action DD / ROD	FY36	1
	0078		Tyndall AFB	TU233	Achieve Site Closeout		
0573	0078AA		Tyndall AFB	TU233	Corrective Measures Implementation Plan (UFP-QAPP PARM Work Plan)	Base Year (2027)	1
0574	0078AB	512	Tyndall AFB	TU233	Construction Completion (Achieve PARM)	Optional Task based on need	2
0575	0078AC	513	Tyndall AFB	TU233	Achieve Response Complete	Optional Task based on need	2
0576	0078AD	514	Tyndall AFB	TU233	Achieve Site Closeout (SRCR and Well Abandonment Report)	Optional Task based on need	2

*1 The Projected/Estimated award timing designation in column E, F, & G indicate projected/estimated award timing each of the associated AFCEC Sub-CLINs will be funded and exercised. The "exercise year" is included for planning purposes only and is not intended to indicate a commitment by the Government to fund and exercise an AFCEC Sub-CLIN in a specific year of the contract. Award of all AFCEC Sub-CLINs will be made pending availability of funds and if bona fide need is determined by the Government. Limitations on funding availability may necessitate the Government to prioritize AFCEC Sub-CLIN award based on funding, regulatory requirements, and other bonafide need requirements. Meeting annual award dates for compliance AFCEC Sub-CLINs is necessary to maintain conformity with AF legal obligations, including Records of Decision (RODs), permits, and other agreements. These dates should not be confused with the time to obtain final regulatory approval of the reports associated with these annually funded events. Final reports generally take more than 12 months so these events, while funded annually, are non-severable in nature.

Installation	Site	USACE CLIN	AFCEC CLIN/Sub-CLIN Number	Category	Milestone Payment Identification Number	AFCEC CLIN/Sub-CLIN Description	Duration (days)	Start	Finish	Percent Complete	Actual Start	Actual Finish	Baseline Start	Baseline Finish
Eglin, Hurlburt Field, Tyndall	**Contract Wide**	**N/A**	**N/A**			**ORC Services for Florida Panhandle Activity Based IMS**								
Eglin, Hurlburt Field, Tyndall	**Contract Wide**	**N/A**	**N/A**			**Contract-wide**								
Eglin, Hurlburt Field, Tyndall	**Contract Wide**	**N/A**	**N/A**			**Meetings**								
Eglin, Hurlburt Field, Tyndall	Contract Wide	N/A	N/A	Meeting		Bi-weekly/Monthly Teleconferences								
Eglin, Hurlburt Field, Tyndall	Contract Wide	N/A	N/A	Meeting		Tier I Partnering Meetings								
Eglin, Hurlburt Field, Tyndall	Contract Wide	N/A	N/A	Meeting		RAB Meetings								
Eglin, Hurlburt Field, Tyndall	Contract Wide	N/A	N/A	Meeting		Kick-off meeting with Government and Regulators								
Eglin, Hurlburt Field, Tyndall	Contract Wide	N/A	N/A			**Contract-wide Tasks**								
Eglin, Hurlburt Field, Tyndall	**Contract Wide**	**N/A**	**0001**			**Project Management Plan (PMP)**								
Eglin, Hurlburt Field, Tyndall	**Contract Wide**	**0001**	**0001CA**			**Complete PMP**								
Eglin, Hurlburt Field, Tyndall	Contract Wide	**0001**	0001CA	Government Submittal		Air Force/CESAM Review PMP, Revision 0								
Eglin, Hurlburt Field, Tyndall	Contract Wide	**0001**	0001CA	Government Submittal		Air Force/CESAM Review PMP, Revision 1 and Resolve Issues								
Eglin, Hurlburt Field, Tyndall	Contract Wide	**0001**	0001CA	Government Submittal	0001CA.01	Air Force/CESAM Approve PMP, Revision 2								
Eglin, Hurlburt Field, Tyndall	**Contract Wide**	**0002**	**0001CB**			**Update PMP #1**								
Eglin, Hurlburt Field, Tyndall	Contract Wide	**0002**	0001CB	Government Submittal		Air Force/CESAM Review PMP Update #1, Revision 0								
Eglin, Hurlburt Field, Tyndall	Contract Wide	**0002**	0001CB	Government Submittal		Air Force/CESAM Review PMP Update #1, Revision 1 and Resolve Issues								
Eglin, Hurlburt Field, Tyndall	Contract Wide	**0002**	0001CB	Government Submittal	0001CB.01	Air Force/CESAM Approve PMP Update #1, Revision 2								
Eglin, Hurlburt Field, Tyndall	**Contract Wide**	**0003**	**0001CC**			**Update PMP # 2**								
Eglin, Hurlburt Field, Tyndall	Contract Wide	**0003**	0001CC	Government Submittal		Air Force/CESAM Review PMP Update #2, Revision 0								
Eglin, Hurlburt Field, Tyndall	Contract Wide	**0003**	0001CC	Government Submittal		Air Force/CESAM Review PMP Update #2, Revision 1 and Resolve Issues								
Eglin, Hurlburt Field, Tyndall	Contract Wide	**0003**	0001CC	Government Submittal	0001CC.01	Air Force/CESAM Approve PMP Update #2, Revision 2								
Eglin, Hurlburt Field, Tyndall	**Contract Wide**	**0004**	**0001CD**			**Complete ORC Transition Plan**								
Eglin, Hurlburt Field, Tyndall	Contract Wide	**0004**	0001CD	Government Submittal		Air Force/CESAM Review ORC Transition Plan, Revision 0								
Eglin, Hurlburt Field, Tyndall	Contract Wide	**0004**	0001CD	Government Submittal		Air Force/CESAM Review ORC Transition Plan, Revision 1 and Resolve Issues								
Eglin, Hurlburt Field, Tyndall	Contract Wide	**0004**	0001CD	Government Submittal	0001CD.01	Air Force/CESAM Approve ORC Transition Plan, Revision 2								

Categories: Meeting, Fieldwork, Government Submittals, Regulatory Submittals, Staffing
Duration: Input number of days, no text
Start and Finish: Future dates when task is estimated to be performed
Actual Start and Actual Finish: Actual dates when task is performed
Baseline Start and Baseline Finish: Start and Finish dates submitted after kick-off; these dates will not change for the life of the contract.

FY27 Florida Panhandle ORC

Key Personnel Requirements

Table of Contents

1. Introduction & General Qualification Requirements 3
1.1 Key Personnel Replacement Protocols 3
1.2. Critical Project Functions Summary 4
2. Critical Program Functions/Key Personnel and Requirements 5
2.1 Program Manager 5
Minimum Qualifications 5
2.2. Senior Project Manager(s) 6
Minimum Qualifications 7
2.3. Senior Site Manager(s) 7
Qualification Tracks 7
Path A: Degreed Track 7
Path B: Experience Track (Non-Degreed) 8
Mandatory Certifications (Applies to BOTH Tracks) 8
2.4. Contracts Manager 8
Minimum Qualifications 8
2.5. Quality Assurance/Quality Control (QA/QC) Manager 9
Minimum Qualifications 9
2.6. Risk Assessor 9
Minimum Qualifications 10
2.7. Health and Safety Manager 10
Minimum Qualifications 10
2.8. Program Chemist 11
Qualification Tracks 11
Path A: Advanced Degree Track 11
Path B: Professional Degree Track 11
2.9 Public Affairs Officer 12
Minimum Qualifications 12

2.10 Project Controls Manager 12
Minimum Qualifications 12
2.11 Project Scheduler 13
Qualification Tracks 13
Path A: Degreed Track 13
Path B: Experience Track (Non-Degreed) 13
2.12 Security Manager 14
Minimum Qualifications 14

1. Introduction & General Qualification Requirements

The following Critical Project Functions (Key Personnel positions) and qualifications are required for this contract. The individuals identified in the proposal of the successful contractor are contractually essential for successful contractor accomplishment of the work to be performed under this Optimized Remediation Contract (ORC). One person may serve in more than one Critical Project Functions role provided they meet the qualifications of each position in which they serve and there are no time conflicts related to performing multiple tasks, but shall demonstrate an effective organizational structure for this contract and depict clear assignment of Critical Project Functions with responsibilities commensurate with authority for their respective positions.

If issues or conflicts are noted during site inspections, the COR/PM may require additional resources to be added (e.g., addition of a site health and safety officer and/or quality control supervisor during field activities). Personnel serving in Critical Project Functions shall be United States Citizens or shall have adequate documentation to allow full unrestricted and unescorted access to US military installations. Other disciplines not listed will be required to have comparable qualifications in their field of expertise.

Unless otherwise indicated by the Contracting Officer (KO) in writing, the design of structural, mechanical, electrical, civil, environmental, or other specific engineering features of work required in this contract shall be reviewed and approved by Engineers licensed in the state of Florida, i.e., Florida PE. Environmental investigations, assessments, remediation, and monitoring work plans, reports, and other documentation involving soil and groundwater sampling/analysis, removal actions, geochemistry, hydrogeology, and other tasks related to the field of geology shall be reviewed and approved by a professional Geologist registered in the state of Florida.

Depending on the management structure approved for this contract, there shall be at least one Program Manager and one Senior Project Manager for this ORC; the Contractor may elect to allocate a Project Manager to each installation or both collectively. An effective management organization and utilization of Critical Project Functions for the ORC is advantageous to the Government and will be a key element in the selection of the successful Contractor.

1.1 Key Personnel Replacement Protocols

The personnel assigned to the Critical Project Functions specified herein are considered essential to the work being performed under this ORC, and the individuals identified in the Contractor's proposal are contractually committed to the performance of this contract. To prevent the replacement of key personnel with individuals holding substandard qualifications, the following protocols are strictly established under the authority of the Contracting Officer (KO):

- **Initial Performance Lock-In:** No key personnel or Critical Project Functions substitutions shall be permitted during the first ninety (90) days of contract performance unless necessitated by sudden illness, death, or termination of employment.
- **Program Manager:** Due to the critical nature of this position in setting the execution perspective for this ORC, in addition to meeting the minimum requirements for this key position, any changes

in program manager shall require an in-person assessment with the COR, PM, and AFCEC RPM. Contractor senior management shall notify the government and arrange details for the in-person assessment. Based on the results of the assessment, the government will confirm if the proposed replacement is a commensurate fit for the position.

- **Prior Notification:** Prior to removing, replacing, or diverting any specified key personnel, the Contractor shall notify the Contracting Officer (KO) and the COR/PM in writing at least thirty (30) days in advance. The Program Manager position requires at least sixty (60) days prior notification.
- **Justification Package:** The Contractor‘s notification must include a detailed justification for the substitution, a comprehensive resume for the proposed replacement, and a comparison matrix mapping the proposed candidate’s credentials against the minimum requirements and the credentials of the departing individual.
- **“Equal to or Greater Than” Standard:** Any proposed substitute must possess qualifications (e.g., education, professional registrations, certifications, and environmental remediation experience) that are equal to or greater than those of the person being replaced.
- **Contracting Officer Approval:** No substitution shall be made without the prior written consent of the Contracting Officer. The KO retains unilateral veto authority over any replacement candidate deemed to have substandard qualifications.

1.2. Critical Project Functions Summary

The following matrix summarizes the required Critical Project Functions positions, minimum educational requirements, and key experience thresholds required under this contract.

Position	Minimum Education	Key Experience Threshold
Program Manager	Bachelor’s (PE/PG if applicable to degree)	10+ yrs Gen / 5+ yrs DoD / 7+ yrs FL/ 3+ yrs AF
Senior Project Manager(s)	Bachelor’s (PE/PG if applicable to degree)	10+ yrs Gen / 5+ yrs FL / 3+ yrs DoD
Senior Site Manager(s)	Bachelor’s (Path A) / Non-degreed (Path B)	7+ yrs (Path A) / 10+ yrs (Path B) / 3+ yrs FL
Contracts Manager	Bachelor’s (Business/Finance preferred)	10+ yrs Gen / 5+ yrs Federal
QA/QC Manager	Bachelor’s (Technical) + CQM-C	10+ yrs Env / 5+ yrs QA/QC
Risk Assessor	Bachelor’s (Scientific)	10+ yrs Federal / 3+ yrs EPA Reg 4/FL

Position	Minimum Education	Key Experience Threshold
Health & Safety Manager	Bachelor's + CSP/CIH	10+ yrs HTRW / 5+ yrs Safety
Program Chemist	Master's (Path A) / Bachelor's (Path B)	5+ yrs (Path A) / 10+ yrs (Path B)
Public Affairs Officer	Bachelor's	5+ yrs Env
Project Controls Manager	Bachelor's	7+ yrs Gen / 5+ yrs Federal
Project Scheduler	Bachelor's (Path A) / Non-degreed (Path B)	5+ yrs Gen / 3+ yrs Env (Path A) / 10+ yrs (Path B)
Security Manager	High School / Equivalent	3+ yrs DoD Security / OPSEC

2. Critical Program Functions/Key Personnel and Requirements

2.1 Program Manager

The Program Manager (PgM) shall be a direct employee of the Prime Contractor and serves as the primary, single point-of-contact for the COR/PM for all programmatic issues regarding contract execution. The Offeror shall assign the proposed PgM upon award, and this individual shall be vested with the corporate authority to seamlessly allocate and commit resources to ensure successful contract performance. The PgM is responsible for the overarching technical, financial, and schedule management of all tasks performed under this ORC. Specifically, the PgM shall:

- Ensure that robust, practical, and effective systems (including project controls, risk management, health and safety, and quality assurance) are developed and implemented to meet the objectives of the action.
- Ensure that high-quality work is completed on schedule and that all site-specific Performance Objectives and firm-fixed-price milestones are successfully achieved.
- Maintain programmatic consistency, regulatory compliance, and cohesive strategic execution across all sites and throughout the entire lifecycle of the contract.
- Proactively identify and mitigate technical and programmatic risks, ensuring continuous alignment with Government and regulatory stakeholder expectations.

Minimum Qualifications

- **Education:** Bachelor's degree from an accredited school in a technically related discipline such as architecture, engineering, environmental science, geology, hydrology, chemistry, industrial hygiene or other technically-related fields is preferred.
- **Professional Registration:** Professional registration, where required by discipline/degree, i.e.,

Florida PE or Florida PG.**General Program Management Experience:** A minimum of ten (10) years of professional experience in a Program Manager role, with at least seven (7) of those years spent managing large-scale environmental remediation or complex civil construction programs.

- **Specialized Federal & ORC Experience:** A minimum of five (5) years of direct experience managing DoD environmental remediation programs. This experience must include the direct management of Performance-Based Remediation (PBR) or Optimized Remediation Contracts (ORC) or equivalent environmental restoration performance-based contract.
- **Florida State Regulatory Experience:** A minimum of seven (7) years of direct environmental investigation and remediation experience within the state of Florida, demonstrating thorough familiarity with Florida Department of Environmental Protection (FDEP) regulations and FAC 62-780.
- **Air Force Installation Experience:** A minimum of three (3) years of direct experience managing environmental remediation services specifically at Air Force installations within the state of Florida (e.g., Eglin AFB, Hurlburt Field, Tyndall AFB, or other Florida-based Air Force sites).

2.2. Senior Project Manager(s)

The Senior Project Manager (PM) position may be held by personnel from either the Prime Contractor or an approved contractual teaming partner; however, the Prime Contractor retains ultimate contractual accountability for their performance and compliance to contract requirements. Based on the organizational structure and span of control proposed by the Offeror, one or more Senior PM(s) shall be assigned to this ORC to ensure adequate oversight of all activities.

The Senior PM is responsible for the direct technical execution and operational implementation of site-specific work. The Senior PM shall evaluate the technical and regulatory requirements of their assigned sites and lead the development, regulatory negotiation, and implementation of the technical approaches and work plans necessary to achieve the contractual Performance Objectives (POs) safely and on schedule. The Senior PM shall serve as the primary operational point-of-contact for the USACE COR/PM and AFCEC RPM, and shall actively participate in technical and programmatic meetings with USACE, the Air Force, and relevant regulatory agencies.

Furthermore, the Senior PM is responsible for providing rigorous management-level oversight of all field operations. This includes:

- Directing and coordinating field personnel and major subcontractors.
- Enforcing strict adherence to the approved Site Safety and Health Plan (SSHP) and Quality Control Plan (QCP).
- Conducting routine site inspections and field audits.
- Managing site-level budgets, field schedules, and logistical requirements to ensure uninterrupted progress toward remedial milestones.

Minimum Qualifications

- **Education:** Bachelor's degree from an accredited school in a technically related field such as: Architecture, engineering, environmental science, geology, hydrology, chemistry, industrial hygiene or other technically related fields.
- **Professional Registration:** Professional registration, where required by discipline/degree, including a Florida PE or PG, as applicable. May hold a current professional registration in another U.S. state or jurisdiction, provided the individual is eligible to obtain Florida registration through reciprocity.
- **General Project Management Experience:** A minimum of ten (10) years of professional experience serving as a Project Manager on complex environmental or heavy civil construction projects.
- **Specialized Regional Experience:** A minimum of five (5) years of experience specifically managing environmental investigation and remediation projects at the field operational level within the state of Florida.
- **Specialized Federal Experience:** A minimum of three (3) years of direct experience managing environmental remediation or construction projects for the Department of Defense (DoD), demonstrating familiarity with USACE/Air Force project execution standards.

2.3. Senior Site Manager(s)

The Senior Site Manager(s) serving as the Field Supervisor or Site Superintendent, is responsible for providing full, direct, on-site oversight and supervision of all field activities conducted by Prime Contractor and subcontractor personnel for all sites other than Land Use Control (LUC) only Sites. Full, direct, on-site oversite and supervision of all field activities conducted by Prime Contractor and subcontractor personnel at LUC only sites may be delegated to a qualified field technician. The SSM position may be held by personnel from either the Prime Contractor or an approved contractual teaming partner. To ensure safe and compliant execution, the Senior Site Manager must be physically present on-site at all times during active field operations.

Specifically, the SSM is responsible for directly supervising and coordinating all daily field operations, site logistics, and subcontractor activities; strictly implementing and enforcing all approved plans; executing daily safety briefings; and exercising explicit "Stop-Work" authority to immediately halt any field operation that poses a hazard to site personnel, the public, the environment, or threatens to compromise data/construction quality.

Qualification Tracks

Path A: Degreed Track

- **Education:** Bachelor's degree from an accredited school in engineering, environmental science, geology, hydrology, chemistry, industrial hygiene, construction management, or a closely related technical discipline.
- **Professional Registration:** Professional registration, where required by discipline/degree, i.e., Florida PE or PG.
- **General Field Experience:** A minimum of seven (7) years of professional experience performing

field management and supervisory duties.

- **Specialized Regional Experience:** A minimum of five (5) years of experience managing environmental investigation and remediation projects at the field operational level within the state of Florida.

Path B: Experience Track (Non-Degreed)

- **Education:** High School Diploma or equivalent. No college degree is required under this path.
- **General Field Experience:** A minimum of ten (10) years of professional experience performing field management and supervisory duties as a Site Manager or Site Superintendent on environmental remediation or heavy civil construction projects.
- **Specialized Regional Experience:** A minimum of five (5) years of experience explicitly managing environmental investigation and remediation projects at the field operational level within the state of Florida.

Mandatory Certifications (Applies to BOTH Tracks)

- **Safety & Field Credentials:** The individual must possess verifiable experience executing field work in accordance with the USACE Safety and Health Requirements Manual (EM 385-1-1). Additionally, the individual must possess a current 40-Hour OSHA HAZWOPER certification (29 CFR 1910.120), an 8-Hour HAZWOPER Supervisor certification, and a current 30-Hour OSHA Construction Safety certification (or equivalent).

2.4. Contracts Manager

The Contracts Manager is responsible for providing comprehensive federal contract administration, financial oversight, and business management support throughout the lifecycle of the ORC. The Contracts Manager shall ensure that all Prime Contractor and subcontractor operations strictly comply with the terms and conditions of the contract, the Federal Acquisition Regulation (FAR), and the Defense Federal Acquisition Regulation Supplement (DFARS). Specific responsibilities include financial & budgetary oversight, subcontract & procurement management, and contractual compliance & change management.

Minimum Qualifications

- **Education:** Bachelor’s degree in business administration, finance, contract management, accounting, or a closely related field.
- **General Experience:** A minimum of ten (10) years of professional, directly applicable experience in federal contract administration, procurement, and financial management.
- **Specialized Federal Compliance Experience:** A minimum of five (5) years of direct experience executing and managing large-scale federal service or construction contracts. This experience must include:
    - Demonstrated, practical application of the Federal Acquisition Regulation (FAR) and Defense Federal Acquisition Regulation Supplement (DFARS).

  - Managing subcontracting plans and monitoring compliance with FAR limitations on subcontracting (e.g., FAR 52.219-14).
  - Preparing and negotiating cost proposals, managing project accounting, and executing Firm-Fixed-Price (FFP) milestone billing.
- **Certifications:** Possession of a recognized federal contracting certification (e.g., Certified Federal Contracts Manager [CFCM] from NCMA, or equivalent DAWIA/FAC-C training credentials) is highly preferred.

2.5. Quality Assurance/Quality Control (QA/QC) Manager

The Program QA/QC Manager shall be responsible for developing, maintaining, and rigorously enforcing the ORC environmental quality program. The QA/QC Manager position may be held by personnel from either the Prime Contractor or an approved contractual teaming partner; however, to maintain objective oversight, the QA/QC Manager must report to a senior corporate official independent of the daily production and project management team. The QA/QC Manager serves as the primary point-of-contact for the Government for all quality-related issues and is directly responsible for maintaining the overarching ORC Quality Management Plan (QMP).

Minimum Qualifications

- **Education:** Bachelor's degree in engineering, geology, environmental science, physical science, or a closely related technical discipline.
- **General Environmental Experience:** A minimum of ten (10) years of professional experience in environmental investigation and remediation practices, field procedures, and analytical testing.
- **Specialized QA/QC Experience:** A minimum of five (5) years of direct experience managing, developing, and executing Quality Assurance/Quality Control (QA/QC) programs on federal construction or environmental remediation contracts. This must include verifiable experience implementing the USACE Three-Phase Quality Control System (Preparatory, Initial, and Follow-up phases). Must have experience preparing detailed operating instructions and standard operating procedures.
- **Required Certification:** The individual must possess a current and active USACE / NAVFAC Construction Quality Management for Contractors (CQM-C) certification. (Note: For any post-award Key Personnel replacements, the proposed substitute must possess an active CQM-C certification at the time the substitution request is submitted to the Government).

2.6. Risk Assessor

This Key Position shall be responsible for the strategic development, execution, and defense of all risk models and supporting risk-related documentation required under this contract. The Program Risk Assessor must possess exceptional quantitative, toxicological, and analytical skills to evaluate complex site data and develop defensible risk-based closure strategies. The Risk Assessor shall be responsible for conducting both Human Health Risk Assessments (HHRA) and Ecological Risk Assessments (ERA) in strict accordance with federal (CERCLA/RCRA, EPA Risk Assessment Guidance for Superfund [RAGS]) and state regulations.

Minimum Qualifications

- **Education:** Bachelor's degree in toxicology, risk management, statistics, biochemistry, environmental science, or a closely related scientific discipline. (Note: A Master's or Ph.D. in one of these fields is highly encouraged but does not substitute for the minimum experience requirements below).
- **Federal Risk Assessment Experience:** A minimum of ten (10) years of professional experience performing human health and ecological risk assessments under federal regulatory frameworks, specifically including CERCLA (Superfund), RCRA, and TSCA on Federal Government contracts. Two resumes may be provided (one for human health and one for ecological risk assessments) to demonstrate professional experience.
- **Regional & State Regulatory Experience:** A minimum of three (3) years of direct experience completing and defending risk assessments within EPA Region 4 and the State of Florida. This must include demonstrated experience negotiating risk-based closures and developing conceptual site models in strict accordance with the Florida Department of Environmental Protection (FDEP) Contaminated Site Cleanup Criteria (FAC 62-780).
- **Technical Proficiency:** Demonstrated experience in fate and transport modeling, exposure pathway analysis, toxicological profiling, and the development of site-specific cleanup target levels (SCTLs) or institutional/engineering control strategies.

2.7. Health and Safety Manager

The Program Health and Safety Manager (HSM) shall be responsible for the overarching development, maintenance, and rigorous implementation of the occupational health and safety programs for this contract. The HSM position may be held by personnel from either the Prime Contractor or an approved contractual teaming partner; however, the Prime Contractor retains ultimate accountability for the safety of all site operations. The HSM shall ensure that all Prime Contractor and subcontractor personnel, processes, and field operations strictly adhere to federal safety regulations, specifically including OSHA HAZWOPER (29 CFR 1910.120), OSHA Construction Standards (29 CFR 1926), and the USACE Safety and Health Requirements Manual (EM 385-1-1).

Minimum Qualifications

- **Education:** Bachelor's degree in occupational safety and health, industrial hygiene, environmental health, or a closely related technical discipline.
- **Professional Board Certification:** The individual must possess, and maintain in active status, certification as either a Certified Safety Professional (CSP) (issued by the Board of Certified Safety Professionals [BCSP]) or a Certified Industrial Hygienist (CIH) (issued by the Board of Global Credentialing [BGC]).
- **General Experience:** A minimum of ten (10) years of comprehensive environmental remediation or hazardous waste (HTRW) experience.
- **Specialized Safety Management Experience:** A minimum of five (5) years of experience explicitly dedicated to developing, managing, and overseeing health and safety programs within the environmental remediation industry.

- **USACE Safety Standards (EM 385-1-1):** Demonstrated experience executing safety programs in strict accordance with the USACE Safety and Health Requirements Manual (EM 385-1-1), explicitly including the development and implementation of programmatic Accident Prevention Plans (APPs) and site-specific Activity Hazard Analyses (AHAs).
- **Required Training & Certifications:** The individual must possess:
  - Current 40-hour OSHA HAZWOPER certification (29 CFR 1910.120).
  - Current 8-hour OSHA HAZWOPER Supervisor certification.
  - Completion of a 30-hour OSHA Construction safety class (or equivalent) within the last five (5) years. If a 30-hour OSHA Construction Safety course (or equivalent) was completed more than five (5) years previous, demonstration of ongoing safety training, continuing professional development, and compliance with applicable EM 381-1-1 qualification requirements since completion of the 30-hour OSHA Construction safety course will be considered responsive to this requirement.

2.8. Program Chemist

The Program Chemist shall be responsible for developing, maintaining, and rigorously enforcing the analytical quality assurance program as it pertains to all field sampling and laboratory chemical analyses. The Program Chemist position may be held by personnel from either the Prime Contractor or an approved contractual teaming partner. The Program Chemist serves as the primary technical point-of-contact for all chemistry-related issues, including analytical methodologies, data validation, chemical data quality, and the initiation and resolution of corrective actions.

Qualification Tracks

Path A: Advanced Degree Track

- **Education:** Master's degree in chemistry, biochemistry, or a closely related scientific discipline.
- **General Analytical Experience:** A minimum of five (5) years of professional chemistry laboratory experience, explicitly including hands-on experience with both organic and inorganic analytical chemistry methodologies, field sampling procedures, and laboratory quality control protocols.
- **DoD Data Validation Experience:** A minimum of five (5) years of experience conducting formal environmental chemical data validation in accordance with the EPA National Functional Guidelines (NFG) and DoD Data Validation guidelines. (Note: This experience may run concurrently with the general analytical experience).
- **Laboratory Management Experience:** A minimum of three (3) years of experience managing, auditing, or overseeing analytical laboratories (including subcontract laboratories), with demonstrated experience in resolving laboratory non-conformances, evaluating analytical method troubleshooting, and implementing corrective action plans. (Note: This experience may be included within the five (5) years of general analytical experience).

Path B: Professional Degree Track

- **Education:** Bachelor's degree in chemistry. No professional experience may be substituted for this degree requirement.

- **General Analytical Experience:** A minimum of ten (10) years of professional chemistry laboratory experience, explicitly including hands-on experience with both organic and inorganic analytical chemistry methodologies, field sampling procedures, and laboratory quality control protocols.
- **DoD Data Validation Experience:** A minimum of five (5) years of experience conducting formal environmental chemical data validation in accordance with the EPA National Functional Guidelines (NFG) and DoD Data Validation guidelines. (Note: This experience may run concurrently with the general analytical experience).
- **Laboratory Management Experience:** A minimum of three (3) years of experience managing, auditing, or overseeing analytical laboratories (including subcontract laboratories), with demonstrated experience in resolving laboratory non-conformances, evaluating analytical method troubleshooting, and implementing corrective action plans. (Note: This experience may be included within the ten (10) years of general analytical experience).

2.9. Public Affairs Officer

The Public Affairs Officer (PAO) shall be responsible for developing, maintaining, and ensuring implementation of the public affairs and community relations programs for the ORC. This responsibility includes interacting with all stakeholders in the remediation process, facilitating communication among all parties and assisting in keeping schedule delays due to public outrage at a minimum. The PAO shall work closely with Government Public Affairs officials, PM, RPM, and others to ensure effective communication is maintained between the Government and public during ORC execution.

Minimum Qualifications

- **Education:** Bachelor's degree in journalism, public affairs, or a closely related discipline.
- **General Experience:** A minimum of five (5) years of successful public affairs experience supporting CERCLA, RCRA, and/or Superfund Cleanup projects. OR A minimum of five (5) years of experience in public affairs related to environmental remediation contracts with an emphasis in Restoration Advisory Boards, public meetings, and other tasks/responsibilities directly related to environmental restoration and public interaction at DoD installations.

2.10. Project Controls Manager

The Project Controls Manager (PCM) shall be responsible for monitoring, analyzing, and controlling project cost and schedule performance to ensure the successful execution of all task orders under this Optimized Remediation Contract (ORC). The PCM position may be held by personnel from either the Prime Contractor or an approved contractual teaming partner. The PCM provides critical, quantitative support to the Program and Senior Project Managers, ensuring that the Integrated Master Schedule (IMS) and Master Project Schedule (MPS) adhere to contractual requirements, USACE scheduling standards, and industry best practices. While a full, formal Earned Value Management (EVM) program is not required for this contract, the PCM shall be responsible for developing, implementing, and reporting on a hybrid earned value and earned schedule approach as described in the PWS.

Minimum Qualifications

- **Education:** Bachelor's degree in engineering, construction management, business administration,

finance, or a related field.

- **General Experience:** A minimum of seven (7) years of directly applicable, professional experience in project controls, including cost engineering, critical path scheduling, and change management.
- **Specialized Federal Experience:** A minimum of five (5) years of experience performing dedicated project control duties on federal construction or environmental remediation contracts (experience on USACE or NAVFAC projects is required). This experience must explicitly include:
  - Developing and implementing Work Breakdown Structures (WBS).
  - Executing cost/schedule variance analysis and performance measurement reporting (e.g., Earned Value or Earned Schedule metrics).
  - Performing cost forecasting, configuration management, and change control.
- **Software Proficiency:** Verifiable, advanced proficiency in enterprise scheduling software (Primavera P6) and advanced financial modeling in MS Excel or other software.

2.11. Project Scheduler

The Project Scheduler plays an essential role in the planning, execution, and monitoring processes of the project. The Project Scheduler position may be held by personnel from either the Prime Contractor or an approved contractual teaming partner. The Project Scheduler shall collaborate with the Program Manager, Senior Project Managers, and technical staff to develop a detailed, realistic, and Critical Path Method (CPM)-based Integrated Master Schedule (IMS). The Project Scheduler supports the Project Controls Manager in developing, implementing, and maintaining an effective schedule management system that supports the contract's hybrid earned value and earned schedule approach and rigorous schedule management requirements.

Qualification Tracks

Path A: Degreed Track

- **Education:** Bachelor's degree in engineering, construction management, business, finance, or a related discipline.
- **General Experience:** A minimum of five (5) years of directly applicable experience in project controls, with a specific focus on Critical Path Method (CPM) scheduling and the development of resource- and cost-loaded schedules within a federal contracting environment.
- **Specialized Environmental Experience:** A minimum of three (3) years of direct experience scheduling, monitoring, and controlling complex environmental restoration projects. This must include experience developing Integrated Master Schedules (IMS), Schedule Risk Analyses, and Schedule Narrative Reports for performance-based contracts.
- **Software Proficiency:** Verifiable proficiency and advanced training in Primavera P6 scheduling software and MS Excel.

Path B: Experience Track (Non-Degreed)

- **Education:** High School Diploma or equivalent. No college degree is required under this path.
- **General Field Experience:** A minimum of ten (10) years of directly applicable experience in

project controls, with a specific focus on Critical Path Method (CPM) scheduling and the development of resource- and cost-loaded schedules within a federal contracting environment.

- **Specialized Environmental Experience:** A minimum of three (3) years of direct experience scheduling, monitoring, and controlling complex environmental restoration projects. This must include experience developing Integrated Master Schedules (IMS), Schedule Risk Analyses, and Schedule Narrative Reports for performance-based contracts.
- **Software Proficiency:** Verifiable proficiency and advanced training in Primavera P6 scheduling software and MS Excel.

2.12. Security Manager

The Security Manager plays a crucial role in maintaining the security, integrity, and operational flow of Contractor activities at Eglin Air Force Base (AFB), Hurlburt Field, and Tyndall AFB.
Given the highly secure nature of these installations, this position is responsible for ensuring that all Prime Contractor and subcontractor personnel, as well as all vendors and delivery drivers, meet the stringent access requirements and strictly comply with installation-specific security directives. The Security Manager serves as the single point-of-contact for all security-related issues for the Optimized Remediation Contract (ORC) and acts as the primary liaison between the Contractor, the Air Force Remedial Project Manager (RPM), Base Security Forces, and the local USACE office.

Minimum Qualifications

- **Experience:** A minimum of three (3) years of directly applicable experience managing physical security, personnel credentialing, and Operations Security (OPSEC) compliance on Department of Defense (DoD) or military installations. (Note: Prior active-duty military or law enforcement experience operating in a security forces/military police capacity may be substituted year-for-year for this requirement).

USACE CLIN	AFCEC CLIN/Sub-CLIN Number	Installation	Site	AFCEC CLIN/Sub-CLIN Description	Projected/Estimated Award Date (Pending availability of funding and bona fide need as determined by the Government. ALL OPTIONS EXPIRE 114 MONTHS AFTER CONTRACT AWARD)*1	Price (Rounded to whole dollar)
	0001	N/A	N/A	Complete Project Management Plan (PMP)		
0001	0001CA	N/A	N/A	Complete PMP	Base Year (2027)	
0002	0001CB	N/A	N/A	Update PMP	Optional Task	
0003	0001CC	N/A	N/A	Update PMP	Optional Task	
0004	0001CD	N/A	N/A	Complete ORC Transition Plan	OY8 (2035)	
	0002	N/A	N/A	Develop Integrated Master Schedule (IMS)/Milestone Payment Schedule (MPS) and Update Monthly		
0005	0002CA	N/A	N/A	Develop IMS/MPS and Update Monthly	Base Year (2027)	
0006	0002CB	N/A	N/A	Update IMS/MPS Monthly - OY1 (2028)	OY1 (2028)	
0007	0002CC	N/A	N/A	Update IMS/MPS Monthly - OY2 (2029)	OY2 (2029)	
0008	0002CD	N/A	N/A	Update IMS/MPS Monthly - OY3 (2030)	OY3 (2030)	
0009	0002CE	N/A	N/A	Update IMS/MPS Monthly - OY4 (2031)	OY4 (2031)	
0010	0002CF	N/A	N/A	Update IMS/MPS Monthly - OY5 (2032)	OY5 (2032)	
0011	0002CG	N/A	N/A	Update IMS/MPS Monthly - OY6 (2033)	OY6 (2033)	
0012	0002CH	N/A	N/A	Update IMS/MPS Monthly - OY7 (2034)	OY7 (2034)	
0013	0002CJ	N/A	N/A	Update IMS/MPS Monthly - OY8 (2035)	OY8 (2035)	
0014	0002CK	N/A	N/A	Update IMS/MPS Monthly - OY9 (2036)	OY9 (2036)	
	0003	Eglin AFB	N/A	Update Community Involvement Plan		
0015	0003CA	Eglin AFB	All Open Sites (IRP, MMRP, PFAS, etc)	Update Community Involvement Plan	Base Year (2027)	
0016	0003CB	Eglin AFB	All Open Sites (IRP, MMRP, PFAS, etc)	Update Community Involvement Plan	OY3 (2030)	
0017	0003CC	Eglin AFB	All Open Sites (IRP, MMRP, PFAS, etc)	Update Community Involvement Plan	OY6 (2033)	
0018	0003CD	Eglin AFB	All Open Sites (IRP, MMRP, PFAS, etc)	Update Community Involvement Plan	OY9 (2036)	
	0004	Eglin AFB	N/A	Complete IRP Basewide Quality Program Plans (QPP)		
0019	0004CA	Eglin AFB	N/A	Complete IRP Basewide QPP	Base Year (2027)	
0020	0004CB	Eglin AFB	N/A	Update IRP Basewide QPP	Optional Task	
0021	0004CC	Eglin AFB	N/A	Update IRP Basewide QPP	Optional Task	
	0005	Eglin AFB	N/A	Perform RCRA Corrective Action/Hazardous and Solid Waste Amendments (CA/HWSA) Permit Renewal and Modification		
0022	0005CA	Eglin AFB	N/A	Perform RCRA CA/HWSA Permit Renewal	OY2 (2029)	
0023	0005CB	Eglin AFB	N/A	Perform RCRA CA/HWSA Permit Modification	Optional Task	
	0006	Eglin AFB	N/A	Perform Well Abandonment		
0024	0006CA	Eglin AFB	N/A	Abandon up to one hundred fifty-five (155) Basewide Wells	OY2 (2029)	
	0007	Eglin AFB	CF288	Achieve Remedial Action Plan (RAP)		
0025	0007AA	Eglin AFB	CF288	Achieve Supplemental Site Assessment	OY1 (2028)	
0026	0007AB	Eglin AFB	CF288	Achieve Remedial Action Plan	Optional Task	
	0008	Eglin AFB	DP009	Conduct LTM		
0027	0008CA	Eglin AFB	DP009	Conduct LTM in accordance with the approved ROD/DD	Base Year (2027)	
0028	0008CB	Eglin AFB	DP009	Conduct LTM in accordance with the approved ROD/DD - OY1 (2028)	OY1 (2028)	
0029	0008CC	Eglin AFB	DP009	Conduct LTM in accordance with the approved ROD/DD - OY2 (2029)	OY2 (2029)	
0030	0008CD	Eglin AFB	DP009	Conduct LTM in accordance with the approved ROD/DD - OY3 (2030)	OY3 (2030)	
0031	0008CE	Eglin AFB	DP009	Conduct LTM in accordance with the approved ROD/DD - OY4 (2031)	OY4 (2031)	
0032	0008CF	Eglin AFB	DP009	Conduct LTM in accordance with the approved ROD/DD - OY5 (2032)	OY5 (2032)	
0033	0008CG	Eglin AFB	DP009	Conduct LTM in accordance with the approved ROD/DD - OY6 (2033)	OY6 (2033)	
0034	0008CH	Eglin AFB	DP009	Conduct LTM in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)	
0035	0008CJ	Eglin AFB	DP009	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0036	0008CK	Eglin AFB	DP009	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0009	Eglin AFB	DP084	Conduct LTM		
0037	0009CA	Eglin AFB	DP084	Conduct LTM in accordance with the approved ROD/DD	Base Year (2027)	
0038	0009CB	Eglin AFB	DP084	Conduct LTM in accordance with the approved ROD/DD - OY1 (2028)	OY1 (2028)	
0039	0009CC	Eglin AFB	DP084	Conduct LTM in accordance with the approved ROD/DD - OY2 (2029)	OY2 (2029)	
0040	0009CD	Eglin AFB	DP084	Conduct LTM in accordance with the approved ROD/DD - OY3 (2030)	OY3 (2030)	
0041	0009CE	Eglin AFB	DP084	Conduct LTM in accordance with the approved ROD/DD - OY4 (2031)	OY4 (2031)	
0042	0009CF	Eglin AFB	DP084	Conduct LTM in accordance with the approved ROD/DD - OY5 (2032)	OY5 (2032)	
0043	0009CG	Eglin AFB	DP084	Conduct LTM in accordance with the approved ROD/DD - OY6 (2033)	OY6 (2033)	
0044	0009CH	Eglin AFB	DP084	Conduct LTM in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)	
0045	0009CJ	Eglin AFB	DP084	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0046	0009CK	Eglin AFB	DP084	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0010	Eglin AFB	DP261	Conduct LTM		
0047	0010CA	Eglin AFB	DP261	Conduct LTM in accordance with the approved ROD/DD	Base Year (2027)	
0048	0010CB	Eglin AFB	DP261	Conduct LTM in accordance with the approved ROD/DD - OY1 (2028)	OY1 (2028)	
0049	0010CC	Eglin AFB	DP261	Conduct LTM in accordance with the approved ROD/DD - OY2 (2029)	OY2 (2029)	
0050	0010CD	Eglin AFB	DP261	Conduct LTM in accordance with the approved ROD/DD - OY3 (2030)	OY3 (2030)	
0051	0010CE	Eglin AFB	DP261	Conduct LTM in accordance with the approved ROD/DD - OY4 (2031)	OY4 (2031)	
0052	0010CF	Eglin AFB	DP261	Conduct LTM in accordance with the approved ROD/DD - OY5 (2032)	OY5 (2032)	
0053	0010CG	Eglin AFB	DP261	Conduct LTM in accordance with the approved ROD/DD - OY6 (2033)	OY6 (2033)	
0054	0010CH	Eglin AFB	DP261	Conduct LTM in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)	
0055	0010CJ	Eglin AFB	DP261	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0056	0010CK	Eglin AFB	DP261	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0011	Eglin AFB	FT028	Conduct LTM		
0057	0011CA	Eglin AFB	FT028	Conduct LTM in accordance with the approved ROD/DD	Base Year (2027)	
0058	0011CB	Eglin AFB	FT028	Conduct LTM in accordance with the approved ROD/DD - OY1 (2028)	OY1 (2028)	
0059	0011CC	Eglin AFB	FT028	Conduct LTM in accordance with the approved ROD/DD - OY2 (2029)	OY2 (2029)	
0060	0011CD	Eglin AFB	FT028	Conduct LTM in accordance with the approved ROD/DD - OY3 (2030)	OY3 (2030)	
0061	0011CE	Eglin AFB	FT028	Conduct LTM in accordance with the approved ROD/DD - OY4 (2031)	OY4 (2031)	
0062	0011CF	Eglin AFB	FT028	Conduct LTM in accordance with the approved ROD/DD - OY5 (2032)	OY5 (2032)	
0063	0011CG	Eglin AFB	FT028	Conduct LTM in accordance with the approved ROD/DD - OY6 (2033)	OY6 (2033)	
0064	0011CH	Eglin AFB	FT028	Conduct LTM in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)	
0065	0011CJ	Eglin AFB	FT028	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0066	0011CK	Eglin AFB	FT028	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	

	0012	Eglin AFB	LF003	Conduct RA-O		
0067	0012CA	Eglin AFB	LF003	Conduct RA-O in accordance with the approved ROD/DD	Base Year (2027)	
0068	0012CB	Eglin AFB	LF003	Conduct RA-O in accordance with the approved ROD/DD - OY1 (2028)	OY1 (2028)	
0069	0012CC	Eglin AFB	LF003	Conduct RA-O in accordance with the approved ROD/DD - OY2 (2029)	OY2 (2029)	
0070	0012CD	Eglin AFB	LF003	Conduct RA-O in accordance with the approved ROD/DD - OY3 (2030)	OY3 (2030)	
0071	0012CE	Eglin AFB	LF003	Conduct RA-O in accordance with the approved ROD/DD - OY4 (2031)	OY4 (2031)	
0072	0012CF	Eglin AFB	LF003	Conduct RA-O in accordance with the approved ROD/DD - OY5 (2032)	OY5 (2032)	
0073	0012CG	Eglin AFB	LF003	Conduct RA-O in accordance with the approved ROD/DD - OY6 (2033)	OY6 (2033)	
0074	0012CH	Eglin AFB	LF003	Conduct RA-O in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)	
0075	0012CJ	Eglin AFB	LF003	Conduct RA-O in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0076	0012CK	Eglin AFB	LF003	Conduct RA-O in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0013	Eglin AFB	LF005	Conduct LTM		
0077	0013CA	Eglin AFB	LF005	Conduct LTM in accordance with the approved ROD/DD	Base Year (2027)	
0078	0013CB	Eglin AFB	LF005	Conduct LTM in accordance with the approved ROD/DD - OY1 (2028)	OY1 (2028)	
0079	0013CC	Eglin AFB	LF005	Conduct LTM in accordance with the approved ROD/DD - OY2 (2029)	OY2 (2029)	
0080	0013CD	Eglin AFB	LF005	Conduct LTM in accordance with the approved ROD/DD - OY3 (2030)	OY3 (2030)	
0081	0013CE	Eglin AFB	LF005	Conduct LTM in accordance with the approved ROD/DD - OY4 (2031)	OY4 (2031)	
0082	0013CF	Eglin AFB	LF005	Conduct LTM in accordance with the approved ROD/DD - OY5 (2032)	OY5 (2032)	
0083	0013CG	Eglin AFB	LF005	Conduct LTM in accordance with the approved ROD/DD - OY6 (2033)	OY6 (2033)	
0084	0013CH	Eglin AFB	LF005	Conduct LTM in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)	
0085	0013CJ	Eglin AFB	LF005	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0086	0013CK	Eglin AFB	LF005	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0014	Eglin AFB	LF008	Conduct LTM		
0087	0014CA	Eglin AFB	LF008	Conduct LTM in accordance with the approved ROD/DD	Base Year (2027)	
0088	0014CB	Eglin AFB	LF008	Conduct LTM in accordance with the approved ROD/DD - OY1 (2028)	OY1 (2028)	
0089	0014CC	Eglin AFB	LF008	Conduct LTM in accordance with the approved ROD/DD - OY2 (2029)	OY2 (2029)	
0090	0014CD	Eglin AFB	LF008	Conduct LTM in accordance with the approved ROD/DD - OY3 (2030)	OY3 (2030)	
0091	0014CE	Eglin AFB	LF008	Conduct LTM in accordance with the approved ROD/DD - OY4 (2031)	OY4 (2031)	
0092	0014CF	Eglin AFB	LF008	Conduct LTM in accordance with the approved ROD/DD - OY5 (2032)	OY5 (2032)	
0093	0014CG	Eglin AFB	LF008	Conduct LTM in accordance with the approved ROD/DD - OY6 (2033)	OY6 (2033)	
0094	0014CH	Eglin AFB	LF008	Conduct LTM in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)	
0095	0014CJ	Eglin AFB	LF008	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0096	0014CK	Eglin AFB	LF008	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0015	Eglin AFB	LF010	Conduct LTM		
0097	0015CA	Eglin AFB	LF010	Conduct LTM in accordance with the approved ROD/DD	Base Year (2027)	
0098	0015CB	Eglin AFB	LF010	Conduct LTM in accordance with the approved ROD/DD - OY1 (2028)	OY1 (2028)	
0099	0015CC	Eglin AFB	LF010	Conduct LTM in accordance with the approved ROD/DD - OY2 (2029)	OY2 (2029)	
0100	0015CD	Eglin AFB	LF010	Conduct LTM in accordance with the approved ROD/DD - OY3 (2030)	OY3 (2030)	
0101	0015CE	Eglin AFB	LF010	Conduct LTM in accordance with the approved ROD/DD - OY4 (2031)	OY4 (2031)	
0102	0015CF	Eglin AFB	LF010	Conduct LTM in accordance with the approved ROD/DD - OY5 (2032)	OY5 (2032)	
0103	0015CG	Eglin AFB	LF010	Conduct LTM in accordance with the approved ROD/DD - OY6 (2033)	OY6 (2033)	
0104	0015CH	Eglin AFB	LF010	Conduct LTM in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)	
0105	0015CJ	Eglin AFB	LF010	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0106	0015CK	Eglin AFB	LF010	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0016	Eglin AFB	LF051	Conduct LTM		
0107	0016CA	Eglin AFB	LF051	Conduct LTM in accordance with the approved ROD/DD	Base Year (2027)	
0108	0016CB	Eglin AFB	LF051	Conduct LTM in accordance with the approved ROD/DD - OY1 (2028)	OY1 (2028)	
0109	0016CC	Eglin AFB	LF051	Conduct LTM in accordance with the approved ROD/DD - OY2 (2029)	OY2 (2029)	
0110	0016CD	Eglin AFB	LF051	Conduct LTM in accordance with the approved ROD/DD - OY3 (2030)	OY3 (2030)	
0111	0016CE	Eglin AFB	LF051	Conduct LTM in accordance with the approved ROD/DD - OY4 (2031)	OY4 (2031)	
0112	0016CF	Eglin AFB	LF051	Conduct LTM in accordance with the approved ROD/DD - OY5 (2032)	OY5 (2032)	
0113	0016CG	Eglin AFB	LF051	Conduct LTM in accordance with the approved ROD/DD - OY6 (2033)	OY6 (2033)	
0114	0016CH	Eglin AFB	LF051	Conduct LTM in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)	
0115	0016CJ	Eglin AFB	LF051	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0116	0016CK	Eglin AFB	LF051	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0017	Eglin AFB	LF322	Achieve Site Assessment		
0117	0017AA	Eglin AFB	LF322	Achieve Site Assessment	OY2 (2029)	
	0018	Eglin AFB	OT083	Conduct LTM		
0118	0018CA	Eglin AFB	OT083	Conduct LTM in accordance with the approved ROD/DD	Base Year (2027)	
0119	0018CB	Eglin AFB	OT083	Conduct LTM in accordance with the approved ROD/DD - OY1 (2028)	OY1 (2028)	
0120	0018CC	Eglin AFB	OT083	Conduct LTM in accordance with the approved ROD/DD - OY2 (2029)	OY2 (2029)	
0121	0018CD	Eglin AFB	OT083	Conduct LTM in accordance with the approved ROD/DD - OY3 (2030)	OY3 (2030)	
0122	0018CE	Eglin AFB	OT083	Conduct LTM in accordance with the approved ROD/DD - OY4 (2031)	OY4 (2031)	
0123	0018CF	Eglin AFB	OT083	Conduct LTM in accordance with the approved ROD/DD - OY5 (2032)	OY5 (2032)	
0124	0018CG	Eglin AFB	OT083	Conduct LTM in accordance with the approved ROD/DD - OY6 (2033)	OY6 (2033)	
0125	0018CH	Eglin AFB	OT083	Conduct LTM in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)	
0126	0018CJ	Eglin AFB	OT083	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0127	0018CK	Eglin AFB	OT083	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0019	Eglin AFB	OT100	Conduct LTM		
0128	0019CA	Eglin AFB	OT100	Conduct LTM in accordance with the approved ROD/DD	Base Year (2027)	
0129	0019CB	Eglin AFB	OT100	Conduct LTM in accordance with the approved ROD/DD - OY1 (2028)	OY1 (2028)	
0130	0019CC	Eglin AFB	OT100	Conduct LTM in accordance with the approved ROD/DD - OY2 (2029)	OY2 (2029)	
0131	0019CD	Eglin AFB	OT100	Conduct LTM in accordance with the approved ROD/DD - OY3 (2030)	OY3 (2030)	
0132	0019CE	Eglin AFB	OT100	Conduct LTM in accordance with the approved ROD/DD - OY4 (2031)	OY4 (2031)	
0133	0019CF	Eglin AFB	OT100	Conduct LTM in accordance with the approved ROD/DD - OY5 (2032)	OY5 (2032)	
0134	0019CG	Eglin AFB	OT100	Conduct LTM in accordance with the approved ROD/DD - OY6 (2033)	OY6 (2033)	
0135	0019CH	Eglin AFB	OT100	Conduct LTM in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)	
0136	0019CJ	Eglin AFB	OT100	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0137	0019CK	Eglin AFB	OT100	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0020	Eglin AFB	OT262	Conduct LTM		
0138	0020CA	Eglin AFB	OT262	Conduct LTM in accordance with the approved ROD/DD	Base Year (2027)	
0139	0020CB	Eglin AFB	OT262	Conduct LTM in accordance with the approved ROD/DD - OY1 (2028)	OY1 (2028)	
0140	0020CC	Eglin AFB	OT262	Conduct LTM in accordance with the approved ROD/DD - OY2 (2029)	OY2 (2029)	
0141	0020CD	Eglin AFB	OT262	Conduct LTM in accordance with the approved ROD/DD - OY3 (2030)	OY3 (2030)	
0142	0020CE	Eglin AFB	OT262	Conduct LTM in accordance with the approved ROD/DD - OY4 (2031)	OY4 (2031)	
0143	0020CF	Eglin AFB	OT262	Conduct LTM in accordance with the approved ROD/DD - OY5 (2032)	OY5 (2032)	
0144	0020CG	Eglin AFB	OT262	Conduct LTM in accordance with the approved ROD/DD - OY6 (2033)	OY6 (2033)	
0145	0020CH	Eglin AFB	OT262	Conduct LTM in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)	
0146	0020CJ	Eglin AFB	OT262	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0147	0020CK	Eglin AFB	OT262	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0021	Eglin AFB	OT263	Conduct LTM		

0148	0021CA	Eglin AFB	OT263	Conduct LTM in accordance with the approved ROD/DD	Base Year (2027)	
0149	0021CB	Eglin AFB	OT263	Conduct LTM in accordance with the approved ROD/DD - OY1 (2028)	OY1 (2028)	
0150	0021CC	Eglin AFB	OT263	Conduct LTM in accordance with the approved ROD/DD - OY2 (2029)	OY2 (2029)	
0151	0021CD	Eglin AFB	OT263	Conduct LTM in accordance with the approved ROD/DD - OY3 (2030)	OY3 (2030)	
0152	0021CE	Eglin AFB	OT263	Conduct LTM in accordance with the approved ROD/DD - OY4 (2031)	OY4 (2031)	
0153	0021CF	Eglin AFB	OT263	Conduct LTM in accordance with the approved ROD/DD - OY5 (2032)	OY5 (2032)	
0154	0021CG	Eglin AFB	OT263	Conduct LTM in accordance with the approved ROD/DD - OY6 (2033)	OY6 (2033)	
0155	0021CH	Eglin AFB	OT263	Conduct LTM in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)	
0156	0021CJ	Eglin AFB	OT263	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0157	0021CK	Eglin AFB	OT263	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0022	Eglin AFB	OT264	Conduct LTM		
0158	0022CA	Eglin AFB	OT264	Conduct LTM in accordance with the approved ROD/DD	Base Year (2027)	
0159	0022CB	Eglin AFB	OT264	Conduct LTM in accordance with the approved ROD/DD - OY1 (2028)	OY1 (2028)	
0160	0022CC	Eglin AFB	OT264	Conduct LTM in accordance with the approved ROD/DD - OY2 (2029)	OY2 (2029)	
0161	0022CD	Eglin AFB	OT264	Conduct LTM in accordance with the approved ROD/DD - OY3 (2030)	OY3 (2030)	
0162	0022CE	Eglin AFB	OT264	Conduct LTM in accordance with the approved ROD/DD - OY4 (2031)	OY4 (2031)	
0163	0022CF	Eglin AFB	OT264	Conduct LTM in accordance with the approved ROD/DD - OY5 (2032)	OY5 (2032)	
0164	0022CG	Eglin AFB	OT264	Conduct LTM in accordance with the approved ROD/DD - OY6 (2033)	OY6 (2033)	
0165	0022CH	Eglin AFB	OT264	Conduct LTM in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)	
0166	0022CJ	Eglin AFB	OT264	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0167	0022CK	Eglin AFB	OT264	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0023	Eglin AFB	OT265	Conduct LTM		
0168	0023CA	Eglin AFB	OT265	Conduct LTM in accordance with the approved ROD/DD	Base Year (2027)	
0169	0023CB	Eglin AFB	OT265	Conduct LTM in accordance with the approved ROD/DD - OY1 (2028)	OY1 (2028)	
0170	0023CC	Eglin AFB	OT265	Conduct LTM in accordance with the approved ROD/DD - OY2 (2029)	OY2 (2029)	
0171	0023CD	Eglin AFB	OT265	Conduct LTM in accordance with the approved ROD/DD - OY3 (2030)	OY3 (2030)	
0172	0023CE	Eglin AFB	OT265	Conduct LTM in accordance with the approved ROD/DD - OY4 (2031)	OY4 (2031)	
0173	0023CF	Eglin AFB	OT265	Conduct LTM in accordance with the approved ROD/DD - OY5 (2032)	OY5 (2032)	
0174	0023CG	Eglin AFB	OT265	Conduct LTM in accordance with the approved ROD/DD - OY6 (2033)	OY6 (2033)	
0175	0023CH	Eglin AFB	OT265	Conduct LTM in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)	
0176	0023CJ	Eglin AFB	OT265	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0177	0023CK	Eglin AFB	OT265	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0024	Eglin AFB	OT269	Conduct LTM		
0178	0024CA	Eglin AFB	OT269	Conduct LTM in accordance with the approved ROD/DD	Base Year (2027)	
0179	0024CB	Eglin AFB	OT269	Conduct LTM in accordance with the approved ROD/DD - OY1 (2028)	OY1 (2028)	
0180	0024CC	Eglin AFB	OT269	Conduct LTM in accordance with the approved ROD/DD - OY2 (2029)	OY2 (2029)	
0181	0024CD	Eglin AFB	OT269	Conduct LTM in accordance with the approved ROD/DD - OY3 (2030)	OY3 (2030)	
0182	0024CE	Eglin AFB	OT269	Conduct LTM in accordance with the approved ROD/DD - OY4 (2031)	OY4 (2031)	
0183	0024CF	Eglin AFB	OT269	Conduct LTM in accordance with the approved ROD/DD - OY5 (2032)	OY5 (2032)	
0184	0024CG	Eglin AFB	OT269	Conduct LTM in accordance with the approved ROD/DD - OY6 (2033)	OY6 (2033)	
0185	0024CH	Eglin AFB	OT269	Conduct LTM in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)	
0186	0024CJ	Eglin AFB	OT269	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0187	0024CK	Eglin AFB	OT269	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0025	Eglin AFB	OT270	Conduct LTM		
0188	0025CA	Eglin AFB	OT270	Conduct LTM in accordance with the approved ROD/DD	Base Year (2027)	
0189	0025CB	Eglin AFB	OT270	Conduct LTM in accordance with the approved ROD/DD - OY1 (2028)	OY1 (2028)	
0190	0025CC	Eglin AFB	OT270	Conduct LTM in accordance with the approved ROD/DD - OY2 (2029)	OY2 (2029)	
0191	0025CD	Eglin AFB	OT270	Conduct LTM in accordance with the approved ROD/DD - OY3 (2030)	OY3 (2030)	
0192	0025CE	Eglin AFB	OT270	Conduct LTM in accordance with the approved ROD/DD - OY4 (2031)	OY4 (2031)	
0193	0025CF	Eglin AFB	OT270	Conduct LTM in accordance with the approved ROD/DD - OY5 (2032)	OY5 (2032)	
0194	0025CG	Eglin AFB	OT270	Conduct LTM in accordance with the approved ROD/DD - OY6 (2033)	OY6 (2033)	
0195	0025CH	Eglin AFB	OT270	Conduct LTM in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)	
0196	0025CJ	Eglin AFB	OT270	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0197	0025CK	Eglin AFB	OT270	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0026	Eglin AFB	OT271	Conduct LTM		
0198	0026CA	Eglin AFB	OT271	Conduct LTM in accordance with the approved ROD/DD	Base Year (2027)	
0199	0026CB	Eglin AFB	OT271	Conduct LTM in accordance with the approved ROD/DD - OY1 (2028)	OY1 (2028)	
0200	0026CC	Eglin AFB	OT271	Conduct LTM in accordance with the approved ROD/DD - OY2 (2029)	OY2 (2029)	
0201	0026CD	Eglin AFB	OT271	Conduct LTM in accordance with the approved ROD/DD - OY3 (2030)	OY3 (2030)	
0202	0026CE	Eglin AFB	OT271	Conduct LTM in accordance with the approved ROD/DD - OY4 (2031)	OY4 (2031)	
0203	0026CF	Eglin AFB	OT271	Conduct LTM in accordance with the approved ROD/DD - OY5 (2032)	OY5 (2032)	
0204	0026CG	Eglin AFB	OT271	Conduct LTM in accordance with the approved ROD/DD - OY6 (2033)	OY6 (2033)	
0205	0026CH	Eglin AFB	OT271	Conduct LTM in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)	
0206	0026CJ	Eglin AFB	OT271	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0207	0026CK	Eglin AFB	OT271	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0027	Eglin AFB	POI523	Conduct LTM		
0208	0027CA	Eglin AFB	POI523	Conduct LTM in accordance with the approved ROD/DD	Base Year (2027)	
0209	0027CB	Eglin AFB	POI523	Conduct LTM in accordance with the approved ROD/DD - OY1 (2028)	OY1 (2028)	
0210	0027CC	Eglin AFB	POI523	Conduct LTM in accordance with the approved ROD/DD - OY2 (2029)	OY2 (2029)	
0211	0027CD	Eglin AFB	POI523	Conduct LTM in accordance with the approved ROD/DD - OY3 (2030)	OY3 (2030)	
0212	0027CE	Eglin AFB	POI523	Conduct LTM in accordance with the approved ROD/DD - OY4 (2031)	OY4 (2031)	
0213	0027CF	Eglin AFB	POI523	Conduct LTM in accordance with the approved ROD/DD - OY5 (2032)	OY5 (2032)	
0214	0027CG	Eglin AFB	POI523	Conduct LTM in accordance with the approved ROD/DD - OY6 (2033)	OY6 (2033)	
0215	0027CH	Eglin AFB	POI523	Conduct LTM in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)	
0216	0027CJ	Eglin AFB	POI523	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0217	0027CK	Eglin AFB	POI523	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0028	Eglin AFB	SS025	Conduct LTM		
0218	0028CA	Eglin AFB	SS025	Conduct LTM in accordance with the approved ROD/DD	Base Year (2027)	
0219	0028CB	Eglin AFB	SS025	Conduct LTM in accordance with the approved ROD/DD - OY1 (2028)	OY1 (2028)	
0220	0028CC	Eglin AFB	SS025	Conduct LTM in accordance with the approved ROD/DD - OY2 (2029)	OY2 (2029)	
0221	0028CD	Eglin AFB	SS025	Conduct LTM in accordance with the approved ROD/DD - OY3 (2030)	OY3 (2030)	
0222	0028CE	Eglin AFB	SS025	Conduct LTM in accordance with the approved ROD/DD - OY4 (2031)	OY4 (2031)	
0223	0028CF	Eglin AFB	SS025	Conduct LTM in accordance with the approved ROD/DD - OY5 (2032)	OY5 (2032)	
0224	0028CG	Eglin AFB	SS025	Conduct LTM in accordance with the approved ROD/DD - OY6 (2033)	OY6 (2033)	
0225	0028CH	Eglin AFB	SS025	Conduct LTM in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)	
0226	0028CJ	Eglin AFB	SS025	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0227	0028CK	Eglin AFB	SS025	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0029	Eglin AFB	SS026	Conduct LTM		
0228	0029CA	Eglin AFB	SS026	Conduct LTM in accordance with the approved ROD/DD	Base Year (2027)	
0229	0029CB	Eglin AFB	SS026	Conduct LTM in accordance with the approved ROD/DD - OY1 (2028)	OY1 (2028)	
0230	0029CC	Eglin AFB	SS026	Conduct LTM in accordance with the approved ROD/DD - OY2 (2029)	OY2 (2029)	

0231	0029CD	Eglin AFB	SS026	Conduct LTM in accordance with the approved ROD/DD - OY3 (2030)	OY3 (2030)	
0232	0029CE	Eglin AFB	SS026	Conduct LTM in accordance with the approved ROD/DD - OY4 (2031)	OY4 (2031)	
0233	0029CF	Eglin AFB	SS026	Conduct LTM in accordance with the approved ROD/DD - OY5 (2032)	OY5 (2032)	
0234	0029CG	Eglin AFB	SS026	Conduct LTM in accordance with the approved ROD/DD - OY6 (2033)	OY6 (2033)	
0235	0029CH	Eglin AFB	SS026	Conduct LTM in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)	
0236	0029CJ	Eglin AFB	SS026	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0237	0029CK	Eglin AFB	SS026	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0030	Eglin AFB	SS086	Conduct LTM		
0238	0030CA	Eglin AFB	SS086	Conduct LTM in accordance with the approved ROD/DD	Base Year (2027)	
0239	0030CB	Eglin AFB	SS086	Conduct LTM in accordance with the approved ROD/DD - OY1 (2028)	OY1 (2028)	
0240	0030CC	Eglin AFB	SS086	Conduct LTM in accordance with the approved ROD/DD - OY2 (2029)	OY2 (2029)	
0241	0030CD	Eglin AFB	SS086	Conduct LTM in accordance with the approved ROD/DD - OY3 (2030)	OY3 (2030)	
0242	0030CE	Eglin AFB	SS086	Conduct LTM in accordance with the approved ROD/DD - OY4 (2031)	OY4 (2031)	
0243	0030CF	Eglin AFB	SS086	Conduct LTM in accordance with the approved ROD/DD - OY5 (2032)	OY5 (2032)	
0244	0030CG	Eglin AFB	SS086	Conduct LTM in accordance with the approved ROD/DD - OY6 (2033)	OY6 (2033)	
0245	0030CH	Eglin AFB	SS086	Conduct LTM in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)	
0246	0030CJ	Eglin AFB	SS086	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0247	0030CK	Eglin AFB	SS086	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0031	Eglin AFB	SS278	Conduct LTM		
0248	0031CA	Eglin AFB	SS278	Conduct LTM in accordance with the approved ROD/DD	Base Year (2027)	
0249	0031CB	Eglin AFB	SS278	Conduct LTM in accordance with the approved ROD/DD - OY1 (2028)	OY1 (2028)	
0250	0031CC	Eglin AFB	SS278	Conduct LTM in accordance with the approved ROD/DD - OY2 (2029)	OY2 (2029)	
0251	0031CD	Eglin AFB	SS278	Conduct LTM in accordance with the approved ROD/DD - OY3 (2030)	OY3 (2030)	
0252	0031CE	Eglin AFB	SS278	Conduct LTM in accordance with the approved ROD/DD - OY4 (2031)	OY4 (2031)	
0253	0031CF	Eglin AFB	SS278	Conduct LTM in accordance with the approved ROD/DD - OY5 (2032)	OY5 (2032)	
0254	0031CG	Eglin AFB	SS278	Conduct LTM in accordance with the approved ROD/DD - OY6 (2033)	OY6 (2033)	
0255	0031CH	Eglin AFB	SS278	Conduct LTM in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)	
0256	0031CJ	Eglin AFB	SS278	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0257	0031CK	Eglin AFB	SS278	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0032	Eglin AFB	SS281	Conduct LTM		
0258	0032CA	Eglin AFB	SS281	Conduct LTM in accordance with the approved ROD/DD	Base Year (2027)	
0259	0032CB	Eglin AFB	SS281	Conduct LTM in accordance with the approved ROD/DD - OY1 (2028)	OY1 (2028)	
0260	0032CC	Eglin AFB	SS281	Conduct LTM in accordance with the approved ROD/DD - OY2 (2029)	OY2 (2029)	
0261	0032CD	Eglin AFB	SS281	Conduct LTM in accordance with the approved ROD/DD - OY3 (2030)	OY3 (2030)	
0262	0032CE	Eglin AFB	SS281	Conduct LTM in accordance with the approved ROD/DD - OY4 (2031)	OY4 (2031)	
0263	0032CF	Eglin AFB	SS281	Conduct LTM in accordance with the approved ROD/DD - OY5 (2032)	OY5 (2032)	
0264	0032CG	Eglin AFB	SS281	Conduct LTM in accordance with the approved ROD/DD - OY6 (2033)	OY6 (2033)	
0265	0032CH	Eglin AFB	SS281	Conduct LTM in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)	
0266	0032CJ	Eglin AFB	SS281	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0267	0032CK	Eglin AFB	SS281	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0033	Eglin AFB	SS283	Conduct LTM		
0268	0033CA	Eglin AFB	SS283	Conduct LTM in accordance with the approved ROD/DD	Base Year (2027)	
0269	0033CB	Eglin AFB	SS283	Conduct LTM in accordance with the approved ROD/DD - OY1 (2028)	OY1 (2028)	
0270	0033CC	Eglin AFB	SS283	Conduct LTM in accordance with the approved ROD/DD - OY2 (2029)	OY2 (2029)	
0271	0033CD	Eglin AFB	SS283	Conduct LTM in accordance with the approved ROD/DD - OY3 (2030)	OY3 (2030)	
0272	0033CE	Eglin AFB	SS283	Conduct LTM in accordance with the approved ROD/DD - OY4 (2031)	OY4 (2031)	
0273	0033CF	Eglin AFB	SS283	Conduct LTM in accordance with the approved ROD/DD - OY5 (2032)	OY5 (2032)	
0274	0033CG	Eglin AFB	SS283	Conduct LTM in accordance with the approved ROD/DD - OY6 (2033)	OY6 (2033)	
0275	0033CH	Eglin AFB	SS283	Conduct LTM in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)	
0276	0033CJ	Eglin AFB	SS283	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0277	0033CK	Eglin AFB	SS283	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0034	Eglin AFB	SS313	Achieve Site Closeout		
0278	0034AA	Eglin AFB	SS313	Achieve Remedial Action	OY1 (2028)	
0279	0034AB	Eglin AFB	SS313	Achieve Site Closeout	Optional Task	
	0035	Eglin AFB	ST069	Achieve Response Complete		
0280	0035AA	Eglin AFB	ST069	Achieve Response Complete	OY1 (2028)	
0281	0035AB	Eglin AFB	ST069	Achieve Conditional Site Closeout	Optional Task	
0282	0035CA	Eglin AFB	ST069	Conduct RA-O in accordance with the approved ROD/DD	Base Year (2027)	
0283	0035CB	Eglin AFB	ST069	Conduct RA-O in accordance with the approved ROD/DD - OY1 (2028)	OY1 (2028)	
0284	0035CC	Eglin AFB	ST069	Conduct RA-O in accordance with the approved ROD/DD - OY2 (2029)	OY2 (2029)	
0285	0035CD	Eglin AFB	ST069	Conduct RA-O in accordance with the approved ROD/DD - OY3 (2030)	OY3 (2030)	
0286	0035CE	Eglin AFB	ST069	Conduct RA-O in accordance with the approved ROD/DD - OY4 (2031)	OY4 (2031)	
0287	0035CF	Eglin AFB	ST069	Conduct RA-O in accordance with the approved ROD/DD - OY5 (2032)	OY5 (2032)	
0288	0035CG	Eglin AFB	ST069	Conduct RA-O in accordance with the approved ROD/DD - OY6 (2033)	OY6 (2033)	
0289	0035CH	Eglin AFB	ST069	Conduct RA-O in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)	
0290	0035CJ	Eglin AFB	ST069	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0291	0035CK	Eglin AFB	ST069	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0036	Hurlburt Field	N/A	Update Community Involvement Plan		
0292	0036CA	Hurlburt Field	All Open Sites (IRP, MMRP, PFAS, etc)	Update Community Involvement Plan	Base Year (2027)	
0293	0036CB	Hurlburt Field	All Open Sites (IRP, MMRP, PFAS, etc)	Update Community Involvement Plan	OY4 (2031)	
0294	0036CC	Hurlburt Field	All Open Sites (IRP, MMRP, PFAS, etc)	Update Community Involvement Plan	OY7 (2034)	
0295	0036CD	Hurlburt Field	All Open Sites (IRP, MMRP, PFAS, etc)	Update Community Involvement Plan	OY9 (2036)	
	0037	Hurlburt Field	N/A	Complete IRP Basewide Quality Program Plans (QPP)		
0296	0037CA	Hurlburt Field	N/A	Complete IRP Basewide QPP	Base Year (2027)	
0297	0037CB	Hurlburt Field	N/A	Update IRP Basewide QPP	Optional Task	
0298	0037CC	Hurlburt Field	N/A	Update IRP Basewide QPP	Optional Task	
	0038	Hurlburt Field	N/A	Complete MMRP Quality Program Plan (QPP)		
0299	0038CA	Hurlburt Field	N/A	Complete MMRP QPP	Base Year (2027)	
0300	0038CB	Hurlburt Field	N/A	Update MMRP QPP	Optional Task	
0301	0038CC	Hurlburt Field	N/A	Update MMRP QPP	Optional Task	
	0039	Hurlburt Field	N/A	Perform Well Survey, Inventory, and Condition Assessment		
0302	0039CA	Hurlburt Field	N/A	Complete Well Survey, Inventory, and Condition Assessment	OY2 (2029)	
0303	0039CB	Hurlburt Field	N/A	Update Well Survey, Inventory, and Condition Assessment	OY6 (2033)	

	0040	Hurlburt Field	N/A	Perform RCRA Corrective Action/Hazardous and Solid Waste Amendments (CA/HWSA) Permit Renewal and Modification		
0304	0040CA	Hurlburt Field	N/A	Perform RCRA CA/HWSA Permit Renewal	OY3 (2030)	
0305	0040CB	Hurlburt Field	N/A	Perform RCRA CA/HWSA Permit Modification	Optional Task	
	0041	Hurlburt Field	N/A	Perform Well Abandonment		
0306	0041CA	Hurlburt Field	N/A	Abandon up to eighty-six (86) Basewide Wells	OY2 (2029)	
	0042	Hurlburt Field	CG219	Remedial Action Plan (RAP)		
0307	0042AA	Hurlburt Field	CG219	Achieve Supplemental Site Assessment	Base Year (2027)	
0308	0042AB	Hurlburt Field	CG219	Achieve Remedial Action Plan	Optional Task	
	0043	Hurlburt Field	LF013	Conduct LTM		
0309	0043CA	Hurlburt Field	LF013	Conduct LTM in accordance with the approved ROD/DD	Base Year (2027)	
0310	0043CB	Hurlburt Field	LF013	Conduct LTM in accordance with the approved ROD/DD - OY1 (2028)	OY1 (2028)	
0311	0043CC	Hurlburt Field	LF013	Conduct LTM in accordance with the approved ROD/DD - OY2 (2029)	OY2 (2029)	
0312	0043CD	Hurlburt Field	LF013	Conduct LTM in accordance with the approved ROD/DD - OY3 (2030)	OY3 (2030)	
0313	0043CE	Hurlburt Field	LF013	Conduct LTM in accordance with the approved ROD/DD - OY4 (2031)	OY4 (2031)	
0314	0043CF	Hurlburt Field	LF013	Conduct LTM in accordance with the approved ROD/DD - OY5 (2032)	OY5 (2032)	
0315	0043CG	Hurlburt Field	LF013	Conduct LTM in accordance with the approved ROD/DD - OY6 (2033)	OY6 (2033)	
0316	0043CH	Hurlburt Field	LF013	Conduct LTM in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)	
0317	0043CJ	Hurlburt Field	LF013	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0318	0043CK	Hurlburt Field	LF013	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0044	Hurlburt Field	LF014	Conduct LTM		
0319	0044CA	Hurlburt Field	LF014	Conduct LTM in accordance with the approved ROD/DD	Base Year (2027)	
0320	0044CB	Hurlburt Field	LF014	Conduct LTM in accordance with the approved ROD/DD - OY1 (2028)	OY1 (2028)	
0321	0044CC	Hurlburt Field	LF014	Conduct LTM in accordance with the approved ROD/DD - OY2 (2029)	OY2 (2029)	
0322	0044CD	Hurlburt Field	LF014	Conduct LTM in accordance with the approved ROD/DD - OY3 (2030)	OY3 (2030)	
0323	0044CE	Hurlburt Field	LF014	Conduct LTM in accordance with the approved ROD/DD - OY4 (2031)	OY4 (2031)	
0324	0044CF	Hurlburt Field	LF014	Conduct LTM in accordance with the approved ROD/DD - OY5 (2032)	OY5 (2032)	
0325	0044CG	Hurlburt Field	LF014	Conduct LTM in accordance with the approved ROD/DD - OY6 (2033)	OY6 (2033)	
0326	0044CH	Hurlburt Field	LF014	Conduct LTM in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)	
0327	0044CJ	Hurlburt Field	LF014	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0328	0044CK	Hurlburt Field	LF014	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0045	Hurlburt Field	LF015	Conduct LTM		
0329	0045CA	Hurlburt Field	LF015	Conduct LTM in accordance with the approved ROD/DD	Base Year (2027)	
0330	0045CB	Hurlburt Field	LF015	Conduct LTM in accordance with the approved ROD/DD - OY1 (2028)	OY1 (2028)	
0331	0045CC	Hurlburt Field	LF015	Conduct LTM in accordance with the approved ROD/DD - OY2 (2029)	OY2 (2029)	
0332	0045CD	Hurlburt Field	LF015	Conduct LTM in accordance with the approved ROD/DD - OY3 (2030)	OY3 (2030)	
0333	0045CE	Hurlburt Field	LF015	Conduct LTM in accordance with the approved ROD/DD - OY4 (2031)	OY4 (2031)	
0334	0045CF	Hurlburt Field	LF015	Conduct LTM in accordance with the approved ROD/DD - OY5 (2032)	OY5 (2032)	
0335	0045CG	Hurlburt Field	LF015	Conduct LTM in accordance with the approved ROD/DD - OY6 (2033)	OY6 (2033)	
0336	0045CH	Hurlburt Field	LF015	Conduct LTM in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)	
0337	0045CJ	Hurlburt Field	LF015	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0338	0045CK	Hurlburt Field	LF015	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0046	Hurlburt Field	LF016	Conduct LTM		
0339	0046CA	Hurlburt Field	LF016	Conduct LTM in accordance with the approved ROD/DD	Base Year (2027)	
0340	0046CB	Hurlburt Field	LF016	Conduct LTM in accordance with the approved ROD/DD - OY1 (2028)	OY1 (2028)	
0341	0046CC	Hurlburt Field	LF016	Conduct LTM in accordance with the approved ROD/DD - OY2 (2029)	OY2 (2029)	
0342	0046CD	Hurlburt Field	LF016	Conduct LTM in accordance with the approved ROD/DD - OY3 (2030)	OY3 (2030)	
0343	0046CE	Hurlburt Field	LF016	Conduct LTM in accordance with the approved ROD/DD - OY4 (2031)	OY4 (2031)	
0344	0046CF	Hurlburt Field	LF016	Conduct LTM in accordance with the approved ROD/DD - OY5 (2032)	OY5 (2032)	
0345	0046CG	Hurlburt Field	LF016	Conduct LTM in accordance with the approved ROD/DD - OY6 (2033)	OY6 (2033)	
0346	0046CH	Hurlburt Field	LF016	Conduct LTM in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)	
0347	0046CJ	Hurlburt Field	LF016	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0348	0046CK	Hurlburt Field	LF016	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0047	Hurlburt Field	LF017	Conduct LTM		
0349	0047CA	Hurlburt Field	LF017	Conduct LTM in accordance with the approved ROD/DD	Base Year (2027)	
0350	0047CB	Hurlburt Field	LF017	Conduct LTM in accordance with the approved ROD/DD - OY1 (2028)	OY1 (2028)	
0351	0047CC	Hurlburt Field	LF017	Conduct LTM in accordance with the approved ROD/DD - OY2 (2029)	OY2 (2029)	
0352	0047CD	Hurlburt Field	LF017	Conduct LTM in accordance with the approved ROD/DD - OY3 (2030)	OY3 (2030)	
0353	0047CE	Hurlburt Field	LF017	Conduct LTM in accordance with the approved ROD/DD - OY4 (2031)	OY4 (2031)	
0354	0047CF	Hurlburt Field	LF017	Conduct LTM in accordance with the approved ROD/DD - OY5 (2032)	OY5 (2032)	
0355	0047CG	Hurlburt Field	LF017	Conduct LTM in accordance with the approved ROD/DD - OY6 (2033)	OY6 (2033)	
0356	0047CH	Hurlburt Field	LF017	Conduct LTM in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)	
0357	0047CJ	Hurlburt Field	LF017	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0358	0047CK	Hurlburt Field	LF017	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0048	Hurlburt Field	LF018	Conduct LTM		
0359	0048CA	Hurlburt Field	LF018	Conduct LTM in accordance with the approved ROD/DD	Base Year (2027)	
0360	0048CB	Hurlburt Field	LF018	Conduct LTM in accordance with the approved ROD/DD - OY1 (2028)	OY1 (2028)	
0361	0048CC	Hurlburt Field	LF018	Conduct LTM in accordance with the approved ROD/DD - OY2 (2029)	OY2 (2029)	
0362	0048CD	Hurlburt Field	LF018	Conduct LTM in accordance with the approved ROD/DD - OY3 (2030)	OY3 (2030)	
0363	0048CE	Hurlburt Field	LF018	Conduct LTM in accordance with the approved ROD/DD - OY4 (2031)	OY4 (2031)	
0364	0048CF	Hurlburt Field	LF018	Conduct LTM in accordance with the approved ROD/DD - OY5 (2032)	OY5 (2032)	
0365	0048CG	Hurlburt Field	LF018	Conduct LTM in accordance with the approved ROD/DD - OY6 (2033)	OY6 (2033)	
0366	0048CH	Hurlburt Field	LF018	Conduct LTM in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)	
0367	0048CJ	Hurlburt Field	LF018	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0368	0048CK	Hurlburt Field	LF018	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0049	Hurlburt Field	LF019	Conduct LTM		
0369	0049CA	Hurlburt Field	LF019	Conduct LTM in accordance with the approved ROD/DD	Base Year (2027)	
0370	0049CB	Hurlburt Field	LF019	Conduct LTM in accordance with the approved ROD/DD - OY1 (2028)	OY1 (2028)	
0371	0049CC	Hurlburt Field	LF019	Conduct LTM in accordance with the approved ROD/DD - OY2 (2029)	OY2 (2029)	
0372	0049CD	Hurlburt Field	LF019	Conduct LTM in accordance with the approved ROD/DD - OY3 (2030)	OY3 (2030)	
0373	0049CE	Hurlburt Field	LF019	Conduct LTM in accordance with the approved ROD/DD - OY4 (2031)	OY4 (2031)	
0374	0049CF	Hurlburt Field	LF019	Conduct LTM in accordance with the approved ROD/DD - OY5 (2032)	OY5 (2032)	
0375	0049CG	Hurlburt Field	LF019	Conduct LTM in accordance with the approved ROD/DD - OY6 (2033)	OY6 (2033)	
0376	0049CH	Hurlburt Field	LF019	Conduct LTM in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)	
0377	0049CJ	Hurlburt Field	LF019	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0378	0049CK	Hurlburt Field	LF019	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0050	Hurlburt Field	LF020	Conduct LTM		
0379	0050CA	Hurlburt Field	LF020	Conduct LTM in accordance with the approved ROD/DD	Base Year (2027)	
0380	0050CB	Hurlburt Field	LF020	Conduct LTM in accordance with the approved ROD/DD - OY1 (2028)	OY1 (2028)	
0381	0050CC	Hurlburt Field	LF020	Conduct LTM in accordance with the approved ROD/DD - OY2 (2029)	OY2 (2029)	
0382	0050CD	Hurlburt Field	LF020	Conduct LTM in accordance with the approved ROD/DD - OY3 (2030)	OY3 (2030)	

0383	0050CE	Hurlburt Field	LF020	Conduct LTM in accordance with the approved ROD/DD - OY4 (2031)	OY4 (2031)	
0384	0050CF	Hurlburt Field	LF020	Conduct LTM in accordance with the approved ROD/DD - OY5 (2032)	OY5 (2032)	
0385	0050CG	Hurlburt Field	LF020	Conduct LTM in accordance with the approved ROD/DD - OY6 (2033)	OY6 (2033)	
0386	0050CH	Hurlburt Field	LF020	Conduct LTM in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)	
0387	0050CJ	Hurlburt Field	LF020	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0388	0050CK	Hurlburt Field	LF020	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0051	Hurlburt Field	SS125	Achieve Site Closeout		
0389	0051AA	Hurlburt Field	SS125	Achieve Remedial Action Plan	OY1 (2028)	
0390	0051AB	Hurlburt Field	SS125	Achieve Response Complete	Optional Task	
0391	0051AC	Hurlburt Field	SS125	Achieve Site Closeout	Optional Task	
	0052	Hurlburt Field	ST123	Conduct LTM		
0392	0052CA	Hurlburt Field	ST123	Conduct LTM in accordance with the approved ROD/DD	Base Year (2027)	
0393	0052CB	Hurlburt Field	ST123	Conduct LTM in accordance with the approved ROD/DD - OY1 (2028)	OY1 (2028)	
0394	0052CC	Hurlburt Field	ST123	Conduct LTM in accordance with the approved ROD/DD - OY2 (2029)	OY2 (2029)	
0395	0052CD	Hurlburt Field	ST123	Conduct LTM in accordance with the approved ROD/DD - OY3 (2030)	OY3 (2030)	
0396	0052CE	Hurlburt Field	ST123	Conduct LTM in accordance with the approved ROD/DD - OY4 (2031)	OY4 (2031)	
0397	0052CF	Hurlburt Field	ST123	Conduct LTM in accordance with the approved ROD/DD - OY5 (2032)	OY5 (2032)	
0398	0052CG	Hurlburt Field	ST123	Conduct LTM in accordance with the approved ROD/DD - OY6 (2033)	OY6 (2033)	
0399	0052CH	Hurlburt Field	ST123	Conduct LTM in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)	
0400	0052CJ	Hurlburt Field	ST123	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0401	0052CK	Hurlburt Field	ST123	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0053	Hurlburt Field	XU002	Achieve ROD/DD		
0402	0053AA	Hurlburt Field	XU002	Achieve Remedial Investigation	Base Year (2027)	
0403	0053AB	Hurlburt Field	XU002	Achieve Feasibility Study	Optional Task	
0404	0053AC	Hurlburt Field	XU002	Achieve Proposed Plan	Optional Task	
0405	0053AD	Hurlburt Field	XU002	Achieve Record of Decision (ROD)	Optional Task	
	0054	Tyndall AFB	N/A	Update Community Involvement Plan		
0406	0054CA	Tyndall AFB	All Open Sites (IRP, MMRP, PFAS, etc)	Update Community Involvement Plan	Base Year (2027)	
0407	0054CB	Tyndall AFB	All Open Sites (IRP, MMRP, PFAS, etc)	Update Community Involvement Plan	OY3 (2030)	
0408	0054CC	Tyndall AFB	All Open Sites (IRP, MMRP, PFAS, etc)	Update Community Involvement Plan	OY6 (2033)	
0409	0054CD	Tyndall AFB	All Open Sites (IRP, MMRP, PFAS, etc)	Update Community Involvement Plan	OY9 (2036)	
	0055	Tyndall AFB	N/A	Complete IRP Basewide Quality Program Plans (QPP)		
0410	0055CA	Tyndall AFB	N/A	Complete IRP Basewide QPP	Base Year (2027)	
0411	0055CB	Tyndall AFB	N/A	Update IRP Basewide QPP	Optional Task	
0412	0055CC	Tyndall AFB	N/A	Update IRP Basewide QPP	Optional Task	
	0056	Tyndall AFB	N/A	Complete MMRP Quality Program Plan (QPP)		
0413	0056CA	Tyndall AFB	N/A	Complete MMRP QPP	Base Year (2027)	
0414	0056CB	Tyndall AFB	N/A	Update MMRP QPP	Optional Task	
0415	0056CC	Tyndall AFB	N/A	Update MMRP QPP	Optional Task	
	0057	Tyndall AFB	N/A	Perform Well Survey, Inventory, and Condition Assessment		
0416	0057CA	Tyndall AFB	N/A	Complete Well Survey, Inventory, and Condition Assessment	OY2 (2029)	
0417	0057CB	Tyndall AFB	N/A	Update Well Survey, Inventory, and Condition Assessment	OY6 (2033)	
	0058	Tyndall AFB	DA046	Achieve Site Closeout		
0418	0058AA	Tyndall AFB	DA046	Achieve Confirmatory Sampling	OY1 (2028)	
0419	0058AB	Tyndall AFB	DA046	Achieve Feasiblity Study	Optional Task	
0420	0058AC	Tyndall AFB	DA046	Achieve Site Closeout (No Action Proposed Plan/Record of Decision (PP/ROD))	Optional Task	
	0059	Tyndall AFB	FR038	Conduct LTM		
0421	0059CA	Tyndall AFB	FR038	Conduct LTM in accordance with the approved ROD/DD	Base Year (2027)	
0422	0059CB	Tyndall AFB	FR038	Conduct LTM in accordance with the approved ROD/DD - OY1 (2028)	OY1 (2028)	
0423	0059CC	Tyndall AFB	FR038	Conduct LTM in accordance with the approved ROD/DD - OY2 (2029)	OY2 (2029)	
0424	0059CD	Tyndall AFB	FR038	Conduct LTM in accordance with the approved ROD/DD - OY3 (2030)	OY3 (2030)	
0425	0059CE	Tyndall AFB	FR038	Conduct LTM in accordance with the approved ROD/DD - OY4 (2031)	OY4 (2031)	
0426	0059CF	Tyndall AFB	FR038	Conduct LTM in accordance with the approved ROD/DD - OY5 (2032)	OY5 (2032)	
0427	0059CG	Tyndall AFB	FR038	Conduct LTM in accordance with the approved ROD/DD - OY6 (2033)	OY6 (2033)	
0428	0059CH	Tyndall AFB	FR038	Conduct LTM in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)	
0429	0059CJ	Tyndall AFB	FR038	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0430	0059CK	Tyndall AFB	FR038	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0060	Tyndall AFB	FT016	Achieve Feasibility Study		
0431	0060AA	Tyndall AFB	FT016	Achieve Land Use Control Implementation Plan	Base Year (2027)	
0432	0060AB	Tyndall AFB	FT016	Achieve Post MILCON Confirmatory Sampling	Optional Task	
0433	0060AC	Tyndall AFB	FT016	Achieve Feasibility Study	Optional Task	
0434	0060CA	Tyndall AFB	FT016	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY1 (2028)	OY1 (2028)	
0435	0060CB	Tyndall AFB	FT016	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY2 (2029)	OY2 (2029)	
0436	0060CC	Tyndall AFB	FT016	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY3 (2030)	OY3 (2030)	
0437	0060CD	Tyndall AFB	FT016	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY4 (2031)	OY4 (2031)	
0438	0060CE	Tyndall AFB	FT016	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY5 (2032)	OY5 (2032)	
0439	0060CF	Tyndall AFB	FT016	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY6 (2033)	OY6 (2033)	
0440	0060CG	Tyndall AFB	FT016	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY7 (2034)	OY7 (2034)	
0441	0060CH	Tyndall AFB	FT016	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY8 (2035)	OY8 (2035)	
0442	0060CJ	Tyndall AFB	FT016	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY9 (2036)	OY9 (2036)	
	0061	Tyndall AFB	FT016	Complete 1,4 Dioxane Step 2		
0443	0061AA	Tyndall AFB	FT016	Complete 1,4-Dioxane Step 2 Nature and Extent Determination	Base Year (2027)	
	0062	Tyndall AFB	FT017	Achieve Feasibility Study		
0444	0062AA	Tyndall AFB	FT017	Achieve Land Use Control Implementation Plan	Base Year (2027)	
0445	0062AB	Tyndall AFB	FT017	Achieve Post MILCON Confirmatory Sampling	Optional Task	
0446	0062AC	Tyndall AFB	FT017	Achieve Feasibility Study	Optional Task	
0447	0062CA	Tyndall AFB	FT017	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY1 (2028)	OY1 (2028)	
0448	0062CB	Tyndall AFB	FT017	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY2 (2029)	OY2 (2029)	
0449	0062CC	Tyndall AFB	FT017	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY3 (2030)	OY3 (2030)	
0450	0062CD	Tyndall AFB	FT017	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY4 (2031)	OY4 (2031)	
0451	0062CE	Tyndall AFB	FT017	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY5 (2032)	OY5 (2032)	
0452	0062CF	Tyndall AFB	FT017	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY6 (2033)	OY6 (2033)	
0453	0062CG	Tyndall AFB	FT017	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY7 (2034)	OY7 (2034)	

0454	0062CH	Tyndall AFB	FT017	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY8 (2035)	OY8 (2035)	
0455	0062CJ	Tyndall AFB	FT017	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY9 (2036)	OY9 (2036)	
	0063	Tyndall AFB	LF006	Achieve Response Complete		
0456	0063AA	Tyndall AFB	LF006	Achieve Record of Decision	Base Year (2027)	
0457	0063AB	Tyndall AFB	LF006	Achieve Remedial Design and Remedial Action Work Plan	Optional Task	
0458	0063AC	Tyndall AFB	LF006	Achieve Remedy in Place	Optional Task	
0459	0063AD	Tyndall AFB	LF006	Optimize the site in support of Response Complete	Optional Task	
0460	0063AE	Tyndall AFB	LF006	Achieve Response Complete	Optional Task	
0461	0063CA	Tyndall AFB	LF006	Conduct LTM in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034) - Upon Completion of 0063AE	
0462	0063CB	Tyndall AFB	LF006	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0463	0063CC	Tyndall AFB	LF006	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0064	Tyndall AFB	LF007	Achieve Response Complete		
0464	0064AA	Tyndall AFB	LF007	Achieve Record of Decision	Base Year (2027)	
0465	0064AB	Tyndall AFB	LF007	Achieve Remedial Design and Remedial Action Work Plan	Optional Task	
0466	0064AC	Tyndall AFB	LF007	Achieve Remedy in Place	Optional Task	
0467	0064AD	Tyndall AFB	LF007	Optimize the site in support of Response Complete	Optional Task	
0468	0064AE	Tyndall AFB	LF007	Achieve Response Complete	Optional Task	
0469	0064CA	Tyndall AFB	LF007	Conduct LTM in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034) - Upon Completion of 0064AE	
0470	0064CB	Tyndall AFB	LF007	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0471	0064CC	Tyndall AFB	LF007	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0065	Tyndall AFB	OT018	Achieve Confirmatory Sampling		
0472	0065AA	Tyndall AFB	OT018	Achieve Confirmatory Sampling	OY3 (2030)	
	0066	Tyndall AFB	OT029	Achieve Response Complete		
0473	0066AA	Tyndall AFB	OT029	Achieve Record of Decision	Base Year (2027)	
0474	0066AB	Tyndall AFB	OT029	Achieve Remedial Design and Remedial Action Work Plan	Optional Task	
0475	0066AC	Tyndall AFB	OT029	Achieve Remedy in Place	Optional Task	
0476	0066AD	Tyndall AFB	OT029	Achieve Response Complete	Optional Task	
0477	0066CA	Tyndall AFB	OT029	Conduct LTM in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)- Upon Completion of 0066AD	
0478	0066CB	Tyndall AFB	OT029	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0479	0066CC	Tyndall AFB	OT029	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0067	Tyndall AFB	OW217	Achieve Final ROD and RA-O		
0480	0067AA	Tyndall AFB	OW217	Achieve Land Use Control Implementation Plan	Base Year (2027)	
0481	0067AB	Tyndall AFB	OW217	Achieve Post MILCON Confirmatory Sampling	Optional Task	
0482	0067AC	Tyndall AFB	OW217	Achieve Feasibility Study	Optional Task	
0483	0067AD	Tyndall AFB	OW217	Achieve Proposed Plan/Record of Decision	Optional Task	
0484	0067CA	Tyndall AFB	OW217	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY1 (2028)	OY1 (2028)	
0485	0067CB	Tyndall AFB	OW217	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY2 (2029)	OY2 (2029)	
0486	0067CC	Tyndall AFB	OW217	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY3 (2030)	OY3 (2030)	
0487	0067CD	Tyndall AFB	OW217	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY4 (2031)	OY4 (2031)	
0488	0067CE	Tyndall AFB	OW217	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY5 (2032)	OY5 (2032)	
0489	0067CF	Tyndall AFB	OW217	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY6 (2033)	OY6 (2033)	
0490	0067CG	Tyndall AFB	OW217	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY7 (2034)	OY7 (2034)	
0491	0067CH	Tyndall AFB	OW217	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY8 (2035)	OY8 (2035)	
0492	0067CJ	Tyndall AFB	OW217	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY9 (2036)	OY9 (2036)	
	0068	Tyndall AFB	OW582	Achieve Remedy in Place and RA-O		
0493	0068AA	Tyndall AFB	OW582	Achieve Remedial Design and Remedial Action Work Plan	OY2 (2029)	
0494	0068AB	Tyndall AFB	OW582	Achieve Remedy in Place	Optional Task	
0495	0068CA	Tyndall AFB	OW582	Conduct RAO in accordance with the approved ROD/DD and evaluate performance model - OY6 (2033)	OY6 (2033) - Upon Completion of 0068AB	
0496	0068CB	Tyndall AFB	OW582	Conduct RA-O in accordance with the approved ROD/DD and evaluate performance model - OY7 (2034)	OY7 (2034)	
0497	0068CC	Tyndall AFB	OW582	Conduct RA-O in accordance with the approved ROD/DD and evaluate performance model - OY8 (2035)	OY8 (2035)	
0498	0068CD	Tyndall AFB	OW582	Conduct RA-O in accordance with the approved ROD/DD and evaluate performance model - OY9 (2036)	OY9 (2036)	
	0069	Tyndall AFB	SR169	Achieve Site Closeout		
0499	0069AA	Tyndall AFB	SR169	Achieve Site Closeout	OY2 (2029)	
	0070	Tyndall AFB	SR170	Achieve ROD/DD		
0500	0070AA	Tyndall AFB	SR170	Achieve Record of Decision	Base Year (2027)	
	0071	Tyndall AFB	SR170A	Conduct LTM		
0501	0071CA	Tyndall AFB	SR170A	Conduct LTM in accordance with the approved ROD/DD - OY2 (2029)	OY2 (2029)	
0502	0071CB	Tyndall AFB	SR170A	Conduct LTM in accordance with the approved ROD/DD - OY3 (2030)	OY3 (2030)	
0503	0071CC	Tyndall AFB	SR170A	Conduct LTM in accordance with the approved ROD/DD - OY4 (2031)	OY4 (2031)	
0504	0071CD	Tyndall AFB	SR170A	Conduct LTM in accordance with the approved ROD/DD - OY5 (2032)	OY5 (2032)	
0505	0071CE	Tyndall AFB	SR170A	Conduct LTM in accordance with the approved ROD/DD - OY6 (2033)	OY6 (2033)	
0506	0071CF	Tyndall AFB	SR170A	Conduct LTM in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)	
0507	0071CG	Tyndall AFB	SR170A	Conduct LTM in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0508	0071CH	Tyndall AFB	SR170A	Conduct LTM in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0072	Tyndall AFB	SS015	Achieve Final ROD and RA-O		
0509	0072AA	Tyndall AFB	SS015	Achieve Land Use Control Implementation Plan	Base Year (2027)	
0510	0072AB	Tyndall AFB	SS015	Achieve Post MILCON Confirmatory Sampling	Optional Task	
0511	0072AC	Tyndall AFB	SS015	Achieve Feasibility Study	Optional Task	
0512	0072AD	Tyndall AFB	SS015	Achieve-Proposed Plan/Record of Decision (PP/ROD)	Optional Task	
0513	0072CA	Tyndall AFB	SS015	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY1 (2028)	OY1 (2028)	
0514	0072CB	Tyndall AFB	SS015	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY2 (2029)	OY2 (2029)	
0515	0072CC	Tyndall AFB	SS015	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY3 (2030)	OY3 (2030)	
0516	0072CD	Tyndall AFB	SS015	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY4 (2031)	OY4 (2031)	
0517	0072CE	Tyndall AFB	SS015	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY5 (2032)	OY5 (2032)	
0518	0072CF	Tyndall AFB	SS015	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY6 (2033)	OY6 (2033)	
0519	0072CG	Tyndall AFB	SS015	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY7 (2034)	OY7 (2034)	
0520	0072CH	Tyndall AFB	SS015	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY8 (2035)	OY8 (2035)	
0521	0072CJ	Tyndall AFB	SS015	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY9 (2036)	OY9 (2036)	
	0073	Tyndall AFB	SS026	Achieve Final ROD and RA-O		
0522	0073AA	Tyndall AFB	SS026	Achieve Land Use Control Implementation Plan	Base Year (2027)	
0523	0073AB	Tyndall AFB	SS026	Achieve Post MILCON Confirmatory Sampling	Optional Task	
0524	0073AC	Tyndall AFB	SS026	Achieve Feasibility Study	Optional Task	
0525	0073AD	Tyndall AFB	SS026	Achieve Proposed Plan/Record of Decision (PP/ROD)	Optional Task	
0526	0073CA	Tyndall AFB	SS026	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY1 (2028)	OY1 (2028)	
0527	0073CB	Tyndall AFB	SS026	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY2 (2029)	OY2 (2029)	
0528	0073CC	Tyndall AFB	SS026	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY3 (2030)	OY3 (2030)	
0529	0073CD	Tyndall AFB	SS026	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY4 (2031)	OY4 (2031)	
0530	0073CE	Tyndall AFB	SS026	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY5 (2032)	OY5 (2032)	
0531	0073CF	Tyndall AFB	SS026	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY6 (2033)	OY6 (2033)	
0532	0073CG	Tyndall AFB	SS026	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY7 (2034)	OY7 (2034)	
0533	0073CH	Tyndall AFB	SS026	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY8 (2035)	OY8 (2035)	

0534	0073CJ	Tyndall AFB	SS026	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY9 (2036)	OY9 (2036)	
	0074	Tyndall AFB	TA523	Conduct LTM		
0535	0074CA	Tyndall AFB	TA523	Conduct LTM in accordance with the approved ROD/DD	Base Year (2027)	
0536	0074CB	Tyndall AFB	TA523	Conduct LTM in accordance with the approved ROD/DD- OY1 (2028)	OY1 (2028)	
0537	0074CC	Tyndall AFB	TA523	Conduct LTM in accordance with the approved ROD/DD- OY2 (2029)	OY2 (2029)	
0538	0074CD	Tyndall AFB	TA523	Conduct LTM in accordance with the approved ROD/DD- OY3 (2030)	OY3 (2030)	
0539	0074CE	Tyndall AFB	TA523	Conduct LTM in accordance with the approved ROD/DD- OY4 (2031)	OY4 (2031)	
0540	0074CF	Tyndall AFB	TA523	Conduct LTM in accordance with the approved ROD/DD- OY5 (2032)	OY5 (2032)	
0541	0074CG	Tyndall AFB	TA523	Conduct LTM in accordance with the approved ROD/DD- OY6 (2033)	OY6 (2033)	
0542	0074CH	Tyndall AFB	TA523	Conduct LTM in accordance with the approved ROD/DD- OY7 (2034)	OY7 (2034)	
0543	0074CJ	Tyndall AFB	TA523	Conduct LTM in accordance with the approved ROD/DD- OY8 (2035)	OY8 (2035)	
0544	0074CK	Tyndall AFB	TA523	Conduct LTM in accordance with the approved ROD/DD- OY9 (2036)	OY9 (2036)	
	0075	Tyndall AFB	TS183	RA-O with Optimization		
0545	0075AA	Tyndall AFB	TS183	Prepare Performance Model in year 2 and achieve the performance goals per the Performance Model and provide Performance Evaluation Report years 3 and 4	OY1 (2028)	
0546	0075AB	Tyndall AFB	TS183	Achieve the performance goals per the performance model and provide Performance Evaluation Report years 5, 6, and 7	Optional Task	
0547	0075AC	Tyndall AFB	TS183	Achieve the performance goals per the performance model and provide Performance Evaluation Report years 8, and 9, develop an Optimization Summary and Forecasting Report in year 8 and provide final performance goal in year 10	Optional Task	
0548	0075CA	Tyndall AFB	TS183	Conduct RA-O in accordance with the approved ROD/DD - OY1 (2028)	OY1 (2028)	
0549	0075CB	Tyndall AFB	TS183	Conduct RA-O in accordance with the approved ROD/DD - OY2 (2029)	OY2 (2029)	
0550	0075CC	Tyndall AFB	TS183	Conduct RA-O in accordance with the approved ROD/DD - OY3 (2030)	OY3 (2030)	
0551	0075CD	Tyndall AFB	TS183	Conduct RA-O in accordance with the approved ROD/DD - OY4 (2031)	OY4 (2031)	
0552	0075CE	Tyndall AFB	TS183	Conduct RA-O in accordance with the approved ROD/DD - OY5 (2032)	OY5 (2032)	
0553	0075CF	Tyndall AFB	TS183	Conduct RA-O in accordance with the approved ROD/DD - OY6 (2033)	OY6 (2033)	
0554	0075CG	Tyndall AFB	TS183	Conduct RA-O in accordance with the approved ROD/DD - OY7 (2034)	OY7 (2034)	
0555	0075CH	Tyndall AFB	TS183	Conduct RA-O in accordance with the approved ROD/DD - OY8 (2035)	OY8 (2035)	
0556	0075CJ	Tyndall AFB	TS183	Conduct RA-O in accordance with the approved ROD/DD - OY9 (2036)	OY9 (2036)	
	0076	Tyndall AFB	TU204	Achieve Site Closeout		
0557	0076AA	Tyndall AFB	TU204	Optimize the site in support of Site Closeout	OY2 (2029)	
0558	0076AB	Tyndall AFB	TU204	Achieve Response Complete	Optional Task	
0559	0076AC	Tyndall AFB	TU204	Achieve Site Closeout	Optional Task	
	0077	Tyndall AFB	TU205	Achieve Final ROD and RA-O		
0560	0077AA	Tyndall AFB	TU205	Achieve Land Use Control Implementation Plan	Base Year (2027)	
0561	0077AB	Tyndall AFB	TU205	Achieve Post MILCON Confirmatory Sampling	Optional Task	
0562	0077AC	Tyndall AFB	TU205	Achieve Feasibility Study	Optional Task	
0563	0077AD	Tyndall AFB	TU205	Achieve Proposed Plan/Record of Decision (PP/ROD)	Optional Task	
0564	0077CA	Tyndall AFB	TU205	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY1 (2028)	OY1 (2028)	
0565	0077CB	Tyndall AFB	TU205	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY2 (2029)	OY2 (2029)	
0566	0077CC	Tyndall AFB	TU205	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY3 (2030)	OY3 (2030)	
0567	0077CD	Tyndall AFB	TU205	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY4 (2031)	OY4 (2031)	
0568	0077CE	Tyndall AFB	TU205	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY5 (2032)	OY5 (2032)	
0569	0077CF	Tyndall AFB	TU205	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY6 (2033)	OY6 (2033)	
0570	0077CG	Tyndall AFB	TU205	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY7 (2034)	OY7 (2034)	
0571	0077CH	Tyndall AFB	TU205	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY8 (2035)	OY8 (2035)	
0572	0077CJ	Tyndall AFB	TU205	Conduct RA-O in accordance with the approved Interim Action ROD/DD - OY9 (2036)	OY9 (2036)	
	0078	Tyndall AFB	TU233	Achieve Site Closeout		
0573	0078AA	Tyndall AFB	TU233	Corrective Measures Implementation Plan (UFP-QAPP PARM Work Plan)	Base Year (2027)	
0574	0078AB	Tyndall AFB	TU233	Construction Completion (Achieve PARM)	Optional Task	
0575	0078AC	Tyndall AFB	TU233	Achieve Response Complete	Optional Task	
0576	0078AD	Tyndall AFB	TU233	Achieve Site Closeout (SRCR and Well Abandonment Report)	Optional Task	
					Total	

*1 The Projected/Estimated award timing designation in column E, F, & G indicate projected/estimated award timing each of the associated AFCEC Sub-CLINs will be funded and exercised. The "exercise year" is included for planning purposes only and is not intended to indicate a commitment by the Government to fund and exercise an AFCEC Sub-CLIN in a specific year of the contract. Award of all AFCEC Sub-CLINs will be made pending availability of funds and if bona fide need is determined by the Government. Limitations on funding availability may necessitate the Government to prioritize AFCEC Sub-CLIN award based on funding, regulatory requirements, and other bonafide need requirements. Meeting annual award dates for compliance AFCEC Sub-CLINs is necessary to maintain conformity with AF legal obligations, including Records of Decision (RODs), permits, and other agreements. These dates should not be confused with the time to obtain final regulatory approval of the reports associated with these annually funded events. Final reports generally take more than 12 months so these events, while funded annually, are non-severable in nature.