140RR027R0010 – PGMB Security Gate November 10, 2026

Amendment 4 Questions and answers

1. **Q:** Which wage determination applies to the gate, fence, and electrical installation labor for this project?

   A: Wage Determination **2015-5485**, incorporated under Amendment 2, applies to all onsite installation labor associated with the gate, fencing, and electrical work for this requirement. Contractors should use the labor classifications listed within WD 2015-5485 that most closely align with their workforce. If any required trade or skill (such as specialized gate installation or access control technicians) is not listed, the contractor should submit a **conformance request** in accordance with the Service Contract Labor Standards.

2. **Q:** Following supplier consultation, we understand that the specified type of automated gate system may require approximately 13 or more weeks for manufacturing before shipment. Could you please clarify whether the 90-calendar-day performance period is firm, or whether an alternative completion schedule may be proposed and considered during evaluation? If an extension is permitted, will it be incorporated through an amendment?

   A: Please provide your lead time for delivery and installation. The performance period listed is an approximate timeframe and may be adjusted based on the information provided in your schedule.

3. **Q:** Amendment 2 adds Service Contract Wage Determination 2015-5485. Please confirm that this wage determination applies to the onsite gate/fence/electrical installation labor and, if so, identify the intended labor classifications or confirm the contractor should request conformance for unlisted classifications.

   A: Wage Determination 2015-5485 has been verified as the applicable wage determination for this requirement. The intended occupation classifications for the work are 11210 – Laborer, Grounds Maintenance, and 23160 – Electrician, Maintenance.

4. **Q:** Payment protection for subcontractors: the solicitation states no bonds are required. Will the awarded contract include any payment protection for subcontractors, such as a payment bond, an irrevocable letter of credit, or another protection under FAR 28.102-1?

   A: This requirement does not involve construction exceeding the thresholds that would mandate payment protections under FAR 28.102-1. As stated in the solicitation, no bonds are required for this procurement. Accordingly, the awarded contract will not include payment protection measures such as a payment bond, irrevocable letter of credit, or other alternative protections. Subcontractor payment protections are not applicable for this acquisition.

5. **Q:** Pricing sheet: The notice states an Excel pricing and response sheet will be provided, but no such sheet was found in the SAM.gov files. Please confirm whether a pricing sheet exists and how it may be obtained.

   A: An Excel pricing and response sheet was referenced in the notice; however, no separate Excel file was included in the SAM.gov posting. As a result, an Excel pricing sheet is **not required** and has been removed from the solicitation.

   For administrative convenience, a PDF version of the complete solicitation will be provided with this announcement. Offerors shall complete and submit all required solicitation documents as part of their quotation package.

6. **Q:** Wage determination: The header references 2015-5485 and the footer references 2015-5484.

A: The correct wage determination for this requirement is **2015-5485**. This will be reflected in the updated solicitation documents.

7. **Q:** 1. Period of performance: The statement of work states 90 calendar days from award, while Amendment 0001 states December 14, 2026 through March 15, 2027. Please confirm which period controls.

   A: The dates provided were intended as an estimated period of performance. Please provide your lead time for delivery and installation. The performance period listed is an approximate timeframe and may be adjusted based on the schedule you submit.

8. **Q:** We were unable to attend the October 26 site visit. Could the Government share any sign-in sheet, notes, photos or Q&A from that visit, and is it possible to schedule a brief field-verification visit for our installation team before quotes are due?

   A: The Government has a sign-in sheet from the October 26 site visit. No notes, photos, or additional information were generated during the visit. Any questions from the site visit have been addressed through the solicitation Q&A and will be provided via amendment.

   At this time, the Government does not plan to schedule additional site visits. Offerors should prepare their quotations using the solicitation and any issued amendments.

9. **Q:** Access control: Please confirm the Lenel platform/version and whether the existing reader and exit loop provide a dry-contact (relay) output to the gate operator. Will Government IT/security staff need to make any Lenel programming changes, or is a hardwired interface at the operator acceptable?

   A:

   1. Lenel Platform/Version: The facility utilizes a custom in-house designed Lenel access control system.
   2. Relay Output & Interface: The Lenel system uses an existing relay to send an open signal to the gate operator. In accordance with SOO Section 4.3(a), the contractor is responsible for providing all interface devices, relays, wiring, controls, and related components required to achieve integration with the existing card/badge reader and exit loop without requiring replacement or alteration of Government access-control components.
   3. Government IT / Programming: No programming changes to the Lenel system will be performed by Government IT/security personnel. Contractors will not perform any work on, configuration of, or modifications to the Government's internal Lenel panels or software. A hardwired interface at the gate operator is the required method of integration.

10. **Q:** Gate type: The Appendix A note references a vertical pivot gate. Will the Government accept other compliant configurations, such as a cantilever slide gate, if they meet all SOO outcomes?

    A: Yes. Offerors may propose alternative automated vehicular gate configurations (such as a cantilever slide gate). Per SOO Sections 2.0 and 8.0, the sketch in Appendix A is provided for planning and reference purposes only and does not prescribe the final gate type, design, or configuration. Proposed solutions will be evaluated against the performance outcomes outlined in SOO Section 4.0 to determine technical acceptability.

11. **Q:** Existing fence: Can you provide the existing fence height, fabric gauge/mesh size and finish (galvanized or vinyl-coated, and color) at the tie-in location?

    A: As noted in SOO Sections 2.0, 3.0, and 4.2, the existing installation consists of standard perimeter security fencing typical of Government facilities. The contractor's proposed automated gate and infill

solution must match the existing fence in height, fabric pattern, alignment, and finish. The exact tie-in location and associated dimensions are dependent upon the contractor's final proposed design/configuration and remain contractor field-verification items.

12. **Q:** Emergency access: Is there a preferred Fire Code Official/AHJ contact (Pleasant Grove Fire or Utah County), and does the site already use Knox key switches or another emergency access device on the two existing automated gates? Please also confirm the make/model of the operators on those two gates.

    A: Pleasant Grove Fire is the preferred Fire Code Official/AHJ. Currently there isn't any emergency access device(s) on the existing gates or Knox Boxes. In accordance with SOO Sections 1.0, 3.0, 4.4(b), and 11.2, the contractor is responsible for coordinating the device type with the Fire Code Official/AHJ, obtaining required approvals, and furnishing/installing the approved emergency access devices integrated with the respective gate operator control circuits.

13. **Q:** Can you tell me the make and model of the existing access control system?

    A: As stated in Question 9, the facility utilizes a custom in-house designed Lenel access control system. Contractors will not access or modify internal Government access control panels. Per SOO Section 4.3(a), the contractor is responsible for providing all necessary interface devices, relays, and wiring to ensure their proposed gate operator operates from the relay open command provided by the existing system.

14. **Q:** The new Gate will be a Chain Link gate?

    A: The new automated security gate/leaf does not need to be made of chain link. Offerors may propose alternative construction materials and configurations for the gate assembly, provided the proposed solution satisfies all performance, structural, environmental, safety, and operational requirements outlined in the SOO. However, the stationary infill panel (closing the remaining approximately 15 feet of the entrance) must be chain-link that ties into and matches the existing facility perimeter fence pattern, alignment, height, and finish.

15. **Q:** What's the magnitude range of construction?

    A: This is not a construction solicitation; therefore, a construction magnitude range is not applicable to this requirement.

16. **Q:** Fire access: Which fire authority approves the emergency access device, and is a Knox key switch required?

    A: As stated in Question 12, the approving fire authority is the local Fire Code Official/AHJ (Pleasant Grove Fire Department). Per SOO Section 3.0 and Section 11.2, the contractor is responsible for proposing and obtaining written AHJ approval for the specific emergency responder access device (e.g., Knox key switch or local AHJ equivalent) prior to installation.

17. **Q:** Installation approach: Would the Government accept preliminary work, including trenching and loop installation, while keeping the existing gate and fence in place until the replacement equipment arrives, followed by removal and replacement, provided entrance security is maintained and all other requirements are met?

    A: Yes. In accordance with SOO Section 4.1, which specifically governs installation and site security at the main entrance, performing preliminary work (such as trenching, conduit placement, and loop sensor installation) while keeping the existing main entrance gate operational until the replacement equipment arrives is acceptable. As outlined in Section 4.1(c), the contractor must maintain security at the main entrance throughout construction; if the main entrance is temporarily taken out of service, temporary

physical security measures must be provided, and vehicular traffic may be routed through the site's other operational gates in coordination with the Government. (Note: The primary work under this contract is the removal and replacement of the main entrance gate; the two additional access gates remain operational and are only subject to the emergency key switch retrofit).

18. **Q:** Existing equipment: Can you provide the make and model of the Lenel controller or panel, and of the two existing gate operators?

    A: Answers Below

    1. Lenel Controller / Panel: Refer to Questions 9 and 13. The site utilizes a custom in-house designed Lenel access control system; contractors will not access, configure, or modify the Lenel controller or panel.
    2. Existing Gate Operators: Specific makes and models of the two existing gate operators are not required for bidding. The operators utilize standard commercial control circuits that accept an emergency open command; the contractor's responsibility under SOO Sections 1.0, 3.0, and 4.4(b) is to furnish and wire the AHJ-approved emergency access devices to those control circuits without replacing Government components.

19. **Q:** Field verification: Appendix A provides a partial sketch only. Please confirm the fence dimensions, fence height and finish, power source voltage, capacity, and location, and the Lenel card, badge, and exit loop interfaces, or confirm whether those details will be provided by amendment.

    A: Appendix A and the SOO provide planning parameters: an entrance span of approximately 40 feet (anticipated ~25-foot gate opening and ~15-foot chain-link infill) and existing power at the gate actuator location confirmed at 115/120V, 15A. In accordance with SOO Section 2.0, Section 3.0, and Section 8.0, exact tie-in dimensions, existing fence heights/finishes, and post-award routing details are contractor field-verification items. Regarding the access control interface, refer to Question 9: the contractor is responsible for providing all necessary interface devices to connect to the existing relay open signal.

20. **Q:** Who is the Authority Having Jurisdiction for this site — Pleasant Grove City Building and Fire, or the Bureau of Reclamation? And are local building and electrical permits required, or is only AHJ approval of the emergency-access method required?

    A: Answers Below

    1. Jurisdiction & Safety Oversight: The Bureau of Reclamation governs the federal property and provides onsite construction management, inspection, and surveillance under SOO Section 12.0. In addition to OSHA regulations, all onsite construction and electrical activities are subject to the Reclamation Safety and Health Standards (RSHS) per SOO Section 11.4.
    2. Emergency Responder Access & Permitting: The designated Authority Having Jurisdiction (AHJ) for fire code compliance and emergency responder access is the Pleasant Grove Fire Department (see Question 12 and Question 16). In accordance with SOO Section 11.2, the contractor is solely responsible for identifying, coordinating, obtaining, and paying for all applicable local AHJ approvals, permits, and inspections required to complete the installation (see also Question 21).

21. **Q:** Permits. The SOO requires Fire Code Official/AHJ approval of the emergency access method for the new gate and the two existing gates. Beyond that AHJ approval, does the Government expect the contractor to obtain a local building or electrical permit from the City of Pleasant Grove or Utah County for work on Reclamation property? If so, may offerors list permit fees as an assumption or exclusion in the quote?

    A: Per SOO Section 11.2, the contractor is responsible for identifying, obtaining, and coordinating all required permits, approvals, and inspections. Because this is a Firm-Fixed-Price contract, all required

permitting, coordination, and inspection costs must be included in the contractor's quoted price. Offerors may not condition their quotations on open-ended permit fee exclusions or assumptions.

22. **Q:** Regarding permits, could you please clarify whether the required permits and associated fees (including gate installation, electrical, excavation, or fire-access permits) are the contractor's responsibility or if they will be handled by the Government?

    A: Refer to the response provided under **Question 21**. In accordance with SOO Section 11.2, all required permits, licensing, inspection fees, and coordination with local regulatory bodies or the AHJ are the sole responsibility of the contractor and must be factored into the firm-fixed-price quotation. The Government will not obtain permits or reimburse separate permit fees outside the firm-fixed contract price.

23. **Q:** Bonds and insurance: Are payment or performance bonds required? Are there minimum insurance requirements?

    A: Payment and performance bonds are **not required** for this solicitation. Contractors shall maintain insurance coverage customary for the work being performed and comply with all applicable federal, state, and local laws and regulations. No additional minimum insurance requirements are specified in the solicitation. Offerors are responsible for ensuring that their insurance coverage is adequate to perform the work safely and in accordance with contract requirements.

24. **Q:** Can the Government confirm the actual voltage, amperage and breaker location at the main entrance? If a heavier-duty operator requires a dedicated or higher-voltage circuit, should that work be included in our price?

    A: The Government confirms that electrical power available at the existing gate actuator location is single-phase 115/120V, 15-Amp. In accordance with SOO Section 3.0 and Section 4.5(b), the contractor is responsible for providing all electrical and control components necessary for the proposed gate system to operate with this available supply. If an offeror proposes an automated gate solution requiring electrical characteristics differing from or exceeding 115/120V, 15A (e.g., higher voltage or dedicated high-draw circuits), the contractor's technical proposal must clearly identify those specific electrical requirements, and the contractor must include all necessary electrical work, transformers, and circuitry modifications within their firm-fixed-price offer. Specific breaker panel locations and wire runs will be verified during post-award field inspection.