GENERAL NOTES:

CODES AND REFERENCES

1. GENERAL:
   a. INTERNATIONAL BUILDING CODE, 2009
   b. DCMR 12 BUILDING CODE, CURRENT EDITION
   c. ASCE 7–05, "MINIMUM DESIGN LOADS FOR BUILDINGS AND OTHER STRUCTURES"

2. STRUCTURAL & MISCELLANEOUS STEEL:
   a. AISC, "SPECIFICATION FOR STRUCTURAL STEEL BUILDINGS", MARCH 9, 2005
   b. AISC, "SPECIFICATION FOR STRUCTURAL JOINTS USING ASTM A325 OR A490 BOLTS", JUNE 30, 2004
   c. AISC, "CODE OF STANDARD PRACTICE FOR STEEL BUILDINGS AND BRIDGES", MARCH 18, 2005
   d. AWS D1.1–2004, "STRUCTURAL WELDING CODE–STEEL"

MATERIALS

ITEM	NOTES	MIN STRENGTH
1. STRUCTURAL STEEL:		
a. "W" SHAPES	ASTM A992, GRADE 50	Fy = 50,000 PSI
b. CHANNEL SHAPES & PLATES	ASTM A36	Fy = 36,000 PSI

DESIGN LOADS

ITEM	NOTES	LOAD
1. DEAD LOAD	SELF WEIGHT+SUPERIMPOSED	ACTUAL + 10 PSF
2. FLOOR LIVE LOAD	MECHANICAL	100 PSF

GENERAL NOTES

1. ALL DETAILS, SECTIONS, AND NOTES SHOWN ON THE DRAWINGS ARE INTENDED TO BE TYPICAL AND SHALL APPLY TO SIMILAR SITUATIONS, UNO.

2. DO NOT SCALE DRAWINGS.

3. NO CHANGE IN SIZE, DIMENSION OR POSITION OF STRUCTURAL ELEMENTS SHALL BE MADE WITHOUT THE APPROVAL OF THE STRUCTURAL ENGINEER.

4. FIELD VERIFY ALL EXISTING CONDITIONS AND DIMENSIONS BEFORE STARTING CONSTRUCTION AND/OR SUBMITTING SHOP DRAWINGS. ANY DISCREPANCIES SHALL BE REPORTED TO THE STRUCTURAL ENGINEER.

5. REFER TO MECHANICAL AND ELECTRICAL DRAWINGS FOR DIMENSIONS AND LOCATIONS OF EQUIPMENT, OPENINGS, INSERTS, AND OTHER SUCH PROJECT REQUIREMENTS NOT SHOWN ON STRUCTURAL DRAWINGS.

6. TAKE ALL MEASURES NECESSARY TO PROTECT EXISTING AND NEW UTILITIES, BUILDINGS, & EQUIPMENT AND ASSUME FULL RESPONSIBILITY FOR ANY DAMAGE DURING CONSTRUCTION. RESTORATION OF DAMAGED AREAS SHALL BE TO THE SATISFACTION OF THE OWNER, AT NO COST TO THE OWNER.

STRUCTURAL STEEL

1. THE EXISTING STRUCTURAL GRATING MAY BE RE–INSTALLED ON TOP OF THE CHANNELS IF THE EXISTING STRUCTURAL GRATING IS UNDAMAGED DURING REMOVAL. REPAIR ANY GALVANIZING DAMAGED DURING REMOVAL WITH SPRAY OR PAINT ON GALVANIZING.

2. THE MINIMUM FILLET WELD SHALL BE PER AISC SPECIFICATIONS, BUT NOT LESS THAN 1/8", UNO.

3. WELDING ELECTRODES SHALL BE E70XX AND SHALL COMPLY WITH AWS REQUIREMENTS.

4. ALL FIELD WELDED CONNECTION SHALL COMPLY WITH AWS D1.1/D1.1M FOR TOLERANCES, APPEARANCES, WELDING PROCEDURE SPECIFICATIONS, WELD QUALITY, AND METHODS USED IN CORRECTING WELDING WORK.

5. AFTER FABRICATION AND PRIOR TO GALVANIZING/PAINTING, STEEL SHALL BE CLEANED OF ALL RUST, LOOSE MILL SCALE AND OTHER FOREIGN MATERIALS.

6. ALL CHANNELS AND NEW METAL GRATING ARE INDICATED AS GALVANIZED ON THE DRAWINGS. AS AN ALTERNATIVE, THE CHANNELS AND NEW METAL GRATING MAY BE SHOP PRIMED AND PAINTED WITH SERIES 69 HI–BUILD EPOXOLINE II BY TNEMEC OR APPROVED EQUAL.

7. ALL STEEL TO BE HOT–DIP ZINC GALVANIZED SHALL BE GALVANIZED AFTER FABRICATION IN ACCORDANCE WITH ASTM A123/A 123M. ANY ON–SITE DAMAGE TO GALVANIZATION SHALL BE TOUCHED UP WITH SPRAY ON GALVANIZING.

8. PAINT ON ALL MEMBERS RECEIVING PAINT SHALL BE APPLIED WHEN THE SURFACE TO BE PAINTED AND AMBIENT AIR TEMPERATURES ARE BETWEEN 50°F AND 95°F.

9. DO NOT APPLY PAINT IN SNOW, RAIN, FOG, OR MIST; WHEN RELATIVE HUMIDITY EXCEEDS 85%; AT TEMPERATURES LESS THAN 5°F ABOVE THE DEW POINT; OR TO DAMP OR WET SURFACES.


10. APPLY PAINT TO STEEL SURFACES IN ACCORDANCE WITH THE MANUFACTURER'S WRITTEN INSTRUCTIONS. USE APPLICATORS AND TECHNIQUES SUITED FOR PAINT AND SUBSTRATE INDICATED.

11. ANY ON SITE DAMAGE TO PAINT OR PRIMER SHALL BE CLEANED AND TOUCHED UP IMMEDIATELY AFTER ERECTION WITH THE SAME MATERIAL AS USED FOR SHOP PAINTING.


12. DO NOT FIELD CUT STRUCTURAL STEEL MEMBERS WITHOUT THE WRITTEN APPROVAL OF THE STRUCTURAL ENGINEER.

13. DO NOT USE THERMAL CUTTING DURING ERECTION UNLESS APPROVED BY ENGINEER. IF APPROVED, FINISH THERMALLY CUT SECTIONS WITHIN SMOOTHNESS LIMITS IN AWS D1.1.


14. DO NOT SPLICE STEEL MEMBERS EXCEPT WHERE SPECIFICALLY DETAILED ON THE DRAWINGS WITHOUT THE WRITTEN APPROVAL OF THE STRUCTURAL ENGINEER.




1 S101 | S101 VFD–1A & VFD–1B FRAMING PLAN
SCALE: 3/8"=1'–0"



2 S101 | S101 VFD–2A & VFD–3A FRAMING PLAN
SCALE: 3/8"=1'–0"



A TYPICAL CHANNEL TO WIDE FLANGE CONNECTION
NOT TO SCALE



3 S101 | S101 VFD–2B & VFD–4A FRAMING PLAN
SCALE: 3/8"=1'–0"

STRUCTURAL STEEL (CONT.)

15. PROVIDE AND BE RESPONSIBLE FOR ALL TEMPORARY BRACING AND ERECTION PROCEDURES. TEMPORARY BRACING SHALL REMAIN IN PLACE UNTIL ALL STRUCTURAL MEMBERS ARE PROPERLY ALIGNED AND CONNECTED.

16. STORE MATERIALS TO PERMIT EASY ACCESS FOR INSPECTION AND IDENTIFICATION. PROTECT STEEL MEMBERS AND PACKAGED MATERIALS FROM CORROSION AND DETERIORATION.

17. DO NOT STORE MATERIALS ON STRUCTURE IN A MANNER THAT MIGHT CAUSE DISTORTION, DAMAGE, OR OVERLOAD TO MEMBERS OR SUPPORTING STRUCTURES. REPAIR OR REPLACE DAMAGED MATERIALS OR STRUCTURE AS DIRECTED.

ABBREVIATIONS

ADD'L	ADDITIONAL	MANUF	MANUFACTURER
ARCH.	ARCHITECTURAL	MAX	MAXIMUM
BOTT.	BOTTOM	MIN.	MINIMUM
CLR.	CLEAR	MECH.	MECHANICAL
CONT.	CONTINUOUS	O.C.	ON CENTER
DIA.	DIAMETER	REQ	REQUIRED
EA	EACH	U.N.O.	UNLESS NOTED OTHERWISE
EQ.	EQUAL	VERT	VERTICAL
EX.	EXISTING	V.I.F.	VERIFY IN FIELD
GALV.	GALVANIZED	W/	WITH

0' 1' 2'
3/8" = 1'–0"

Alpha Corporation
1850 S. Loudoun Street
Suite 200
Winchester, VA 22601
(540) 723-0704

DISTRICT OF COLUMBIA
MARY A. BILLINGS
No. PE905698
CIVIL/STRUCTURAL
PROFESSIONAL ENGINEER
12/4/12

PROJECT INFORMATION
BUREAU OF ENGRAVING AND PRINTING
DUNNAGE LAYOUT
14TH STREET SOUTHWEST
WASHINGTON, DC

SHEET TITLE
GENERAL NOTES, PLANS, AND DETAILS

DATE 12/4/12

REVISIONS

TITLE	DATE

DESIGN AJA
DRAWN AJA
CHECKED MAB
CLIENT NUMBER
ALPHA PROJECT NUMBER S540–010
SHEET 1 OF 1
S101