Performance Work Statement (PWS)

Elevator Support Services

Completed: Apr 2025
Revised:

TABLE OF CONTENTS

1	Introduction	2
2	Objectives	2
3	Requirements	3
4	Contract Administration and Management	3
5	Personnel	4
6	Organizational Conflict of Interest (OCI)	5
7	Performance Requirements and Standards.	6
8	Maintenance	6
9	Stock of Material	6
10	Schedules and Records	6
11	Services	6
12	Annual, and Five-Year Inspection and Testing Services	8
13	Emergency and Repair Calls	11
14	Responsibility for Damages	11
15	Payment	12
16	Warranty	12
17	Contractor Manpower Reporting Application (CMRA)	13
18	Performance Requirements Summary (PRS)	15
19	Quality Assurance (QA), Quality Control Plan (QCP)	14
20	Deliverables	19
21	Garrison Information	20
22	Security	20
23	Safety	22
24	Environmental Requirements	22
25	Definitions	23
26	Acronyms	24
27	Applicable Directives and Publications	25
28	Elevator Service Location and Requirement	26
29	Attachments	27

1. Introduction.
This is a non-personal services contract to provide Elevator repairs and services. The Government shall not exercise any supervision or control over the contract service providers performing the services herein. Such contract service providers shall be accountable solely to the Contractor who, in turn is responsible to the Government. The contractor shall provide all personnel, equipment, supplies, transportation, tools, materials, supervision, and other items necessary to perform elevator maintenance services as defined in this Performance Work Statement (PWS).

2. Objectives. The work covered by this section of the specifications consists of furnishing all plant, labor, equipment, supplies and materials, and in performing all operations necessary for the inspection, maintenance, and repair of all elevators systems specified herein and in Technical Exhibit 1. The work accomplished shall be in strict accordance with applicable specifications and drawings, and subject to the terms and conditions of the Contract. The Contractor shall provide personnel, management, administration, facilities and clerical functions, except as furnished by the Government, for Fort Huachuca Arizona, as set forth in this performance work statement (PWS) to inspect, repair, and monitor elevators on the Fort Huachuca Installation.

2.1. Technical Exhibit I (TE I) identifies Fort Huachuca's elevator locations for the services to be performed in accordance with (IAW) this PWS.

a. conduct service and inspection of the elevators per paragraph 12 in accordance with ANSI 17.2 outlining the maintenance of the elevators;

b. conduct monthly testing of fire recall operations;

c. conduct bi-annual and 5-year inspections and testing;

d. provides emergency call backs

d. provide scheduling and record keeping

3. Requirements.

3.1. Scope. The work covered by this section of the specifications consists of furnishing all plant, labor, equipment, supplies and materials, and in performing all operations necessary for the inspection, maintenance, and repair of all elevators systems specified herein and in Technical Exhibit 1. The work accomplished shall be in strict accordance with applicable specifications and drawings, and subject to the terms and conditions of the Contract. The contractor shall perform non-personal elevator services in accordance with the PWS and TE I. During performance of the contract the Government reserves the right to add or delete facilities and/or the level of services required. A modification to the contract will be executed to incorporate these changes.

3.2. Period of Performance. Period of performance (POP) consists of:

Base Period:	01 March 2027 through 29 February 2028
Option Period 1:	01 March 2028 through 28 February 2029
Option Period 2:	01 March 2029 through 28 February 2030
Option Period 3:	01 March 2030 through 28 February 2031
Option Period 4:	01 March 2031 through 29 February 2032
FAR 52.217-8:	01 March 2032 through 31 August 2032

3.3. Place of Performance. The work to be performed under this contract will be performed at Fort Huachuca. The contractor shall provide the COR a schedule/list of elevators described in TE I that will be serviced/inspected no later than (10) workdays prior to commencing work. Schedule shall outline tasks to be performed by specific building and identify the timeline for the task to be accomplished. The KO/COR will provide the Contractor with requirements to make changes to the schedule as they occur.

3.4. Hours of Operation. The contractor is responsible for providing services between the hours of 0700 to 1530 hrs. Monday through Friday except Federal holidays or when the Government facility is closed due to local or national emergencies, administrative closings, or similar Government directed facility closings. The contractor must at all times maintain an adequate workforce for the uninterrupted performance of all tasks defined within this PWS when the Government facility is not closed for the above reasons.

3.5. Recognized Federal Holidays. Contractor will not schedule services during the following recognized Federal Holidays.

New Year's Day	Labor Day
Martin Luther King Jr.'s Birthday	Columbus Day
President's Day	Veterans Day
Memorial Day	Thanksgiving Day
Independence Day	Christmas Day
Juneteenth	

3.6. Special Qualifications: The contractor shall be regularly engaged in the installation and servicing of elevators of the general type indicated for maintenance and repair service. The contractor shall maintain a fulltime service and warehouse operation within 70 miles of Ft. Huachuca Arizona. Parts and materials must be on hand and stocked to repair the variety of elevators throughout the installation. Common elevator circuit boards, switches, bulbs, cart buttons, pumps, valves, and electrical repair parts must be available to prevent any extended down time. The contractor shall employ personnel knowledgeable with ANSI A17.1 Elevator and Escalator Safety Package. Qualifications for Elevator Service Personnel (to include Welders and Mechanics): all personnel of an elevator company providing proposed elevator services for Ft. Huachuca must be licensed by the State of Arizona and in current good standing with the State of Arizona and have no less than 2 years' experience repairing, inspecting or otherwise maintaining elevators of the general type and rating specified, except that helpers or apprentices will be permitted to work directly under the direct supervision of a responsible-certified mechanic/ technician. Copies of all current Arizona Department of Labor Mechanic Licenses will be submitted with your proposals. Welding: The quality of the welding procedures and the quality of the welding shall be in compliance with MIL-STD-248 and AWS B3.0 and Dl.1.

4. Contract Administration and Management.

4.1. Post Award Conference/Periodic Progress Meetings. The contractor agrees to attend any post award conference convened by the contracting activity or contract administration office in accordance with Federal Acquisition Regulation (FAR) Subpart 42.5. The KO and COR shall meet when requested by the Government with the contractor to review the contractor's performance. At these meetings the KO will apprise the contractor of how the Government views the contractor's performance and the contractor will apprise the Government of problems, if any, being experienced. Appropriate action shall be taken to resolve outstanding issues.

4.2. Quality Control (QC). The contractor shall develop and maintain an effective quality control process to ensure services are performed in accordance with this PWS. The contractor shall develop and implement procedures to identify, prevent, and ensure against recurrence of defective services. The Quality Control Plan (QCP) must be reviewed and accepted by the KO 30 days after start of the contract (The QCP is addressed at paragraph 20.2).

4.3. Contracting Officer Representative (COR). The COR will be identified by separate letter. The COR monitors all technical aspects of the contract and assists in contract administration. The COR is authorized to perform the following functions: Assure that the contractor performs the technical requirements of the contract; perform inspections necessary in connection with contract performance; maintain written and oral communications with the contractor concerning technical aspects of the contract; issue written interpretations of technical requirements, including Government drawings, designs, and specifications; monitor contractor's performance and notifies both the KO and contractor of any deficiencies; coordinate availability of Government furnished property, and provide site entry of contractor personnel. A letter of designation issued to the COR, a copy of which is sent to the contractor, states the responsibilities and limitations of the COR, especially with regard to changes in cost or price, estimates or changes in delivery dates. The COR is not authorized to change any of the terms and conditions of the resulting contract.

4.4. Materials. Unless otherwise specified, where removal of material or items is required, contractor shall patch or rework such that existing adjacent area is matched, and the intended function of the facility is preserved. Materials used shall match existing materials in appearance and shall be equal or better in quality.

4.5 Emergency Response. The Contractor shall provide primary and secondary emergency phone numbers to DPW for on-call personal for 24 hour-7 days a week. All service calls for regular service will be answered and responded to within (1) hour of receipt of call during the normal work day, for 'Entrapment calls' all calls will be answered and responded to within 45 minutes of receipt of call. Failure to meet these requirements will be grounds for immediate termination of the contract. On weekends and holidays service calls will be answered and responded to within 90 minutes of receipt of call, and (1) hour in the case of entrapments.

4.5.1 The Contractor shall include in their proposal a work plan as to how they will accomplish the requirements listed in 4.5. They shall also discuss how they will handle these calls when the primary on call person is unavailable due to vacation, sickness, or other scheduled work outside the 1-hour parameter.

5. Personnel.

5.1. The contractor shall provide a contract manager who shall be responsible for the performance of the work. The name of this person and an alternate who shall act for the contractor when the manager is absent shall be designated in writing to the KO and COR. The contract manager or alternate shall have full authority to act for the contractor on all contract matters relating to daily operation of this contract. The contract manager or alternate shall be available between 0700 and 1530 hrs. Monday through Friday except Federal holidays or when the Government facility is closed for administrative reasons.

5.2. Contractor agrees that all services shall be performed by certified maintenance and repair personnel, directly employed and supervised by the contractor. All work shall be performed by a Journeyman Level Mechanic as a minimum. Helpers/Apprentices may not work alone but may assist the Mechanic as needed.

5.3. Removed.

5.4. Identification of Contractor Employees. Contractor personnel will be required to obtain an installation access card throughout the performance of this service.

5.5. All contract personnel shall wear a badge and company shirt that clearly delineates them as a contractor employee. All contract personnel attending meetings, and working in other situations where their contractor status is not obvious to third parties are required to identify themselves such that they avoid creating an impression in the minds of members of the public that they are Government officials. They must also ensure that all correspondence (documents, emails etc.,) or reports produced by contractor are suitably marked as contractor products or that contractor participation is appropriately disclosed.

5.6. Non-Personal Services. The FAR provides that each contract arrangement be judged in the light of its own facts and circumstances, with the key question always being whether the Government will exercise relatively continuous supervision and control over the contractor personnel performing the contract. To ensure that services provided under this contract are non-personal in nature, employees performing services under this contract shall be controlled, directed and supervised at all times by management personnel of the contractor. The Government will notify the contractor's management of all tasks that require completion and the contractor's management will assign those tasks to the appropriate contractor personnel under this contract. The contractor's management shall ensure that employees comply with the performance standards outlined in this PWS and as required by the KO or the COR. Contractor employees shall perform independent of and without the supervision of any Government official. Actions of contractor employees may not be interpreted or implemented in any manner that results in any contractor employee creating or modifying Federal policy, obligating the appropriated funds of the U.S. Government, overseeing the work of Federal employees, providing direct personal services to any Federal employee or otherwise violating the prohibitions set forth in Parts 7.5 and 37.1 of the FAR. The Government will control access to the facility and will perform the inspection and acceptance of completed work and tasks.

5.7. Standards of Conduct. Contractor personnel's conduct shall not reflect discredit upon the Government. The contractor shall ensure that personnel present a professional appearance. The contractor's employees shall observe and comply with all local policies and procedures concerning fire, safety, environmental protection, sanitation, security, and possession of firearms or other lethal or illegal weapons or substance. The contractor is responsible for ensuring that any contractor employees providing services under this contract conduct themselves and perform services in a professional, safe, and responsible manner. Contractor employees shall comply with all DOD and local requirements that establish uniform policies governing smoking in and around Government Owned buildings and vehicles. The contractor shall remove from the job site any employee for reasons of misconduct or security. In accordance with DOD Directive 5500.7-R, "Joint Ethics Regulation", contractor employees must avoid being improperly influenced in the execution of their duties under the contract. Particular attention should be paid to acceptance of gifts/ gratuities, and on non-disclosure of sensitive or classified information. The contractor shall ensure employee conduct complies with 41 United States Code (USC) 423 relative to release of acquisition related information or actions or discussions which may prejudice future competitions. The contractor shall ensure no contractor employees conduct political related activities or events on the installation.

6. Organizational Conflict of Interest (OCI).

6.1. Contractor and subcontractor personnel performing work under this contract may receive, have access to, or participate in the development of proprietary or source selection information (e.g., cost or pricing information, budget information or analyses, specifications or work statements, etc.), or perform evaluation services which may create a current or subsequent OCI as defined in FAR Subpart 9.5. The contractor shall notify the KO immediately whenever it becomes aware that such access or participation may result in any actual or potential OCI and shall promptly submit a plan to the KO to avoid or mitigate any such OCI. The contractor's mitigation plan will be determined to be acceptable solely at the discretion of the KO, and in the event the KO unilaterally determines that any such OCI cannot be satisfactorily avoided or mitigated, the KO may affect other remedies as he or she deems necessary, including prohibiting the contractor from participation in subsequent contracted requirements which may be affected by the OCI.

7. Performance Requirements and Standards.

7.1. High Level Objectives. The contractor shall furnish all labor, transportation, tools, equipment, materials, and supplies including all repair parts necessary to inspect, clean, adjust, lubricate, and provide full and complete service maintenance (Reference paragraph 12) and repair of the elevators identified in TE I in order to meet the requirements of the PWS. The replacement of high cost repair parts may be allowable at the discretion of the KO. All work performed by the contractor shall be performed in accordance with all applicable laws, regulations, Army standards, instructions, and commercial practices. Contractor shall display the appropriate caution signs when working on the elevators in order to avoid injury or accidents while conducting service/maintenance.

7.2. Conditions of Service. Contractor shall maintain all Equipment in good operating condition in accordance with manufacturer's specifications and should conditions warrant repair or replacement of the equipment a proposed quote shall be sent to the KO and COR for approval of repair. The contractor shall provide to the KO and COR a non-emergency hourly rate for repair for the base contract and each additional option period.

7.3. Initial Inspection/Certification. The contractor shall furnish a certified inspector in accordance with ANSI/ASME QEI-1 to be present during the initial tests on the elevators. The contractor shall conduct an initial static and relief pressure test on all elevators during the first 90 days of the start of the contract. The test shall be performed in accordance with ANSI/ASME A17.1, Rule 1005.2. The results of this test shall be submitted to the COR within 10 working days upon completion of test. The contractor shall place certification cards in each elevator showing the date the test was performed.

8. Maintenance.

8.1. Regular cleaning within the first three (3) months of this contract is in effect, the contractor shall thoroughly clean all elevator hoist ways, pits, car tops, controller interiors including filters and machine rooms. In addition, during the same period of time, all car and hoist way door tracks, hangers, interlocks and closers shall be cleaned, lubricated and adjusted. Continuing cleaning must be on-going. Cleaning and refinishing of the interior of car and exterior of hoist way doors and frames are excluded.

8.2. The exterior of the machinery and any other parts of the equipment subject to rust shall be properly painted and presentable at all times. The motor windings and controller coils are to be periodically treated with proper insulating compound. The contractor shall keep the elevator machinery rooms clean.

8.3. All debris resulting from this work shall be promptly removed and properly disposed of by the Contractor.

9. Stock of Materials.

9.1. The contractor shall maintain an adequate supply of contacts, switch parts, coils, conductors, springs, holders, resistors, relays, lamps, condensers, tubes, transformers, car and hall buttons, fuses and other parts which are required for prompt replacement together with an adequate supply of lubricants and wiping rags.

10. Schedules and Records.

10.1. The contractor shall provide a schedule on a monthly basis to the KO and COR prior to servicing the elevators identified in TE I.

10.2. Work schedules shall be designed for each type of equipment to be serviced, such as geared elevators, hydraulic elevators, etc., and shall conform to the manufacturer's recommended practice for the particular equipment concerned. They shall show the kind and frequency of service and lubrication proposed by the contractor for the duration of the contract.

10.3. All inspections, lubrication, adjustments, tests, cleaning, routine repairing and other preventative maintenance activities shall be performed in accordance with schedules submitted by the Contractor to the COR.

10.4. Schedules posted shall be of the chart type. The technician shall print and sign when each scheduled inspection is performed.

10.5. Contractor shall maintain an accurate and complete log of all work performed in addition to routine service at each location. These logs shall include call back service describing the nature of all complaints and their resolution. The logs shall be kept in the equipment rooms at each location. In addition to the specified machine room log, contractor's workmen or supervisor shall log in and out of each facility/building on each and every visit. This includes, but is not limited to, routine maintenance, trouble calls, repairs and supervisor's visits. These logs will remain the property of the Government.

10.6. The contractor, on a monthly basis, shall deliver to the COR a copy of the callback and repair log.

10.7. All forms required for the above schedules, monthly work sheets, call back records and performance reports must be approved by the COR.

10.8. Maintenance records shall be kept on each visit delineating all work accomplished. Copies shall be provided to the COR for retention in office files.

11. Services.

11.1. Preventive Maintenance. The contractor shall provide and complete routine servicing of scheduled equipment identified on TE I during each visit. Required service shall be performed on a weekday during normal business hours and the schedule of this service shall be approved by the KO or COR. In the event this day falls on a holiday, the required service shall be performed on the preceding or following workday. Services shall include:

11.1.1. Lubrication (Will meet the manufacturer’s specifications).

11.1.2. Car interior. The doors should open and close smoothly and with appropriate force. In addition, the "Stop Elevator" button should be fully functional. The elevator should accurately stop at each of the floors. Internal and external lights should be checked and replaced if necessary. In addition, the "Emergency Exit" button must be checked and operational. If the elevator is equipped with an emergency phone line, it should also be checked that it connects promptly with the local fire department or 911 operator.

11.1.3. Machine room. It is important that there is appropriate access to the room and that no equipment interferes with adequate headroom in the area. The lighting must be checked and any lights replaced if necessary. In addition, the machine room should be properly heated and ventilated and equipped with fire extinguishers. The stop switch and control panel should be tested. The electric motor or hydraulic pump must be tested as well.

11.1.4. Ceiling and roof of car. The mechanical equipment on the top of the car must be inspected, including the wiring and pipes. The top emergency exit in the interior of the car should be inspected for proper ingress and egress, and lights should be checked to ensure proper functioning. In addition, the stopping devices on the top of the car need to be tested.

11.1.5. Hoist way and pit. The hoist way door and elevator parking devices should be tested. The emergency doors in the hoist way must also be tested. The pit should be inspected for proper access, lighting and clearance. The cables, terminal stopping device and other machinery must be tested. The car frame and platform are also examined.

11.1.7. Service shall include examination, adjustment, and cleaning.

11.2. Monthly Services. The contractor shall provide and complete routine servicing of equipment identified on TE I on a monthly basis to include preventive maintenance. Required service shall be performed on a weekday during normal business hours and the schedule of this service shall be approved by the KO or COR. In the event this day falls on a holiday, the required service shall be performed on the preceding or following workday. Contractor shall guarantee that a supervisor employee who is regularly engaged in inspection and supervision shall visit each elevator monthly to observe the quality of maintenance and to make certain that the quality of maintenance meets the specific and intended standards. The supervisor shall schedule each visit with the COR. Services shall meet the manufacturer's specifications. Monthly inspections shall consist of:

11.2.1. Machine, drive sheave, drive sheave shaft bearings, brake pulley, brake coil, brake contact, linings and component parts, gears, worms, thrusts.

11.2.2. Motor and motor generator, motor and generator windings, rotating elements, commutator, brushes, brush holders and bearings.

11.2.3. Controller, selector and dispatching equipment, all relays, solid state components, resistors, condensers, transformers, filters, SCR's, tachometers, contacts, leads, dashpots, timing devices, computer devices, steel selector tape or cable and mechanical and electrical driving equipment.

11.2.4. Governor, governor sheave and shaft assembly, bearings, contacts and governor jaws.

11.2.5. Deflector, car and counterweight sheaves, bearings, car and counterweight buffers, car and counterweight guide rails and brackets, hoist way top and bottom limit switches, governor tension sheave assembly and compensating sheave assembly.

11.2.6. Hoist way door interlocks, hoist way door hangers, bottom door guides and auxiliary door closing devices. Automatic power operated door operator, car door hanger, car door contact, door protective devices, load- weighing equipment, car frame, safety mechanisms, platform, platform sub-flooring, elevator car and counterweight roller anchor slide guides, gibes or rollers, signal and operating fixtures including lights, buzzers and gongs in all signal and operating fix times.

11.2.7. Renew all wire ropes as often as is necessary to maintain an adequate factor of safety, equalize the tension on all hoisting ropes, repair or replace conductor cables and hoist way and machine room elevator wiring.

11.2.8. Shorten and re-shackle hoist cables if stretching of ropes makes this necessary.

11.2.9. The contractor shall check the condition and operation of detectors, safety edges and light rays on car during each visit and, if they are inoperative, the contractor shall repair them within one business day. If, the door protection devices are not maintainable, the contractor shall replace them.

11.2.10. Seismic triggers and/or derailment devices shall be maintained at least quarterly.

11.2.11. Fire related elevator controls, including monthly firefighters' recall operation of all Elevators.

11.2.12. Tests of firefighter service recall systems. The systems shall be tested and adjusted for proper operation and properly annotated on the Elevator Firefighter's service test record.

12. Bi-Annual, Annual, and Five-Year Inspection and Testing Services.

12.1. Bi-Annual Certification/Inspection. The contractor shall furnish a certified inspector in accordance with ANSI/ASME QEI-1 to be present during the bi-annual tests on elevators.

12.2. Bi-Annual Inspection and Test. The contractor shall conduct a bi-annual static and relief pressure test on all elevators during the months of November and May of each year. The test shall be performed in accordance with ANSI/ASME A17.1, Rule 1005.2. The results of this test shall be submitted to the COR within 10 working days upon completion of test. The contractor shall place certification cards in each elevator showing the date of the last test performed.

12.3. Bi-Annual Safety Test. The contractor shall conduct a bi-annual safety test on all elevators in accordance with ANSI/ASME A17.1, Rule 1002.1 during the months of November and May of each year. Results of this test shall be submitted to the COR within 10 working days upon completion of test. The contractor shall place certification cards in each elevator showing the date of the last safety test performed.

12.4. Annual Inspection. Elevators provided with fire service, derailment devices, seismic switches, pre-torque (car load sensing) motor control, or other special circuitries shall be checked one (1) time every year to make certain that these devices are operating correctly and as designed. The COR and the contractor shall arrange for mutually acceptable dates to perform the tests which will be performed on or about November of each year. The inspection and testing shall include the following:

12.4.1. Hydraulic Elevators. (ASME Sections 8.11.3.2.1 thru 5).

a. Relief Valve Setting and System Pressure Test.

b. Hydraulic Cylinders and Pressure Piping

c. Normal Terminal Stopping Devices

d. Governors, Over-speed Switch, and Seals

e. Safeties

f. Oil Buffers

g. Firefighter's Emergency Operation

h. Standby Power Operation

i. Power Operations of Door System

j. Emergency Terminal Speed Reducing Devices

k. Low Oil Protection Operation

l. Flexible Hose and Fitting Assemblies

m. Pressure Switch

12.4.2. Electric Elevators. (ASME Sections 8.11.2.2.1 thru 10).

a. Oil Buffers.

b. Safeties.

c. Governors.

d. Slack-Rope Devices on Winding Drum Machines.

e. Normal and Final Terminal Stopping Devices.

f. Firefighters' Emergency Operation.

g. Standby or Emergency Power Operation.

h. Power Operation of Door System.

i. Broken Rope, Tape, or Chain Switch.

j. E/E/PES Electrical Protective Devices.

12.5. Handicap Lifts and Chairs. The contractor shall conduct a bi-annual safety test on all handicap lifts and chairs in accordance with the manufacturer's specifications and ASME A18.1. The inspections should include; but, not limited to:

12.5.1. Inside Platform.

12.5.2. Machine Inspection.

12.5.3. Inside Runway Inspections.

12.5.4. Outside Runway Inspections.

12.5.5. Cylinders.

12.5.6. Safeties.

12.5.7. Governors.

12.5.8. Slack-Rope Devices on Winding Drum Machines.

12.5.9. Broken Rope, Tape, or Chain Switch.

12.5.10. Slack-Rope Device on Roped-Hydraulic Machines.

12.6. Five (5) Year Inspection and Testing. The contractor shall conduct the inspections of the elevators identified in TE I. The work shall be certified by an accredited American Society of Mechanical Engineers (ASME) QEI Inspector provided by the contractor. Upon completion of the 5-Year inspection, the Contractor shall perform an after-hours test witnessed by the COR to ensure proper elevator operation.

12.7. The 5-year inspection/test shall be performed during the month of November of the base year of this contract in the presence of the COR or the Government inspector of all elevators. The inspection shall include weight test as prescribed in ANSI/ASME A.17.1, Rule 1002.3. Results of this test shall be provided to the COR within 10 working days upon completion of test. The inspection and testing shall include the following:

12.7.1. Hydraulic Elevators. (ASME Sections 8.11.3.4.1 thru 5).

a. Car and Counterweight Safeties.

b. Governors.

c. Oil Buffers.

d. Coated Ropes.

e. Wire Rope Fastenings.

f. Plunger Gripper.

g. Over-speed valves.

12.7.2. Electric Elevators. (ASME Section 8.11.2.3.1 thru 10).

a. Car and Counterweight Safeties.

b. Governors.

c. Oil Buffers.

d. Braking System.

e. Emergency and Standby Power Operation.

f. Emergency Terminal Stopping and Speed Limiting Devices.

g. Power Opening of Doors.

h. Leveling Zone and Leveling Speed.

i. Inner Landing Zone.

j. Emergency Stopping Distance.

12.8. Handicap Lifts and Chairs. The contractor shall conduct a five (5) year inspection and test requirements on all handicap lifts and chairs in accordance with the manufacturer's specifications and ASME A18.1. The inspections should include; but, not limited to:

12.8.1. Platform Safeties.

12.8.2. Governors.

12.8.3. Brake.

12.8.4. Ropes.

12.8.5. Fastenings.

12.9. All work will be performed during normal working hours from 0700 to 1530 hrs. Monday through Friday except Federal holidays or when the Government facility is closed for administrative reasons.

13. Emergency Repair Calls.

13.1. In the event of a malfunction of the elevators, the contractor shall begin repair not later than 6 hours after being notified.

13.2. The contractor shall provide a list of phone numbers that includes the contractor's project manager, contract administrator, elevator technician, and after hours emergency call center to the COR upon award of the contract.

14. Responsibility for Damages.

14.1. The contractor shall be held responsible for any damages to existing facilities, utilities, other public facilities or private property caused by contractor's operations. Where the work calls for cutting into or disturbing existing materials, the contractor shall patch or repair the existing structure to a neat, finished product.

14.2. The Contractor shall notify the Government on the same day of any damages caused by the contractor.

14.3. The Contractor shall inform the Government at least 3 working days prior to any work that requires modification to an existing structure

15. Payment.

15.1. Items accepted. Payment shall be made for services accepted by the Government that have been performed by the contractor.

15.2. Prompt payment. The Government will make payment in accordance with the Prompt Payment Act (31 U.S.C. 3903) and prompt payment regulations at 5 CFR part 1315.

15.3. Electronic Funds Transfer (EFT). If the Government makes payment by EFT, see 52.212-5(b) for the appropriate EFT clause.

15.4. Discount. In connection with any discount offered for early payment, time shall be computed from the date of the invoice. For the purpose of computing the discount earned, payment shall be considered to have been made on the date which appears on the payment check or the specified payment date if an electronic funds transfer payment is made.

15.5. Overpayments. If the contractor becomes aware of a duplicate contract financing or invoice payment or that the Government has otherwise overpaid on a contract financing or invoice payment, the contractor shall remit the overpayment amount to the payment office cited in the contract along with a description of the overpayment including:

15.5.1. Circumstances of the overpayment (e.g., duplicate payment, erroneous payment, liquidation errors, date(s) of overpayment);

15.5.2. Affected contract number and delivery order number, if applicable;

15.5.3. Affected contract line item or subline item, if applicable; and

15.5.4. Contractor point of contact.

15.6. Provide a copy of the remittance and supporting documentation to the KO.

15.7. Wide Area Workflow (WAWF) system is the method to electronically process vendor payment requests and receiving reports, as authorized by DFARS 252.232-7003, Electronic Submission of Payment Requests and Receiving Reports.

15.8. The contractor shall have a designated electronic business point of contact in the System for Award Management at https://www.acquisition.gov; and be registered to use WAWF at https://wawf.eb.mil/ following the step-by-step procedures for self-registration available at this Web site.

15.9. The Contractor should follow the training instructions of the WAWF Web-Based Training Course and use the Practice Training Site before submitting payment requests through WAWF. Both can be accessed by selecting the “Web Based Training” link on the WAWF home page at https://wawf.eb.mil/.

16. Warranty.

16.1. The contractor shall provide the manufacturer's warranty for all purchased equipment, materials, components, and will provide the purchased documents to the KO and COR.

17. Contractor Manpower Reporting Application.

17.1. The Contractor shall report ALL Contractor labor hours (including subcontractor labor hours) required for performance of services provided under this contract via a secure data collection site. The Contractor is required to completely fill in all required data fields using the following web address: https://www.sam.gov. Reporting inputs will be for the labor executed during the period of performance during each Government fiscal year (FY), which runs October 1 through September 30. While inputs may be reported any time during the FY, all data shall be reported no later than October 31 of each calendar year.

18. Performance Requirements Summary (PRS).

Required Services (Tasks)	Performance Standards	Acceptable Quality Levels	Methods of Surveillance
Perform preventive maintenance	Contractor performs preventive maintenance per schedule	Contractor performs preventive maintenance 100% of the time	COR/Quality Assurance Evaluators provide random inspection of equipment being tested
Ensure elevators are operational and serviceable	Minimize emergency calls	Customer notification of in-operational elevators are less than two (2) calls per month	Customer notification
Repair service calls	Repairs are made in a timely manner;	Customers are informed of expected repair time within three hours of call	COR/QA Evaluator
Emergency calls	Response and repair is made within the specified time.	response: 6 hours	COR/QA Evaluator
Submit maintenance and repair reports	Accurate reports are delivered within two business days	Reports are submitted within the allotted time 90% of the time	COR

Safety program	Program meets current requirements of federal law	No OSHA – reportable violations resulting from contractor action or inaction.	COR/QA inspector conducts random inspections
Examine, adjust, clean and lubricate the equipment	All lubrication frequencies and types will meet the manufacturer's specifications	Contractor shall meet 100% manufacturer's specifications.	COR/QA inspector conducts random inspections
Conduct checks on machine, drive sheave, drive sheave shaft bearings, brake pulley, brake coil, brake contact, linings and component parts, gears, worms, thrusts	The test shall be performed in accordance with ANSI/ASME A17.1	Contractor shall meet 100% manufacturer's specifications.	COR/QA inspector conducts random inspections
Conduct check of the motor and motor generator, motor and generator windings, rotating elements, commutator, brushes, brush holders and bearings	The test shall be performed in accordance with ANSI/ASME A17.1	Contractor shall meet 100% manufacturer's specifications.	COR/QA inspector conducts random inspections
Check the controller, selector and dispatching equipment, all relays, solid state components, resistors, condensers, transformers, filters, SCR's, tachometers, contacts, leads, dashpots, timing devices, computer devices, steel selector tape or cable and Mechanical and electrical driving equipment	The test shall be performed in accordance with ANSI/ASME A17.1	Contractor shall meet 100% manufacturer's specifications.	COR/QA inspector conducts random inspections
Check the governor, governor sheave and shaft assembly, bearings, contacts and governor jaws.	The test shall be performed in accordance with ANSI/ASME A17.1	Contractor shall meet 100% manufacturer's specifications.	COR/QA inspector conducts random inspections

Check the deflector, car and counterweight sheaves, bearings, car and counterweight buffers, car and counterweight guide rails and brackets, hoistway top and bottom limit switches, governor tension sheave assembly and compensating sheave assembly	The test shall be performed in accordance with ANSI/ASME A17.1	Contractor shall meet 100% manufacturer's specifications.	COR/QA inspector conducts random inspections
Inspect hoistway door interlocks, hoistway door hangers, bottom door guides and auxiliary door closing devices. Automatic power operated door operator, car door hanger, car door contact, door protective devices, load- weighing equipment, car frame, safety mechanisms, platform, platform sub-flooring, elevator car and counterweight roller anchor slide guides, gibs or rollers, signal and operating fixtures including lights, buzzers and gongs in all signal and operating fix times	The test shall be performed in accordance with ANSI/ASME A17.1	Contractor shall meet 100% manufacturer's specifications.	COR/QA inspector conducts random inspections
Renew all wire ropes as often as is necessary to maintain an adequate factor of safety, equalize the tension on all	The test shall be performed in accordance with ANSI/ASME A17.1	Contractor shall meet 100% manufacturer's specifications.	COR/QA inspector conducts random inspections

hoisting ropes, repair or replace conductor cables and hoist way and machine room elevator wiring			
Shorten and re-shackle hoist cables if stretching of ropes makes this necessary	The test shall be performed in accordance with ANSI/ASME A17.1	Contractor shall meet 100% manufacturer's specifications	Contractor shall meet 100% manufacturer's specifications
The contractor shall check the condition and operation of detectors, safety edges and light rays on car during each visit and, if they are inoperative, shall repair them within one business day. If, in the Contractor's opinion, the door protection devices are not maintainable, they shall replace them	The test shall be performed in accordance with ANSI/ASME A17.1	Contractor shall meet 100% manufacturer's specifications.	COR/QA inspector conducts random inspections
Seismic triggers and/or derailment devices shall be maintained at least quarterly	The test shall be performed in accordance with ANSI/ASME A17.1	Contractor shall meet 100% manufacturer's specifications.	COR/QA inspector conducts random inspections
Fire related elevator controls, including monthly firefighters' recall operation of all Elevators	The test shall be performed in accordance with ANSI/ASME A17.1	Contractor shall meet 100% manufacturer's specifications.	COR/QA inspector conducts random inspections
Tests of firefighter service recall systems. The systems shall be tested and adjusted for proper operation and properly annotated on the Elevator Firefighter's service test record	The test shall be performed in accordance with ANSI/ASME A17.1	Contractor shall meet 100% manufacturer's specifications.	COR/QA inspector conducts random inspections

The contractor shall furnish a certified inspector in accordance with ANSI/ASME QEI-1 to be present during the bi-annual tests on elevators	The test shall be performed in accordance with ANSI/ASME A17.1	Certified inspector shall be present 100% of the time	COR/QA inspector conducts random inspections
Conduct a bi-annual static and relief pressure test on all elevators during the months of November and May of each year.	The test shall be performed in accordance with ANSI/ASME A17.1, Rule 1005.2	Contractor shall meet 100% manufacturer's specifications.	COR/QA inspector conducts random inspections
conduct a bi-annual safety test on all elevators during the months of November and May of each year	The test shall be performed in accordance with ANSI/ASME A17.1, Rule 1002.1	Contractor shall meet 100% manufacturer's specifications.	COR/QA inspector conducts random inspections
Elevators provided with fire service, derailment devices, seismic switches, pre-torque (car load sensing) motor control, or other special circuitries shall be checked one (1) time every year to make certain that these devices are operating correctly and as designed	The test shall be performed in accordance with ANSI/ASME A17.1	Contractor shall meet 100% manufacturer's specifications.	COR/QA inspector conducts random inspections
Conduct a Five (5) year inspection and testing	Work shall be certified by an accredited American Society of Mechanical Engineers (ASME) QEI Inspector provided by the contractor The inspection shall include weight test as prescribed in ANSI/ASME A.17.1, Rule 1002.3	Certified inspector shall be present 100% of the time	COR/QA inspector conducts random inspections

19. Quality Assurance (QA), Quality Control Plan (QCP).

19.1. Quality Assurance. The Government will evaluate the Contractor's performance under the contract IAW the QASP. This plan is primarily focused on what the Government must do to ensure that the contractor has performed IAW the performance standards. The plan defines how the performance standards will be applied, the frequency of surveillance, and the minimum Acceptance Quality Level (AQL) at which the standard shall be met. Although the Government may develop a QASP, Government surveillance of contractor performance is not limited to the QASP or the performance objectives, incentives/remedies, etc. outlined in the PRS. The Government has the right to inspect and test all services called for by the contract. The Government will perform inspections and tests in a manner that will not unduly delay the work. If any of the services performed do not conform to contract requirements, the Government may require the Contractor to perform the services again in conformity with contract requirements, at no increase in contract amount.

19.2. Quality Control Plan. The purpose of this paragraph is to describe the requirement for Quality Control QC and the QCP. QC is the responsibility of the Contractor. The Contractor is responsible for the delivery of quality services/supplies to the Government. The Contractor shall establish and maintain an effective QC system in compliance with the solicitation and contract requirements. The Contractor's QCP shall consist of plans, procedures, and organization necessary to produce an end product which complies with the contract requirements and covers all aspects of the PWS as it relates to the contract. The Contractor shall develop and implement procedures to identify, prevent, and ensure non-recurrence of defective services. The Contractor's QC program is the means by which the Contractor assures itself that its work complies with the requirements of the contract. The Contractor shall implement and maintain a documented QC system that identifies and results in correction of potential and actual problem areas throughout the entire scope of this contract. The Contractor shall maintain records of all Contractor QC checks and corrective actions. These files shall be maintained by the Contractor throughout the PoP of this contract and shall be made available to the KO or COR upon request. The QCP shall include but is not limited to the following:

19.2.1. The name of your cognizant QC point of contact (POC).

19.2.2. An inspection system covering all the services listed on the PRS. The inspection plan shall specify the areas to be inspected on both a scheduled or unscheduled basis, and the individual who will perform the inspection.

19.2.3. The method(s) for identifying and preventing defects in the quality of service performed before the level of performance becomes unacceptable.

19.2.4. On site records of all inspections conducted by the Contractor and necessary corrective action taken. This documentation shall be made available to the KO and/or COR during the term of the contract.

20. Deliverables.

20.1. Provide an Inspection and Test Report NLT 30 days after inspection has been conducted.

20.2. Provide a copy of preventive maintenance, bi-annual, annual, and five (5) year check list to the COR upon completion of each service as reflected in attachments I and II (Electric and hydraulic Preventive Maintenance checklist, each visit); attachment III and IV (Electric and hydraulic bi-annual, annual, and five (5) year inspection/service).

21. Garrison Information. Fort Huachuca, which includes 73,142 acres, is situated along the foothills and north plateau of the Huachuca Mountains in Cochise County, located in the southeast portion of the State of Arizona. Distances by highway and air from U.S. Army Garrison, Fort Huachuca, to principal cities and towns are as follows:

Location	Highway	Air
Sierra Vista, Arizona, east	3 miles	
Huachuca City, Arizona, north	3 miles	
Tombstone, Arizona, northeast	28 miles	20 miles
Bisbee, Arizona, east, southeast	28 miles	27 miles
Benson, Arizona, north	28 miles	28 miles
Douglas, Arizona, southeast	50 miles	50 miles
Nogales, Arizona, south, southwest	63 miles	37 miles
Tucson, Arizona, northwest	75 miles	58 miles
Phoenix, Arizona, northwest	186 miles	160 miles
El Paso, Texas, east	320 miles	225 miles
San Diego, California, west	482 miles	420 miles

Primary access to Fort Huachuca and its neighboring communities of Sierra Vista and Huachuca City is via State Highway 90, which links with Interstate Highway 10 (U.S. 80), approximately 25 miles north of Fort Huachuca near Benson. Fort Huachuca is within the corporate limits of Sierra Vista, Arizona. In addition to the 73,142 acres contained within Fort Huachuca proper, Fort Huachuca also manages 28,230 acres of off post property consisting of the following:

A Wilcox Dry Lake Area - 27,397 acres

B Gila Bend Area - 679 acres

C Various test sites within the vicinity of Fort Huachuca -154 acres

22. Security.

22.1. Security Policies. All contractor and all associated sub-contractors employees shall comply with applicable installation, facility and area commander installation/facility access and local security policies and procedures (provided by Government representative). The contractor shall also provide all information required for background checks to meet installation access requirements to be accomplished by installation Provost Marshal Office, Director of Emergency Services or Security Office. Contractor workforce must comply with all personal identity verification requirements as directed by Department of Defense (DOD), Headquarters Department of the Army (HQDA) and/or local policy. The contractor shall submit the AT Level I certificate of completion for each employee and subcontractor employee to the COR, or to the KO if a COR is not assigned within 5 calendar days after completion of training by all employees and subcontractor personnel.

22.2. Antiterrorism/ Operation Security (AT/OPSEC). Pursuant to Department of Defense Instruction Number 2000.16, "DoD AT Standards," dated October 2, 2006, each contractor employee requiring access to a Federally-controlled installation, facility and/or Federally-controlled information system(s) shall complete Level I AT Awareness Training on an annual basis and receive a certificate of completion. The training is accessible from any computer and is available at https://atlevel1.dtic.mil/at/. The

contractor is responsible for ensuring that all applicable employees have completed AT awareness training and shall certify that their workforce has completed the training through the submission of completion certificate(s) to the KO and the COR within five working days after contract award or prior to access to a Federally-controlled installation or information system.

22.3. In the event that the automated system at https://atlevel1.dtic.mil/at/ is not available (e.g., server problems), Level I AT Awareness Training can be provided by a qualified instructor. However, if the training is not completed online, the Level I AT Awareness Instructor qualification must be coordinated with the Installation Antiterrorism Officer (ATO) (or Installation Security equivalent) and the resultant name(s) of approved instructors shall be provided the contracting officer or designee along with all associated cost or schedule impacts to the contract.

22.4. iWATCH Training. The contractor and all associated sub-contractors shall brief all employees on the local iWATCH program (training standards provided by the requiring activity ATO). This local developed training will be used to inform employees of the types of behavior to watch for and instruct employees to report suspicious activity to the COR. This training shall be completed within 30 calendar days of contract award and within 10 calendar days of new employees commencing performance with the results reported to the COR not later than (NLT) 30 calendar days after contract award.

22.5. Physical Security. The contractor shall safeguard all Government equipment, information and property provided for contractor use. Contractor shall maintain a physical security checklist/log which will be forwarded to the COR on a monthly or quarterly basis, no later than the fifth day of the month or after the quarter ends. At the close of each work period, Government facilities, equipment, and materials shall be secured.

22.6 Key Control. The contractor shall establish and implement methods of making sure all Key/cards issued to the Contractor by the Government are not lost or misplaced and are not used by unauthorized persons. NOTE: All references to keys include key cards. No keys issued to the Contractor by the Government shall be duplicated. The Contractor shall develop procedures covering key control that shall be included in the QCP. Such procedures shall include turn-in of any issued keys by personnel who no longer require access to locked areas. The Contractor shall immediately report any occurrences of lost or duplicate keys/key cards to the KO and COR.

23.7. Lost keys shall be reported to the COR and the KO. In the event keys, other than master keys, are lost or duplicated, the Contractor shall, upon direction of the KO, re-key or replace the affected lock or locks; however, the Government, at its option, may replace the affected lock or locks or perform re-keying. When the replacement of locks or re-keying is performed by the Government, the total cost of re-keying or the replacement of the lock or locks shall be deducted from the monthly payment due the contractor. In the event a master key is lost or duplicated, all locks and keys for that system shall be replaced by the Government and the total cost deducted from the monthly payment due the contractor.

22.8. The contractor shall prohibit the use of Government issued keys by any persons other than the contractor's employees. The contractor shall prohibit the opening of locked areas by contractor employees to permit entrance of persons other than contractor employees engaged in the performance of assigned work in those areas, or personnel authorized entrance by the KO.

22.9. Lock Combinations. The contractor shall establish and implement methods of ensuring that all lock combinations are not revealed to unauthorized persons. These procedures shall be included in the contractor's QCP.

23. Safety.

23.1. The contractor shall perform work in a safe manner as required by Occupational Safety and Health Administration (OSHA) Safety and Health Requirements. Provide a verbal notification to the KO as soon as possible of each occurrence of damage to Government property or an accident resulting in death, injury, occupational disease, or adverse environmental impact. Provide a completed copy of DA Form 285 (Technical Report of U.S. Army Ground Accident) to the KO within five calendar days of each occurrence.

23.2. Special Training / Qualifications. The contractor shall provide a Certified Elevator Technician (CET).

24. Environmental Requirements.

24.1. Environment and OSHA. The contractor shall comply with all local, state, and Federal environmental and occupational safety laws, rules, and regulations. Any apparent conflict between compliance with such local, state and Federal laws, rules and regulations, and compliance with the requirements of the contract shall be immediately brought to the attention of the KO and/or the COR for final resolution. The contractor shall notify the KO and COR in writing in addition to any verbal notification of such conflicts. The contractor shall be liable for all fines, penalties, and costs which result from violations of, or failure to comply with, all such local state, or Federal laws, rules, and regulations. All unsafe acts or conditions fostered by the contractor or contractor personnel may be grounds for the KO or COR, to halt all contractor performance with a commensurate deduction of monies due the contractor until such unsafe conditions are corrected. The contractor shall take due caution not to endanger personnel during performance of this contract. Upon discovery of any hazard such as, but not limited to, fire, or large fuel spill, the contractor shall immediately notify the KO or COR.

24.2. Green Procurement. In order to comply with the green procurement requirements of Section 6002 of the Resource Conservation and Recovery Act of 1976 (RCRA) and Executive Order 13423, the Government requires the use of recycled and recovered materials and products identified in the Environmental Protection Agency's (EPA) Comprehensive Procurement Guidelines. These materials and products must meet the requirements of the PWS, must not delay the progress of work, must be available from more than one source, and must not be cost prohibitive. EPA guideline items are seen as the minimum that should be considered when evaluating recyclable materials. Other materials and products not listed, but commonly used in industry outside of the Government, should also be considered. Material and product submittals for all recycled-content items should list the recycled and recovered materials used and the percentage content. The contractor shall track the purchase, quantities, and the percent of recyclable content for these materials throughout the life of the contract. The contractor shall consolidate and provide this information to the COR in quarterly reports.

24.3. Disposal. The contractor shall properly dispose of any parts, cleaning supplies, cleaning waste, hydraulic fluids, lubricants, and oils in accordance with product disposal standards and environmental regulations.

25. Definitions

Acceptable Quality Level (AQL): The AQL is the maximum percent defective (or the number of defects per hundred units) that, for purposes of sampling inspection can be considered satisfactory.

Contractor. A supplier or vendor awarded a contract to provide specific supplies or service to the Government. The term used in this contract refers to the prime.

Contracting Officer (KO). A person with authority to enter into, administer, and or terminate contracts, and make related determinations and findings on behalf of the Government. Note: The only individual who can legally bind the Government.

Contracting Officer's Representative (COR). An employee of the U.S. Government appointed by the contracting officer to administer the contract. Such appointment shall be in writing and shall state the scope of authority and limitations. This individual has authority to provide technical direction to the Contractor as long as that direction is within the scope of the contract, does not constitute a change, and has no funding implications. This individual does NOT have authority to change the terms and conditions of the contract.

Defective Service. A service output that does not meet the standard of performance associated with the Performance Work Statement.

Deliverable. Anything that can be physically delivered, but may include non-manufactured things such as meeting minutes or reports.

Equipment. A tangible item that is functionally complete for its intended purpose, durable, nonexpendable, and needed for the performance of a contract. Equipment is not intended for sale, and does not ordinarily lose its identity or become a component part of another article when put into use. Equipment does not include material, real property, special test equipment or special tooling.

Material. Property that may be consumed or expended during the performance of a contract, component parts of a higher assembly, or items that lose their individual identity through incorporation into an end-item. Material does not include equipment, special tooling, and special test equipment or real property.

Non-Personal Services. The personnel rendering the services are not subject; either by the contract's terms or by the manner of its administration, to the supervision and control usually prevailing in relationships between the Government and its employees. Non personal service contracts are authorized by the Government in accordance with FAR 37.012, under general contracting authority, and do not require specific statutory authorization.

Performance Requirements Summary. Identifies the key service outputs of the Contractor.

Physical Security. Actions that prevent the loss or damage of Government property.

Property. All tangible property, both real and personal.

Quality Assurance. The Government procedures to verify that services being performed by the Contractor are performed according to acceptable standards.

Quality Assurance Surveillance Plan. An organized document written by the Government specifying the surveillance methodology used for surveillance of Contractor performance.

Quality Control. All necessary measures taken by the Contractor to assure that the quality of an end product or service shall meet contract requirements.

Real Property. See Federal Management Regulation 102-71.20 (41 CFR 102-71.20).

Sensitive Property. Property potentially dangerous to the public safety or security if stolen, lost, or misplaced, or that shall be subject to exceptional physical security, protection, control, and accountability. Examples include weapons, ammunition, explosives, controlled substances, radioactive materials, hazardous materials or wastes, or precious metals.

Wide Area Work Flow (WAWF). A secure web system for electronic invoicing, receipt, and acceptance. WAWF allows Government vendors to submit and track invoices and receipt/acceptance documents over the web and allows Government personnel to process those invoices in a real-time, paperless environment.

Work Day. The number of hours per day the Contractor provides services in accordance with the contract.

Work Week. Monday through Friday, unless specified otherwise.

26. Acronyms.

ACOR	Alternate Contracting Officer's Representative
AFARS	Army Federal Acquisition Regulation Supplement
AR	Army Regulation
CFR	Code of Federal Regulations
COR	Contracting Officer Representative
DA	Department of the Army
DFARS	Defense Federal Acquisition Regulation Supplement
DMDC	Defense Manpower Data Center
DOD	Department of Defense
DPW	Directorate of Public Works
FAR	Federal Acquisition Regulation
GFP	Government-Furnished Property
KO	Contracting Officer
OCI	Organizational Conflict of Interest
ODC	Other Direct Costs
PIPO	Phase In/Phase Out
POC	Point of Contact
PRS	Performance Requirements Summary
PWS	Performance Work Statement
QA	Quality Assurance
QAP	Quality Assurance Program
QASP	Quality Assurance Surveillance Plan
QC	Quality Control
QCP	Quality Control Program
TE	Technical Exhibit
WAWF	Wide Area Work Flow

27. Applicable Directives and Publications.

AR 200-1, Dec 07 Protection and Enhancement.
AR 385-10, Nov 13 Army Safety Program Administration.
EM-385-1-1, Jul 11 Safety and Health Requirements Manual.
29 CFR 1910, General Industry's OSHA.
AR 420-90, Mar 05, Fire Emergency Services.

EO 13423, Jan 07, Strengthening Federal Environmental, Energy, and Transportation Management.
ASME/ANSI A17.1, 2013 Safety Code for elevators and escalators.
ASME Al7.3, 2015 Safety Code for elevators and escalators.
National Fire Protection Association (NFPA) 101: Life Safety Code, 2015 Edition or latest edition.
All local, state and Federal codes which govern.

28. Elevator Service location and Requirement..

BLDG #	BLDG NAME	QTY	FREQUENCY OF SERVICE	DESCRIPTION	(LBS)	BRAND	TYPE
11640	UAV Tng Ctr	1	Monthly	Passenger	3500	Montgomery	Hydraulic
41412	DPTMS	1	Monthly	Passenger	3500		Electric
45001	RWBAH	1	Bi-Weekly	Passenger	4500	Montgomery	Hydraulic
45001	RWBAH	1	Bi-Weekly	Passenger	4500	Montgomery	Hydraulic
52308	TB Village Bks	1	Monthly	Passenger	3500	Dover	Hydraulic
52309	TB Village Bks	1	Monthly	Passenger	3500	Dover	Hydraulic
53301	CMET 1	1	Monthly	Passenger	4000	US Elevator	Hydraulic
53302	CMET 2	1	Monthly	Passenger	4000	Minnesota	Hydraulic
57305	JITC	1	Bi-Weekly	Passenger	2500	Dover	Hydraulic
57305	JITC	1	Bi-Weekly	Freight	4000	Dover	Hydraulic
61730	Operations Bldg	1	Monthly	Passenger	2100	Dover	Hydraulic
61730	Operations Bldg	1	Monthly	Passenger	2100	Dover	Hydraulic
61801	Greely Hall	1	Weekly	Freight – (#7)	12000	Elser	Electric
61801	Greely Hall	1	Weekly	Freight – (#8)	12000	Elser	Electric
61801	Greely Hall	1	Weekly	Freight – (#6)	12000	Watson	Electric
61801	Greely Hall	1	Weekly	Freight – (#5)	12000	Watson	Electric
61801	Greely Hall	1	Weekly	Passenger	3000	US Elevator	Electric
61801	Greely Hall	1	Weekly	Passenger	3000	US Elevator	Electric
61801	Greely Hall	1	Weekly	Passenger	3000	US Elevator	Electric
61801	Greely Hall	1	Weekly	Passenger	3000	US Elevator	Electric
61801	Greely Hall	1	Bi-Weekly	Passenger	2100	Schindler	Hydraulic
61801	Greely Hall	1	Bi-Weekly	Passenger	2500	Schindler	Hydraulic
61809	O'Neil Hall	1	Monthly	Passenger	3500	Montgomery	Hydraulic
63845	Rowe Hall	1	Monthly	Passenger	2500	US Elevator	Hydraulic
63902	Friedman Hall	1	Monthly	Passenger	3500	Dover	Hydraulic
80505	Nicholson Hall	1	Monthly	Freight	8000	Dover	Hydraulic
11653	UASTB	1	Monthly	Passenger	2500	Schindler	Hydraulic
61801	Greely Hall	1	Bi-Annual	Handicap			Electric
61801	Greely Hall	1	Bi-Annual	Handicap Chair			Electric
61801	Greely Hall	1	Bi-Annual	Freight			Hydraulic
53301	CMET	1	Bi-Annual	Freight			Hydraulic
21112	Ed Ctr Annex	1	Bi-Annual	Handicap Chair			Electric
22414	ASAP	1	Bi-Annual	Handicap			Electric
22408	AMC	1	Bi-Annual	Handicap			Electric
Number of elevators		**21**					
Number of handicap lifts		**5**					
Number of freight lifts		**8**					

29. Attachments

Attachment I



Attachment I - Preventive Maintena

Attachment II



Attachment II - Preventive Maintena

Attachment III



Attachment III - Electric Elevator Rep

Attachment IV



Attachment IV - Hydraulic Elevator R